


STEPS/WALKWAY/BRIDGE PLAN
EXHIBIT "A-5"

Elevated boardwalks and platform steps may be allowed for safety. Handrails are required for all steps one foot or more above the ground. All improved steps must be between 4 to 6 feet wide, *please note dimensions on form*. Maximum distance between support posts on handrails is 8 feet. Vertical posts can be used in place of mid-rails if they are 12 inches or less apart. All wooden construction shall be pressure treated or made decay resistant with preservatives approved by the Corps of Engineers. Creosote, arsenic, and "penta" treatment are *not* acceptable. Minimum dimension lumber size permitted is five-quarter (5/4) inches.

NOTE: Please attach a detailed diagram of your Step/Walkway configuration on Public Property to this form .



CONCEPTUALLY APPROVED
for
U.S. Army Corps of Engineers, Mobile District

BY: _____
DATE: _____



NOTICE: This approval stamp DOES NOT certify an engineering review. The builder should rely on professional engineering services to certify that the design is suitable for intended purposes and meets minimum standards including those related to the safety of the users.

I will construct this facility according to this plan.

Name: _____
 Subdivision: _____
 Lot No.: _____

STEPS/WALKWAY/BRIDGE PLAN (Con't)
EXHIBIT "A-5"

Natural Steps



NOTE: Handrails Minimum 2 X 4" Wood or 1½ Square Tubing or other Rigid Material (NO ROPES)

