

## AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

0

1

2. AMENDMENT/MODIFICATION NO. P00003	3. EFFECTIVE DATE 09-Aug-2000	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. (If applicable)
6. ISSUED BY CONTRACTING DIVISION P. O. BOX 2288 109 ST. JOSEPH ST/6TH FLR  MOBILE, AL 36628-0001	CODE K5P00C0	7. ADMINISTERED BY (If other than item 6) U S ARMY ENGINEER DISTRICT MOBILE-CORPS OF ENGINEERS 109 ST. JOSEPH ST (PO BOX 2288)  MOBILE, AL 36628-0001	CODE DACA01

8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code) ENVIRONMENTAL CHEMICAL CORPORATION ECC Manjiv Vohra 1240 BAYSHORE HIGHWAY BURLINGAME CA 94010-1805	9A. AMENDMENT OF SOLICITATION NO.
	9B. DATED (SEE ITEM 11)
	X 10A. MOD. OF CONTRACT ORDER NO. DACW01-99-D-0046
	X 10B. DATED (SEE ITEM 13) 29-Aug-1999
CODE 0T0F8	FACILITY CODE

## 11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☐ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer ☐ is extended. ☐ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods:  
 (a) By completing Items 8 and 15, and returning \_\_\_\_\_ copies of the document; (b) By acknowledging receipt of this amendment on each copy of the offer submitted;  
 or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE  
 RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN THE  
 REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter,  
 provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

## 12. ACCOUNTING AND APPROPRIATION DATA (If required)

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14	
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.	
B. THE ABOVE NUMBERED CONTRACT ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).	
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF: <u>Changes Clause</u>	
D. OTHER (Specify type of modification and authority)	

E. IMPORTANT: Contractor ☐ is not. ☒ is required to sign this document and return 1 copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)	
1. The purpose of this modification is to include a new paragraph to the scope of work on subject contract covering Debris Removal/Reduction operations after any natural or manmade catastrophe or major disaster supported by the U.S. Army Corps of Engineers.	
2. Page C-8, Paragraph C2.7.4.3 is provided.	
3. Change in Contract Amount: NONE	
4. Total Contract Amount: \$100,000.00 for Base Year and \$100,000.00 for Option Year 1	

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print) TONI S CARNEY / CONTRACTING OFFICER	
15B. CONTRACTOR/OFFEROR  (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA BY <u>Toni S. Carney</u> (Signature of Contracting Officer)	16C. DATE SIGNED 08-Sep-2000

EXCEPTION TO SF 30  
APPROVED BY OIRM 11-84

30-105-04

STANDARD FORM 30 (Rev. 10-83)  
Prescribed by GSA  
FAR (48 CFR) 53.243

C2.7.2.2 The night foreman will be responsible for monitoring and documenting equipment and labor time and providing the daily operational report to the contracting officer's representative.

C2.7.2.3 All hourly manpower rates include the cost of a cellular telephone, protective clothing (to include hard-hats and steel toed boots), fringe benefits, hand tools, supervision, transportation and any other costs.

C2.7.3.2 This item includes all labor and materials costs associated with developing this plan.

### **C2.7.3 Site Management Plan.**

C2.7.3.1 Once the dumpsite is located, the contractor will provide a Site Management Plan. Five (5) copies of the plan are required. The plan shall be drawn to a scale of 1" = 50' and address following functions:

- a. Access to site
- b. Site preparation - clearing, erosion control, and grading
- c. Traffic control procedures
- d. Safety
- e. Segregation of debris
- f. Location of ash disposal area, hazardous material containment area, contractor work area, and inspection tower
- g. Location of incineration operations, chipping operation (if required). Burning operations require a 100 foot clearance for the stockpile and a 1000 foot clearance for structures.

Location of existing structures or sensitive areas requiring protection

C2.7.3.2 This item includes all labor and materials costs associated with developing this plan.

### **C2.7.4 Inspection Tower.**

C2.7.4.1 The contractor shall construct an inspection tower. The tower shall be constructed using pressure treated wood. The floor elevation of the tower shall be 10 foot above the existing ground elevation. The floor area shall be 8' by 8', constructed of 2"x8" joists, 16" O.C. with ¾" plywood supported by four 6" x 6" posts. A 4 foot high wall constructed of 2" x 4" studs and ½" shall protect the perimeter of the floor area" inch plywood. The floor area shall be covered with a corrugated tin roof. The roof shall provide a minimum of 6'-6" of head room below the support beams. Wooden steps shall provide access with a hand rail.

C2.7.4.2 This item includes all labor and materials costs associated with constructing this tower.

\*C2.7.4.3 Hauling operations will not be allowed into the reduction site until an inspection platform is provided. A temporary mechanical lift may be used until a fixed tower can be constructed as specified.

### **C2.7.5 Hazardous Materials Containment Area:**

C2.7.5.1 The contractor shall construct a hazardous material containment area. This area shall be 30' x 30'. The perimeter shall be lined with hay bales and staked in place. The area shall be lined with a heavy gage plastic to provide a water proof barrier. Additional plastic sufficient to cover the area is required to prevent rain from entering the containment. Site