DEPARTMENT OF THE ARMY



MOBILE DISTRICT, CORPS OF ENGINEERS P.O. BOX 2288 ' MOBILE, ALABAMA 36628-0001

CESAM-OP-S PUBLIC NOTICE NO. AL01-02628-F 3 October 2001

JOINT PUBLIC NOTICE
U.S. ARMY CORPS OF ENGINEERS
AND
STATE OF ALABAMA

DEPARTMENT OF ENVIRONMENTAL MANAGEMENT

CONSTRUCTION OF A NORTH-SOUTH PIPELINE WEST OF BIG CREEK LAKE, NEAR MOBILE, MOBILE COUNTY, ALABAMA

TO WHOM IT MAY CONCERN:

This District has received an application for a Department of the Army permit pursuant to Section 404 of the Clean Water Act (33 USC 1344). Please communicate this information to interested parties.

APPLICANT: Florida Gas Transmission Company

Attention: Mr. Rockford G. Meyer, President

1400 Smith Street, EB 3963

Houston, Texas 77002

WATERWAY: Wetlands adjacent to Puppy Creek, Jackson Branch, Boggy Branch, Big Creek and Big Creek Lake, near Mobile, Mobile County, Alabama

WORK: The applicant is proposing the construction of 29.1 miles of 30-inch natural gas pipeline as part of their Phase V Expansion Project. This north-south connector (Mobile Bay Lateral) will begin at a new interconnect with the Florida Gas Transmission Company (FGT) mainline system in Mobile County extending south and west of Big Creek and Big Creek Lake to a new compressor station located south of Airport Boulevard. This tie in will be located approximately 500 feet west of the intersection of FGT's mainline right-of-way (ROW) and the pipeline ROW occupied by Transco's Mobile Bay pipeline at the existing meter station. The north-south connector will proceed east paralleling the existing FGT ROW until intersecting the Transco easement and will turn south at that point. FGT's north-south connector will be installed parallel to and west of the Transco pipeline in new ROW acquired by FGT. FGT's north-south connector will then proceed southward for 27.8 miles where the proposed pipeline will cross existing 12-inch and 30-inch pipelines. South of this crossing the pipeline will continue southward paralleling a 30-inch Koch Gateway (Koch) pipeline which occupies an easement adjacent to the Transco line. The pipeline route continues adjacent to the Koch easement to the location of a

proposed compressor station at Mile Post 28.8. The pipeline will again continue southward following the Koch pipeline corridor to interconnect at a new measurement station at the Koch Mobile Bay Lateral.

In general, the FGT north-south connector will utilize a 100-foot-wide ROW. This includes a 30-foot permanent easement and 70-foot-wide temporary work space. Additionally, 20 feet of the temporary work space will be located within FGT's existing ROW.

FGT is proposing the construction of a single 3,335 horse power, high-speed, reciprocating compressor and associated appurtenances as Compressor Station 44 at station 44 south of Airport Boulevard, west of Mobile. Compressor Station 44 will occupy 4.5 acres of a 6-acre site.

The north-south connector ROW crosses primarily forested and open areas. The proposed work will impact 352.6 acres of which 35.3 acres are wetlands. Of these wetlands 17.9 acres are forested wetlands. 11.5 acres of these forested wetlands will be temporarily impacted by pipeline construction and will be allowed to revegetate back to their original condition within the temporary ROW. However, 6.3 acres of the forested wetlands will be maintained as herbaceous/shrub wetland within 15 feet of the installed pipeline. As mitigation for the replacement of forested wetland with herbaceous/shrub wetland FGT is proposing the enhancement (4:1 ratio) of 25.3 acres at their Dead Lake mitigation site.

A total of 17.3 acres of non-forested wetlands will be impacted by the proposed construction. Of this total, 9.8 acres occur within the temporary ROW and 7.4 acres within the permanent ROW. These herbaceous and shrubby wetlands are expected to return to their previous condition following construction. Approximately 0.02 acre of open water will be crossed by the proposed construction.

The permit, if issued, will be subject to but not limited to the following special conditions:

- a. The permittee will maintain water quality certification by the State of Alabama.
- b. The permittee will comply with the Alabama Oil and Gas Board safeguards, regulations and restrictions.

- c. All spoil material placed in wetlands will be used as backfill in the pipeline trench in order to reestablish pre-project elevations and contours. All organic soils will be stockpiled and maintained for use in wetlands restoration. Excess material will be placed in an approved upland location. Construction equipment used in wetlands will work from mats.
- d. That portion of the proposed pipeline crossing wetlands will be inspected periodically for three years after the right of way has been returned to it original contour and elevation to determine the status of natural revegetation of impacted wetlands. Should a determination be made by the Mobile District that natural revegetation has not been successfully accomplished the permittee will provide, for approval to the Mobile District, a detailed wetland restoration plan that includes replacement ratios, the species and density of plants to be utilized, success criteria, monitoring and remedial measures in case of restoration failure.
- e. Temporary erosion control measures shall be installed in the wetland portion of the on-shore pipeline construction sites and must be maintained until such time as the disturbed wetland is revegetated with native wetland species either through natural processes or attificial planting. All upland areas will be stabilized and planted with vegetation to control erosion.
- f. The permittee will utilize, as required, an impermeable barrier or slurry wall to insure that their proposed construction does not act as a drain and change subsurface hydrology in any of the wetlands crossed. This barrier would be located were the pipeline enters and exits the wetlands.
- g. In the event that cultural resources or artifacts are encountered during pipeline construction, work shall cease and the Alabama Historical Commission and the Mobile District shall be notified immediately.
- h. No discharge of cuttings, drilling mud or any other waste materials shall occur unless authorized by a National Pollution Discharge Elimination System permit pursuant to Section 402 of the Clean Water Act.
- All work will be in accordance with the attached plans provided by the applicant. The applicant's supplemental information and the Federal Energy Regulatory Commission's Final Environmental Impact Statement is available for review at the Mobile District.

The applicant has applied for certification from the State of Alabama in accordance with Section 401(a)(1) of the Clean Water Act, and upon completion of the required advertising, a determination relative to certification will be made.

The applicant has certified that the proposed activity complies with and will be conducted in a manner that is consistent with the State Coastal Zone Management Program. Upon completion of the required advertising, a determination relative to consistency will be made by the Alabama Department of Environmental Management.

This public notice is being distributed to all known interested persons in order to assist in developing facts on which a decision by the U.S. Army Corps of Engineers (Corps) can be based. For accuracy and completeness of the record, all data in support of or in opposition to the proposed work should be submitted in writing setting forth sufficient detail to furnish a clear understanding of the reasons for support or opposition. The decision whether to issue a permit will be based on an evaluation of the probable impact, including cumulative impacts, of the proposed activity on the public interest. That decision will reflect the national concern for both protection and utilization of important resources. benefit which reasonably may be expected to accrue from the proposal must be balanced against its reasonably foreseeable detriments. All factors which may be relevant to the proposal will be considered, including the cumulative effects thereof; among those are conservation, economics, aesthetics, general environmental concerns, wetlands, cultural values, fish and wildlife values, flood hazards, flood plain values, land use, navigation, shoreline erosion and accretion, recreation, water supply and conservation, water quality, energy needs, safety, food production, and in general, the needs and welfare of the people.

The Corps is soliciting comments from the public; Federal, State, and local agencies and officials; Indian Tribes; and other interested parties in order to consider and evaluate the impacts of this proposed activity. Any comments received will be considered by the Corps to determine whether to issue, modify, condition or deny a permit for this proposal. To make this decision, comments are used to assess impacts on endangered species, historic properties, water quality, general environmental effects, and the other public interest factors listed above. Comments are used in the preparation of an Environmental Assessment and/or an Environmental Impact Statement pursuant to the National Environmental Policy Act. Comments are also used to determine the need for a public hearing and to determine the overall public interest of the proposed activity.

CESAM-OP-S PUBLIC NOTICE NO. AL01-02628-F

Any person may request, in writing, within the comment period specified in this notice, that a public hearing be held to consider this application. Requests for public hearings shall state with particularity, the reasons for holding a public hearing.

Evaluation of the probable impacts involving deposits of dredged or fill material into waters of the United States will include the application of guidelines established by the Administrator of the U.S. Environmental Protection Agency.

The National Register of Historic Places has been consulted and no properties listed in or eligible for the National Register are known to exist which would be affected by the proposed work. This review constitutes the full extent of cultural resources investigations unless comment to this notice is received documenting that significant sites or properties exist which may be affected by this work, or that adequately documents that a potential exists for the location of significant sites or properties within the permit area. Copies of this notice are being sent to the U.S. Department of the Interior, National Park Service, Division of Archeological Services.


Preliminary review of this application and the U.S. Department of the Interior List of Endangered and Threatened Wildlife and Plants indicates that the proposed activity will not affect listed endangered or threatened species, or their critical habitat.


Correspondence concerning this Public Notice should refer to Public Notice Number AL01-02628-F and should be directed to the District Engineer, U.S. Army Engineer District, Mobile, Post Office Box 2288, Mobile, Alabama 36628-0001, Attention: Regulatory Branch, with a copy to the Alabama Department of Environmental Management, 4171 Commanders Drive, Mobile, Alabama 36615, in time to be received prior to 05 November 2001.


If you have any questions concerning this publication, you may contact this office, Mr. David J. Schwartz, telephone number (251) 690-3246. Please refer to the above Public Notice number.


MOBILE DISTRICT U.S. Army Corps of Engineers


Enclosures















:




- 1. CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH FGT'S WETLAND AND WATERBODY CONSTRUCTION AND MITIGATION PROCEDURES (APPENDIX C), AND UPLAND EROSION CONTROL, REVEGETATION AND MAINTENANCE PLAN (APPENDIX D).
- 2. CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE FEDERAL, STATE AND LOCAL PERMITS.
- 3. EROSION CONTROL DEVICES TO BE INSTALLED AS NECESSARY.
- 4. WETLAND SOIL CONDITIONS MAY WARRANT USE OF ADDITIONAL 25' OF EXISTING UTILITY CORRIDORS FOR SPOIL STORAGE.

An Enron/El Paso Affiste

Mailland, Florida

FGT PHASE V EXPANSION
WETLAND CROSSING
METHOD 1
(NON-SATURATED)
"DRY"

DRAWN BY	DATE
GLB	4/14/00
SCALE	YEAR
NONE	2000
FILE NAME	P11-1405
DWG. NO.	
*	TYPICAL 1



An Erron/El Paso Affiliate

Moitland, Florida

FGT PHASE V EXPANSION
WETLAND CROSSING
METHOD 2
(FORESTED WETLAND)

TED WETLAND)

DRY


DRAWN BY
GLB
4/14/00


SCALE
NONE
2000

FILE NAME

P11-1406

DWG. NO.





An Enron/El Paso Affiliata

Mailland, Florida

FGT PHASE V EXPANSION
WETLAND CROSSING
METHOD 4
(SATURATED WETLAND)


GLB 4/14/00

SCALE YEAR
NONE 2000

FILE NAME

DWG. NO.

TYPICAL 4




METHOD 5
An Enron/El Paso Affiliato
(SATURATED WETLAND,
Moitiond, Florido
FLOODED)


NONE
FILE NAME


OWG. NO.

. NO. TYPICAL 5

P11-1403







PROFILE TYPICAL OPEN CUT DETAIL

NOTES:

- CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH FGS'S WETLAND AND WATERBODY CONSTRUCTION AND MITIGATION PROCEDURES (APPENDIX C), AND UPLAND EROSION CONTROL, REVEGETATION AND MAINTENANCE PLAN (APPENDIX D).
- 2. CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE FEDERAL, STATE AND LOCAL PERMITS.
- 3. EROSION CONTROL DEVICES AND TURBIDITY BARRIERS TO BE INSTALLED, AS REQUIRED.
- 4. WETLAND SOIL CONDITIONS MAY WARRANT USE OF ADDITIONAL 25' OF EXISTING UTILITY CORRIDORS.

Florida Gas Transmission Company


An Erron/El Paso Affiliate


Mailland, Florida

FGT PHASE V EXPANSION

"OPEN CUT"
WATERBODY CROSSING
CONSTRUCTION METHOD

DRAWN BY GLB	DATE 4/14/00
scale NONE	YEAR 2000
FILE NAME	P11-1400C
DWG. NO.	72/01/01/1






PROFILE YPICAL DAM & PUMP AROUND DETAIL


NOTES:

- CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH FGT'S WETLAND AND WATERBODY CONSTRUCTION AND MITIGATION PROCEDURES (APPENDIX C), AND UPLAND EROSION CONTROL, REVEGETATION AND MAINTENANCE PLAN (APPENDIX D).
- CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE FEDERAL, STATE AND LOCAL PERMITS.
- 3. TOSION CONTROL DEVICES AND TURBIDITY BARRIERS TO BE INSTALLED, AS REQUIRED.
- 4. WETLAND SOIL CONDITIONS MAY WARRANT USE OF ADDITIONAL 25' OF EXISTING UTILITY CORRIDORS.

DATE

Florida Gas	FGT PHASE V EXPANSION	GLB	4/14/00
Transmission		SCALE NONE	YEAR 2000
Company An Encon/El Peso Affiliate	**************************************	FILE NAME	P11-1400A
Moitland, Fl-cida	CONSTRUCTION METHOD	, DWG. NO.	TYPICAL 8





NOTES:

- CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH FGT'S WETLAND AND WATERBODY CONSTRUCTION AND MITIGATION PROCFOURES (APPENDIX C), AND UPLAND EROSION CONTROL, REVEGETATION AND MAINTENANCE PLAN (APPENDIX D).
- 2. CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE FEDERAL, STATE AND LOCAL PERMITS.
- 3. EROSION CONTROL DEVICES AND TURBIDITY BARRIERS TO BE INSTALLED, AS REQUIRED.
- 4. WETLAND SOIL CONDITIONS MAY WARRANT USE OF ADDITIONAL 25' OF EXISTING UTILITY CORRIDORS.

Floride Ges Transmission Company

An Erron/El Paso Afficia


Mailland, Florida


FGT PHASE V EXPANSION

FLUME CROSSING DETAIL

"FLUME"
WATERBODY CROSSING
CONSTRUCTION METHOD

,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		
	DRÁWN BY	DATE
	GLB	4/14/00
	SCALE	YEAR
1	NONE	2000
	FILE NAME	P11-1400B
	DWG. NO.	
		TYPICAL 9





CROSS-SECTION (A-A) (HOT TO SCALE)

Florida Gus Transmission Compuny


An Erron/El Paso Affiliate

FGT PHASE V EXPANSION

DIVERSION TERRACES (SLOPE BREAKERS)

	·	
	DRAWN BY	DATE
	GLB	4/14/00
	SCALE	YEAR
	ЗИОИ	2000
	FILE NAME	P11-1308
1	DWG. NO.	TYPICAL 10

Mailliand, Florida




An Enron/El Paso Afficate


Mailland, Florida

FGT PHASE V EXPANSION

A PROPERLY INSTALLED
STRAW BALE

CONTROL OF A PROPERTY OF THE P				
DRAWN BY	DATE			
GLB	4/14/00			
SCALE	YEAR			
NONE	2000			
FILE NAME				
	P11-1305			
DWG. NO.				






An Erron/El Paso Affiliata


Mailland, Florida

FGT PHASE V EXPANSION

STRAW OR HAY
BALE FILTER

CONTRACTOR OF STREET	THE COURSE CONTRACT CONTRACT AND DESCRIPTIONS
DRAWN BY GLB	DATE 4/14/00
SCALE	YEAR
NONE	2000
FILE NAME	P11-1323
DWG. NO.	
•	TYPICAL 12





An Erron/El Paso Afficate


Moitland, Florida

FGT PHASE V EXPANSION

SILT FENCE INSTALLATION EROSION CONTROL DEVICE

œ.	CONTRACTOR DE LA CONTRA	CONTRACTOR OF THE CONTRACTOR O
	DRÁWN BY	DATE
į	GLB	4/14/00
	SCALE	YEAR
	NONE	2000
ı	FILE NAME	
		P11-1307


DWG. NO.




NOTES:

- 1. SILT FENCE AND/OR ROCK APRON INSTALLATION DETAILS TO DIFFUSE WATER RUNOFF FROM DIP OUTLETS FOR AREAS WITH SPARSE VEGETATION.
- 2. HAY BALES ARE TO BE INSTALLED APPROXIMATELY 120° TO DIRECTION OF FLOW.

E			·	THE PARTY OF THE P
	Florida Gas	FGT PHASE V EXPANSION	DRAWN BY GLB	DATE 4/14/00
4	Transmission Company	0117 55405 440 400	scale NONE	YEAR 2000
1	An Erron/El Paso Affiliate	SILT FENCE AND/OR HAY BALE OUTLET	FILE NAME	P11-1315
	Mailland, Florida	INSTALLATION !-	DWG. NO .	TYPICAL 14





NOTE: ;

1. PLACEMENT OF SILT FENCE WILL VARY TO ACCOMODATE TOPOGRAPHY & SITE CONDITIONS.

Floride Gas
Trunsmission
Company

An Erron/E Paso Affiliate

Moitiond, Florido

FGT PHASE V EXPANSION


SILT SCREEN DETAILS FOR SPOIL PILES


E.T. DESCRIPTION OF THE PROPERTY OF THE PROPER				
DRAWN BY	DATE			
GLB	4/14/00			
SCALE	YEAR			
NONE	2000			

FILE NAME

P11-1314

DWG. NO.






QTES:

- DEWATERING SHALL BE PERFORMED IN ACCORDANCE WITH FGT'S WETLAND AND WATERBODY CONSTRUCTION AND MITIGATION PROCEDURES (APPENDIX C), AND UPLAND EROSION CONTROL, REVEGETATION AND MAINTENANCE PLAN (APPENDIX D).
- 2. DEWATERING SHALL BE PERFORMED IN ACCORDANCE WITH ALL, APPLICABLE FEDERAL, STATE AND LOCAL PERMITS.
- 3. LIMIT ONE DISCHARGE HOSE PER BAG.

	Florida Gas	FGT PHASE V EXPANSION	drawn by GLB	DATE 4/14/00
•	Transmission	7	SCALE NONE	YEAR 2000
	COMPONY An Erron/El Paso Affiliate	FILTER BAG DEWATERING (METHOD 1)	FILE NAME	P11-1322
	Moitland, Florida		DWG. NO.	TYPICAL 16



NOTES:

- 1. DEWATERING SHALL BE PERFORMED IN ACCORDANCE WITH FGT'S WETLAND AND WATERBODY CONSTRUCTION AND MITIGATION PROCEDURES (APPENDIX C), AND UPLAND EROSION CONTROL, REVEGETATION AND MAINTENANCE PLAN (APPENDIX D).
- 2. DEWATERING SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE FEDERAL, STATE AND LOCAL PERMITS.
- 3. LIMIT ONE DISCHARGE HOSE PER BAG.

Florida Gas
Transmission
Company


An Erron/El Paso Afficate

Maitland, Florida

FGT PHASE V EXPANSION

UPLAND TRENCH OR HYDROSTATIC
TEST DEWATERING
(METHOD 1)

	70.75	
	DRAWN BY	DATE
i	GLB	4/14/00
i	SCALE	YEAR
	NONE	2000
	FILE NAME	P11-1003
	DWG. NO.	
		TYPICAL 17



NOTES:

- DEWATERING SHALL BE PERFORMED IN ACCORDANCE WITH FGT'S WETLAND AND WATERBODY CONSTRUCTION AND MITIGATION PROCEDURES (APPENDIX C), AND UPLAND EROSION CONTROL, REVEGETATION AND MAINTENANCE PLAN (APPENDIX D).
- 2. DEWATERING SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE FEDERAL, STATE AND LOCAL PERMITS.
- 3. LIMIT ONE DISCHARGE HOSE PER BAG.
- 4. PRESSURE IS RELEASED INITIALLY THROUGH 1" VALVE.

Florida Gas Transmission
Company


An Errow Pago Affas

Mailtiand, Florida


FGT PHASE V EXPANSION


WATERBODY HYDROSTATIC TEST DEWATERING (METHOD 2)

DRAWN BY GLB	DATE 4/14/00
SCALE NONE	YEAR 2000
FILE NAME	P11-1003A
DWG. NO.	TYPICAL 18



EXAMPLE: 20 SLOPE WOULD REQUIRE SPACING OF 16' IF HEIGHT OF BREAKER IS 6'.





SECTION B-13

NOTES:

- 1. BREAKERS SHALL BE INSTALLED AT SHARP CHANGES OF SLOPE WHERE THE NATURAL DRAINAGE PATTERN, PROFILE WILL CAUSE THE TRENCH TO ACT AS A DRAIN.
- 2. ADJUST SPACING OF BREAKERS SO TOP OF BREAKER IS APPROXIMATELY THE SAME ELEVATION AS BOTTOM OF UPHILL BREAKER, OR AS INDICATED IN TABLE SAME ELEVATION AS BOTTOM OF TO RIGHT (MORE STRINGENT SHALL APPLY).
- 3. COMPANY MAY SPECIFY POLYURETHANE FOAT BREAKERS OR OTHER MATERIALS AS REQUIRED SEE T. CAL DWG. TYPICAL 20.
- 4. WHERE PIPELINE TRENCH WAY DRAIN A WETLAND, CONSTRUCT TRENCH BREAKER MID/OR SEAL TRENCH BOTTOM AS NECESSARY TO MAINTAIN ORIGINAL WETLAND HYDROLOGY.
- 5. FOR EACH WATERBODY CROSSED, INSTALL PERMANENT TRENCH BREAKER AT THE BASE OF SLOPES NEAR THE WATERBODY, LOCATE TRENCH BREAKER UPSLOPE OF THE SLOPE BREAKER.

SLOPE	SPACING
LESS THAN 5%	NO STRUCTURE
5 TO 10%	100 TO 150 FEET
11 TO 15%	BO TO 100 FEET
16 TO 20%	70 to 80 feet
21 TO 30%	50 70 70 FEET
GREATER THAN 30%	25 TO 50 FEET

Florida Gas Transmission Company


An Enron/El Paso Affiliato

Maitland, Florida

FGT. PHASE V EXPANSION


SACK (TRENCH) BREAKERS
REQUIREMENTS

DRAWN BY	DATE
GLB	4/14/00
SCALE	YEAR
NONE	2000
FILE NAME	P11-1317
DWG. NO.	
<u>}</u> .	TYPICAL 19



SECTION "A"-"A"

- 1. POLYUPETHANE DAM SHALL CONFORM TO ALL EMMR. THENTAL REGULATIONS WITH RESPECT TO LONG TERM STABILITY CONCERNING CHEMICAL COMPOSITION.
 - 2. FOAM WITH 2 lbs./cu. II. DENSITY AND 30 psi MINIMUM COMPRESSIVE STRENGTH OR EQUAL SHALL BE USED.
 - IF FORMING REQUIRED, STYROFOAM BOARD CAN BE USED.
 - 4. IN VALLEYS, DRAINAGE AREAS OR AREAS WHERE WATER MAY FLOW ALONG TRENCH AND REMOVE PADDING OR BACKFILL FUDM AROUND THE PIPE ADJUST SPACING OF BREAKERS SO TOP OF BREAKER IS AT APPROXIMATELY THE SAME ELEVATION AS BOTTOM OF UPHILL BREAKER.
 - 5. APPROXIMATE SPACING OF BREAKERS SHALL BE AS SHOWN ON TYPICAL DWG. TYPICAL 19 OR AS DIRECED BY COMPANY INSPECTOR.
 - 6. ALL SAFETY REQUIREMENTS DURING INSTALLATION SHALL BE STRICTLY ENFORCED.
 - WHERE PIPELINE TRENCH MAY DRAIN A WETLAND, CONSTRUCT TRENCH BREAKER AND/OR SEAL TRENCH BOTTOM AS NECESSARY TO MAINTAIN ORIGINAL WETLAND HYDROLOGY.
 - 8. FOR EACH WATERBODY CROSSED, INSTALL PERMANENT TRENCH TRENCH BREAKER AT THE BASE OF SLOPES NEAR THE WATERBOOY, LOCATE TRENCH BREAKER UPSLOPE OF THE SLOPE BREAKER.



APPROXMATE BREAKER SPACING $S = \frac{H}{\sin \theta}$

Florida Gas
Transmission
Company


An Erron/El Paso Affiliate


Mailiand, Florida

FGT PHASE V EXPANSION

POLYURETHANE FOAM TRENCH BREAKER PLACEMENT

DRAWN BY GLB	DATE 4/14/00
SCALE NONE	YEAR 2000
FILE NAME	P11-1318
DWG. NO.	





NOTES:

- 1. RIGHT-OF-WAY TO BE MULCHED AND SEEDED IF REQUESTED PRIOR TO THE INSTALLATION OF MATTING/NETTING.
- 2. MATTING/NETTING SHALL BE RUN HORIZONTAL AND PARALLEL TO THE GROUND CONTOUR.
- 3: STAPLES SHALL BE 10"-LONG, STANDARD MATTING/NETTING STAPLES.
- 4. STAKE EROSION CONTROL MATERIAL (CURLEX, JUTE, DR EQUAL) TO THE SLOPE PER MANUFACTURER'S RECOMMENDATIONS WITH WOOD PEGS OR STAPLES. INSTALL IN DRAINAGE SHALES AS NECESSARY TO HOLD SOIL IN PLACE UNTIL THE VEGETATION IS ESTABLISHED.
- 5. IN ABSENCE OF DETAILED REVEGETATION PLAN, SEED WITH ANNUAL RYE CRASS SEED AT A RATE OF 40 POUNTS/ACRE, PRIOR TO ROLLING OUT EROSION CONTROL, MATERIAL

Florida Gas
Trensmission
Company

An Enron/El Paso Affaite


Moitland, Florida


FGT PHASE V EXPANSION

TYPICAL MATTING/NETTING
INSTALLATION
FOR WATER CROSSINGS

	DRAWN BY	DATE
	GLB	4/14/00
ļ	SCAL!	YEAR
	NONE	2000
-	FILE NAME	D11 1300
-		P11-1309
1	D1110 110	

DWG. NO.





NOTE:

- 1. SIGN IS BLACK LETTERS ON YELLOW BACKGROUND.
- 2. SIGN TO BE PLACED ON WORKING SIDE OF ROW.

Florida Gas
Transmission
Company

An Enron/El Paso Affiliate

Maitland, Florida

FGT PHASE V EXPANSION

TYPICAL (TEMP.)
SIGN FOR WETLAND
BOUNDARIES

3.4	DRAYN BY	DATE
	GLB	4/14/00
	SCALE	YEAR
	NONE	2000
	FILE NAME	P11-405
	DWG ED	

DEPARTMENT OF THE ARMY
U.S. ARMY ENGINEER DISTRICT, MOBILE
P.O. BOX 2288
MOBILE, ALABAMA 36628-0001
OFFICIAL BUSINESS

FIRST-CLASS MAIL U.S. POSTAGE PAID MOBILE, AL PERMIT NO. 283

