



**INDEFINITE DELIVERY INDEFINITE QUANTITY (IDIQ) CONTRACT
FOR RENTAL OF HOPPER DREDGE WITH ATTENDANT PLANT
AND OPERATORS FOR MAINTENANCE DREDGING IN ALABAMA,
MISSISSIPPI, FLORIDA**

SOLICITATION: **W91278-17-B-0002**
AWARD: **W9127817D0092**

“GOOD ENGINEERING RESULTS IN A BETTER ENVIRONMENT”



***U.S. ARMY ENGINEER DISTRICT, MOBILE
109 St. Joseph Street
Mobile, Alabama 36602***

TABLE OF CONTENTS

SECTIONS

00 11 00	Standard Form 1442 - Solicitation, Offer, and Award
00 00 10	Bid Schedule

00600	Representations, Certifications and Other Statements of Offerors
00700	Contract Clauses
00800	Special Contract Requirements

DIVISION 01 – GENERAL REQUIREMENTS & SPECIFICATIONS

01 00 00	Statement of Work Specifications
01 00 01	General Contract Requirements
01 33 00	Submittal Procedures
01 35 26	Governmental Safety Requirements
01 45 00.15 10	Resident Management System Contractor Mode (RMS CM)
01 45 01	USACE Quality Control
01 45 01.10	USACE Quality Control System
01 57 20	Environmental Protection
35 20 23.23	National Dredging Quality Management Program

ATTACHMENTS

Attachment 1	– SAM Form 696 – Contractor Quality Control Report
Attachment 2	– Project Sign Instructions
Attachment 3	– ENG 4025
Attachment 4	– ENG 27A
Attachment 5	– Environmental Appendix

WAGE RATES

Current wage rates will be assigned for each individual task order.

SOLICITATION, OFFER AND AWARD (Construction, Alteration, or Repair)	1. SOLICITATION NO. W91278-17-B-0002	2. TYPE OF SOLICITATION <input checked="" type="checkbox"/> SEALED BID (IFB) <input type="checkbox"/> NEGOTIATED (RFI)	3. DATE ISSUED 03 May 2017	PAGES OF PAGES 1 OF
	IMPORTANT - The "offer" section on the reverse must be fully completed by offeror.			
4. CONTRACT NO. W9127817D0092	5. REQUISITION/PURCHASE REQUEST NO. W31XNJ71790916	6. PROJECT NO.		
7. ISSUED BY CODE	W91278	8. ADDRESS OFFER TO U S ARMY ENGINEER DISTRICT, MOBILE CONTRACTING DIVISION (CESAM-CT) (109 ST. JOSEPH ST. 36602) P.O. BOX 2288 MOBILE, AL 36628-0001		
9. FOR INFORMATION CALL :	A. NAME Nathan J. Fry, Contract Specialist	B. TELEPHONE NO. (Include area code) (NO COLLECT CALLS) (251) 690-2536 nathan.j.fry@usace.army.mil		

SOLICITATION

NOTE: In sealed bid solicitations "offer" and "offeror" mean "bid" and "bidder".

10. THE GOVERNMENT REQUIRES PERFORMANCE OF THE WORK DESCRIBED IN THESE DOCUMENTS (Title, identifying no., date):

Rental of Hopper Dredge with Attendant Plan and Operators for Maintenance Dredging in Alabama, Mississippi and Florida

This is an UNRESTRICTED solicitation.

The guaranteed minimum quantity of work which will be required under this contract and which will be initiated by one or more task orders, will not be less than \$100,000.00 for the 14 month term of the contract.

11. The Contractor shall begin performance within * _____ calendar days and complete it within * _____ calendar days after receiving

☐ award, ☒ notice to proceed. This performance period is: ☒ mandatory, ☐ negotiable. (See *Task Order.)

12A. THE CONTRACTOR MUST FURNISH ANY REQUIRED PERFORMANCE AND PAYMENT BONDS?
(If "YES," indicate within how many calendar days after award in Item 12B.)

☒ YES ☐ NO

12B. CALENDAR DAYS

10

13. ADDITIONAL SOLICITATION REQUIREMENTS:

A. Sealed offers in original and 2 copies to perform the work required are due at the place specified in Item 8 by 14:00 local time ~~06 June 2017~~ ~~06 July 2017~~ 20 June 2017. If this is a sealed bid solicitation, offers must be publicly opened at that time. Sealed envelopes containing offers shall be marked to show the offeror's name and address, the solicitation number, and the date and time offers are due.

B. An offer guarantee ☒ is, ☐ is not required.

C. All offers are subject to the (1) work requirements, and (2) other provisions and clauses incorporated in the solicitation in full text or by reference.

D. Offers providing less than 120 calendar days for Government acceptance after the date offers are due will not be considered and will be rejected.

14. NAME AND ADDRESS OF OFFEROR (Include ZIP Code) The Dutra Group 2350 Kerner Blvd., Suite 200 San Rafael, CA 949401-5595 Duns. #: 05 913 3509 Federal I.D.#: 94-2278920 Cage #: 3GSX7				15. TELEPHONE NO. (Include area code) 415-258-6876 fax: 415-459-3295	
CODE FACILITY CODE				16. REMITTANCE ADDRESS (Include only if different than Item 14)	
17. The offeror agrees to perform the work required at the prices specified below in strict accordance with the terms of this solicitation, if this offer is accepted by the Government in writing within <u>120</u> calendar days after the date offers are due. (Insert any number equal to or greater than the minimum requirement)					
AMOUNTS		See attached schedule			
18. The offeror agrees to furnish any required performance and payment bonds.					
19. ACKNOWLEDGMENT OF AMENDMENTS (The offeror acknowledges receipt of amendments to the solicitation - give number and date of each)					
AMENDMENT NO.	0001	0002	0003		
DATE	5/18/17	6/9/17	6/12/17		
20A. NAME AND TITLE OF PERSON AUTHORIZED TO SIGN OFFER (Type or print) The Dutra Group by: Molly F. Jacoboson, Secretary and General Counsel			20B. SIGNATURE 		20C. OFFER DATE 20 June, 2017
AWARD (To be completed by Government)					
21. ITEMS ACCEPTED:					
* Contractor's Bid Schedule and Rates as attached					
22. AMOUNT NTE \$8,000,000.00			23. ACCOUNTING AND APPROPRIATION DATA 96 NA X 2017 3123 000 0000 CCS: 111 K5 2017 08 2446 011670 96015 2520 5022H7 NA 5022H7 Min Guarantee \$100,000.00		
24. SUBMIT INVOICES TO ADDRESS SHOWN IN (4 copies unless otherwise specified) Per Task Order		ITEM	25. OTHER THAN FULL AND OPEN COMPETITION PURSUANT TO <input type="checkbox"/> 10 U.S.C. 2304(c) () <input type="checkbox"/> 41 U.S.C. 253(c) ()		
26. ADMINISTERED BY CODE W91278 ENDIST Mobile Contracting Division 109 Saint Joseph Street Mobile, AL 36602		27. PAYMENT WILL BE MADE BY W916TX USACE Finance Center - Disbursing Office 5722 Integrity Drive Millington, TN 38054-5005			
CONTRACTING OFFICER WILL COMPLETE ITEM 28 OR 29 AS APPLICABLE					
<input type="checkbox"/> 28. NEGOTIATED AGREEMENT (contractor is required to sign this document and return _____ copies to issuing office.) Contractor agrees to furnish and deliver all items or perform all work, requisitions identified on this form and any continuation sheets for the consideration stated in this contract. The rights and obligations of the parties to this contract shall be governed by (a) this contract award, (b) the solicitation, and (c) the clauses, representations, certifications, and specifications incorporated by reference in or attached to this contract.			<input checked="" type="checkbox"/> 29. AWARD (Contractor is not required to sign this document.) Your offer on this solicitation, is hereby accepted as to the items listed. This award commutes the contract, which consists of (a) the Government solicitation and your offer, and (b) this contract award. No further contractual document is necessary.		
30A. NAME AND TITLE OF CONTRACTOR OR PERSON AUTHORIZED TO SIGN (Type or print)			31A. NAME OF CONTRACTING OFFICER (Type or print) Kyle M. Rodgers Contracting Officer		
30B. SIGNATURE		30C. DATE	31B. UNITED STATES OF AMERICA BY  2017.07.28 16:05:05 -05'00'		31C. AWARD DATE 28 July 2017

Section 00 00 10

BIDDING SCHEDULE

CONTRACTOR NAME: The Dutra Group

Item No.	Description	Estimated Quantity	Unit	Unit Price	Estimated Amount
1.	Mobilization and Demobilization Dredge and Attendant Plant	1	JOB	XXX	<u>100,000⁰⁰</u>
2.	Dredge Pay Time: 100% Pay Time (See chart in section 01 00 00)	<u>2989</u>	HR	<u>1,450⁰⁰</u>	<u>4,334,050⁰⁰</u>
3.	Mobilization and Demobilization Trawler	1	JOB	XXX	<u>4,500⁰⁰</u>
4.	Sea Turtle/Gulf Sturgeon Trawling	<u>6</u>	DAYS	<u>3700⁰⁰</u>	<u>22,200⁰⁰</u>
				TOTAL BID	<u>4,467,050⁰⁰</u>

NOTES

1. Bidders must insert a price on all numbered items of the bidding schedule. Failure to do so will disqualify the bid.
2. All the extensions of the unit price shown will be subject to verification by the Government. In case of variation between the unit price and extension, the unit price will be considered to be the bid.
3. The number of hours/days indicated on the Bidding Schedule is approximate. The Contractor may be required to work either more or less than the number of hours/days specified.
4. For Bid Items No. 1 through No. 4 refer to Section 00 00 10 paragraph entitled BID EVALUATION.

BID EVALUATION

- (1) It is the intent of the Government to secure a dredge, meeting the requirement set

forth in the Statement of Work of the specifications. The Table in the paragraph entitled DREDGE AND ATTENDANT PLANT REQUIREMENTS indicates the estimated average output for dredges of various power based on average theoretical conditions under which this work is to be accomplished. Bids will be evaluated and award will be made on the basis of employment of the plant; which will result in the lowest overall total price, as described hereinafter, to the Government for the equipment. For the purpose of bidding and evaluating bids, it will be considered the dredge will work for the estimated amount of hours in the Table. This is not to be construed by the Contractor that the Government guarantees this number of hours will be worked.

(2) Bidders should insert the appropriate number of hours obtained from the Table found in Paragraph 15 in Section 01 00 00 into Bid Item No. 2. The number of hours listed in the table are identical to the "97% efficiency hours" found in Attachment 1 at the end of Section 01 00 00.

(3) The number of days for Bid Item No. 4 for the dredge bid is obtained by taking the "97% efficiency hours" (Attachment #1) and multiplying by 5% and dividing by 24 hours and round to the nearest whole number. Example using the Newport: $(3708 \times .05)/24 = 7.7$ insert 8 days in Bid Item No. 4. Maximum amount for this bid item is \$5,000.00 per day.

(4) Bids based on dredges smaller or larger than those listed in the Table will be considered non-responsive. Other dredges are considered inadequate for satisfactory performance of work required within the period of the contract.

(5) The Government will check the bidder's computation for accuracy and to insure that the bidder's computation was made in accordance with the above evaluation procedures. In case of variation between the bidder's computation procedures and those prescribed above, the Government will correct the bidder's computation and the bid will be evaluated by the corrected computation.

INFORMATION TO BE SUBMITTED WITH BID: Each bidder shall furnish the information required below by filling in the blank spaces:

GENERAL DREDGE INFORMATION:

Dredge Name: Columbia

Fair Market Value of the Dredge: \$11,000,000

Minimum width of channel in which dredge can successfully operate and turn around (ft): 320

Minimum depth of water in which dredge will operate with hoppers filled (ft): 20

Maximum draft of vessel (ft): 17

Loaded freeboard (ft): 06

Depth range at which dredge can dig, maximum 65 ft., minimum 20 ft.

Total length of dredge (ft): 320

Hopper capacity (cu yds): 4,387

DREDGING PUMPS AND PROPULSION:

Number of pumps one (1) Number of dragarms: one (1)

Pump suction 28 Discharge 24 (I.D. in inches)

Brake HP applied to pump impeller: 1,800

Brake HP applied to propeller: two (2) by 1,500

The dredge may be inspected at: Mobile, AL

ATTENDANT PLANT: Cape Anne

Crewboat size: 42 ft

Total HP: 400 HP

May be inspected at: Mobile, AL

Survey Boat size: 24 ft

Total HP: 200 HP

May be inspected at: Mobile, AL

DREDGE CREW
(A complete listing of positions is required below)

POSITION	NUMBER OF EMPLOYEES IN THIS POSITION
Captain	One (1)
Chief	One (1)
Mate	Two (2)
Assistant Engineer	Two (2)
Drag Tender	Two (2)
A.B.	Two (2)
QMED	Two (2)
Cook	One (1)
Boat Operator	Two (2)

SUBSISTENCE: The plant (x) will () will not have the facilities for furnishing the meals required by the "Accommodations and Meals for Inspectors" clause of the contract.

The rate to be charged for the above plant, complete with full operating personnel and in operating status on a 24-hour day, 7 days per week basis, will be set forth in the bid schedule.

DREDGE PLANT OPERATION: The number of shifts to be worked per day on a 24-hour basis, 7 days per week is Two (2).

BID BOND (See instructions on reverse)	DATE BOND EXECUTED (Must not be later than bid opening date) June 9, 2017	OMB Control Number: 9000-0045 Expiration Date: 7/31/2019
--	---	---

Paperwork Reduction Act Statement - This information collection meets the requirements of 44 USC § 3507, as amended by section 2 of the Paperwork Reduction Act of 1995. You do not need to answer these questions unless we display a valid Office of Management and Budget (OMB) control number. The OMB control number for this collection is 9000-0045. We estimate that it will take 25 minutes to read the instructions, gather the facts, and answer the questions. Send only comments relating to our time estimate, including suggestions for reducing this burden, or any other aspects of this collection of information to: General Services Administration, Regulatory Secretariat Division (M1V1CB), 1600 F Street, NW, Washington, DC 20405.

PRINCIPAL (Legal name and business address) The Dutra Group 2350 Kerner Blvd., Suite #200 San Rafael, CA 94901	TYPE OF ORGANIZATION ("X" one) <input type="checkbox"/> INDIVIDUAL <input type="checkbox"/> PARTNERSHIP <input type="checkbox"/> JOINT VENTURE <input checked="" type="checkbox"/> CORPORATION <input type="checkbox"/> OTHER (Specify) STATE OF INCORPORATION California
--	--

SURETY(IES) (Name and business address)

Liberty Mutual Insurance Company
175 Berkeley Street
Boston, MA 02116

PENAL SUM OF BOND				BID IDENTIFICATION		
PERCENT OF BID PRICE	AMOUNT NOT TO EXCEED				BID DATE	INVITATION NUMBER
	MILLION(S)	THOUSAND(S)	HUNDRED(S)	CENTS	6-20-17	W91278-17-B-0002
20%	*** TWENTY PERCENT ***				FOR (Construction, Supplies or Services)	Construction

OBLIGATION:

We, the Principal and Surety(ies) are firmly bound to the United States of America (hereinafter called the Government) in the above penal sum. For payment of the penal sum, we bind ourselves, our heirs, executors, administrators, and successors, jointly and severally. However, where the Sureties are corporations acting as co-sureties, we, the Sureties, bind ourselves in such sum "jointly and severally" as well as "severally" only for the purpose of allowing a joint action or actions against any or all of us. For all other purposes, each Surety binds itself, jointly and severally with the Principal, for the payment of the sum shown opposite the name of the Surety. If no limit of liability is indicated, the limit of liability is the full amount of the penal sum.

CONDITIONS:

The Principal has submitted the bid identified above.

THEREFORE:

The above obligation is void if the Principal - (a) upon acceptance by the Government of the bid identified above, within the period specified therein for acceptance (sixty (60) days if no period is specified), executes the further contractual documents and gives the bond(s) required by the terms of the bid as accepted within the time specified (ten (10) days if no period is specified) after receipt of the forms by the principal; or (b) in the event of failure to execute such further contractual documents and give such bonds, pays the Government for any cost of procuring the work which exceeds the amount of the bid.

Each Surety executing this instrument agrees that its obligation is not impaired by any extension(s) of the time for acceptance of the bid that the Principal may grant to the Government. Notice to the surety(ies) of extension(s) is waived. However, waiver of the notice applies only to extensions aggregating not more than sixty (60) calendar days in addition to the period originally allowed for acceptance of the bid.

WITNESS:

The Principal and Surety(ies) executed this bid bond and affixed their seals on the above date.

The Dutra Group		PRINCIPAL	
SIGNATURE(S)	1. (Seal)	2. (Seal)	3. (Seal)
NAME(S) & TITLE(S) (Typed)	1. Molly F. Jacobson Secretary & General Counsel	2. Counsel	3.

INDIVIDUAL SURETY(IES)			
SIGNATURE(S)	1. (Seal)	2. (Seal)	3. (Seal)
NAME(S) (Typed)	1. 	2. 	3.

CORPORATE SURETY(IES)				
SURETY A	NAME & ADDRESS	Liberty Mutual Insurance Company 175 Berkeley Street, Boston, MA 02116	STATE OF INCORPORATION Massachusetts	LIABILITY LIMIT (\$) 20% of Bid
	SIGNATURE(S)	1.	2. 	Corporate Seal
	NAME(S) & TITLE(S) (Typed)	1. Jana B. Pilgard Attorney in Fact	2. 	



THIS POWER OF ATTORNEY IS NOT VALID UNLESS IT IS PRINTED ON RED BACKGROUND.

This Power of Attorney limits the acts of those named herein, and they have no authority to bind the Company except in the manner and to the extent herein stated.

Certificate No. 7657004

Liberty Mutual Insurance Company
The Ohio Casualty Insurance Company West American Insurance Company

POWER OF ATTORNEY

KNOWN ALL PERSONS BY THESE PRESENTS: That The Ohio Casualty Insurance Company is a corporation duly organized under the laws of the State of New Hampshire, that Liberty Mutual Insurance Company is a corporation duly organized under the laws of the State of Massachusetts, and West American Insurance Company is a corporation duly organized under the laws of the State of Indiana (herein collectively called the "Companies"), pursuant to and by authority herein set forth, does hereby name, constitute and appoint, Dona Lisa Buschmann; Edward D. Johnson; J. Buschmann; Jana B. Pilgard; Julie A. Shiroma; Karina Palmer; Kathy Rangel; Robert D. Laux; Stephen D. Bender

all of the city of Sacramento, state of CA each individually if there be more than one named, its true and lawful attorney-in-fact to make, execute, seal, acknowledge and deliver, for and on its behalf as surety and as its act and deed, any and all undertakings, bonds, recognizances and other surety obligations, in pursuance of these presents and shall be as binding upon the Companies as if they have been duly signed by the president and attested by the secretary of the Companies in their own proper persons.

IN WITNESS WHEREOF, this Power of Attorney has been subscribed by an authorized officer or official of the Companies and the corporate seals of the Companies have been affixed thereto this 8th day of March, 2017.



STATE OF PENNSYLVANIA SS
COUNTY OF MONTGOMERY

The Ohio Casualty Insurance Company
Liberty Mutual Insurance Company
West American Insurance Company

By: David M. Carey
David M. Carey, Assistant Secretary

On this 8th day of March, 2017, before me personally appeared David M. Carey, who acknowledged himself to be the Assistant Secretary of Liberty Mutual Insurance Company, The Ohio Casualty Company, and West American Insurance Company, and that he, as such, being authorized so to do, execute the foregoing instrument for the purposes therein contained by signing on behalf of the corporations by himself as a duly authorized officer.

IN WITNESS WHEREOF, I have hereunto subscribed my name and affixed my notarial seal at King of Prussia, Pennsylvania, on the day and year first above written.



COMMONWEALTH OF PENNSYLVANIA
Notarial Seal
Teresa Pastella, Notary Public
Upper Merion Twp., Montgomery County
My Commission Expires March 28, 2021
Member, Pennsylvania Association of Notaries

By: Teresa Pastella
Teresa Pastella, Notary Public

This Power of Attorney is made and executed pursuant to and by authority of the following By-laws and Authorizations of The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company which resolutions are now in full force and effect reading as follows:

ARTICLE IV – OFFICERS – Section 12. Power of Attorney. Any officer or other official of the Corporation authorized for that purpose in writing by the Chairman or the President, and subject to such limitation as the Chairman or the President may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Corporation to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact, subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Corporation by their signature and execution of any such instruments and to attach thereto the seal of the Corporation. When so executed, such instruments shall be as binding as if signed by the President and attested to by the Secretary. Any power or authority granted to any representative or attorney-in-fact under the provisions of this article may be revoked at any time by the Board, the Chairman, the President or by the officer or officers granting such power or authority.

ARTICLE XIII – Execution of Contracts – SECTION 5. Surety Bonds and Undertakings. Any officer of the Company authorized for that purpose in writing by the chairman or the president, and subject to such limitations as the chairman or the president may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Company by their signature and execution of any such instruments and to attach thereto the seal of the Company. When so executed such instruments shall be as binding as if signed by the president and attested by the secretary.

Certificate of Designation – The President of the Company, acting pursuant to the Bylaws of the Company, authorizes David M. Carey, Assistant Secretary to appoint such attorneys-in-fact as may be necessary to act on behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations.

Authorization – By unanimous consent of the Company's Board of Directors, the Company consents that facsimile or mechanically reproduced signature of any assistant secretary of the Company, wherever appearing upon a certified copy of any power of attorney issued by the Company in connection with surety bonds, shall be valid and binding upon the Company with the same force and effect as though manually affixed.

I, Renee C. Llewellyn, the undersigned, Assistant Secretary, The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company do hereby certify that the original power of attorney of which the foregoing is a full, true and correct copy of the Power of Attorney executed by said Companies, is in full force and effect and has not been revoked.

IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed the seals of said Companies this 9th day of June, 2017



By: Renee C. Llewellyn
Renee C. Llewellyn, Assistant Secretary

Not valid for mortgage, note, loan, letter of credit, currency rate, interest rate or residual value guarantees.

To confirm the validity of this Power of Attorney call 1-610-832-8240 between 9:00 am and 4:30 pm EST on any business day.

DISCLOSURE OF LOBBYING ACTIVITIES

Complete this form to disclose lobbying activities pursuant to 31 U.S.C. 1352
(See reverse for public burden disclosure.)

Approved by OM
0348 0046

1. Type of Federal Action: <input type="checkbox"/> a. contract <input type="checkbox"/> b. grant <input type="checkbox"/> c. cooperative agreement <input type="checkbox"/> d. loan <input type="checkbox"/> e. loan guarantee <input type="checkbox"/> f. loan insurance		2. Status of Federal Action: <input type="checkbox"/> a. bid/offer/application <input type="checkbox"/> b. initial award <input type="checkbox"/> c. post-award		3. Report Type: <input type="checkbox"/> a. initial filing <input type="checkbox"/> b. material change For Material Change Only: year _____ quarter _____ date of last report _____	
4. Name and Address of Reporting Entity: <input type="checkbox"/> Prime <input type="checkbox"/> Subawardee Tier _____, if known: Congressional District, if known: _____			5. If Reporting Entity in No. 4 is Subawardee, Enter Name and Address of Prime: Congressional District, if known: _____		
6. Federal Department/Agency:			7. Federal Program Name/Description: CFDA Number, if applicable: _____		
8. Federal Action Number, if known:			9. Award Amount, if known: \$ _____		
10. a. Name and Address of Lobbying Entity (if individual, last name, first name, MI): (attach Continuation Sheet(s) SF-LLL-A, if necessary)			b. Individuals Performing Services (including address if different from No. 10a) (last name, first name, MI): (attach Continuation Sheet(s) SF-LLL-A, if necessary)		
11. Amount of Payment (check all that apply): \$ _____ <input type="checkbox"/> actual <input type="checkbox"/> planned			13. Type of Payment (check all that apply): <input type="checkbox"/> a. retainer <input type="checkbox"/> b. one-time fee <input type="checkbox"/> c. commission <input type="checkbox"/> d. contingent fee <input type="checkbox"/> e. deferred <input type="checkbox"/> f. other; specify: _____		
12. Form of Payment (check all that apply): <input type="checkbox"/> a. cash <input type="checkbox"/> b. in-kind; specify: nature _____ value _____					
14. Brief Description of Services Performed or to be Performed and Date(s) of Service, including officer(s), employee(s), or Member(s) contacted, for Payment indicated in Item 11: (attach Continuation Sheet(s) SF-LLL-A, if necessary)					
15. Continuation Sheet(s) SF-LLL-A attached: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No					
16. Information requested through this form is authorized by title 31 U.S.C. section 1352. This disclosure of lobbying activities is a material representation of fact upon which reliance was placed by the tier above when this transaction was made or entered into. This disclosure is required pursuant to 31 U.S.C. 1352. This information will be reported to the Congress semi-annually and will be available for public inspection. Any person who fails to file the required disclosure shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.			Signature: <u>Molly F. Jacobson</u> Print Name: Molly F. Jacobson Title: Secretary and General Counsel Telephone No.: 415.258.6876 Date: 20 June 2017		
Federal Use Only:			Authorized for Local Reproduction Standard Form - LLL		

INSTRUCTIONS FOR COMPLETION OF SF-LLL, DISCLOSURE OF LOBBYING ACTIVITIES

This disclosure form shall be completed by the reporting entity, whether subawardee or prime Federal recipient, at the initiation or receipt of a covered Federal action, or a material change to a previous filing, pursuant to title 31 U.S.C. section 1352. The filing of a form is required for each payment or agreement to make payment to any lobbying entity for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a member of Congress in connection with a covered Federal action. Use the SF-LLL-A Continuation Sheet for additional information if the space on the form is inadequate. Complete all items that apply for both the initial filing and material change report. Refer to the implementing guidance published by the Office of Management and Budget for additional information.

1. Identify the type of covered Federal action for which lobbying activity is and/or has been secured to influence the outcome of a covered Federal action.
2. Identify the status of the covered Federal action.
3. Identify the appropriate classification of this report. If this is a followup report caused by a material change to the information previously reported, enter the year and quarter in which the change occurred. Enter the date of the last previously submitted report by this reporting entity for this covered Federal action.
4. Enter the full name, address, city, state and zip code of the reporting entity. Include Congressional District, if known. Check the appropriate classification of the reporting entity that designates if it is, or expects to be, a prime or subaward recipient. Identify the tier of the subawardee, e.g., the first subawardee of the prime is the 1st tier. Subawards include but are not limited to subcontracts, subgrants and contract awards under grants.
5. If the organization filing the report in item 4 checks "Subawardee", then enter the full name, address, city, state and zip code of the prime Federal recipient. Include Congressional District, if known.
6. Enter the name of the Federal agency making the award or loan commitment. Include at least one organizational level below agency name, if known. For example, Department of Transportation, United States Coast Guard.
7. Enter the Federal program name or description for the covered Federal action (item 1). If known, enter the full Catalog of Federal Domestic Assistance (CFDA) number for grants, cooperative agreements, loans, and loan commitments.
8. Enter the most appropriate Federal identifying number available for the Federal action identified in item 1 (e.g., Request for Proposal (RFP) number; Invitation for Bid (IFB) number; grant announcement number; the contract, grant, or loan award number; the application/proposal control number assigned by the Federal agency). Include prefixes, e.g., "RFP-DE-90-001."
9. For a covered Federal action where there has been an award or loan commitment by the Federal agency, enter the Federal amount of the award/loan commitment for the prime entity identified in item 4 or 5.
10. (a) Enter the full name, address, city, state and zip code of the lobbying entity engaged by the reporting entity identified in item 4 to influence the covered Federal action.
(b) Enter the full names of the individual(s) performing services, and include full address if different from 10 (a). Enter Last Name, First Name, and Middle Initial (MI).
11. Enter the amount of compensation paid or reasonably expected to be paid by the reporting entity (item 4) to the lobbying entity (item 10). Indicate whether the payment has been made (actual) or will be made (planned). Check all boxes that apply. If this is a material change report, enter the cumulative amount of payment made or planned to be made.
12. Check the appropriate box(es). Check all boxes that apply. If payment is made through an in-kind contribution, specify the nature and value of the in-kind payment.
13. Check the appropriate box(es). Check all boxes that apply. If other, specify nature.

Provide a specific and detailed description of the services that the lobbyist has performed, or will be expected to perform, and the date(s) of any services rendered. Include all preparatory and related activity, not just time spent in

Public reporting burden for this collection of information is estimated to average 30 minutes per response, including time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding the burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to the Office of Management and Budget, Paperwork Reduction Project (0348-0046), Washington, D.C. 20503.

DISCLOSURE OF LOBBYING ACTIVITIES
CONTINUATION SHEET

Approved by OM
0348-0046

Reporting Entity: _____ Page _____ of _____

Section 00600

Representations & Certifications

52.204-8 Annual Representations And Certifications (Feb 2016).....	2
52.204-16 Commercial And Government Entity Code Reporting (Jul 2016)	5
52.209-7 Information Regarding Responsibility Matters (July 2013).....	6
252.203-7005 Representation Relating To Compensation Of Former Dod Officials (Nov	8
2011)	8
252.204-7007 Alternate A, Annual Representations And Certifications (Jan 2015).....	8

52.204-8 ANNUAL REPRESENTATIONS AND CERTIFICATIONS (FEB 2016)

(a)(1) The North American Industry Classification System (NAICS) code for this acquisition is 237990.

(2) The small business size standard is \$36,500,000.

(3) The small business size standard for a concern which submits an offer in its own name, other than on a construction or service contract, but which proposes to furnish a product which it did not itself manufacture, is 500 employees.

(b)(1) If the provision at 52.204-7, System for Award Management, is included in this solicitation, paragraph (d) of this provision applies.

(2) If the provision at 52.204-7 is not included in this solicitation, and the offeror is currently registered in System for Award Management (SAM), and has completed the Representations and Certifications section of SAM electronically, the offeror may choose to use paragraph (d) of this provision instead of completing the corresponding individual representations and certifications in the solicitation. The offeror shall indicate which option applies by checking one of the following boxes:

(☒) Paragraph (d) applies.

(☐) Paragraph (d) does not apply and the offeror has completed the individual representations and certifications in the solicitation.

(c) (1) The following representations or certifications in SAM are applicable to this solicitation as indicated:

(i) 52.203-2, Certificate of Independent Price Determination. This provision applies to solicitations when a firm-fixed-price contract or fixed-price contract with economic price adjustment is contemplated, unless—

(A) The acquisition is to be made under the simplified acquisition procedures in Part 13;

(B) The solicitation is a request for technical proposals under two-step sealed bidding procedures; or

(C) The solicitation is for utility services for which rates are set by law or regulation.

(ii) 52.203-11, Certification and Disclosure Regarding Payments to Influence Certain Federal Transactions. This provision applies to solicitations expected to exceed \$150,000.

(iii) 52.204-3, Taxpayer Identification. This provision applies to solicitations that do not include the provision at 52.204-7, System for Award Management.

IDIQ CONTRACT FOR RENTAL OF HOPPER
DREDGE WITH ATTENDANT PLANT AND
OPERATORS FOR MAINTENANCE DREDGING IN
ALABAMA, MISSISSIPPI, FLORIDA

W91278-17-B-0002

(iv) 52.204-5, Women-Owned Business (Other Than Small Business). This provision applies to solicitations that—

(A) Are not set aside for small business concerns;

(B) Exceed the simplified acquisition threshold; and

(C) Are for contracts that will be performed in the United States or its outlying areas.

(v) 52.209-2; Prohibition on Contracting with Inverted Domestic Corporations--Representation.

(vi) 52.209-5; Certification Regarding Responsibility Matters. This provision applies to solicitations where the contract value is expected to exceed the simplified acquisition threshold.

(vii) 52.209-11, Representation by Corporations Regarding Elinquent Tax Liability or a Felony Conviction under any Federal Law. This provision applies to all solicitations.

(viii) 52.214-14, Place of Performance--Sealed Bidding. This provision applies to invitations for bids except those in which the place of performance is specified by the Government.

(ix) 52.215-6, Place of Performance. This provision applies to solicitations unless the place of performance is specified by the Government.

(x) 52.219-1, Small Business Program Representations (Basic & Alternate I). This provision applies to solicitations when the contract will be performed in the United States or its outlying areas.

(A) The basic provision applies when the solicitations are issued by other than DoD, NASA, and the Coast Guard.

(B) The provision with its Alternate I applies to solicitations issued by DoD, NASA, or the Coast Guard.

(xi) 52.219-2, Equal Low Bids. This provision applies to solicitations when contracting by sealed bidding and the contract will be performed in the United States or its outlying areas.

(xii) 52.222-22, Previous Contracts and Compliance Reports. This provision applies to solicitations that include the clause at 52.222-26, Equal Opportunity.

(xiii) 52.222-25, Affirmative Action Compliance. This provision applies to solicitations, other than those for construction, when the solicitation includes the clause at 52.222-26, Equal Opportunity.

(xiv) 52.222-38, Compliance with Veterans' Employment Reporting Requirements. This provision applies to solicitations when it is anticipated the contract award will exceed the simplified acquisition threshold and the contract is not for acquisition of commercial items.

(xv) 52.223-1, Biobased Product Certification. This provision applies to solicitations that require the delivery or specify the use of USDA-designated items; or include the clause at 52.223-2, Affirmative Procurement of Biobased Products Under Service and Construction Contracts.

IDIQ CONTRACT FOR RENTAL OF HOPPER
DREDGE WITH ATTENDANT PLANT AND
OPERATORS FOR MAINTENANCE DREDGING IN
ALABAMA, MISSISSIPPI, FLORIDA

W91278-17-B-0002

(xvi) 52.223-4, Recovered Material Certification. This provision applies to solicitations that are for, or specify the use of, EPA- designated items.

(xvii) 52.225-2, Buy American Certificate. This provision applies to solicitations containing the clause at 52.225-1.

(xviii) 52.225-4, Buy American--Free Trade Agreements--Israeli Trade Act Certificate. (Basic, Alternates I, II, and III.) This provision applies to solicitations containing the clause at 52.225- 3.

(A) If the acquisition value is less than \$25,000, the basic provision applies.

(B) If the acquisition value is \$25,000 or more but is less than \$50,000, the provision with its Alternate I applies.

(C) If the acquisition value is \$50,000 or more but is less than \$77,533, the provision with its Alternate II applies.

(D) If the acquisition value is \$77,533 or more but is less than \$100,000, the provision with its Alternate III applies.

(xix) 52.225-6, Trade Agreements Certificate. This provision applies to solicitations containing the clause at 52.225-5.

(xx) 52.225-20, Prohibition on Conducting Restricted Business Operations in Sudan--Certification. This provision applies to all solicitations.

(xxi) 52.225-25, Prohibition on Contracting with Entities Engaging in Certain Activities or Transactions Relating to Iran--Representation and Certification. This provision applies to all solicitations.

(xxii) 52.226-2, Historically Black College or University and Minority Institution Representation. This provision applies to solicitations for research, studies, supplies, or services of the type normally acquired from higher educational institutions.

(2) The following representations or certifications are applicable as indicated by the Contracting Officer:

[Contracting Officer check as appropriate.]

(i) 52.204-17, Ownership or Control of Offeror.

(ii) 52.222-18, Certification Regarding Knowledge of Child Labor for Listed End Products.

(iii) 52.222-48, Exemption from Application of the Service Contract Labor Standards to Contracts for Maintenance, Calibration, or Repair of Certain Equipment--Certification.

(iv) 52.222-52 Exemption from Application of the Service Contract Labor Standards to Contracts for Certain Services--Certification.

IDIQ CONTRACT FOR RENTAL OF HOPPER
DREDGE WITH ATTENDANT PLANT AND
OPERATORS FOR MAINTENANCE DREDGING IN
ALABAMA, MISSISSIPPI, FLORIDA

W91278-17-B-0002

(v) 52.223-9, with its Alternate I, Estimate of Percentage of Recovered Material Content for EPA-Designated Products (Alternate I only).

(vi) 52.227-6, Royalty Information.

(A) Basic.

(B) Alternate I.

(vii) 52.227-15, Representation of Limited Rights Data and Restricted Computer Software.

(d) The offeror has completed the annual representations and certifications electronically via the SAM website accessed through <https://www.acquisition.gov>. After reviewing the SAM database information, the offeror verifies by submission of the offer that the representations and certifications currently posted electronically that apply to this solicitation as indicated in paragraph (c) of this provision have been entered or updated within the last 12 months, are current, accurate, complete, and applicable to this solicitation (including the business size standard applicable to the NAICS code referenced for this solicitation), as of the date of this offer and are incorporated in this offer by reference (see FAR 4.1201); except for the changes identified below [offeror to insert changes, identifying change by clause number, title, date]. These amended representation(s) and/or certification(s) are also incorporated in this offer and are current, accurate, and complete as of the date of this offer.

FAR Clause	Title	Date	Change
-----PLEASE SEE ATTACHED-----			

Any changes provided by the offeror are applicable to this solicitation only, and do not result in an update to the representations and certifications posted on SAM.

(End of provision)

52.204-16 COMMERCIAL AND GOVERNMENT ENTITY CODE REPORTING (JUL 2016)

(a) Definition. As used in this provision--

Commercial and Government Entity (CAGE) code means—

(1) An identifier assigned to entities located in the United States or its outlying areas by the Defense Logistics Agency (DLA) Commercial and Government Entity (CAGE) Branch to identify a commercial or government entity; or

(2) An identifier assigned by a member of the North Atlantic Treaty Organization (NATO) or by the NATO Support and Procurement Agency (NSPA) to entities located outside the United States and its outlying areas that the DLA Commercial and Government Entity (CAGE) Branch records and maintains in the CAGE master file. This type of code is known as a NATO CAGE (NCAGE) code.

IDIQ CONTRACT FOR RENTAL OF HOPPER
DREDGE WITH ATTENDANT PLANT AND
OPERATORS FOR MAINTENANCE DREDGING IN
ALABAMA, MISSISSIPPI, FLORIDA

W91278-17-B-0002

(b) The Offeror shall enter its CAGE code in its offer with its name and address or otherwise include it prominently in its proposal. The CAGE code entered must be for that name and address. Enter "CAGE" before the number. The CAGE code is required prior to award.

(c) CAGE codes may be obtained via--

(1) Registration in the System for Award Management (SAM) at www.sam.gov. If the Offeror is located in the United States or its outlying areas and does not already have a CAGE code assigned, the DLA Commercial and Government Entity (CAGE) Branch will assign a CAGE code as a part of the SAM registration process. SAM registrants located outside the United States and its outlying areas shall obtain a NCAGE code prior to registration in SAM (see paragraph (c)(3) of this provision).

(2) The DLA Commercial and Government Entity (CAGE) Branch. If registration in SAM is not required for the subject procurement, and the offeror does not otherwise register in SAM, an offeror located in the United States or its outlying areas may request that a CAGE code be assigned by submitting a request at <https://cage.dla.mil>.

(3) The appropriate country codification bureau. Entities located outside the United States and its outlying areas may obtain an NCAGE code by contacting the Codification Bureau in the foreign entity's country if that country is a member of NATO or a sponsored nation. NCAGE codes may be obtained from the NSPA at <https://eportal.nspa.nato.int/AC135Public/scage/CageList.aspx> if the foreign entity's country is not a member of NATO or a sponsored nation. Points of contact for codification bureaus, as well as additional information on obtaining NCAGE codes, are available at <http://www.nato.int/structur/AC/135/main/links/contacts.htm>.

(d) Additional guidance for establishing and maintaining CAGE codes is available at <https://cage.dla.mil>.

(e) When a CAGE Code is required for the immediate owner and/or the highest-level owner by 52.204-17 or 52.212-3(p), the Offeror shall obtain the respective CAGE Code from that entity to supply the CAGE Code to the Government.

(f) Do not delay submission of the offer pending receipt of a CAGE code.

(End of Provision)

52.209-7 INFORMATION REGARDING RESPONSIBILITY MATTERS (JULY 2013)

(a) Definitions. As used in this provision--

Administrative proceeding means a non-judicial process that is adjudicatory in nature in order to make a determination of fault or liability (e.g., Securities and Exchange Commission Administrative Proceedings, Civilian Board of Contract Appeals Proceedings, and Armed Services Board of Contract Appeals Proceedings). This includes administrative proceedings at the Federal and State level but only in connection with performance of a Federal contract or grant. It does not include agency actions such as contract audits, site visits, corrective plans, or inspection of deliverables.

Federal contracts and grants with total value greater than \$10,000,000 means--

IDIQ CONTRACT FOR RENTAL OF HOPPER
DREDGE WITH ATTENDANT PLANT AND
OPERATORS FOR MAINTENANCE DREDGING IN
ALABAMA, MISSISSIPPI, FLORIDA

W91278-17-B-0002

(1) The total value of all current, active contracts and grants, including all priced options; and

(2) The total value of all current, active orders including all priced options under indefinite-delivery, indefinite-quantity, 8(a), or requirements contracts (including task and delivery and multiple-award Schedules).

Principal means an officer, director, owner, partner, or a person having primary management or supervisory responsibilities within a business entity (e.g., general manager; plant manager; head of a division or business segment; and similar positions).

(b) The offeror (☒) has (☐) does not have current active Federal contracts and grants with total value greater than \$10,000,000.

(c) If the offeror checked "has" in paragraph (b) of this provision, the offeror represents, by submission of this offer, that the information it has entered in the Federal Awardee Performance and Integrity Information System (FAPIS) is current, accurate, and complete as of the date of submission of this offer with regard to the following information:

(1) Whether the offeror, and/or any of its principals, has or has not, within the last five years, in connection with the award to or performance by the offeror of a Federal contract or grant, been the subject of a proceeding, at the Federal or State level that resulted in any of the following dispositions:

(i) In a criminal proceeding, a conviction.

(ii) In a civil proceeding, a finding of fault and liability that results in the payment of a monetary fine, penalty, reimbursement, restitution, or damages of \$5,000 or more.

(iii) In an administrative proceeding, a finding of fault and liability that results in--

(A) The payment of a monetary fine or penalty of \$5,000 or more; or

(B) The payment of a reimbursement, restitution, or damages in excess of \$100,000.

(iv) In a criminal, civil, or administrative proceeding, a disposition of the matter by consent or compromise with an acknowledgment of fault by the Contractor if the proceeding could have led to any of the outcomes specified in paragraphs (c)(1)(i), (c)(1)(ii), or (c)(1)(iii) of this provision.

(2) If the offeror has been involved in the last five years in any of the occurrences listed in (c)(1) of this provision, whether the offeror has provided the requested information with regard to each occurrence.

(d) The offeror shall post the information in paragraphs (c)(1)(i) through (c)(1)(iv) of this provision in FAPIS as required through maintaining an active registration in the System for Award Management database via <https://www.acquisition.gov> (see 52.204-7).

(End of provision)

IDIQ CONTRACT FOR RENTAL OF HOPPER
DREDGE WITH ATTENDANT PLANT AND
OPERATORS FOR MAINTENANCE DREDGING IN
ALABAMA, MISSISSIPPI, FLORIDA

W91278-17-B-0002

252.203-7005 REPRESENTATION RELATING TO COMPENSATION OF FORMER DOD
OFFICIALS (NOV

2011)

(a) Definition. Covered DoD official is defined in the clause at 252.203-7000, Requirements Relating to Compensation of Former DoD Officials.

(b) By submission of this offer, the offeror represents, to the best of its knowledge and belief, that all covered DoD officials employed by or otherwise receiving compensation from the offeror, and who are expected to undertake activities on behalf of the offeror for any resulting contract, are presently in compliance with all post-employment restrictions covered by 18 U.S.C. 207, 41 U.S.C. 2101-2107, and 5 CFR parts 2637 and 2641, including Federal Acquisition Regulation 3.104-2.

(End of provision)

252.204-7007 ALTERNATE A. ANNUAL REPRESENTATIONS AND CERTIFICATIONS (JAN
2015)

Substitute the following paragraphs (d) and (e) for paragraph (d) of the provision at FAR 52.204-8:

(d)(1) The following representations or certifications in the System for Award Management (SAM) database are applicable to this solicitation as indicated:

(i) 252.209-7003, Reserve Officer Training Corps and Military Recruiting on Campus--Representation. Applies to all solicitations with institutions of higher education.

(ii) 252.216-7008, Economic Price Adjustment--Wage Rates or Material Prices Controlled by a Foreign Government. Applies to solicitations for fixed-price supply and service contracts when the contract is to be performed wholly or in part in a foreign country, and a foreign government controls wage rates or material prices and may during contract performance impose a mandatory change in wages or prices of materials.

(iii) 252.222-7007, Representation Regarding Combating Trafficking in Persons, as prescribed in 222.1771. Applies to solicitations with a value expected to exceed the simplified acquisition threshold.

(iv) 252.225-7042, Authorization to Perform. Applies to all solicitations when performance will be wholly or in part in a foreign country.

(v) 252.225-7049, Prohibition on Acquisition of Commercial Satellite Services from Certain Foreign Entities--Representations. Applies to solicitations for the acquisition of commercial satellite services.

(vi) 252.225-7050, Disclosure of Ownership or Control by the Government of a Country that is a State Sponsor of Terrorism. Applies to all solicitations expected to result in contracts of \$150,000 or more.

IDIQ CONTRACT FOR RENTAL OF HOPPER
DREDGE WITH ATTENDANT PLANT AND
OPERATORS FOR MAINTENANCE DREDGING IN
ALABAMA, MISSISSIPPI, FLORIDA

W91278-17-B-0002

(vii) 252.229-7012, Tax Exemptions (Italy)--Representation. Applies to solicitations when contract performance will be in Italy.

(viii) 252.229-7013, Tax Exemptions (Spain)--Representation. Applies to solicitations when contract performance will be in Spain.

(ix) 252.247-7022, Representation of Extent of Transportation by Sea. Applies to all solicitations except those for direct purchase of ocean transportation services or those with an anticipated value at or below the simplified acquisition threshold.

(2) The following representations or certifications in SAM are applicable to this solicitation as indicated by the Contracting Officer: [Contracting Officer check as appropriate.]

____ (i) 252.209-7002, Disclosure of Ownership or Control by a Foreign Government.

____ (ii) 252.225-7000, Buy American--Balance of Payments Program Certificate.

____ (iii) 252.225-7020, Trade Agreements Certificate.

____ Use with Alternate I.

____ (iv) 252.225-7031, Secondary Arab Boycott of Israel.

____ (v) 252.225-7035, Buy American--Free Trade Agreements--Balance of Payments Program Certificate.

____ Use with Alternate I.

____ Use with Alternate II.

____ Use with Alternate III.

____ Use with Alternate IV.

____ Use with Alternate V.

(e) The offeror has completed the annual representations and certifications electronically via the SAM Web site at <https://www.acquisition.gov/>. After reviewing the SAM database information, the offeror verifies by submission of the offer that the representations and certifications currently posted electronically that apply to this solicitation as indicated in FAR 52.204-8(c) and paragraph (d) of this provision have been entered or updated within the last 12 months, are current, accurate, complete, and applicable to this solicitation (including the business size standard applicable to the NAICS code referenced for this solicitation), as of the date of this offer, and are incorporated in this offer by reference (see FAR 4.1201); except for the changes identified below ____ [offeror to insert changes, identifying change by provision number, title, date]. These amended representation(s) and/or certification(s) are also incorporated in this offer and are current, accurate, and complete as of the date of this offer.

FAR/DFARS Clause	Title	Date	Change
------------------	-------	------	--------

IDIQ CONTRACT FOR RENTAL OF HOPPER
DREDGE WITH ATTENDANT PLANT AND
OPERATORS FOR MAINTENANCE DREDGING IN
ALABAMA, MISSISSIPPI, FLORIDA

W91278-17-B-0002

#			
PLEASE SEE ATTACHED			

Any changes provided by the offeror are applicable to this solicitation only, and do not result in an update to the representations and certifications located in the SAM database.

(End of provision)




FAR 52.204-8 (d): The offeror has completed the annual representations and certifications electronically via the SAM website accessed through <https://www.acquisition.gov>. After reviewing the SAM database information, the offeror verifies by submission of the offer that the representations and certifications currently posted electronically that apply to this solicitation as indicated in paragraph (c) of this provision have been entered or updated within the last 12 months, are current, accurate, complete, and applicable to this solicitation (including the business size standard applicable to the NAICS code referenced for this solicitation), as of the date of this offer and are incorporated in this offer by reference (see FAR 4.1201); except for the changes identified below [offeror to insert changes, identifying change by clause number, title, date]. These amended representation(s) and/or certification(s) are also incorporated in this offer and are current, accurate, and complete as of the date of this offer.

FAR CLAUSE #	TITLE	DATE	CHANGE
52.219-1(a) Representation	Small Business Program Representations (Alternate I), (b) (1)	4/16/2013-present	As follows
<p><u>From:</u> The offeror represents and certifies as part of its offer that it <input checked="" type="checkbox"/> is, <input type="checkbox"/> is not a small business concern and that <input type="checkbox"/> all, <input type="checkbox"/> not all end items to be furnished will be manufactured or produced by a small business concern in the United States, its territories or possessions, Puerto Rico or the Trust Territory of the Pacific Islands.</p> <p><u>To:</u> The offeror represents and certifies as part of its offer that it <input type="checkbox"/> is, <input checked="" type="checkbox"/> is not a small business concern and that <input type="checkbox"/> all, <input type="checkbox"/> not all end items to be furnished will be manufactured or produced by a small business concern in the United States, its territories or possessions, Puerto Rico or the Trust Territory of the Pacific Islands.</p>			

Any changes provided by the offeror are applicable to this solicitation only, and do not result in an update to the representations and certifications posted on SAM.gov.

(End of provision)

The Dutra Group does not claim to be a small business and has repeatedly contacted SAM personnel to correct this mistaken representation, which we have been told was caused during the data migration from ORCA/CCR to SAM. Despite our repeated efforts, SAM personnel have not yet been able to correct the underlying problem preventing this modification.


Molly F. Jacobson, Secretary and General Counsel
The Dutra Group
2350 Kerner Boulevard, Suite 200
San Rafael, CA 94901-5595
(415) 258-6876

Duns #: 059133509
Federal I.D. #: 94-2278920
Cage Code: 3GSX7

Section 00700

Contract Clauses

52.202-1	Definitions (Nov 2013).....	6
52.203-3	Gratuities (Apr 1984).....	6
52.203-5	Covenant Against Contingent Fees (May 2014).....	6
52.203-6	Restrictions On Subcontractor Sales To The Government (Sep 2006)	7
52.203-7	Anti-Kickback Procedures. (May 2014).....	7
52.203-8	Cancellation, Rescission, And Recovery Of Funds For Illegal Or Improper Activity (May 2014)	8
52.203-10	Price Or Fee Adjustment For Illegal Or Improper Activity (May 2014).....	9
52.203-12	Limitation On Payments To Influence Certain Federal Transactions (Oct 2010)	10
52.203-13	Contractor Code Of Business Ethics And Conduct (Oct 2015).....	13
52.203-14	Display Of Hotline Poster(S) (Oct 2015)	16
52.203-17	Contractor Employee Whistleblower Rights And Requirement To Inform Employees Of Whistleblower Rights (Apr 2014).....	17
52.204-4	Printed Or Copied Double-Sided On Postconsumer Fiber Content Paper (May 2011).....	17
52.204-7	System For Award Management (July 2013).....	18
52.204-9	Personal Identity Verification Of Contractor Personnel (Jan 2011).....	19
52.204-10	Reporting Executive Compensation And First-Tier Subcontract Awards (Oct 2015)	20
52.204-13	System For Award Management Maintenance (July 2013)	22
52.204-18	Commercial And Government Entity Code Maintenance.....	24
52.204-19	– Incorporation By Reference Of Representations And Certifications.	25
52.204-21	– Basic Safeguarding Of Covered Contractor Information Systems.	25
52.209-6	Protecting The Government's Interest When Subcontracting With Contractors Debarred, Suspended, Or Proposed For Debarment (Oct 2015).....	26
52.209-9	– Updates Of Publicly Available Information Regarding Responsibility Matters.	27
52.209-10	Prohibition On Contracting With Inverted Domestic Corporations. (Nov 2015).....	28
52.210-1	Market Research (Apr 2011)	29
52.211-10	Commencement, Prosecution, And Completion Of Work (Apr 1984)	29
52.211-12	Liquidated Damages--Construction (Sep 2000)	29
52.211-13	Time Extensions (Sep 2000).....	30
52.214-26	-- Audit And Records -- Sealed Bidding.	30

52.214-27	Price Reduction For Defective Certified Cost Or Pricing Data - Modifications - Sealed Bidding. (Aug 2011)	31
52.214-28	Subcontractor Certified Cost Or Pricing Data - Modifications - Sealed Bidding. (Oct 2010)	32
52.216-19	Order Limitations. (Oct 1995)	33
52.216-22	Indefinite Quantity. (Oct 1995)	33
52.216-24	Limitation Of Government Liability (Apr 1984).....	34
52.219-4	Notice Of Price Evaluation Preference For Hubzone Small Business Concerns (Oct 2014) .	34
52.219-8	Utilization Of Small Business Concerns (Oct 2014)	36
52.219-9	Small Business Subcontracting Plan (Jan 2017)--Alternate I (Nov 2016).	37
52.219-16	Liquidated Damages-Subcontracting Plan (Jan 1999).....	45
52.219-28	Post-Award Small Business Program Rerepresentation (July 2013).....	46
52.222-1	Notice To The Government Of Labor Disputes (Feb 1997).....	47
52.222-3	Convict Labor (Jun 2003).....	48
52.222-4	Contract Work Hours And Safety Standards - Overtime Compensation. (May 2014).....	48
52.222-6	Construction Wage Rate Requirements (May 2014).....	49
52.222-7	Withholding Of Funds (May 2014)	51
52.222-8	Payrolls And Basic Records (May 2014)	52
52.222-9	Apprentices And Trainees (Jul 2005)	53
52.222-10	Compliance With Copeland Act Requirements (Feb 1988)	54
52.222-11	Subcontracts (Labor Standards) (May 2014).....	54
52.222-12	Contract Termination--Debarment (May 2014)	56
52.222-13	Compliance With Construction Wage Rate Requirements And Related Regulations (May 2014)	56
52.222-14	Disputes Concerning Labor Standards (Feb 1988).....	56
52.222-15	Certification Of Eligibility (May 2014).....	56
52.222-17	Nondisplacement Of Qualified Workers (May 2014)	57
52.222-21	Prohibition Of Segregated Facilities (Apr 2015).....	60
52.222-26	Equal Opportunity (Apr 2015).....	60
52.222-27	Affirmative Action Compliance Requirements For Construction (Apr 2015)	62
52.222-35	Equal Opportunity For Veterans (Oct 2015)	66
52.222-36	Equal Opportunity For Workers With Disabilities (Jul 2014).....	66
52.222-37	Employment Reports On Veterans (Feb 2016).....	67
52.222-40	Notification Of Employee Rights Under The National Labor Relations Act (Dec 2010).....	68
52.222-50	Combating Trafficking In Persons (Mar 2015)	69

52.222-54 – Employment Eligibility Verification.	75
52.222-55 Minimum Wages Under Executive Order 13658 (Dec 2015)	77
52.222-62 Paid Sick Leave Under Executive Order 13706 (Jan 2017)	80
52.223-2 Affirmative Procurement Of Biobased Products Under Service And Construction Contracts (Deviation) (Sep 2013)	85
52.223-5 -- Pollution Prevention And Right-To-Know Information.	86
52.223-6 Drug-Free Workplace (May 2001)	86
52.223-15 – Energy Efficiency In Energy-Consuming Products.....	88
52.223-17 – Affirmative Procurement Of Epa-Designated Items In Service And Construction Contracts.	88
52.223-18 Encouraging Contractor Policies To Ban Text Messaging While Driving (Aug 2011)	89
52.225-9 -- Buy American--Construction Materials.....	89
52.225-12 Notice Of Buy American Requirement-- Construction Materials Under Trade Agreements (May 2014)	93
52.225-13 Restrictions On Certain Foreign Purchases (Jun 2008)	93
52.226-1 Utilization Of Indian Organizations And Indian-Owned Economic Enterprises (Jun 2000) ..	94
52.227-2 Notice And Assistance Regarding Patent And Copyright Infringement (Dec 2007)	95
52.227-4 Patent Indemnity--Construction Contracts (Dec 2007)	96
52.228-1 Bid Guarantee (Sep 1996)	96
52.228-2 Additional Bond Security (Oct 1997).....	96
52.228-5 Insurance--Work On A Government Installation (Jan 1997)	97
52.228-11 Pledges Of Assets (Jan 2012)	97
52.228-12 Prospective Subcontractor Requests For Bonds. (May 2014)	98
52.228-15 Performance And Payment Bonds--Construction (Oct 2010)	101
52.229-3 Federal, State, And Local Taxes (Feb 2013)	102
52.232-5 Payments Under Fixed-Price Construction Contracts (May 2014)	103
52.232-13 Notice Of Progress Payments (Apr 1984)	106
52.232-16 Progress Payments (Apr 2012)	106
52.232-17 Interest (May 2014)	111
52.232-23 Assignment Of Claims (May 2014).....	112
52.232-27 Prompt Payment For Construction Contracts (May 2014)	113
52.232-33 Payment By Electronic Funds Transfer—System For Award Management (July 2013)...	119
52.232-39 Unenforceability Of Unauthorized Obligations (Jun 2013).....	120
52.232-40 Providing Accelerated Payments To Small Business Subcontractors (Dec 2013)	121
52.233-1 Disputes. (May 2014) -- Alternate I (Dec 1991)	121

52.233-3	Protest After Award (Aug. 1996)	122
52.233-4	Applicable Law For Breach Of Contract Claim (Oct 2004).....	123
52.236-1	Performance Of Work By The Contractor (Apr 1984).....	123
52.236-2	Differing Site Conditions (Apr 1984).....	123
52.236-3	Site Investigation And Conditions Affecting The Work (Apr 1984)	124
52.236-4	Physical Data (Apr 1984)	124
52.236-5	Material And Workmanship (Apr 1984)	125
52.236-6	Superintendence By The Contractor (Apr 1984).....	125
52.236-7	Permits And Responsibilities (Nov 1991)	125
52.236-8	Other Contracts (Apr 1984).....	126
52.236-9	Protection Of Existing Vegetation, Structures, Equipment, Utilities, And Improvements (Apr 1984)	126
52.236-10	Operations And Storage Areas (Apr 1984).....	126
52.236-11	Use And Possession Prior To Completion (Apr 1984).....	127
52.236-12	Cleaning Up (Apr 1984)	127
52.236-13	Accident Prevention (Nov 1991)	127
52.236-15	Schedules For Construction Contracts (Apr 1984).....	128
52.236-21	Specifications And Drawings For Construction (Feb 1997).....	129
52.242-13	Bankruptcy (Jul 1995)	130
52.242-14	Suspension Of Work (Apr 1984).....	130
52.243-4	Changes (Jun 2007)	130
52.244-6	Subcontracts For Commercial Items (Feb 2016).....	131
52.246-12	Inspection Of Construction (Aug 1996)	133
52.247-63	Preference For U.S.-Flag Air Carriers (Jun 2003).....	134
52.248-3	Value Engineering--Construction (Oct 2015).....	135
52.249-2	Termination For Convenience Of The Government (Fixed-Price) (Apr 2012).....	137
52.249-10	Default (Fixed-Price Construction) (Apr 1984).....	140
52.253-1	Computer Generated Forms (Jan 1991).....	141
252.201-7000	Contracting Officer's Representative (Dec 1991)	142
252.203-7000	Requirements Relating To Compensation Of Former Dod Officials (Sep 2011).....	142
252.203-7001	Prohibition On Persons Convicted Of Fraud Or Other Defense-Contract-Related Felonies (Dec 2008).....	143
252.203-7002	Requirement To Inform Employees Of Whistleblower Rights (Sep 2013).....	144
252.203-7003	Agency Office Of The Inspector General (Dec 2012).....	144
252.204-7000	Disclosure Of Information.	144

252.204-7003	Control Of Government Personnel Work Product (Apr 1992).....	145
252.204-7009	Limitations On The Use Or Disclosure Of Third-Party Contractor Reported Cyber Incident Information.	145
252.204-7012	Safeguarding Covered Defense Information And Cyber Incident Reporting (Dec 2015)	147
252.204-7015	Notice Of Authorized Disclosure Of Information For Litigation Support.	151
252.205-7000	Provision Of Information To Cooperative Agreement Holders (Dec 1991)	151
252.209-7004	Subcontracting With Firms That Are Owned Or Controlled By The Government Of A Country That Is A State Sponsor Of Terrorism (Oct 2015).....	152
252.219-7003	Small Business Subcontracting Plan (Dod Contracts) (Oct 2014)	153
252.222-7006	Restrictions On The Use Of Mandatory Arbitration Agreements (Dec 2010)	154
252.223-7004	Drug-Free Work Force (Sep 1988).....	155
252.223-7006	Prohibition On Storage, Treatment, And Disposal Of Toxic Or Hazardous Materials-- Basic (Sep 2014).....	156
252.223-7008	Prohibition Of Hexavalent Chromium (Jun 2013)	156
252.225-7012	Preference For Certain Domestic Commodities (Feb 2013).....	157
252.225-7048	Export-Controlled Items (June 2013)	160
252.227-7000	Non-Estoppel. (Oct 1966).....	160
252.232-7003	Electronic Submission Of Payment Requests And Receiving Reports.	161
252.232-7010	Levies On Contract Payments (Dec 2006)	161
252.236-7000	Modification Proposals - Price Breakdown. (Dec 1991).....	162
252.236-7001	Contract Drawings And Specifications (Aug 2000).....	163
252.236-7002	Obstruction Of Navigable Waterways. (Dec 1991).....	163
252.236-7004	Payment For Mobilization And Demobilization (Dec 1991)	164
252.236-7008	Contract Prices - Bidding Schedules. (Dec 1991)	164
252.242-7004	Material Management And Accounting System (May 2011).....	164
252.242-7005	Contractor Business Systems.....	167
252.242-7006	Accounting System Administration (Feb 2012)	170
252.243-7001	Pricing Of Contract Modifications (Dec 1991)	172
252.243-7002	Requests For Equitable Adjustment (Dec 2012)	172
252.244-7000	Subcontracts For Commercial Items (Jun 2013)	173
252.247-7023	Transportation Of Supplies By Sea (Apr 2014).....	173
252.247-7024	Notification Of Transportation Of Supplies By Sea (Mar 2000).....	176

52.202-1 DEFINITIONS (NOV 2013)

When a solicitation provision or contract clause uses a word or term that is defined in the Federal Acquisition Regulation (FAR), the word or term has the same meaning as the definition in FAR 2.101 in effect at the time the solicitation was issued, unless--

- (a) The solicitation, or amended solicitation, provides a different definition;
- (b) The contracting parties agree to a different definition;
- (c) The part, subpart, or section of the FAR where the provision or clause is prescribed provides a different meaning;
or
- (d) The word or term is defined in FAR Part 31, for use in the cost principles and procedures.

(End of clause)

52.203-3 GRATUITIES (APR 1984)

(a) The right of the Contractor to proceed may be terminated by written notice if, after notice and hearing, the agency head or a designee determines that the Contractor, its agent, or another representative--

(1) Offered or gave a gratuity (e.g., an entertainment or gift) to an officer, official, or employee of the Government;
and

(2) Intended, by the gratuity, to obtain a contract or favorable treatment under a contract.

(b) The facts supporting this determination may be reviewed by any court having lawful jurisdiction.

(c) If this contract is terminated under paragraph (a) of this clause, the Government is entitled--

(1) To pursue the same remedies as in a breach of the contract; and

(2) In addition to any other damages provided by law, to exemplary damages of not less than 3 nor more than 10 times the cost incurred by the Contractor in giving gratuities to the person concerned, as determined by the agency head or a designee. (This subparagraph (c) (2) is applicable only if this contract uses money appropriated to the Department of Defense.)

(d) The rights and remedies of the Government provided in this clause shall not be exclusive and are in addition to any other rights and remedies provided by law or under this contract.

(End of clause)

52.203-5 COVENANT AGAINST CONTINGENT FEES (MAY 2014)

(a) The Contractor warrants that no person or agency has been employed or retained to solicit or obtain this contract upon an agreement or understanding for a contingent fee, except a bona fide employee or agency. For breach or violation of this warranty, the Government shall have the right to annul this contract without liability or, to deduct from the contract price or consideration, or otherwise recover, the full amount of the contingent fee.

(b) "Bona fide agency," as used in this clause, means an established commercial or selling agency, maintained by a

contractor for the purpose of securing business, that neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds itself out as being able to obtain any Government contract or contracts through improper influence.

"Bona fide employee," as used in this clause, means a person, employed by a contractor and subject to the contractor's supervision and control as to time, place, and manner of performance, who neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds out as being able to obtain any Government contract or contracts through improper influence.

"Contingent fee," as used in this clause, means any commission, percentage, brokerage, or other fee that is contingent upon the success that a person or concern has in securing a Government contract.

"Improper influence," as used in this clause, means any influence that induces or tends to induce a Government employee or officer to give consideration or to act regarding a Government contract on any basis other than the merits of the matter.

(End of clause)

52.203-6 RESTRICTIONS ON SUBCONTRACTOR SALES TO THE GOVERNMENT (SEP 2006)

(a) Except as provided in (b) of this clause, the Contractor shall not enter into any agreement with an actual or prospective subcontractor, nor otherwise act in any manner, which has or may have the effect of restricting sales by such subcontractors directly to the Government of any item or process (including computer software) made or furnished by the subcontractor under this contract or under any follow-on production contract.

(b) The prohibition in (a) of this clause does not preclude the Contractor from asserting rights that are otherwise authorized by law or regulation.

(c) The Contractor agrees to incorporate the substance of this clause, including this paragraph (c), in all subcontracts under this contract which exceed the simplified acquisition threshold.

52.203-7 Anti-Kickback Procedures. (MAY 2014)

(a) Definitions.

"Kickback," as used in this clause, means any money, fee, commission, credit, gift, gratuity, thing of value, or compensation of any kind which is provided to any prime Contractor, prime Contractor employee, subcontractor, or subcontractor employee for the purpose of improperly obtaining or rewarding favorable treatment in connection with a prime contractor in connection with a subcontract relating to a prime contract.

"Person," as used in this clause, means a corporation, partnership, business association of any kind, trust, joint-stock company, or individual.

"Prime contract," as used in this clause, means a contract or contractual action entered into by the United States for the purpose of obtaining supplies, materials, equipment, or services of any kind.

"Prime Contractor," as used in this clause, means a person who has entered into a prime contract with the United States.

"Prime Contractor employee," as used in this clause, means any officer, partner, employee, or agent of a prime Contractor.

"Subcontract," as used in this clause, means a contract or contractual action entered into by a prime Contractor or subcontractor for the purpose of obtaining supplies, materials, equipment, or services of any kind under a prime contract.

"Subcontractor," as used in this clause, (1) means any person, other than the prime Contractor, who offers to furnish or furnishes any supplies, materials, equipment, or services of any kind under a prime contract or a subcontract entered into in connection with such prime contract, and (2) includes any person who offers to furnish or furnishes general supplies to the prime Contractor or a higher tier subcontractor.

"Subcontractor employee," as used in this clause, means any officer, partner, employee, or agent of a subcontractor.

(b) 41 U.S.C. chapter 87, Kickbacks, prohibits any person from--

(1) Providing or attempting to provide or offering to provide any kickback;

(2) Soliciting, accepting, or attempting to accept any kickback; or

(3) Including, directly or indirectly, the amount of any kickback in the contract price charged by a prime Contractor to the United States or in the contract price charged by a subcontractor to a prime Contractor or higher tier subcontractor.

(c)(1) The Contractor shall have in place and follow reasonable procedures designed to prevent and detect possible violations described in paragraph (b) of this clause in its own operations and direct business relationships.

(2) When the Contractor has reasonable grounds to believe that a violation described in paragraph (b) of this clause may have occurred, the Contractor shall promptly report in writing the possible violation. Such reports shall be made to the inspector general of the contracting agency, the head of the contracting agency if the agency does not have an inspector general, or the Attorney General.

(3) The Contractor shall cooperate fully with any Federal agency investigating a possible violation described in paragraph (b) of this clause.

(4) The Contracting Officer may (i) offset the amount of the kickback against any monies owed by the United States under the prime contract and/or (ii) direct that the Prime Contractor withhold, from sums owed a subcontractor under the prime contract, the amount of any kickback. The Contracting Officer may order the monies withheld under subdivision (c)(4)(ii) of this clause be paid over to the Government unless the Government has already offset those monies under subdivision (c)(4)(i) of this clause. In either case, the Prime Contractor shall notify the Contracting Officer when the monies are withheld.

(5) The Contractor agrees to incorporate the substance of this clause, including this subparagraph (c)(5) but excepting subparagraph (c)(1), in all subcontracts under this contract which exceed \$150,000.

52.203-8 CANCELLATION, RESCISSION, AND RECOVERY OF FUNDS FOR ILLEGAL OR IMPROPER ACTIVITY (MAY 2014)

(a) If the Government receives information that a contractor or a person has violated 41 U.S.C. 2102-2104, Restrictions on Obtaining and Disclosing Certain Information, the Government may--

(1) Cancel the solicitation, if the contract has not yet been awarded or issued; or

(2) Rescind the contract with respect to which--

(i) The Contractor or someone acting for the Contractor has been convicted for an offense where the conduct violates 41 U.S.C. 2102 for the purpose of either--

(A) Exchanging the information covered by such subsections for anything of value; or

(B) Obtaining or giving anyone a competitive advantage in the award of a Federal agency procurement contract; or

(ii) The head of the contracting activity has determined, based upon a preponderance of the evidence, that the Contractor or someone acting for the Contractor has engaged in conduct punishable under 41 U.S.C. 2105(a).

(b) If the Government rescinds the contract under paragraph (a) of this clause, the Government is entitled to recover, in addition to any penalty prescribed by law, the amount expended under the contract.

(c) The rights and remedies of the Government specified herein are not exclusive, and are in addition to any other rights and remedies provided by law, regulation, or under this contract.

(End of clause)

52.203-10 PRICE OR FEE ADJUSTMENT FOR ILLEGAL OR IMPROPER ACTIVITY (MAY 2014)

(a) The Government, at its election, may reduce the price of a fixed-price type contract and the total cost and fee under a cost-type contract by the amount of profit or fee determined as set forth in paragraph (b) of this clause if the head of the contracting activity or designee determines that there was a violation of 41 U.S.C. 2102 or 2103, as implemented in section 3.104 of the Federal Acquisition Regulation.

(b) The price or fee reduction referred to in paragraph (a) of this clause shall be--

(1) For cost-plus-fixed-fee contracts, the amount of the fee specified in the contract at the time of award;

(2) For cost-plus-incentive-fee contracts, the target fee specified in the contract at the time of award, notwithstanding any minimum fee or "fee floor" specified in the contract;

(3) For cost-plus-award-fee contracts--

(i) The base fee established in the contract at the time of contract award;

(ii) If no base fee is specified in the contract, 30 percent of the amount of each award fee otherwise payable to the Contractor for each award fee evaluation period or at each award fee determination point.

(4) For fixed-price-incentive contracts, the Government may--

(i) Reduce the contract target price and contract target profit both by an amount equal to the initial target profit specified in the contract at the time of contract award; or

(ii) If an immediate adjustment to the contract target price and contract target profit would have a significant adverse impact on the incentive price revision relationship under the contract, or adversely affect the contract financing provisions, the Contracting Officer may defer such adjustment until establishment of the total final price of the contract. The total final price established in accordance with the incentive price revision provisions of the contract shall be reduced by an amount equal to the initial target profit specified in the contract at the time of contract award and such reduced price shall be the total final contract price.

(5) For firm-fixed-price contracts, by 10 percent of the initial contract price or a profit amount determined by the

Contracting Officer from records or documents in existence prior to the date of the contract award.

(c) The Government may, at its election, reduce a prime contractor's price or fee in accordance with the procedures of paragraph (b) of this clause for violations of the statute by its subcontractors by an amount not to exceed the amount of profit or fee reflected in the subcontract at the time the subcontract was first definitively priced.

(d) In addition to the remedies in paragraphs (a) and (c) of this clause, the Government may terminate this contract for default. The rights and remedies of the Government specified herein are not exclusive, and are in addition to any other rights and remedies provided by law or under this contract.

(End of clause)

52.203-12 LIMITATION ON PAYMENTS TO INFLUENCE CERTAIN FEDERAL TRANSACTIONS (OCT 2010)

(a) Definitions. As used in this clause--

Agency means executive agency as defined in Federal Acquisition Regulation (FAR) 2.101.

Covered Federal action means any of the following actions:

- (1) Awarding any Federal contract.
- (2) Making any Federal grant.
- (3) Making any Federal loan.
- (4) Entering into any cooperative agreement.
- (5) Extending, continuing, renewing, amending, or modifying any Federal contract, grant, loan, or cooperative agreement.

Indian tribe and tribal organization have the meaning provided in section 4 of the Indian Self-Determination and Education Assistance Act (25 U.S.C. 450b) and include Alaskan Natives.

Influencing or attempting to influence means making, with the intent to influence, any communication to or appearance before an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with any covered Federal action.

Local government means a unit of government in a State and, if chartered, established, or otherwise recognized by a State for the performance of a governmental duty, including a local public authority, a special district, an intrastate district, a council of governments, a sponsor group representative organization, and any other instrumentality of a local government.

Officer or employee of an agency includes the following individuals who are employed by an agency:

- (1) An individual who is appointed to a position in the Government under Title 5, United States Code, including a position under a temporary appointment.
- (2) A member of the uniformed services, as defined in subsection 101(3), Title 37, United States Code.
- (3) A special Government employee, as defined in section 202, Title 18, United States Code.

(4) An individual who is a member of a Federal advisory committee, as defined by the Federal Advisory Committee Act, Title 5, United States Code, appendix 2.

Person means an individual, corporation, company, association, authority, firm, partnership, society, State, and local government, regardless of whether such entity is operated for profit, or not for profit. This term excludes an Indian tribe, tribal organization, or any other Indian organization eligible to receive Federal contracts, grants, cooperative agreements, or loans from an agency, but only with respect to expenditures by such tribe or organization that are made for purposes specified in paragraph (b) of this clause and are permitted by other Federal law.

Reasonable compensation means, with respect to a regularly employed officer or employee of any person, compensation that is consistent with the normal compensation for such officer or employee for work that is not furnished to, not funded by, or not furnished in cooperation with the Federal Government.

Reasonable payment means, with respect to professional and other technical services, a payment in an amount that is consistent with the amount normally paid for such services in the private sector.

Recipient includes the Contractor and all subcontractors. This term excludes an Indian tribe, tribal organization, or any other Indian organization eligible to receive Federal contracts, grants, cooperative agreements, or loans from an agency, but only with respect to expenditures by such tribe or organization that are made for purposes specified in paragraph (b) of this clause and are permitted by other Federal law.

Regularly employed means, with respect to an officer or employee of a person requesting or receiving a Federal contract, an officer or employee who is employed by such person for at least 130 working days within 1 year immediately preceding the date of the submission that initiates agency consideration of such person for receipt of such contract. An officer or employee who is employed by such person for less than 130 working days within 1 year immediately preceding the date of the submission that initiates agency consideration of such person shall be considered to be regularly employed as soon as he or she is employed by such person for 130 working days.

State means a State of the United States, the District of Columbia, or an outlying area of the United States, an agency or instrumentality of a State, and multi-State, regional, or interstate entity having governmental duties and powers.

(b) Prohibition. 31 U.S.C. 1352 prohibits a recipient of a Federal contract, grant, loan, or cooperative agreement from using appropriated funds to pay any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with any covered Federal actions. In accordance with 31 U.S.C. 1352, the Contractor shall not use appropriated funds to pay any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the award of this contract the extension, continuation, renewal, amendment, or modification of this contract.

(1) The term appropriated funds does not include profit or fee from a covered Federal action.

(2) To the extent the Contractor can demonstrate that the Contractor has sufficient monies, other than Federal appropriated funds, the Government will assume that these other monies were spent for any influencing activities that would be unallowable if paid for with Federal appropriated funds.

(c) Exceptions. The prohibition in paragraph (b) of this clause does not apply under the following conditions:

(1) Agency and legislative liaison by Contractor employees.

(i) Payment of reasonable compensation made to an officer or employee of the Contractor if the payment is for agency and legislative liaison activities not directly related to this contract. For purposes of this paragraph, providing any information specifically requested by an agency or Congress is permitted at any time.

(ii) Participating with an agency in discussions that are not related to a specific solicitation for any covered Federal action, but that concern--

(A) The qualities and characteristics (including individual demonstrations) of the person's products or services, conditions or terms of sale, and service capabilities; or

(B) The application or adaptation of the person's products or services for an agency's use.

(iii) Providing prior to formal solicitation of any covered Federal action any information not specifically requested but necessary for an agency to make an informed decision about initiation of a covered Federal action;

(iv) Participating in technical discussions regarding the preparation of an unsolicited proposal prior to its official submission; and

(v) Making capability presentations prior to formal solicitation of any covered Federal action by persons seeking awards from an agency pursuant to the provisions of the Small Business Act, as amended by Pub.L. 95-507, and subsequent amendments.

(2) Professional and technical services. (i) A payment of reasonable compensation made to an officer or employee of a person requesting or receiving a covered Federal action or an extension, continuation, renewal, amendment, or modification of a covered Federal action, if payment is for professional or technical services rendered directly in the preparation, submission, or negotiation of any bid, proposal, or application for that Federal action or for meeting requirements imposed by or pursuant to law as a condition for receiving that Federal action.

(ii) Any reasonable payment to a person, other than an officer or employee of a person requesting or receiving a covered Federal action or an extension, continuation, renewal, amendment, or modification of a covered Federal action if the payment is for professional or technical services rendered directly in the preparation, submission, or negotiation of any bid, proposal, or application for that Federal action or for meeting requirements imposed by or pursuant to law as a condition for receiving that Federal action. Persons other than officers or employees of a person requesting or receiving a covered Federal action include consultants and trade associations.

(iii) As used in paragraph (c)(2) of this clause, "professional and technical services" are limited to advice and analysis directly applying any professional or technical discipline (for examples, see FAR 3.803(a)(2)(iii)).

(iv) Requirements imposed by or pursuant to law as a condition for receiving a covered Federal award include those required by law or regulation and any other requirements in the actual award documents.

(3) Only those communications and services expressly authorized by paragraphs (c)(1) and (2) of this clause are permitted.

(d) Disclosure. (1) If the Contractor did not submit OMB Standard Form LLL, Disclosure of Lobbying Activities, with its offer, but registrants under the Lobbying Disclosure Act of 1995 have subsequently made a lobbying contact on behalf of the Contractor with respect to this contract, the Contractor shall complete and submit OMB Standard Form LLL to provide the name of the lobbying registrants, including the individuals performing the services.

(2) If the Contractor did submit OMB Standard Form LLL disclosure pursuant to paragraph (d) of the provision at FAR 52.203-11, Certification and Disclosure Regarding Payments to Influence Certain Federal Transactions, and a change occurs that affects Block 10 of the OMB Standard Form LLL (name and address of lobbying registrant or individuals performing services), the Contractor shall, at the end of the calendar quarter in which the change occurs, submit to the Contracting Officer within 30 days an updated disclosure using OMB Standard Form LLL.

(e) Penalties. (1) Any person who makes an expenditure prohibited under paragraph (b) of this clause or who fails to file or amend the disclosure to be filed or amended by paragraph (d) of this clause shall be subject to civil penalties as provided for by 31 U.S.C.1352. An imposition of a civil penalty does not prevent the Government from seeking any other remedy that may be applicable.

(2) Contractors may rely without liability on the representation made by their subcontractors in the certification and disclosure form.

(f) Cost allowability. Nothing in this clause makes allowable or reasonable any costs which would otherwise be unallowable or unreasonable. Conversely, costs made specifically unallowable by the requirements in this clause will not be made allowable under any other provision.

(g) Subcontracts. (1) The Contractor shall obtain a declaration, including the certification and disclosure in paragraphs (c) and (d) of the provision at FAR 52.203-11, Certification and Disclosure Regarding Payments to Influence Certain Federal Transactions, from each person requesting or receiving a subcontract exceeding \$150,000 under this contract. The Contractor or subcontractor that awards the subcontract shall retain the declaration.

(2) A copy of each subcontractor disclosure form (but not certifications) shall be forwarded from tier to tier until received by the prime Contractor. The prime Contractor shall, at the end of the calendar quarter in which the disclosure form is submitted by the subcontractor, submit to the Contracting Officer within 30 days a copy of all disclosures. Each subcontractor certification shall be retained in the subcontract file of the awarding Contractor.

(3) The Contractor shall include the substance of this clause, including this paragraph (g), in any subcontract exceeding \$150,000.

(End of clause)

52.203-13 CONTRACTOR CODE OF BUSINESS ETHICS AND CONDUCT (OCT 2015)

(a) Definitions. As used in this clause--

Agent means any individual, including a director, an officer, an employee, or an independent Contractor, authorized to act on behalf of the organization.

Full cooperation—

(1) Means disclosure to the Government of the information sufficient for law enforcement to identify the nature and extent of the offense and the individuals responsible for the conduct. It includes providing timely and complete response to Government auditors' and investigators' request for documents and access to employees with information;

(2) Does not foreclose any Contractor rights arising in law, the FAR, or the terms of the contract. It does not require--
-

(i) A Contractor to waive its attorney-client privilege or the protections afforded by the attorney work product doctrine; or

(ii) Any officer, director, owner, or employee of the Contractor, including a sole proprietor, to waive his or her attorney client privilege or Fifth Amendment rights; and

(3) Does not restrict a Contractor from--

(i) Conducting an internal investigation; or

(ii) Defending a proceeding or dispute arising under the contract or related to a potential or disclosed violation.

Principal means an officer, director, owner, partner, or a person having primary management or supervisory responsibilities within a business entity (e.g., general manager; plant manager; head of a division or business segment; and similar positions).

Subcontract means any contract entered into by a subcontractor to furnish supplies or services for performance of a prime contract or a subcontract.

Subcontractor means any supplier, distributor, vendor, or firm that furnished supplies or services to or for a prime contractor or another subcontractor.

United States means the 50 States, the District of Columbia, and outlying areas.

(b) Code of business ethics and conduct. (1) Within 30 days after contract award, unless the Contracting Officer establishes a longer time period, the Contractor shall--

(i) Have a written code of business ethics and conduct;

(ii) Make a copy of the code available to each employee engaged in performance of the contract.

(2) The Contractor shall--

(i) Exercise due diligence to prevent and detect criminal conduct; and

(ii) Otherwise promote an organizational culture that encourages ethical conduct and a commitment to compliance with the law.

(3)(i) The Contractor shall timely disclose, in writing, to the agency Office of the Inspector General (OIG), with a copy to the Contracting Officer, whenever, in connection with the award, performance, or closeout of this contract or any subcontract thereunder, the Contractor has credible evidence that a principal, employee, agent, or subcontractor of the Contractor has committed--

(A) A violation of Federal criminal law involving fraud, conflict of interest, bribery, or gratuity violations found in Title 18 of the United States Code; or

(B) A violation of the civil False Claims Act (31 U.S.C. 3729-3733).

(ii) The Government, to the extent permitted by law and regulation, will safeguard and treat information obtained pursuant to the Contractor's disclosure as confidential where the information has been marked "confidential" or "proprietary" by the company. To the extent permitted by law and regulation, such information will not be released by the Government to the public pursuant to a Freedom of Information Act request, 5 U.S.C. Section 552, without prior notification to the Contractor. The Government may transfer documents provided by the Contractor to any department or agency within the Executive Branch if the information relates to matters within the organization's jurisdiction.

(iii) If the violation relates to an order against a Government wide acquisition contract, a multi-agency contract, a multiple-award schedule contract such as the Federal Supply Schedule, or any other procurement instrument intended for use by multiple agencies, the Contractor shall notify the OIG of the ordering agency and the IG of the agency responsible for the basic contract.

(c) Business ethics awareness and compliance program and internal control system. This paragraph (c) does not apply if the Contractor has represented itself as a small business concern pursuant to the award of this contract or if this contract is for the acquisition of a commercial item as defined at FAR 2.101. The Contractor shall establish the following within 90 days after contract award, unless the Contracting Officer establishes a longer time period:

(1) An ongoing business ethics awareness and compliance program.

(i) This program shall include reasonable steps to communicate periodically and in a practical manner the Contractor's standards and procedures and other aspects of the Contractor's business ethics awareness and

compliance program and internal control system, by conducting effective training programs and otherwise disseminating information appropriate to an individual's respective roles and responsibilities.

(ii) The training conducted under this program shall be provided to the Contractor's principals and employees, and as appropriate, the Contractor's agents and subcontractors.

(2) An internal control system.

(i) The Contractor's internal control system shall--

(A) Establish standards and procedures to facilitate timely discovery of improper conduct in connection with Government contracts; and

(B) Ensure corrective measures are promptly instituted and carried out.

(ii) At a minimum, the Contractor's internal control system shall provide for the following:

(A) Assignment of responsibility at a sufficiently high level and adequate resources to ensure effectiveness of the business ethics awareness and compliance program and internal control system.

(B) Reasonable efforts not to include an individual as a principal, whom due diligence would have exposed as having engaged in conduct that is in conflict with the Contractor's code of business ethics and conduct.

(C) Periodic reviews of company business practices, procedures, policies, and internal controls for compliance with the Contractor's code of business ethics and conduct and the special requirements of Government contracting, including--

(1) Monitoring and auditing to detect criminal conduct;

(2) Periodic evaluation of the effectiveness of the business ethics awareness and compliance program and internal control system, especially if criminal conduct has been detected; and

(3) Periodic assessment of the risk of criminal conduct, with appropriate steps to design, implement, or modify the business ethics awareness and compliance program and the internal control system as necessary to reduce the risk of criminal conduct identified through this process.

(D) An internal reporting mechanism, such as a hotline, which allows for anonymity or confidentiality, by which employees may report suspected instances of improper conduct, and instructions that encourage employees to make such reports.

(E) Disciplinary action for improper conduct or for failing to take reasonable steps to prevent or detect improper conduct.

(F) Timely disclosure, in writing, to the agency OIG, with a copy to the Contracting Officer, whenever, in connection with the award, performance, or closeout of any Government contract performed by the Contractor or a subcontractor thereunder, the Contractor has credible evidence that a principal, employee, agent, or subcontractor of the Contractor has committed a violation of Federal criminal law involving fraud, conflict of interest, bribery, or gratuity violations found in Title 18 U.S.C. or a violation of the civil False Claims Act (31 U.S.C. 3729-3733).

(1) If a violation relates to more than one Government contract, the Contractor may make the disclosure to the agency OIG and Contracting Officer responsible for the largest dollar value contract impacted by the violation.

(2) If the violation relates to an order against a Government wide acquisition contract, a multi-agency contract, a multiple-award schedule contract such as the Federal Supply Schedule, or any other procurement instrument intended for use by multiple agencies, the contractor shall notify the OIG of the ordering agency and the IG of the agency responsible for the basic contract, and the respective agencies' contracting officers.

(3) The disclosure requirement for an individual contract continues until at least 3 years after final payment on the contract.

(4) The Government will safeguard such disclosures in accordance with paragraph (b)(3)(ii) of this clause.

(G) Full cooperation with any Government agencies responsible for audits, investigations, or corrective actions.

(d) Subcontracts.

(1) The Contractor shall include the substance of this clause, including this paragraph (d), in subcontracts that have a value in excess of \$5.5 million and a performance period of more than 120 days.

(2) In altering this clause to identify the appropriate parties, all disclosures of violation of the civil False Claims Act or of Federal criminal law shall be directed to the agency Office of the Inspector General, with a copy to the Contracting Officer.

(End of clause)

52.203-14 DISPLAY OF HOTLINE POSTER(S) (OCT 2015)

(a) Definition.

United States, as used in this clause, means the 50 States, the District of Columbia, and outlying areas.

(b) Display of fraud hotline poster(s). Except as provided in paragraph (c)--

(1) During contract performance in the United States, the Contractor shall prominently display in common work areas within business segments performing work under this contract and at contract work sites--

(i) Any agency fraud hotline poster or Department of Homeland Security (DHS) fraud hotline poster identified in paragraph (b)(3) of this clause; and

(ii) Any DHS fraud hotline poster subsequently identified by the Contracting Officer.

(2) Additionally, if the Contractor maintains a company website as a method of providing information to employees, the Contractor shall display an electronic version of the poster(s) at the website.

(3) Any required posters may be obtained as follows:

Poster(s) Obtain from

Contracting Officer
US Army Corps of Engineers, Mobile District
Contracting Division

(i) Appropriate agency name(s) and/or title of applicable Department of Homeland Security fraud hotline poster);
and

(ii) The website(s) or other contact information for obtaining the poster(s).)

(c) If the Contractor has implemented a business ethics and conduct awareness program, including a reporting mechanism, such as a hotline poster, then the Contractor need not display any agency fraud hotline posters as required in paragraph (b) of this clause, other than any required DHS posters.

(d) Subcontracts. The Contractor shall include the substance of this clause, including this paragraph (d), in all subcontracts that exceed \$5.5 million , except when the subcontract--

(1) Is for the acquisition of a commercial item; or

(2) Is performed entirely outside the United States.

(End of clause)

52.203-17 CONTRACTOR EMPLOYEE WHISTLEBLOWER RIGHTS AND REQUIREMENT TO INFORM EMPLOYEES OF WHISTLEBLOWER RIGHTS (APR 2014)

(a) This contract and employees working on this contract will be subject to the whistleblower rights and remedies in the pilot program on Contractor employee whistleblower protections established at 41 U.S.C. 4712 by section 828 of the National Defense Authorization Act for Fiscal Year 2013 (Pub. L. 112-239) and FAR 3.908.

(b) The Contractor shall inform its employees in writing, in the predominant language of the workforce, of employee whistleblower rights and protections under 41 U.S.C. 4712, as described in section 3.908 of the Federal Acquisition Regulation.

(c) The Contractor shall insert the substance of this clause, including this paragraph (c), in all subcontracts over the simplified acquisition threshold.

(End of clause)

52.204-4 Printed or Copied Double-Sided on Postconsumer Fiber Content Paper (May 2011)

(a) Definitions. As used in this clause--

Postconsumer fiber means—

(1) Paper, paperboard, and fibrous materials from retail stores, office buildings, homes, and so forth, after they have passed through their end-usage as a consumer item, including: used corrugated boxes; old newspapers; old magazines; mixed waste paper; tabulating cards; and used cordage; or

(2) All paper, paperboard, and fibrous materials that enter and are collected from municipal solid waste; but not

(3) Fiber derived from printers' over-runs, converters' scrap, and over-issue publications.

(b) The Contractor is required to submit paper documents, such as offers, letters, or reports that are printed or copied double-sided on paper containing at least 30 percent postconsumer fiber, whenever practicable, when not using electronic commerce methods to submit information or data to the Government.

(End of clause)

52.204-7 SYSTEM FOR AWARD MANAGEMENT (JULY 2013)

(a) Definitions. As used in this provision--

Data Universal Numbering System (DUNS) number means the 9-digit number assigned by Dun and Bradstreet, Inc. (D&B) to identify unique business entities.

Data Universal Numbering System +4 (DUNS+4) number means the DUNS number assigned by D&B plus a 4-character suffix that may be assigned by a business concern. (D&B has no affiliation with this 4-character suffix.) This 4-character suffix may be assigned at the discretion of the business concern to establish additional System for Award Management records for identifying alternative Electronic Funds Transfer (EFT) accounts (see the FAR at Subpart 32.11) for the same parent concern.

Registered in the System for Award Management SAM database means that--

(1) The offeror has entered all mandatory information, including the DUNS number or the DUNS+4 number, the Contractor and Government Entity (CAGE) code, as well as data required by the Federal Funding Accountability and Transparency Act of 2006 (see Subpart 4.14) into the SAM database;

(2) The offeror has completed the Core, Assertions, and Representations and Certifications, and Points of Contact sections of the registration in the SAM database;

(3) The Government has validated all mandatory data fields, to include validation of the Taxpayer Identification Number (TIN) with the Internal Revenue Service (IRS). The offeror will be required to provide consent for TIN validation to the Government as a part of the SAM registration process; and

(4) The Government has marked the record ``Active".

(b)(1) By submission of an offer, the offeror acknowledges the requirement that a prospective awardee shall be registered in the SAM database prior to award, during performance, and through final payment of any contract, basic agreement, basic ordering agreement, or blanket purchasing agreement resulting from this solicitation.

(2) The offeror shall enter, in the block with its name and address on the cover page of its offer, the annotation "DUNS" or "DUNS +4" followed by the DUNS or DUNS +4 number that identifies the offeror's name and address exactly as stated in the offer. The DUNS number will be used by the Contracting Officer to verify that the offeror is registered in the SAM database.

(c) If the offeror does not have a DUNS number, it should contact Dun and Bradstreet directly to obtain one.

(1) An offeror may obtain a DUNS number--

(i) Via the Internet at <http://fedgov.dnb.com/webform> or if the offeror does not have internet access, it may call Dun and Bradstreet at 1-866-705-5711 if located within the United States; or

(ii) If located outside the United States, by contacting the local Dun and Bradstreet office. The offeror should indicate that it is an offeror for a U.S. Government contract when contacting the local Dun and Bradstreet office.

(2) The offeror should be prepared to provide the following information:

(i) Company legal business.

- (ii) Tradestyle, doing business, or other name by which your entity is commonly recognized.
 - (iii) Company Physical Street Address, City, State, and Zip Code.
 - (iv) Company Mailing Address, City, State and Zip Code (if separate from physical).
 - (v) Company Telephone Number.
 - (vi) Date the company was started.
 - (vii) Number of employees at your location.
 - (viii) Chief executive officer/key manager.
 - (ix) Line of business (industry).
 - (x) Company Headquarters name and address (reporting relationship within your entity).
- (d) If the Offeror does not become registered in the SAM database in the time prescribed by the Contracting Officer, the Contracting Officer will proceed to award to the next otherwise successful registered Offeror.
- (e) Processing time, which normally takes 48 hours, should be taken into consideration when registering. Offerors who are not registered should consider applying for registration immediately upon receipt of this solicitation.
- (f) Offerors may obtain information on registration at <https://www.acquisition.gov>.
- (End of clause)

52.204-9 PERSONAL IDENTITY VERIFICATION OF CONTRACTOR PERSONNEL (JAN 2011)

- (a) The Contractor shall comply with agency personal identity verification procedures identified in the contract that implement Homeland Security Presidential Directive-12 (HSPD-12), Office of Management and Budget (OMB) guidance M-05-24, and Federal Information Processing Standards Publication (FIPS PUB) Number 201.
- (b) The Contractor shall account for all forms of Government-provided identification issued to the Contractor employees in connection with performance under this contract. The Contractor shall return such identification to the issuing agency at the earliest of any of the following, unless otherwise determined by the Government:
- (1) When no longer needed for contract performance.
 - (2) Upon completion of the Contractor employee's employment.
 - (3) Upon contract completion or termination.
- (c) The Contracting Officer may delay final payment under a contract if the Contractor fails to comply with these requirements.
- (d) The Contractor shall insert the substance of this clause, including this paragraph (d), in all subcontracts when the subcontractor's employees are required to have routine physical access to a Federally-controlled facility and/or routine access to a Federally-controlled information system. It shall be the responsibility of the prime Contractor to return such identification to the issuing agency in accordance with the terms set forth in paragraph (b) of this section, unless otherwise approved in writing by the Contracting Officer.

52.204-10 REPORTING EXECUTIVE COMPENSATION AND FIRST-TIER SUBCONTRACT AWARDS
(OCT 2015)

(a) Definitions. As used in this clause:

Executive means officers, managing partners, or any other employees in management positions.

First-tier subcontract means a subcontract awarded directly by the Contractor for the purpose of acquiring supplies or services (including construction) for performance of a prime contract. It does not include the Contractor's supplier agreements with vendors, such as long-term arrangements for materials or supplies that benefit multiple contracts and/or the costs of which are normally applied to a Contractor's general and administrative expenses or indirect costs.

Month of award means the month in which a contract is signed by the Contracting Officer or the month in which a first-tier subcontract is signed by the Contractor.

Total compensation means the cash and noncash dollar value earned by the executive during the Contractor's preceding fiscal year and includes the following (for more information see 17 CFR 229.402(c)(2)):

(1) Salary and bonus.

(2) Awards of stock, stock options, and stock appreciation rights. Use the dollar amount recognized for financial statement reporting purposes with respect to the fiscal year in accordance with the Financial Accounting Standards Board's Accounting Standards Codification (FASB ASC) 718, Compensation-Stock Compensation.

(3) Earnings for services under non-equity incentive plans. This does not include group life, health, hospitalization or medical reimbursement plans that do not discriminate in favor of executives, and are available generally to all salaried employees.

(4) Change in pension value. This is the change in present value of defined benefit and actuarial pension plans.

(5) Above-market earnings on deferred compensation which is not tax-qualified.

(6) Other compensation, if the aggregate value of all such other compensation (e.g., severance, termination payments, value of life insurance paid on behalf of the employee, perquisites or property) for the executive exceeds \$10,000.

(b) Section 2(d)(2) of the Federal Funding Accountability and Transparency Act of 2006 (Pub. L. 109-282), as amended by section 6202 of the Government Funding Transparency Act of 2008 (Pub. L. 110-252), requires the Contractor to report information on subcontract awards. The law requires all reported information be made public, therefore, the Contractor is responsible for notifying its subcontractors that the required information will be made public.

(c) Nothing in this clause requires the disclosure of classified information.

(d)(1) Executive compensation of the prime contractor. As a part of its annual registration requirement in the System for Award Management (SAM) database (FAR provision 52.204-7), the

IDIQ CONTRACT FOR RENTAL OF HOPPER
DREDGE WITH ATTENDANT PLANT AND
OPERATORS FOR MAINTENANCE DREDGING IN
ALABAMA, MISSISSIPPI, FLORIDA

W91278-17-B-0002

Contractor shall report the names and total compensation of each of the five most highly compensated executives for its preceding completed fiscal year, if—

(i) In the Contractor's preceding fiscal year, the Contractor received—

(A) 80 percent or more of its annual gross revenues from Federal contracts (and subcontracts), loans, grants (and subgrants), cooperative agreements, and other forms of Federal financial assistance; and

(B) \$25,000,000 or more in annual gross revenues from Federal contracts (and subcontracts), loans, grants (and subgrants), cooperative agreements, and other forms of Federal financial assistance; and

(ii) The public does not have access to information about the compensation of the executives through periodic reports filed under section 13(a) or 15(d) of the Securities Exchange Act of 1934 (15 U.S.C. 78m(a), 78o(d)) or section 6104 of the Internal Revenue Code of 1986. (To determine if the public has access to the compensation information, see the U.S. Security and Exchange Commission total compensation filings at <http://www.sec.gov/answers/execomp.htm>.)

(2) First-tier subcontract information. Unless otherwise directed by the contracting officer, or as provided in paragraph (g) of this clause, by the end of the month following the month of award of a first-tier subcontract with a value of \$30,000 or more, the Contractor shall report the following information at <http://www.fsrc.gov> for that first-tier subcontract. (The Contractor shall follow the instructions at <http://www.fsrc.gov> to report the data.)

(i) Unique identifier (DUNS Number) for the subcontractor receiving the award and for the subcontractor's parent company, if the subcontractor has a parent company.

(ii) Name of the subcontractor.

(iii) Amount of the subcontract award.

(iv) Date of the subcontract award.

(v) A description of the products or services (including construction) being provided under the subcontract, including the overall purpose and expected outcomes or results of the subcontract.

(vi) Subcontract number (the subcontract number assigned by the Contractor).

(vii) Subcontractor's physical address including street address, city, state, and country. Also include the nine-digit zip code and congressional district.

(viii) Subcontractor's primary performance location including street address, city, state, and country. Also include the nine-digit zip code and congressional district.

(ix) The prime contract number, and order number if applicable.

(x) Awarding agency name and code.

(xi) Funding agency name and code.

(xii) Government contracting office code.

(xiii) Treasury account symbol (TAS) as reported in FPDS.

(xiv) The applicable North American Industry Classification System code (NAICS).

(3) Executive compensation of the first-tier subcontractor.

Unless otherwise directed by the Contracting Officer, by the end of the month following the month of award of a first-tier subcontract with a value of \$30,000 or more, and annually thereafter (calculated from the prime contract award date), the Contractor shall report the names and total compensation of each of the five most highly compensated executives for that first-tier subcontractor for the first-tier subcontractor's preceding completed fiscal year at <http://www.fsrs.gov>, if—

(i) In the subcontractor's preceding fiscal year, the subcontractor received—

(A) 80 percent or more of its annual gross revenues from Federal contracts (and subcontracts), loans, grants (and subgrants), cooperative agreements, and other forms of Federal financial assistance; and

(B) \$25,000,000 or more in annual gross revenues from Federal contracts (and subcontracts), loans, grants (and subgrants), cooperative agreements, and other forms of Federal financial assistance; and

(ii) The public does not have access to information about the compensation of the executives through periodic reports filed under section 13(a) or 15(d) of the Securities Exchange Act of 1934 (15 U.S.C. 78m(a), 78o(d)) or section 6104 of the Internal Revenue Code of 1986. (To determine if the public has access to the compensation information, see the U.S. Security and Exchange Commission total compensation filings at <http://www.sec.gov/answers/execomp.htm>.)

(e) The Contractor shall not split or break down first-tier subcontract awards to a value less than \$30,000 to avoid the reporting requirements in paragraph (d) of this clause.

(f) The Contractor is required to report information on a first-tier subcontract covered by paragraph (d) when the subcontract is awarded. Continued reporting on the same subcontract is not required unless one of the reported data elements changes during the performance of the

subcontract. The Contractor is not required to make further reports after the first-tier subcontract expires.

(g)(1) If the Contractor in the previous tax year had gross income, from all sources, under \$300,000, the Contractor is exempt from the requirement to report subcontractor awards.

(2) If a subcontractor in the previous tax year had gross income from all sources under \$300,000, the Contractor does not need to report awards for that subcontractor.

(h) The FSRS database at <http://www.fsrs.gov> will be prepopulated with some information from SAM and FPDS databases. If FPDS information is incorrect, the contractor should notify the contracting officer. If the SAM database information is incorrect, the contractor is responsible for correcting this information.

(End of clause)

52.204-13 SYSTEM FOR AWARD MANAGEMENT Maintenance (JULY 2013)

(a) Definitions. As used in this clause--

Data Universal Numbering System (DUNS) number means the 9-digit number assigned by Dun and Bradstreet, Inc. (D&B) to identify unique business entities, which is used as the identification number for Federal Contractors.

Data Universal Numbering System+4 (DUNS+4) number means the DUNS number assigned by D&B plus a 4-character suffix that may be assigned by a business concern. (D&B has no affiliation with this 4-character suffix.) This 4-character suffix may be assigned at the discretion of the business concern to establish additional SAM records for identifying alternative Electronic Funds Transfer (EFT) accounts (see the FAR at subpart 32.11) for the same concern.

Registered in the System for Award Management (SAM) database means that—

- (1) The Contractor has entered all mandatory information, including the DUNS number or the DUNS+4 number, the Contractor and Government Entity (CAGE) code, as well as data required by the Federal Funding Accountability and Transparency Act of 2006 (see subpart 4.14), into the SAM database;
- (2) The Contractor has completed the Core, Assertions, Representations and Certifications, and Points of Contact sections of the registration in the SAM database;
- (3) The Government has validated all mandatory data fields, to include validation of the Taxpayer Identification Number (TIN) with the Internal Revenue Service (IRS). The Contractor will be required to provide consent for TIN validation to the Government as a part of the SAM registration process; and
- (4) The Government has marked the record ``Active".

System for Award Management (SAM) means the primary Government repository for prospective Federal awardee and Federal awardee information and the centralized Government system for certain contracting, grants, and other assistance-related processes. It includes—

- (1) Data collected from prospective Federal awardees required for the conduct of business with the Government;
 - (2) Prospective contractor-submitted annual representations and certifications in accordance with FAR subpart 4.12; and
 - (3) Identification of those parties excluded from receiving Federal contracts, certain subcontracts, and certain types of Federal financial and non-financial assistance and benefits.
- (b) The Contractor is responsible for the accuracy and completeness of the data within the SAM database, and for any liability resulting from the Government's reliance on inaccurate or incomplete data. To remain registered in the SAM database after the initial registration, the Contractor is required to review and update on an annual basis, from the date of initial registration or subsequent updates, its information in the SAM database to ensure it is current, accurate and complete. Updating information in the SAM does not alter the terms and conditions of this contract and is not a substitute for a properly executed contractual document.
- (c)(1)(i) If a Contractor has legally changed its business name, doing business as name, or division name (whichever is shown on the contract), or has transferred the assets used in performing the contract, but has not completed the necessary requirements regarding novation and change-of-name agreements in subpart 42.12, the Contractor shall provide the responsible Contracting Officer a minimum of one business day's written notification of its intention to—
- (A) Change the name in the SAM database;
 - (B) Comply with the requirements of subpart 42.12 of the FAR; and
 - (C) Agree in writing to the timeline and procedures specified by the responsible Contracting Officer. The Contractor shall provide with the notification sufficient documentation to support the legally changed name.

(ii) If the Contractor fails to comply with the requirements of paragraph (c)(1)(i) of this clause, or fails to perform the agreement at paragraph (c)(1)(i)(C) of this clause, and, in the absence of a properly executed novation or change-of-name agreement, the SAM information that shows the Contractor to be other than the Contractor indicated in the contract will be considered to be incorrect information within the meaning of the "Suspension of Payment" paragraph of the electronic funds transfer (EFT) clause of this contract.

(2) The Contractor shall not change the name or address for EFT payments or manual payments, as appropriate, in the SAM record to reflect an assignee for the purpose of assignment of claims (see FAR subpart 32.8, Assignment of Claims). Assignees shall be separately registered in the SAM. Information provided to the Contractor's SAM record that indicates payments, including those made by EFT, to an ultimate recipient other than that Contractor will be considered to be incorrect information within the meaning of the "Suspension of Payment" paragraph of the EFT clause of this contract.

(3) The Contractor shall ensure that the DUNS number is maintained with Dun & Bradstreet throughout the life of the contract. The Contractor shall communicate any change to the DUNS number to the Contracting Officer within 30 days after the change, so an appropriate modification can be issued to update the data on the contract. A change in the DUNS number does not necessarily require a novation be accomplished. Dun & Bradstreet may be contacted—

(i) Via the internet at <http://fedgov.dnb.com/webform> or if the Contractor does not have internet access, it may call Dun and Bradstreet at 1-866-705-5711 if located within the United States; or

(ii) If located outside the United States, by contacting the local Dun and Bradstreet office.

(d) Contractors may obtain additional information on registration and annual confirmation requirements at <https://www.acquisition.gov>.

(End of clause)

52.204-18 Commercial and Government Entity Code Maintenance.

(a) Definition. As used in this clause—

“Commercial and government Entity (CAGE) code” means—

(1) An identifier assigned to entities located in the United States or its outlying areas by the Defense Logistics Agency (DLA) Commercial and Government Entity (CAGE) Branch to identify a commercial or Government entity, or

(2) An identifier assigned by a member of the North Atlantic Treaty Organization (NATO) or by the NATO Support and Procurement Agency (NSPA) to entities located outside the United States and its outlying areas that the DLA Commercial and Government Entity (CAGE) Branch records and maintains in the CAGE master file. This type of code is known as the NATO CAGE (NCAGE) code.

(b) Contractors shall ensure that the CAGE code is maintained throughout the life of the contract. For contractors registered in the System for Award Management (SAM), the DLA Commercial and Government Entity (CAGE) Branch shall only modify data received from SAM in the CAGE master file if the contractor initiates those changes via update of its SAM registration. Contractors undergoing a novation or change-of-name agreement shall notify the contracting officer in accordance with subpart 42.12. The contractor shall communicate any change to the CAGE code to the contracting officer within 30 days after the change, so that a modification can be issued to update the CAGE code on the contract.

(c) Contractors located in the United States or its outlying areas that are not registered in SAM shall submit written change requests to the DLA Commercial and Government Entity (CAGE) Branch. Requests for changes shall be provided at <https://cage.dla.mil> . Change requests to the CAGE master file are accepted from the entity identified by the code.

(d) Contractors located outside the United States and its outlying areas that are not registered in SAM shall contact the appropriate National Codification Bureau (points of contact available at <http://www.nato.int/structur/AC/135/main/links/contacts.htm>) or NSPA at <https://eportal.nspa.nato.int/AC135Public/scage/CageList.aspx>.

(e) Additional guidance for maintaining CAGE codes is available at <https://cage.dla.mil>.

(End of Clause)

[52.204-19 – Incorporation by Reference of Representations and Certifications.](#)

The Contractor's representations and certifications, including those completed electronically via the System for Award Management (SAM), are incorporated by reference into the contract.

(End of clause)

[52.204-21 – Basic Safeguarding of Covered Contractor Information Systems.](#)

As prescribed in 4.1903, insert the following clause:

Basic Safeguarding of Covered Contractor Information Systems (Jun 2016)

(a) Definitions. As used in this clause--

“Covered contractor information system” means an information system that is owned or operated by a contractor that processes, stores, or transmits Federal contract information.

“Federal contract information” means information, not intended for public release, that is provided by or generated for the Government under a contract to develop or deliver a product or service to the Government, but not including information provided by the Government to the public (such as on public Web sites) or simple transactional information, such as necessary to process payments.

“Information” means any communication or representation of knowledge such as facts, data, or opinions, in any medium or form, including textual, numerical, graphic, cartographic, narrative, or audiovisual (Committee on National Security Systems Instruction (CNSSI) 4009).

“Information system” means a discrete set of information resources organized for the collection, processing, maintenance, use, sharing, dissemination, or disposition of information (44 U.S.C. 3502).

“Safeguarding” means measures or controls that are prescribed to protect information systems.

(b) Safeguarding requirements and procedures.

(1) The Contractor shall apply the following basic safeguarding requirements and procedures to protect covered contractor information systems. Requirements and procedures for basic safeguarding of covered contractor information systems shall include, at a minimum, the following security controls:

(i) Limit information system access to authorized users, processes acting on behalf of authorized users, or devices (including other information systems).

(ii) Limit information system access to the types of transactions and functions that authorized users are permitted to execute.

(iii) Verify and control/limit connections to and use of external information systems.

(iv) Control information posted or processed on publicly accessible information systems.

(v) Identify information system users, processes acting on behalf of users, or devices.

(vi) Authenticate (or verify) the identities of those users, processes, or devices, as a prerequisite to allowing access to organizational information systems.

(vii) Sanitize or destroy information system media containing Federal Contract Information before disposal or release for reuse.

(viii) Limit physical access to organizational information systems, equipment, and the respective operating environments to authorized individuals.

(ix) Escort visitors and monitor visitor activity; maintain audit logs of physical access; and control and manage physical access devices.

(x) Monitor, control, and protect organizational communications (i.e., information transmitted or received by organizational information systems) at the external boundaries and key internal boundaries of the information systems.

(xi) Implement subnetworks for publicly accessible system components that are physically or logically separated from internal networks.

(xii) Identify, report, and correct information and information system flaws in a timely manner.

(xiii) Provide protection from malicious code at appropriate locations within organizational information systems.

(xiv) Update malicious code protection mechanisms when new releases are available.

(xv) Perform periodic scans of the information system and real-time scans of files from external sources as files are downloaded, opened, or executed.

(2) Other requirements. This clause does not relieve the Contractor of any other specific safeguarding requirements specified by Federal agencies and departments relating to covered contractor information systems generally or other Federal safeguarding requirements for controlled unclassified information (CUI) as established by Executive Order 13556.

(c) Subcontracts. The Contractor shall include the substance of this clause, including this paragraph (c), in subcontracts under this contract (including subcontracts for the acquisition of commercial items, other than commercially available off-the-shelf items), in which the subcontractor may have Federal contract information residing in or transiting through its information system.

(End of clause)

52.209-6 Protecting the Government's Interest When Subcontracting With Contractors Debarred, Suspended, or Proposed for Debarment (OCT 2015)

(a) Definition. Commercially available off-the-shelf (COTS) item, as used in this clause--

(1) Means any item of supply (including construction material) that is--

(i) A commercial item (as defined in paragraph (1) of the definition in FAR 2.101);

(ii) Sold in substantial quantities in the commercial marketplace; and

(iii) Offered to the Government, under a contract or subcontract at any tier, without modification, in the same form in which it is sold in the commercial marketplace; and

(2) Does not include bulk cargo, as defined in 46 U.S.C. 40102(4), such as agricultural products and petroleum products.

(b) The Government suspends or debar Contractors to protect the Government's interests. Other than a subcontract for a commercially available off-the-shelf item, the Contractor shall not enter into any subcontract, in excess of \$35,000 with a Contractor that is debarred, suspended, or proposed for debarment by any executive agency unless there is a compelling reason to do so.

(c) The Contractor shall require each proposed subcontractor whose subcontract will exceed \$35,000, other than a subcontractor providing a commercially available off-the-shelf item, to disclose to the Contractor, in writing, whether as of the time of award of the subcontract, the subcontractor, or its principals, is or is not debarred, suspended, or proposed for debarment by the Federal Government.

(d) A corporate officer or a designee of the Contractor shall notify the Contracting Officer, in writing, before entering into a subcontract with a party (other than a subcontractor providing a commercially available off-the-shelf item) that is debarred, suspended, or proposed for debarment (see FAR 9.404 for information on the System for Award Management (SAM) Exclusions). The notice must include the following:

(1) The name of the subcontractor.

(2) The Contractor's knowledge of the reasons for the subcontractor being listed with an exclusion in SAM.

(3) The compelling reason(s) for doing business with the subcontractor notwithstanding its being listed with an exclusion in SAM.

(4) The systems and procedures the Contractor has established to ensure that it is fully protecting the Government's interests when dealing with such subcontractor in view of the specific basis for the party's debarment, suspension, or proposed debarment.

(e) Subcontracts. Unless this is a contract for the acquisition of commercial items, the Contractor shall include the requirements of this clause, including this paragraph (e) (appropriately modified for the identification of the parties), in each subcontract that--

(1) Exceeds \$35,000 in value; and

(2) Is not a subcontract for commercially available off-the-shelf items.

(End of clause)

[52.209-9 – Updates of Publicly Available Information Regarding Responsibility Matters.](#)

(a) The Contractor shall update the information in the Federal Awardee Performance and Integrity Information System (FAPIS) on a semi-annual basis, throughout the life of the contract, by posting the required information in the System for Award Management database via <https://www.acquisition.gov>.

(b) As required by section 3010 of the Supplemental Appropriations Act, 2010 (Pub. L. 111-212), all information posted in FAPIS on or after April 15, 2011, except past performance reviews, will be publicly available. FAPIS consist of two segments—

(1) The non-public segment, into which Government officials and the Contractor post information, which can only be viewed by—

(i) Government personnel and authorized users performing business on behalf of the Government; or

(ii) The Contractor, when viewing data on itself; and

(2) The publicly-available segment, to which all data in the non-public segment of FAPIS is automatically transferred after a waiting period of 14 calendar days, except for--

(i) Past performance reviews required by subpart 42.15;

(ii) Information that was entered prior to April 15, 2011; or

(iii) Information that is withdrawn during the 14-calendar-day waiting period by the Government official who posted it in accordance with paragraph (c)(1) of this clause.

(c) The Contractor will receive notification when the Government posts new information to the Contractor's record.

(1) If the Contractor asserts in writing within 7 calendar days, to the Government official who posted the information, that some of the information posted to the non-public segment of FAPIS is covered by a disclosure exemption under the Freedom of Information Act, the Government official who posted the information must within 7 calendar days remove the posting from FAPIS and resolve the issue in accordance with agency Freedom of Information procedures, prior to reposting the releasable information. The contractor must cite 52.209-9 and request removal within 7 calendar days of the posting to FAPIS.

(2) The Contractor will also have an opportunity to post comments regarding information that has been posted by the Government. The comments will be retained as long as the associated information is retained, i.e., for a total period of 6 years. Contractor comments will remain a part of the record unless the Contractor revises them.

(3) As required by section 3010 of Pub. L. 111-212, all information posted in FAPIS on or after April 15, 2011, except past performance reviews, will be publicly available.

(d) Public requests for system information posted prior to April 15, 2011, will be handled under Freedom of Information Act procedures, including, where appropriate, procedures promulgated under E.O. 12600.

(End of clause)

52.209-10 Prohibition on Contracting With Inverted Domestic Corporations. (NOV 2015)

(a) Definitions. As used in this clause--

Inverted domestic corporation means a foreign incorporated entity that meets the definition of an inverted domestic corporation under 6 U.S.C. 395(b), applied in accordance with the rules and definitions of 6 U.S.C. 395(c).

Subsidiary means an entity in which more than 50 percent of the entity is owned--

(1) Directly by a parent corporation; or

(2) Through another subsidiary of a parent corporation.

(b) If the contractor reorganizes as an inverted domestic corporation or becomes a subsidiary of an inverted domestic corporation at any time during the period of performance of this contract, the Government may be prohibited from paying for Contractor activities performed after the date when it becomes an inverted domestic corporation or subsidiary. The Government may seek any available remedies in the event the Contractor fails to perform in accordance with the terms and conditions of the contract as a result of Government action under this clause.

(c) Exceptions to this prohibition are located at 9.108-2.

(d) In the event the Contractor becomes either an inverted domestic corporation, or a subsidiary of an inverted domestic corporation during contract performance, the Contractor shall give written notice to the Contracting Officer within five business days from the date of the inversion event.

(End of clause)

52.210-1 Market Research (APR 2011)

(a) Definition. As used in this clause--

Commercial item and nondevelopmental item have the meaning contained in Federal Acquisition Regulation 2.101.

(b) Before awarding subcontracts over the simplified acquisition threshold for items other than commercial items, the Contractor shall conduct market research to--

(1) Determine if commercial items or, to the extent commercial items suitable to meet the agency's needs are not available, nondevelopmental items are available that--

(i) Meet the agency's requirements;

(ii) Could be modified to meet the agency's requirements; or

(iii) Could meet the agency's requirements if those requirements were modified to a reasonable extent; and

(2) Determine the extent to which commercial items or nondevelopmental items could be incorporated at the component level.

(End of clause)

52.211-10 COMMENCEMENT, PROSECUTION, AND COMPLETION OF WORK (APR 1984)

The Contractor shall be required to (a) commence work under this contract within **Twenty (20)** calendar days after the date the Contractor receives the notice to proceed, (b) prosecute the work diligently, and (c) complete the entire work ready for use not later than *** identified per Task Order**. The time stated for completion shall include final cleanup of the premises.

*The Contracting Officer shall specify either a number of days after the date the contractor receives the notice to proceed, or a calendar date.

(End of clause)

(a) If the Contractor fails to complete the work within the time specified in the contract, the Contractor shall pay liquidated damages to the Government in the amount of * identified per task order for each calendar day of delay until the work is completed or accepted.

(b) If the Government terminates the Contractor's right to proceed, liquidated damages will continue to accrue until the work is completed. These liquidated damages are in addition to excess costs of repurchase under the Termination clause.

(End of clause)

52.211-13 TIME EXTENSIONS (SEP 2000)

Time extensions for contract changes will depend upon the extent, if any, by which the changes cause delay in the completion of the various elements of construction. The change order granting the time extension may provide that the contract completion date will be extended only for those specific elements related to the changed work and that the remaining contract completion dates for all other portions of the work will not be altered. The change order also may provide an equitable readjustment of liquidated damages under the new completion schedule.

(End of clause)

52.214-26 -- Audit and Records -- Sealed Bidding.

(a) As used in this clause, "records" includes books, documents, accounting procedures and practices, and other data, regardless of type and regardless of whether such items are in written form, in the form of computer data, or in any other form.

(b) Certified cost or pricing data. If the Contractor has been required to submit certified cost or pricing data in connection with the pricing of any modification to this contract, the Contracting Officer, or an authorized representative of the Contracting Officer, in order to evaluate the accuracy, completeness, and currency of the certified cost or pricing data, shall have the right to examine and audit all of the Contractor's records, including computations and projections, related to --

(1) The proposal for the modification;

(2) The discussions conducted on the proposal(s), including those related to negotiating;

(3) Pricing of the modification; or

(4) Performance of the modification.

(c) Comptroller General. In the case of pricing any modification, the Comptroller General of the United States, or an authorized representative, shall have the same rights as specified in paragraph (b) of this clause and also the right to interview any current employee regarding such transactions.

(d) Availability. The Contractor shall make available at its office at all reasonable times the materials described in paragraph (b) of this clause, for examination, audit, or reproduction, until 3 years after final payment under this contract, or for any other period specified in Subpart 4.7 of the Federal Acquisition Regulation (FAR). FAR Subpart 4.7, Contractor Records Retention, in effect on the date of this contract, is incorporated by reference in its entirety and made a part of this contract.

(1) If this contract is completely or partially terminated, the records relating to the work terminated shall be made available for 3 years after any resulting final termination settlement.

(2) Records pertaining to appeals under the Disputes clause or to litigation or the settlement of claims arising under or relating to the performance of this contract shall be made available until disposition of such appeals, litigation, or claims.

(e) The Contractor shall insert a clause containing all the provisions of this clause, including this paragraph (e), in all subcontracts expected to exceed the threshold in FAR 15.403-4(a)(1) for submission of certified cost or pricing data.

(End of Clause)

**52.214-27 Price Reduction for Defective CERTIFIED Cost or Pricing Data - Modifications - Sealed Bidding.
(AUG 2011)**

(a) This clause shall become operative only for any modification to this contract involving aggregate increases and/or decreases in costs, plus applicable profits, expected to exceed the threshold for the submission of certified cost or pricing data at FAR 15.403-4(a)(1), except that this clause does not apply to a modification if an exception under FAR 15.403-1(b) applies.

(b) If any price, including profit, negotiated in connection with any modification under this clause, was increased by any significant amount because

(1) the Contractor or a subcontractor furnished certified cost or pricing data that were not complete, accurate, and current as certified in its Certificate of Current Cost or Pricing Data;

(2) a subcontractor or prospective subcontractor furnished the Contractor certified cost or pricing data that were not complete, accurate, and current as certified in the Contractor's Certificate of Current Cost or Pricing Data; or

(3) any of these parties furnished data of any description that were not accurate, the price shall be reduced accordingly and the contract shall be modified to reflect the reduction. This right to a price reduction is limited to that resulting from defects in data relating to modifications for which this clause becomes operative under paragraph (a) above.

(c) Any reduction in the contract price under paragraph (b) of this clause due to defective data from a prospective subcontractor that was not subsequently awarded the subcontract shall be limited to the amount, plus applicable overhead and profit markup, by which:

(1) the actual subcontract; or

(2) the actual cost to the Contractor, if there was no subcontract, was less than the prospective subcontract cost estimate submitted by the Contractor; provided, that the actual subcontract price was not itself affected by defective certified cost or pricing data.

(d) If the Contracting Officer determines under paragraph (b) of this clause that a price or cost reduction should be made:

(1) the Contractor agrees not to raise the following matters as a defense:

(i) The Contractor or subcontractor was a sole source supplier or otherwise was in a superior bargaining position and thus the price of the contract would not have been modified even if accurate, complete, and current certified cost or pricing data had been submitted;

(ii) The Contracting Officer should have known that the certified cost or pricing data in issue were defective even though the Contractor or subcontractor took no affirmative action to bring the character of the data to the attention of the Contracting Officer;

(iii) The contract was based on an agreement about the total cost of the contract and there was no agreement about the cost of each item procured under the contract; or

(iv) The Contractor or subcontractor did not submit a Certificate of Current Cost or Pricing Data.

(2) Except as prohibited by subdivision (d)(2)(ii) of this clause:

(i) an offset in an amount determined appropriate by the Contracting Officer based upon the facts shall be allowed against the amount of a contract price reduction if:

(A) The Contractor certifies to the Contracting Officer that, to the best of the Contractor's knowledge and belief, the Contractor is entitled to the offset in the amount requested; and

(B) The Contractor proves that the certified cost or pricing data were available before the date of agreement on the price of the contract (or price of the modification) and that the data were not submitted before such date.

(ii) An offset shall not be allowed if:

(A) The understated data was known by the Contractor to be understated when the Certificate of Current Cost or Pricing Data was signed; or (B) The Government proves that the facts demonstrate that the contract price would not have increased in the amount to be offset even if the available data had been submitted before the date of agreement on price.

(e) If any reduction in the contract price under this clause reduces the price of items for which payment was made prior to the date of the modification reflecting the price reduction, the Contractor shall be liable to and shall pay the United States at the time such overpayment is repaid:

(1) Interest compounded daily, as required by 26 U.S.C. 6622, on the amount of such overpayment to be computed from the date(s) of overpayment to the Contractor to the date the Government is repaid by the Contractor at the applicable underpayment rate effective for each quarter prescribed by the Secretary of the Treasury under 26 U.S.C. 6621(a)(2); and

(2) A penalty equal to the amount of the overpayment, if the Contractor or subcontractor knowingly submitted certified cost or pricing data which were incomplete, inaccurate, or noncurrent.

(End of clause)

52.214-28 Subcontractor CERTIFIED Cost or Pricing Data - Modifications - Sealed Bidding. (OCT 2010)

(a) The requirements of paragraphs (b) and (c) of this clause shall—

(1) Become operative only for any modification to this contract involving aggregate increases and/or decreases in costs, plus applicable profits, expected to exceed the threshold for submission of certified cost or pricing data at FAR [15.403-4](#)(a)(1); and

(2) Be limited to such modifications.

(b) Before awarding any subcontract expected to exceed the threshold for submission of certified cost or pricing data at FAR [15.403-4\(a\)\(1\)](#), on the date of agreement on price or the date of award, whichever is later, or before pricing any subcontract modifications involving aggregate increases and/or decreases in costs, plus applicable profits, expected to exceed the threshold for submission of certified cost or pricing data at FAR [15.403-4\(a\)\(1\)](#), the Contractor shall require the subcontractor to submit certified cost or pricing data (actually or by specific identification in writing), as part of the subcontractor's proposal in accordance with FAR [15.408](#), Table [15-2](#) (to include any information reasonably required to explain the subcontractor's estimating process such as the judgmental factors applied and the mathematical or other methods used in the estimate, including those used in projecting from known data, and the nature and amount of any contingencies included in the price), unless an exception under FAR [15.403-1\(b\)](#) applies.

(c) The Contractor shall require the subcontractor to certify in substantially the form prescribed in FAR subsection [15.406-2](#) that, to the best of its knowledge and belief, the data submitted under paragraph (b) of this clause were accurate, complete, and current as of the date of agreement on the negotiated price of the subcontract or subcontract modification.

(d) The Contractor shall insert the substance of this clause, including this paragraph (d), in each subcontract that, when entered into, exceeds the threshold for submission of certified cost or pricing data at FAR [15.403-4\(a\)\(1\)](#).

(End of clause)

[52.216-19](#) Order Limitations. (OCT 1995)

(a) Minimum order. When the Government requires supplies or services covered by this contract in an amount of less than **\$25,000.00**, the Government is not obligated to purchase, nor is the Contractor obligated to furnish, those supplies or services under the contract.

(b) Maximum order. The Contractor is not obligated to honor:

(1) Any order for a single item in excess of **\$8,000,000.00**;

(2) Any order for a combination of items in excess of **\$8,000,000.00**; or

(3) A series of orders from the same ordering office within **Fourteen 14 Months** that together call for quantities exceeding the limitation in subparagraph (1) or (2) above.

(c) If this is a requirements contract (i.e., includes the Requirements clause at subsection 52.216-21 of the Federal Acquisition Regulation (FAR)), the Government is not required to order a part of any one requirement from the Contractor if that requirement exceeds the maximum-order limitations in paragraph (b) above.

(d) Notwithstanding paragraphs (b) and (c) above, the Contractor shall honor any order exceeding the maximum order limitations in paragraph (b), unless that order (or orders) is returned to the ordering office within **seven (7)** days after issuance, with written notice stating the Contractor's intent not to ship the item (or items) called for and the reasons. Upon receiving this notice, the Government may acquire the supplies or services from another source.

(End of clause)

[52.216-22](#) INDEFINITE QUANTITY. (OCT 1995)

(a) This is an indefinite-quantity contract for the supplies or services specified, and effective for the period stated, in

the Schedule. The quantities of supplies and services specified in the Schedule are estimates only and are not purchased by this contract.

(b) Delivery or performance shall be made only as authorized by orders issued in accordance with the Ordering clause. The Contractor shall furnish to the Government, when and if ordered, the supplies or services specified in the Schedule up to and including the quantity designated in the Schedule as the "maximum". The Government shall order at least the quantity of supplies or services designated in the Schedule as the "minimum".

(c) Except for any limitations on quantities in the Order Limitations clause or in the Schedule, there is no limit on the number of orders that may be issued. The Government may issue orders requiring delivery to multiple destinations or performance at multiple locations.

(d) Any order issued during the effective period of this contract and not completed within that period shall be completed by the Contractor within the time specified in the order. The contract shall govern the Contractor's and Government's rights and obligations with respect to that order to the same extent as if the order were completed

during the contract's effective period; provided, that the Contractor shall not be required to make any deliveries under this contract after **completion of all work required by any task order(s) issued under this contract.**

(End of clause)

52.216-24 LIMITATION OF GOVERNMENT LIABILITY (APR 1984)

(a) In performing this contract, the Contractor is not authorized to make expenditures or incur obligations exceeding **(amount identified per task order)** dollars.

(b) The maximum amount for which the Government shall be liable if this contract is terminated is **the minimum guarantee.**

(End of clause)

52.219-4 NOTICE OF PRICE EVALUATION PREFERENCE FOR HUBZONE SMALL BUSINESS CONCERNS (OCT 2014)

(a) Definitions. See 13 CFR 125.6(e) for definitions of terms used in paragraph (d).

(b) Evaluation preference. (1) Offers will be evaluated by adding a factor of 10 percent to the price of all offers, except--

(i) Offers from HUBZone small business concerns that have not waived the evaluation preference; and

(ii) Otherwise successful offers from small business concerns.

(2) The factor of 10 percent shall be applied on a line item basis or to any group of items on which award may be made. Other evaluation factors described in the solicitation shall be applied before application of the factor.

(3) When the two highest rated offerors are a HUBZone small business concern and a large business, and the evaluated offer of the HUBZone small business concern is equal to the evaluated offer of the large business after considering the price evaluation preference, award will be made to the HUBZone small business concern.

(c) Waiver of evaluation preference. A HUBZone small business concern may elect to waive the evaluation preference, in which case the factor will be added to its offer for evaluation purposes. The agreements in paragraphs (d) and (e) of this clause do not apply if the offeror has waived the evaluation preference.

___ Offeror elects to waive the evaluation preference.

(d) Agreement. A HUBZone small business concern agrees that in the performance of the contract, in the case of a contract for

(1) Services (except construction), at least 50 percent of the cost of personnel for contract performance will be spent for employees of the concern or employees of other HUBZone small business concerns;

(2) Supplies (other than procurement from a nonmanufacturer of such supplies), at least 50 percent of the cost of manufacturing, excluding the cost of materials, will be performed by the concern or other HUBZone small business concerns;

(3) General construction. (i) At least 15 percent of the cost of contract performance to be incurred for personnel will be spent on the prime contractor's employees;

(ii) At least 50 percent of the cost of the contract performance to be incurred for personnel will be spent on the prime contractor's employees or on a combination of the prime contractor's employees and employees of HUBZone small business concern subcontractors;

(iii) No more than 50 percent of the cost of contract performance to be incurred for personnel will be subcontracted to concerns that are not HUBZone small business concerns; or

(4) Construction by special trade contractors. (i) At least 25 percent of the cost of contract performance to be incurred for personnel will be spent on the prime contractor's employees;

(ii) At least 50 percent of the cost of the contract performance to be incurred for personnel will be spent on the prime contractor's employees or on a combination of the prime contractor's employees and employees of HUBZone small business concern subcontractors;

(iii) No more than 50 percent of the cost of contract performance to be incurred for personnel will be subcontracted to concerns that are not HUBZone small business concerns.

(e) A HUBZone joint venture agrees that the aggregate of the HUBZone small business concerns to the joint venture, not each concern separately, will perform the applicable percentage of work requirements.

(f)(1) When the total value of the contract exceeds \$25,000, a HUBZone small business concern nonmanufacturer agrees to furnish in performing this contract only end items manufactured or produced by HUBZone small business concern manufacturers.

(2) When the total value of the contract is equal to or less than \$25,000, a HUBZone small business concern nonmanufacturer may provide end items manufactured by other than a HUBZone small business concern manufacturer provided the end items are produced or manufactured in the United States.

(3) Paragraphs (f)(1) and (f)(2) of this section do not apply in connection with construction or service contracts.

(g) Notice. The HUBZone small business offeror acknowledges that a prospective HUBZone awardee must be a HUBZone small business concern at the time of award of this contract. The HUBZone offeror shall provide the Contracting Officer a copy of the notice required by 13 CFR 126.501 if material changes occur before contract award

that could affect its HUBZone eligibility. If the apparently successful HUBZone offeror is not a HUBZone small business concern at the time of award of this contract, the Contracting Officer will proceed to award to the next otherwise successful HUBZone small business concern or other offeror.

(End of clause)

52.219-8 UTILIZATION OF SMALL BUSINESS CONCERNS (OCT 2014)

(a) Definitions. As used in this contract--

HUBZone small business concern means a small business concern that appears on the List of Qualified HUBZone Small Business Concerns maintained by the Small Business Administration.

Service-disabled veteran-owned small business concern--

(1) Means a small business concern--

(i) Not less than 51 percent of which is owned by one or more service-disabled veterans or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more service-disabled veterans; and

(ii) The management and daily business operations of which are controlled by one or more service-disabled veterans or, in the case of a service-disabled veteran with permanent and severe disability, the spouse or permanent caregiver of such veteran.

(2) Service-disabled veteran means a veteran, as defined in 38 U.S.C. 101(2), with a disability that is service-connected, as defined in 38 U.S.C. 101(16).

Small business concern means a small business as defined pursuant to Section 3 of the Small Business Act and relevant regulations promulgated pursuant thereto.

Small disadvantaged business concern, consistent with 13 CFR 124.1002, means a small business concern under the size standard applicable to the acquisition, that--

(1) Is at least 51 percent unconditionally and directly owned (as defined at 13 CFR 124.105) by--

(i) One or more socially disadvantaged (as defined at 13 CFR 124.103) and economically disadvantaged (as defined at 13 CFR 124.104) individuals who are citizens of the United States; and

(ii) Each individual claiming economic disadvantage has a net worth not exceeding \$750,000 after taking into account the applicable exclusions set forth at 13 CFR 124.104(c)(2); and

(2) The management and daily business operations of which are controlled (as defined at 13.CFR 124.106) by individuals, who meet the criteria in paragraphs (1)(i) and (ii) of this definition.

Veteran-owned small business concern means a small business concern--

(1) Not less than 51 percent of which is owned by one or more veterans (as defined at 38 U.S.C. 101(2)) or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more veterans; and

(2) The management and daily business operations of which are controlled by one or more veterans.

Women-owned small business concern means a small business concern--

(1) That is at least 51 percent owned by one or more women, or, in the case of any publicly owned business, at least 51 percent of the stock of which is owned by one or more women; and

(2) Whose management and daily business operations are controlled by one or more women.

(b) It is the policy of the United States that small business concerns, veteran-owned small business concerns, service-disabled veteran-owned small business concerns, HUBZone small business concerns, small disadvantaged business concerns, and women-owned small business concerns shall have the maximum practicable opportunity to participate in performing contracts let by any Federal agency, including contracts and subcontracts for subsystems, assemblies, components, and related services for major systems. It is further the policy of the United States that its prime contractors establish procedures to ensure the timely payment of amounts due pursuant to the terms of their subcontracts with small business concerns, veteran-owned small business concerns, service-disabled veteran-owned small business concerns, HUBZone small business concerns, small disadvantaged business concerns, and women-owned small business concerns.

(c) The Contractor hereby agrees to carry out this policy in the awarding of subcontracts to the fullest extent consistent with efficient contract performance. The Contractor further agrees to cooperate in any studies or surveys as may be conducted by the United States Small Business Administration or the awarding agency of the United States as may be necessary to determine the extent of the Contractor's compliance with this clause.

(d)(1) Contractors acting in good faith may rely on written representations by their subcontractors regarding their status as a small business concern, a veteran-owned small business concern, a service-disabled veteran-owned small business concern, a small disadvantaged business concern, or a women-owned small business concern.

(2) The Contractor shall confirm that a subcontractor representing itself as a HUBZone small business concern is certified by SBA as a HUBZone small business concern by accessing the System for Award Management database or by contacting the SBA. Options for contacting the SBA include--

(i) HUBZone small business database search application Web page at http://dsbs.sba.gov/dsbs/search/dsp_searchhubzone.cfm; or <http://www.sba.gov/hubzone>;

(ii) In writing to the Director/HUB, U.S. Small Business Administration, 409 3rd Street, SW., Washington DC 20416; or

(iii) The SBA HUBZone Help Desk at hubzone@sba.gov.

(End of clause)

52.219-9 SMALL BUSINESS SUBCONTRACTING PLAN (JAN 2017)--ALTERNATE I (NOV 2016).

(a) This clause does not apply to small business concerns.

(b) Definitions. As used in this clause--

“Alaska Native Corporation (ANC)” means any Regional Corporation, Village Corporation, Urban Corporation, or Group Corporation organized under the laws of the State of Alaska in accordance with the Alaska Native Claims Settlement Act, as amended (43 U.S.C. 1601, et seq.) and which is considered a minority and economically disadvantaged concern under the criteria at 43 U.S.C. 1626(e)(1). This definition also includes ANC direct and indirect subsidiary corporations, joint ventures, and partnerships that meet the requirements of 43 U.S.C. 1626(e)(2).

“Commercial item” means a product or service that satisfies the definition of commercial item in section 2.101 of the Federal Acquisition Regulation.

“Commercial plan” means a subcontracting plan (including goals) that covers the offeror’s fiscal year and that applies to the entire production of commercial items sold by either the entire company or a portion thereof (e.g., division, plant, or product line).

“Electronic Subcontracting Reporting System (eSRS)” means the Governmentwide, electronic, web-based system for small business subcontracting program reporting. The eSRS is located at <http://www.esrs.gov>.

“Indian tribe” means any Indian tribe, band, group, pueblo, or community, including native villages and native groups (including corporations organized by Kenai, Juneau, Sitka, and Kodiak) as defined in the Alaska Native Claims Settlement Act (43 U.S.C.A. 1601 et seq.), that is recognized by the Federal Government as eligible for services from the Bureau of Indian Affairs in accordance with 25 U.S.C. 1452(c). This definition also includes Indian-owned economic enterprises that meet the requirements of 25 U.S.C. 1452(e).

“Individual subcontracting plan” means a subcontracting plan that covers the entire contract period (including option periods), applies to a specific contract, and has goals that are based on the offeror's planned subcontracting in support of the specific contract, except that indirect costs incurred for common or joint purposes may be allocated on a prorated basis to the contract.

“Master subcontracting plan” means a subcontracting plan that contains all the required elements of an individual subcontracting plan, except goals, and may be incorporated into individual subcontracting plans, provided the master subcontracting plan has been approved.

“Reduced payment” means a payment that is for less than the amount agreed upon in a subcontract in accordance with its terms and conditions, for supplies and services for which the Government has paid the prime contractor.

“Subcontract” means any agreement (other than one involving an employer-employee relationship) entered into by a Federal Government prime Contractor or subcontractor calling for supplies or services required for performance of the contract or subcontract.

“Total contract dollars” means the final anticipated dollar value, including the dollar value of all options.

“Untimely payment” means a payment to a subcontractor that is more than 90 days past due under the terms and conditions of a subcontract for supplies and services for which the Government has paid the prime contractor.

(c)(1) The apparent low bidder, upon request by the Contracting Officer, shall submit a subcontracting plan, where applicable, that separately addresses subcontracting with small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns. If the bidder is submitting an individual subcontracting plan, the plan must separately address subcontracting with small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns, with a separate part for the basic contract and separate parts for each option (if any). The plan shall be included in and made a part of the resultant contract. The subcontracting plan shall be submitted within the time specified by the Contracting Officer. Failure to submit the subcontracting plan shall make the bidder ineligible for the award of a contract.

(2)(i) The Contractor may accept a subcontractor's written representations of its size and socioeconomic status as a small business, small disadvantaged business, veteran-owned small business, service-disabled veteran-owned small business, or a women-owned small business if the subcontractor represents that the size and socioeconomic status representations with its offer are current, accurate, and complete as of the date of the offer for the subcontract.

(ii) The Contractor may accept a subcontractor's representations of its size and socioeconomic status as a small business, small disadvantaged business, veteran-owned small business, service-disabled veteran-owned small

business, or a women-owned small business in the System for Award Management (SAM) if--

(A) The subcontractor is registered in SAM; and

(B) The subcontractor represents that the size and socioeconomic status representations made in SAM are current, accurate and complete as of the date of the offer for the subcontract.

(iii) The Contractor may not require the use of SAM for the purposes of representing size or socioeconomic status in connection with a subcontract.

(iv) In accordance with 13 CFR 121.411, 124.1015, 125.29, 126.900, and 127.700, a contractor acting in good faith is not liable for misrepresentations made by its subcontractors regarding the subcontractor's size or socioeconomic status.

(d) The Offeror's subcontracting plan shall include the following:

(1) Separate goals, expressed in terms of total dollars subcontracted, and as a percentage of total planned subcontracting dollars, for the use of small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns as subcontractors. For individual subcontracting plans, and if required by the Contracting Officer, goals shall also be expressed in terms of percentage of total contract dollars, in addition to the goals expressed as a percentage of total subcontract dollars. The Offeror shall include all subcontracts that contribute to contract performance, and may include a proportionate share of products and services that are normally allocated as indirect costs. In accordance with 43 U.S.C. 1626--

(i) Subcontracts awarded to an ANC or Indian tribe shall be counted towards the subcontracting goals for small business and small disadvantaged business concerns, regardless of the size or Small Business Administration certification status of the ANC or Indian tribe; and

(ii) Where one or more subcontractors are in the subcontract tier between the prime Contractor and the ANC or Indian tribe, the ANC or Indian tribe shall designate the appropriate Contractor(s) to count the subcontract towards its small business and small disadvantaged business subcontracting goals.

(A) In most cases, the appropriate Contractor is the Contractor that awarded the subcontract to the ANC or Indian tribe.

(B) If the ANC or Indian tribe designates more than one Contractor to count the subcontract toward its goals, the ANC or Indian tribe shall designate only a portion of the total subcontract award to each Contractor. The sum of the amounts designated to various Contractors cannot exceed the total value of the subcontract.

(C) The ANC or Indian tribe shall give a copy of the written designation to the Contracting Officer, the prime Contractor, and the subcontractors in between the prime Contractor and the ANC or Indian tribe within 30 days of the date of the subcontract award.

(D) If the Contracting Officer does not receive a copy of the ANC's or the Indian tribe's written designation within 30 days of the subcontract award, the Contractor that awarded the subcontract to the ANC or Indian tribe will be considered the designated Contractor.

(2) A statement of --

(i) Total dollars planned to be subcontracted for an individual subcontracting plan; or the Offeror's total projected sales, expressed in dollars, and the total value of projected subcontracts to support the sales for a commercial plan;

(ii) Total dollars planned to be subcontracted to small business concerns (including ANC and Indian tribes);

(iii) Total dollars planned to be subcontracted to veteran-owned small business concerns;

(iv) Total dollars planned to be subcontracted to service-disabled veteran-owned small business;

(v) Total dollars planned to be subcontracted to HUBZone small business concerns;

(vi) Total dollars planned to be subcontracted to small disadvantaged business concerns (including ANCs and Indian tribes); and

(vii) Total dollars planned to be subcontracted to women-owned small business concerns.

(3) A description of the principal types of supplies and services to be subcontracted, and an identification of the types planned for subcontracting to--

(i) Small business concerns,

(ii) Veteran-owned small business concerns;

(iii) Service-disabled veteran-owned small business concerns;

(iv) HUBZone small business concerns;

(v) Small disadvantaged business concerns, and

(vi) Women-owned small business concerns.

(4) A description of the method used to develop the subcontracting goals in paragraph (d)(1) of this clause.

(5) A description of the method used to identify potential sources for solicitation purposes (e.g., existing company source lists, SAM, veterans service organizations, the National Minority Purchasing Council Vendor Information Service, the Research and Information Division of the Minority Business Development Agency in the Department of Commerce, or small, HUBZone, small disadvantaged, and women-owned small business trade associations). A firm may rely on the information contained in SAM as an accurate representation of a concern's size and ownership characteristics for the purposes of maintaining a small, veteran-owned small, service-disabled veteran-owned small, HUBZone small, small disadvantaged, and women-owned small business source list. Use of SAM as its source list does not relieve a firm of its responsibilities (e.g., outreach, assistance, counseling, or publicizing subcontracting opportunities) in this clause.

(6) A statement as to whether or not the Offeror included indirect costs in establishing subcontracting goals, and a description of the method used to determine the proportionate share of indirect costs to be incurred with--

(i) Small business concerns (including ANC and Indian tribes);

(ii) Veteran-owned small business concerns;

(iii) Service-disabled veteran-owned small business concerns;

(iv) HUBZone small business concerns;

(v) Small disadvantaged business concerns (including ANC and Indian tribes); and

(vi) Women-owned small business concerns.

(7) The name of the individual employed by the Offeror who will administer the Offeror's subcontracting program, and a description of the duties of the individual.

(8) A description of the efforts the Offeror will make to assure that small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns have an equitable opportunity to compete for subcontracts.

(9) Assurances that the Offeror will include the clause of this contract entitled "Utilization of Small Business Concerns" in all subcontracts that offer further subcontracting opportunities, and that the Offeror will require all subcontractors (except small business concerns) that receive subcontracts in excess of \$700,000 (\$1.5 million for construction of any public facility) with further subcontracting possibilities to adopt a subcontracting plan that complies with the requirements of this clause.

(10) Assurances that the Offeror will--

(i) Cooperate in any studies or surveys as may be required;

(ii) Submit periodic reports so that the Government can determine the extent of compliance by the Offeror with the subcontracting plan;

(iii) After November 30, 2017, include subcontracting data for each order when reporting subcontracting achievements for indefinite-delivery, indefinite-quantity contracts intended for use by multiple agencies;

(iv) Submit the Individual Subcontract Report (ISR) and/or the Summary Subcontract Report (SSR), in accordance with paragraph (l) of this clause using the Electronic Subcontracting Reporting System (eSRS) at <http://www.esrs.gov>. The reports shall provide information on subcontract awards to small business concerns (including ANCs and Indian tribes that are not small businesses), veteran-owned small business concerns, service-disabled veteran-owned small business concerns, HUBZone small business concerns, small disadvantaged business concerns (including ANCs and Indian tribes that have not been certified by SBA as small disadvantaged businesses), women-owned small business concerns, and for NASA only, Historically Black Colleges and Universities and Minority Institutions. Reporting shall be in accordance with this clause, or as provided in agency regulations;

(v) Ensure that its subcontractors with subcontracting plans agree to submit the ISR and/or the SSR using eSRS;

(vi) Provide its prime contract number, its DUNS number, and the email address of the Offeror's official responsible for acknowledging receipt of or rejecting the ISRs, to all first-tier subcontractors with subcontracting plans so they can enter this information into the eSRS when submitting their ISRs; and

(vii) Require that each subcontractor with a subcontracting plan provide the prime contract number, its own DUNS number, and the email address of the subcontractor's official responsible for acknowledging receipt of or rejecting the ISRs, to its subcontractors with subcontracting plans.

(11) A description of the types of records that will be maintained concerning procedures that have been adopted to comply with the requirements and goals in the plan, including establishing source lists; and a description of the offeror's efforts to locate small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns and award subcontracts to them. The records shall include at least the following (on a plant-wide or company-wide basis, unless otherwise indicated):

(i) Source lists (e.g., SAM), guides, and other data that identify small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns.

(ii) Organizations contacted in an attempt to locate sources that are small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, or women-owned small business concerns.

(iii) Records on each subcontract solicitation resulting in an award of more than \$150,000, indicating --

- (A) Whether small business concerns were solicited and if not, why not;
- (B) Whether veteran-owned small business concerns were solicited and, if not, why not;
- (C) Whether service-disabled veteran-owned small business concerns were solicited and, if not, why not;
- (D) Whether HUBZone small business concerns were solicited and, if not, why not;
- (E) Whether small disadvantaged business concerns were solicited and if not, why not;
- (F) Whether women-owned small business concerns were solicited and if not, why not; and
- (G) If applicable, the reason award was not made to a small business concern.

(iv) Records of any outreach efforts to contact --

- (A) Trade associations;
- (B) Business development organizations;
- (C) Conferences and trade fairs to locate small, HUBZone small, small disadvantaged, service-disabled veteran-owned, and women-owned small business sources; and
- (D) Veterans service organizations.

(v) Records of internal guidance and encouragement provided to buyers through --

- (A) Workshops, seminars, training, etc., and
- (B) Monitoring performance to evaluate compliance with the program's requirements.

(vi) On a contract-by-contract basis, records to support award data submitted by the offeror to the Government, including the name, address, and business size of each subcontractor. Contractors having commercial plans need not comply with this requirement.

(12) Assurances that the Offeror will make a good faith effort to acquire articles, equipment, supplies, services, or materials, or obtain the performance of construction work from the small business concerns that it used in preparing the bid or proposal, in the same or greater scope, amount, and quality used in preparing and submitting the bid or proposal. Responding to a request for a quote does not constitute use in preparing a bid or proposal. The Offeror used a small business concern in preparing the bid or proposal if--

- (i) The Offeror identifies the small business concern as a subcontractor in the bid or proposal or associated small business subcontracting plan, to furnish certain supplies or perform a portion of the subcontract; or
- (ii) The Offeror used the small business concern's pricing or cost information or technical expertise in preparing the bid or proposal, where there is written evidence of an intent or understanding that the small business concern will be awarded a subcontract for the related work if the Offeror is awarded the contract.

(13) Assurances that the Contractor will provide the Contracting Officer with a written explanation if the Contractor fails to acquire articles, equipment, supplies, services or materials or obtain the performance of construction work as described in (d)(12) of this clause. This written explanation must be submitted to the Contracting Officer within 30 days of contract completion.

(14) Assurances that the Contractor will not prohibit a subcontractor from discussing with the Contracting Officer any material matter pertaining to payment to or utilization of a subcontractor.

(15) Assurances that the offeror will pay its small business subcontractors on time and in accordance with the terms and conditions of the underlying subcontract, and notify the contracting officer when the prime contractor makes either a reduced or an untimely payment to a small business subcontractor (see 52.242-5).

(e) In order to effectively implement this plan to the extent consistent with efficient contract performance, the Contractor shall perform the following functions:

(1) Assist small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns by arranging solicitations, time for the preparation of bids, quantities, specifications, and delivery schedules so as to facilitate the participation by such concerns. Where the Contractor's lists of potential small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business subcontractors are excessively long, reasonable effort shall be made to give all such small business concerns an opportunity to compete over a period of time.

(2) Provide adequate and timely consideration of the potentialities of small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns in all "make-or-buy" decisions.

(3) Counsel and discuss subcontracting opportunities with representatives of small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business firms.

(4) Confirm that a subcontractor representing itself as a HUBZone small business concern is certified by SBA as a HUBZone small business concern in accordance with 52.219-8(d)(2).

(5) Provide notice to subcontractors concerning penalties and remedies for misrepresentations of business status as small, veteran-owned small business, HUBZone small, small disadvantaged or women-owned small business for the purpose of obtaining a subcontract that is to be included as part or all of a goal contained in the Contractor's subcontracting plan.

(6) For all competitive subcontracts over the simplified acquisition threshold in which a small business concern received a small business preference, upon determination of the successful subcontract offeror, prior to award of the subcontract the Contractor must inform each unsuccessful small business subcontract offeror in writing of the name and location of the apparent successful offeror and if the successful subcontract offeror is a small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, or women-owned small business concern.

(7) Assign each subcontract the NAICS code and corresponding size standard that best describes the principal purpose of the subcontract.

(f) A master subcontracting plan on a plant or division-wide basis that contains all the elements required by paragraph (d) of this clause, except goals, may be incorporated by reference as a part of the subcontracting plan required of the Offeror by this clause; provided--

(1) The master subcontracting plan has been approved;

(2) The Offeror ensures that the master subcontracting plan is updated as necessary and provides copies of the approved master subcontracting plan, including evidence of its approval, to the Contracting Officer; and

(3) Goals and any deviations from the master subcontracting plan deemed necessary by the Contracting Officer to

satisfy the requirements of this contract are set forth in the individual subcontracting plan.

(g) A commercial plan is the preferred type of subcontracting plan for contractors furnishing commercial items. The commercial plan shall relate to the offeror's planned subcontracting generally, for both commercial and Government business, rather than solely to the Government contract. Once the Contractor's commercial plan has been approved, the Government will not require another subcontracting plan from the same Contractor while the plan remains in effect, as long as the product or service being provided by the Contractor continues to meet the definition of a commercial item. A Contractor with a commercial plan shall comply with the reporting requirements stated in paragraph (d)(10) of this clause by submitting one SSR in eSRS for all contracts covered by its commercial plan. This report shall be acknowledged or rejected in eSRS by the Contracting Officer who approved the plan. This report shall be submitted within 30 days after the end of the Government's fiscal year.

(h) Prior compliance of the offeror with other such subcontracting plans under previous contracts will be considered by the Contracting Officer in determining the responsibility of the offeror for award of the contract.

(i) A contract may have no more than one subcontracting plan. When a contract modification exceeds the subcontracting plan threshold in 19.702(a), or an option is exercised, the goals of the existing subcontracting plan shall be amended to reflect any new subcontracting opportunities. When the goals in a subcontracting plan are amended, these goal changes do not apply retroactively.

(j) Subcontracting plans are not required from subcontractors when the prime contract contains the clause at 52.212-5, Contract Terms and Conditions Required to Implement Statutes or Executive Orders--Commercial Items, or when the subcontractor provides a commercial item subject to the clause at 52.244-6, Subcontracts for Commercial Items, under a prime contract.

(k) The failure of the Contractor or subcontractor to comply in good faith with (1) the clause of this contract entitled "Utilization Of Small Business Concerns," or (2) an approved plan required by this clause, shall be a material breach of the contract and may be considered in any past performance evaluation of the Contractor.

(1) The Contractor shall submit ISRs and SSRs using the web-based eSRS at <http://www.esrs.gov>. Purchases from a corporation, company, or subdivision that is an affiliate of the Contractor or subcontractor are not included in these reports. Subcontract awards by affiliates shall be treated as subcontract awards by the Contractor. Subcontract award data reported by the Contractor and subcontractors shall be limited to awards made to their immediate next-tier subcontractors. Credit cannot be taken for awards made to lower tier subcontractors, unless the Contractor or subcontractor has been designated to receive a small business or small disadvantaged business credit from an ANC or Indian tribe. Only subcontracts involving performance in the United States or its outlying areas should be included in these reports with the exception of subcontracts under a contract awarded by the State Department or any other agency that has statutory or regulatory authority to require subcontracting plans for subcontracts performed outside the United States and its outlying areas.

(l) ISR. This report is not required for commercial plans. The report is required for each contract containing an individual subcontracting plan.

(i) The report shall be submitted semi-annually during contract performance for the periods ending March 31 and September 30. A report is also required for each contract within 30 days of contract completion. Reports are due 30 days after the close of each reporting period, unless otherwise directed by the Contracting Officer. Reports are required when due, regardless of whether there has been any subcontracting activity since the inception of the contract or the previous reporting period. When the Contracting Officer rejects an ISR, the Contractor shall submit a corrected report within 30 days of receiving the notice of ISR rejection.

(ii)(A) When a subcontracting plan contains separate goals for the basic contract and each option, as prescribed by FAR 19.704(c), the dollar goal inserted on this report shall be the sum of the base period through the current option; for example, for a report submitted after the second option is exercised, the dollar goal would be the sum of the goals for the basic contract, the first option, and the second option.

(B) If a subcontracting plan has been added to the contract pursuant to 19.702(a)(3) or 19.301-2(e), the Contractor's achievements must be reported in the ISR on a cumulative basis from the date of incorporation of the subcontracting plan into the contract.

(iii) When a subcontracting plan includes indirect costs in the goals, these costs must be included in this report.

(iv) The authority to acknowledge receipt or reject the ISR resides--

(A) In the case of the prime Contractor, with the Contracting Officer; and

(B) In the case of a subcontract with a subcontracting plan, with the entity that awarded the subcontract.

(2) SSR.

(i) Reports submitted under individual subcontracting plans.

(A) This report encompasses all subcontracting under prime contracts and subcontracts with an executive agency, regardless of the dollar value of the subcontracts. This report also includes indirect costs on a prorated basis when the indirect costs are excluded from the subcontracting goals.

(B) The report may be submitted on a corporate, company or subdivision (e.g. plant or division operating as a separate profit center) basis, unless otherwise directed by the agency.

(C) If the Contractor or a subcontractor is performing work for more than one executive agency, a separate report shall be submitted to each executive agency covering only that agency's contracts, provided at least one of that agency's contracts is over \$700,000 (over \$1.5 million for construction of a public facility) and contains a subcontracting plan. For DoD, a consolidated report shall be submitted for all contracts awarded by military departments/agencies and/or subcontracts awarded by DoD prime contractors.

(D) The report shall be submitted annually by October 30 for the twelve month period ending September 30. When a Contracting Officer rejects an SSR, the Contractor shall submit a revised report within 30 days of receiving the notice of SSR rejection.

(E) Subcontract awards that are related to work for more than one executive agency shall be appropriately allocated.

(F) The authority to acknowledge or reject SSRs in eSRS, including SSRs submitted by subcontractors with subcontracting plans, resides with the Government agency awarding the prime contracts unless stated otherwise in the contract.

(ii) Reports submitted under a commercial plan.

(A) The report shall include all subcontract awards under the commercial plan in effect during the Government's fiscal year and all indirect costs.

(B) The report shall be submitted annually, within thirty days after the end of the Government's fiscal year.

(C) If a Contractor has a commercial plan and is performing work for more than one executive agency, the Contractor shall specify the percentage of dollars attributable to each agency.

(D) The authority to acknowledge or reject SSRs for commercial plans resides with the Contracting Officer who approved the commercial plan.

(End of clause)

(a) Failure to make a good faith effort to comply with the subcontracting plan, as used in this clause, means a willful or intentional failure to perform in accordance with the requirements of the subcontracting plan approved under the clause in this contract entitled "Small Business Subcontracting Plan," or willful or intentional action to frustrate the plan.

(b) Performance shall be measured by applying the percentage goals to the total actual subcontracting dollars or, if a commercial plan is involved, to the pro rata share of actual subcontracting dollars attributable to Government contracts covered by the commercial plan. If, at contract completion or, in the case of a commercial plan, at the close of the fiscal year for which the plan is applicable, the Contractor has failed to meet its subcontracting goals and the Contracting Officer decides in accordance with paragraph (c) of this clause that the Contractor failed to make a good faith effort to comply with its subcontracting plan, established in accordance with the clause in this contract entitled "Small Business Subcontracting Plan," the Contractor shall pay the Government liquidated damages in an amount stated. The amount of probable damages attributable to the Contractor's failure to comply shall be an amount equal to the actual dollar amount by which the Contractor failed to achieve each subcontract goal.

(c) Before the Contracting Officer makes a final decision that the Contractor has failed to make such good faith effort, the Contracting Officer shall give the Contractor written notice specifying the failure and permitting the Contractor to demonstrate what good faith efforts have been made and to discuss the matter. Failure to respond to the notice may be taken as an admission that no valid explanation exists. If, after consideration of all the pertinent data, the Contracting Officer finds that the Contractor failed to make a good faith effort to comply with the subcontracting plan, the Contracting Officer shall issue a final decision to that effect and require that the Contractor

pay the Government liquidated damages as provided in paragraph (b) of this clause.

(d) With respect to commercial plans, the Contracting Officer who approved the plan will perform the functions of the Contracting Officer under this clause on behalf of all agencies with contracts covered by the commercial plan.

(e) The Contractor shall have the right of appeal, under the clause in this contract entitled Disputes, from any final decision of the Contracting Officer.

(f) Liquidated damages shall be in addition to any other remedies that the Government may have.

(End of clause)

52.219-28 POST-AWARD SMALL BUSINESS PROGRAM REREPRESENTATION (JULY 2013)

(a) Definitions. As used in this clause--

Long-term contract means a contract of more than five years in duration, including options. However, the term does not include contracts that exceed five years in duration because the period of performance has been extended for a cumulative period not to exceed six months under the clause at 52.217-8, Option to Extend Services, or other appropriate authority.

Small business concern means a concern, including its affiliates, that is independently owned and operated, not dominant in the field of operation in which it is bidding on Government contracts, and qualified as a small business under the criteria in 13 CFR part 121 and the size standard in paragraph (c) of this clause. Such a concern is "not dominant in its field of operation" when it does not exercise a controlling or major influence on a national basis in a kind of business activity in which a number of business concerns are primarily engaged. In determining whether dominance exists, consideration shall be given to all appropriate factors, including volume of business, number of employees, financial resources, competitive status or position, ownership or control of materials, processes, patents, license agreements, facilities, sales territory, and nature of business activity.

(b) If the Contractor represented that it was a small business concern prior to award of this contract, the Contractor shall rerepresent its size status according to paragraph (e) of this clause or, if applicable, paragraph (g) of this clause, upon the occurrence of any of the following:

(1) Within 30 days after execution of a novation agreement or within 30 days after modification of the contract to include this clause, if the novation agreement was executed prior to inclusion of this clause in the contract.

(2) Within 30 days after a merger or acquisition that does not require a novation or within 30 days after modification of the contract to include this clause, if the merger or acquisition occurred prior to inclusion of this clause in the contract.

(3) For long-term contracts--

(i) Within 60 to 120 days prior to the end of the fifth year of the contract; and

(ii) Within 60 to 120 days prior to the date specified in the contract for exercising any option thereafter.

(c) The Contractor shall rerepresent its size status in accordance with the size standard in effect at the time of this rerepresentation that corresponds to the North American Industry Classification System (NAICS) code assigned to this contract. The small business size standard corresponding to this NAICS code can be found at <http://www.sba.gov/content/table-small-business-size-standards>.

(d) The small business size standard for a Contractor providing a product which it does not manufacture itself, for a contract other than a construction or service contract, is 500 employees.

(e) Except as provided in paragraph (g) of this clause, the Contractor shall make the representation required by paragraph (b) of this clause by validating or updating all its representations in the Representations and Certifications section of the System for Award Management (SAM) and its other data in SAM, as necessary, to ensure that they reflect the Contractor's current status. The

Contractor shall notify the contracting office in writing within the timeframes specified in paragraph (b) of this clause that the data have been validated or updated, and provide the date of the validation or update.

(f) If the Contractor represented that it was other than a small business concern prior to award of this contract, the Contractor may, but is not required to, take the actions required by paragraphs (e) or (g) of this clause.

(g) If the Contractor does not have representations and certifications in SAM, or does not have a representation in SAM for the NAICS code applicable to this contract, the Contractor is required to complete the following rerepresentation and submit it to the contracting office, along with the contract number and the date on which the rerepresentation was completed:

The Contractor represents that it () is, () is not a small business concern under NAICS Code 237990- assigned to contract number .

(Contractor to sign and date and insert authorized signer's name and title).

(End of clause)

52.222-1 NOTICE TO THE GOVERNMENT OF LABOR DISPUTES (FEB 1997)

If the Contractor has knowledge that any actual or potential labor dispute is delaying or threatens to delay the timely performance of this contract, the Contractor shall immediately give notice, including all relevant information, to the Contracting Officer.

52.222-3 **Convict Labor (JUN 2003)**

(a) Except as provided in paragraph (b) of this clause, the Contractor shall not employ in the performance of this contract any person undergoing a sentence of imprisonment imposed by any court of a State, the District of Columbia, Puerto Rico, the Northern Mariana Islands, American Samoa, Guam, or the U.S. Virgin Islands.

(b) The Contractor is not prohibited from employing persons--

(1) On parole or probation to work at paid employment during the term of their sentence;

(2) Who have been pardoned or who have served their terms; or

(3) Confined for violation of the laws of any of the States, the District of Columbia, Puerto Rico, the Northern Mariana Islands, American Samoa, Guam, or the U.S. Virgin Islands who are authorized to work at paid employment in the community under the laws of such jurisdiction, if--

(i) The worker is paid or is in an approved work training program on a voluntary basis;

(ii) Representatives of local union central bodies or similar labor union organizations have been consulted;

(iii) Such paid employment will not result in the displacement of employed workers, or be applied in skills, crafts, or trades in which there is a surplus of available gainful labor in the locality, or impair existing contracts for services;

(iv) The rates of pay and other conditions of employment will not be less than those paid or provided for work of a similar nature in the locality in which the work is being performed; and

(v) The Attorney General of the United States has certified that the work-release laws or **regulations** of the jurisdiction involved are in conformity with the requirements of Executive Order 11755, as amended by Executive Orders 12608 and 12943.

(End of clause)

52.222-4 **Contract Work Hours and Safety Standards - Overtime Compensation. (MAY 2014)**

(a) Overtime requirements. No Contractor or subcontractor employing laborers or mechanics (see Federal Acquisition Regulation 22.300) shall require or permit them to work over 40 hours in any workweek unless they are paid at least 1 and 1/2 times the basic rate of pay for each hour worked over 40 hours.

(b) Violation; liability for unpaid wages; liquidated damages. The responsible Contractor and subcontractor are liable for unpaid wages if they violate the terms in paragraph (a) of this clause. In addition, the Contractor and subcontractor are liable for liquidated damages payable to the Government. The Contracting Officer will assess liquidated damages at the rate of \$10 per affected employee for each calendar day on which the employer required or permitted the employee to work in excess of the standard workweek of 40 hours without paying overtime wages required by the Contract Work Hours and Safety Standards statute (found at 40 U.S.C. chapter 37).

(c) Withholding for unpaid wages and liquidated damages. The Contracting Officer will withhold from payments due under the contract sufficient funds required to satisfy any Contractor or subcontractor liabilities for unpaid wages and liquidated damages. If amounts withheld under the contract are insufficient to satisfy Contractor or subcontractor liabilities, the Contracting Officer will withhold payments from other Federal or Federally assisted contracts held by the same Contractor that are subject to the Contract Work Hours and Safety Standards statute.

(d) Payrolls and basic records.

(1) The Contractor and its subcontractors shall maintain payrolls and basic payroll records for all laborers and mechanics working on the contract during the contract and shall make them available to the Government until 3 years after contract completion. The records shall contain the name and address of each employee, social security number, labor classifications, hourly rates of wages paid, daily and weekly number of hours worked, deductions made, and actual wages paid. The records need not duplicate those required for construction work by Department of Labor regulations at 29 CFR 5.5(a)(3) implementing the Construction Wage Rate Requirements statute.

(2) The Contractor and its subcontractors shall allow authorized representatives of the Contracting Officer or the Department of Labor to inspect, copy, or transcribe records maintained under paragraph (d)(1) of this clause. The Contractor or subcontractor also shall allow authorized representatives of the Contracting Officer or Department of Labor to interview employees in the workplace during working hours.

(e) Subcontracts. The Contractor shall insert the provisions set forth in paragraphs (a) through (d) of this clause in subcontracts that may require or involve the employment of laborers and mechanics and require subcontractors to include these provisions in any such lower tier subcontracts. The Contractor shall be responsible for compliance by any subcontractor or lower-tier subcontractor with the provisions set forth in paragraphs (a) through (d) of this clause.

(End of clause)

52.222-6 Construction Wage Rate Requirements (MAY 2014)

(a) Definition.—“Site of the work”—

(1) Means—

(i) *The primary site of the work.* The physical place or places where the construction called for in the contract will remain when work on it is completed; and

(ii) *The secondary site of the work, if any.* Any other site where a significant portion of the building or work is constructed, provided that such site is—

(A) Located in the United States; and

(B) Established specifically for the performance of the contract or project;

(2) Except as provided in paragraph (3) of this definition, includes any fabrication plants, mobile factories, batch plants, borrow pits, job headquarters, tool yards, etc., provided—

(i) They are dedicated exclusively, or nearly so, to performance of the contract or project; and

(ii) They are adjacent or virtually adjacent to the “primary site of the work” as defined in paragraph (a)(1)(i), or the “secondary site of the work” as defined in paragraph (a)(1)(ii) of this definition;

(3) Does not include permanent home offices, branch plant establishments, fabrication plants, or tool yards of a Contractor or subcontractor whose locations and continuance in operation are determined wholly without regard to a

particular Federal contract or project. In addition, fabrication plants, batch plants, borrow pits, job headquarters, yards, etc., of a commercial or material supplier which are established by a supplier of materials for the project before opening of bids and not on the Project site, are not included in the "site of the work." Such permanent, previously established facilities are not a part of the "site of the work" even if the operations for a period of time may be dedicated exclusively or nearly so, to the performance of a contract.

(b)(1) All laborers and mechanics employed or working upon the site of the work will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR part 3)), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, or as may be incorporated for a secondary site of the work, regardless of any contractual relationship which may be alleged to exist between the Contractor and such laborers and mechanics. Any wage determination incorporated for a secondary site of the work shall be effective from the first day on which work under the contract was performed at that site and shall be incorporated without any adjustment in contract price or estimated cost. Laborers employed by the construction Contractor or construction subcontractor that are transporting portions of the building or work between the secondary site of the work and the primary site of the work shall be paid in accordance with the wage determination applicable to the primary site of the work.

(2) Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Construction Wage Rate Requirements statute on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of paragraph (e) of this clause; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such period.

(3) Such laborers and mechanics shall be paid not less than the appropriate wage rate and fringe benefits in the wage determination for the classification of work actually performed, without regard to skill, except as provided in the clause entitled Apprentices and Trainees. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein; provided that the employer's payroll records accurately set forth the time spent in each classification in which work is performed.

(4) The wage determination (including any additional classifications and wage rates conformed under paragraph (c) of this clause) and the Construction Wage Rate Requirements statute poster (WH-1321) shall be posted at all times by the Contractor and its subcontractors at the primary site of the work and the secondary site of the work, if any, in a prominent and accessible place where it can be easily seen by the workers.

(c)(1) The Contracting Officer shall require that any class of laborers or mechanics which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. The Contracting Officer shall approve an additional classification and wage rate and fringe benefits therefor only when all the following criteria have been met:

(i) The work to be performed by the classification requested is not performed by a classification in the wage determination.

(ii) The classification is utilized in the area by the construction industry.

(iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.

(2) If the Contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the Contracting Officer agree on the classification and wage rate (including the amount designated for fringe benefits, where appropriate), a report of the action taken shall be sent by the Contracting Officer to the Administrator of the:

Wage and Hour Division
Employment Standards Administration
U.S. Department of Labor
Washington, DC 20210

The Administrator or an authorized representative will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the Contracting Officer or will notify the Contracting Officer within the 30-day period that additional time is necessary.

(3) In the event the Contractor, the laborers or mechanics to be employed in the classification, or their representatives, and the Contracting Officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the Contracting Officer shall refer the questions, including the views of all interested parties and the recommendation of the Contracting Officer, to the Administrator of the Wage and Hour Division for determination. The Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the Contracting Officer or will notify the Contracting Officer within the 30-day period that additional time is necessary.

(4) The wage rate (including fringe benefits, where appropriate) determined pursuant to paragraphs (c)(2) and (c)(3) of this clause shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.

(d) Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the Contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.

(e) If the Contractor does not make payments to a trustee or other third person, the Contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program; provided, That the Secretary of Labor has found, upon the written request of the Contractor, that the applicable standards of the Construction Wage Rate Requirements statute have been met. The Secretary of Labor may require the Contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

(End of clause)

52.222-7 WITHHOLDING OF FUNDS (MAY 2014)

The Contracting Officer shall, upon his or her own action or upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the Contractor under this contract or any other Federal contract with the same Prime Contractor, or any other Federally assisted contract subject to Construction Wage Rate Requirements statute prevailing wage requirements, which is held by the same Prime Contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the Contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the Contracting Officer may, after written notice to the Contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

(End of clause)

52.222-8 PAYROLLS AND BASIC RECORDS (MAY 2014)

(a) Payrolls and basic records relating thereto shall be maintained by the Contractor during the course of the work and preserved for a period of 3 years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such worker, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in 40 U.S.C. 3141(2)(B) (Construction Wage Rate

Requirement statute)), daily and weekly number of hours worked, deductions made, and actual wages paid. Whenever the Secretary of Labor has found, under paragraph (d) of the clause entitled Construction Wage Rate Requirements, that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in 40 U.S.C. 3141(2)(B), the Contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.

(b)(1) The Contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the Contracting Officer. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under paragraph(a) of this clause, except that full social security numbers and home addresses shall not be included on weekly transmittals. Instead the payrolls shall only need to include an individually identifying number for each employee (e.g., the last four digits of the employee's social security number). The required weekly payroll information may be submitted in any form desired. Optional Form WH-347 is available for this purpose and may be obtained from the U.S. Department of Labor Wage and Hour Division website at <http://www.dol.gov/whd/forms/wh347.pdf>. The Prime Contractor is responsible for the submission of copies of payrolls by all subcontractors. Contractors and subcontractors shall maintain the full social security number and current address of each covered worker, and shall provide them upon request to the Contracting Officer, the Contractor, or the Wage and Hour Division of the Department of Labor for purposes of an investigation or audit of compliance with prevailing wage requirements. It is not a violation of this section for a Prime Contractor to require a subcontractor to provide addresses and social security numbers to the Prime Contractor for its own records, without weekly submission to the Contracting Officer.

(2) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the Contractor or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify--

(i) That the payroll for the payroll period contains the information required to be maintained under paragraph (a) of this clause and that such information is correct and complete;

(ii) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR Part 3; and

(iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.

(3) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by subparagraph (b)(2) of this clause.

(4) The falsification of any of the certifications in this clause may subject the Contractor or subcontractor to civil or criminal prosecution under Section 1001 of Title 18 and Section 3729 of Title 31 of the United States Code.

(c) The Contractor or subcontractor shall make the records required under paragraph (a) of this clause available for inspection, copying, or transcription by the Contracting Officer or authorized representatives of the Contracting Officer or the Department of Labor. The Contractor or subcontractor shall permit the Contracting Officer or representatives of the Contracting Officer or the Department of Labor to interview employees during working hours on the job. If the Contractor or subcontractor fails to submit required records or to make them available, the

Contracting Officer may, after written notice to the Contractor, take such action as may be necessary to cause the suspension of any further payment. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

(End of clause)

52.222-9 APPRENTICES AND TRAINEES (JUL 2005)

(a) Apprentices. (1) An apprentice will be permitted to work at less than the predetermined rate for the work performed when employed--

(i) Pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship Training, Employer, and Labor Services (OATELS) or with a State Apprenticeship Agency recognized by the OATELS; or

(ii) In the first 90 days of probationary employment as an apprentice in such an apprenticeship program, even though not individually registered in the program, if certified by the OATELS or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice.

(2) The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the Contractor as to the entire work force under the registered program.

(3) Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated in paragraph (a)(1) of this clause, shall be paid not less than the applicable wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.

(4) Where a Contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the Contractor's or subcontractor's registered program shall be observed. Every apprentice must be paid at not less than

the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination.

(5) Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.

(6) In the event OATELS, or a State Apprenticeship Agency recognized by OATELS, withdraws approval of an apprenticeship program, the Contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

(b) Trainees.

(1) Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship Training, Employer, and Labor Services (OATELS). The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by OATELS.

(2) Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination.

Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed in the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate in the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the OATELS shall be paid not less than the applicable wage rate in the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate in the wage determination for the work actually performed.

(3) In the event OATELS withdraws approval of a training program, the Contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

(c) Equal employment opportunity. The utilization of apprentices, trainees, and journeymen under this clause shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR Part 30.

(End of clause)

52.222-10 COMPLIANCE WITH COPELAND ACT REQUIREMENTS (FEB 1988)

The Contractor shall comply with the requirements of 29 CFR Part 3, which are hereby incorporated by reference in this contract.

(End of clause)

(a) Definition. Construction, alteration or repair, as used in this clause, means all types of work done by laborers and mechanics employed by the construction Contractor or construction subcontractor on a particular building or work at the site thereof, including without limitation--

- (1) Altering, remodeling, installation (if appropriate) on the site of the work of items fabricated off-site;
- (2) Painting and decorating;
- (3) Manufacturing or furnishing of materials, articles, supplies, or equipment on the site of the building or work;
- (4) Transportation of materials and supplies between the site of the work within the meaning of paragraphs (a)(1)(i) and (ii) of the "site of work" as defined in the FAR clause at 52.222-6, Construction Wage Rate Requirements of this contract, and a facility which is dedicated to the construction of the building or work and is deemed part of the site of the work within the meaning of paragraph (2) of the "site of work" definition; and
- (5) Transportation of portions of the building or work between a secondary site where a significant portion of the building or work is constructed, which is part of the "site of work" definition in paragraph (a)(1)(ii) of the FAR clause at 52.222-6, Construction Wage Rate Requirements, and the physical place or places where the building or work will remain (paragraph (a)(1)(i) of the FAR clause at 52.222-6, in the "site of the work" definition).

(b) The Contractor shall insert in any subcontracts for construction, alterations and repairs within the United States the clauses entitled--

- (1) Construction Wage Rate Requirements;
- (2) Contract Work Hours and Safety Standards--Overtime Compensation (if the clause is included in this contract);
- (3) Apprentices and Trainees;
- (4) Payrolls and Basic Records;
- (5) Compliance with Copeland Act Requirements;
- (6) Withholding of Funds;
- (7) Subcontracts (Labor Standards);
- (8) Contract Termination--Debarment;
- (9) Disputes Concerning Labor Standards;
- (10) Compliance with Construction Wage Rate Requirements and Related Regulations; and
- (11) Certification of Eligibility.

(c) The prime Contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor performing construction within the United States with all the contract clauses cited in paragraph (b).

(d)(1) Within 14 days after award of the contract, the Contractor shall deliver to the Contracting Officer a completed Standard Form (SF) 1413, Statement and Acknowledgment, for each subcontract for construction within the United States, including the subcontractor's signed and dated acknowledgment that the clauses set forth in paragraph (b) of this clause have been included in the subcontract.

(2) Within 14 days after the award of any subsequently awarded subcontract the Contractor shall deliver to the Contracting Officer an updated completed SF 1413 for such additional subcontract.

(e) The Contractor shall insert the substance of this clause, including this paragraph (e) in all subcontracts for construction within the United States.

(End of clause)

52.222-12 CONTRACT TERMINATION--DEBARMENT (MAY 2014)

A breach of the contract clauses entitled Construction Wage Rate Requirements, Contract Work Hours and Safety Standards--Overtime Compensation, Apprentices and Trainees, Payrolls and Basic Records, Compliance with Copeland Act Requirements, Subcontracts (Labor Standards), Compliance with Construction Wage Rate Requirements and Related Regulations, or Certification of Eligibility may be grounds for termination of the contract, and for debarment as a Contractor and subcontractor as provided in 29 CFR 5.12.

(End of clause)

52.222-13 Compliance With Construction Wage Rate Requirements and Related Regulations (MAY 2014)

All rulings and interpretations of the Construction Wage Rate Requirements and related statutes contained in 29 CFR parts 1, 3, and 5 are hereby incorporated by reference in this contract.

(End of clause)

52.222-14 DISPUTES CONCERNING LABOR STANDARDS (FEB 1988)

The United States Department of Labor has set forth in 29 CFR Parts 5, 6, and 7 procedures for resolving disputes concerning labor standards requirements. Such disputes shall be resolved in accordance with those procedures and not the Disputes clause of this contract. Disputes within the meaning of this clause include disputes between the Contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

(End of clause)

52.222-15 CERTIFICATION OF ELIGIBILITY (MAY 2014)

(a) By entering into this contract, the Contractor certifies that neither it nor any person or firm who has an interest in the Contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of 40 U.S.C. 3144(b)(2) or 29 CFR 5.12(a)(1).

(b) No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of 40 U.S.C. 3144(b)(2) or 29 CFR 5.12(a)(1).

(c) The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 U.S.C. 1001.

(End of clause)

52.222-17 Nondisplacement of Qualified Workers (MAY 2014)

(a) Service employee, as used in this clause, means any person engaged in the performance of a service contract other than any person employed in a bona fide executive, administrative, or professional capacity, as those terms are defined in 29 CFR part 541. The term "service employee" includes all such persons regardless of any contractual relationship that may be alleged to exist between a contractor or subcontractor and such persons.

(b) The Contractor and its subcontractors shall, except as otherwise provided herein, in good faith offer those service employees employed under the predecessor contract whose employment will be terminated as a result of award of this contract or the expiration of the contract under which the service employees were hired, a right of first refusal of employment under this contract in positions for which the service employees are qualified.

(1) The Contractor and its subcontractors shall determine the number of service employees necessary for efficient performance of this contract and may elect to employ fewer employees than the predecessor Contractor employed in connection with performance of the work.

(2) Except as provided in paragraph (c) of this clause, there shall be no employment opening under this contract, and the Contractor and any subcontractors shall not offer employment under this contract, to any person prior to having complied fully with this obligation.

(i) The successor Contractor and its subcontractors shall make a bona fide express offer of employment to each service employee as provided herein and shall state the time within which the service employee must accept such offer, but in no case shall the period within which the service employee must accept the offer of employment be less than 10 days.

(ii) The successor Contractor and its subcontractors shall decide any question concerning a service employee's qualifications based upon the individual's education and employment history, with particular emphasis on the employee's experience on the predecessor contract, and the Contractor may utilize employment screening processes only when such processes are provided for by the contracting agency, are conditions of the service contract, and are consistent with Executive Order 13495.

(iii) Where the successor Contractor does not initially offer employment to all the predecessor contract service employees, the obligation to offer employment shall continue for 90 days after the successor contractor's first date of performance on the contract.

(iv) An offer of employment will be presumed to be bona fide even if it is not for a position similar to the one the employee previously held, but is one for which the employee is qualified, and even if it is subject to different employment terms and conditions, including changes to pay or benefits. (See 29 CFR 9.12 for a detailed description of a bonafide offer of employment).

(c)(1) Notwithstanding the obligation under paragraph (b) of this clause, the successor Contractor and any subcontractors (i) may employ under this contract any service employee who has worked for the contractor or subcontractor for at least three months immediately preceding the commencement of this contract and who would otherwise face lay-off or discharge, (ii) are not required to offer a right of first refusal to any service employee(s) of the predecessor contractor who are not service employees within the meaning of the Service Contract Labor Standards statute, 41 U.S.C. 6701(3), and (iii) are not required to offer a right of first refusal to any service employee(s) of the predecessor contractor whom the Contractor or any of its subcontractors reasonably believes, based on the particular service employee's past performance, has failed to perform suitably on the job (see 29 CFR 9.12(c)(4) for additional information). The successor Contractor bears the responsibility of demonstrating the appropriateness of claiming any of these exceptions.

(2) In addition, any Contractor or subcontractor that has been certified by the U.S. Small Business Administration as a HUBZone small business concern must ensure that it complies with the statutory and regulatory requirements of the HUBZone Program (e.g., it must ensure that at least 35 percent of all of its employees reside within a HUBZone). The HUBZone small business Contractor or subcontractor must consider whether it can meet the requirements of this clause and Executive Order 13495 while also ensuring it meets the HUBZone Program's requirements.

(3) Nothing in this clause shall be construed to permit a Contractor or subcontractor to fail to comply with any provision of any other Executive order or law. For example, the requirements of the HUBZone Program (see FAR subpart 19.13), Executive Order 11246 (Equal Employment Opportunity), and the Vietnam Era Veterans' Readjustment Assistance Act of 1974 may conflict, in certain circumstances, with the requirements of Executive Order 13495. All applicable laws and Executive orders must be satisfied in tandem with, and if necessary prior to, the requirements of Executive Order 13495, 29 CFR part 9, and this clause.

(d)(1) The Contractor shall, not less than 30 days before completion of the Contractor's performance of services on the contract, furnish the Contracting Officer with a certified list of the names of all service employees working under this contract and its subcontracts at the time the list is submitted. The list shall also contain anniversary dates of employment of each service employee under this contract and its predecessor contracts with either the current or predecessor contractors or their subcontractors. Where changes to the workforce are made after the submission of the certified list described in this paragraph, the Contractor shall, in accordance with paragraph (e) of this clause, not less than 10 days before completion of the services on this contract, furnish the Contracting Officer with an updated certified list of the names of all service employees employed within the last month of contract performance. The updated list shall also contain anniversary dates of employment, and, where applicable, dates of

separation of each service employee under the contract and its predecessor contracts with either the current or predecessor Contractors or their subcontractors.

(2) Immediately upon receipt of the certified service employee list but not before contract award, the contracting officer shall provide the certified service employee list to the successor contractor, and, if requested, to employees of the predecessor contractor or subcontractors or their authorized representatives.

(3) The Contracting Officer will direct the predecessor Contractor to provide written notice (Appendix B to 29 CFR chapter 9) to service employees of their possible right to an offer of employment with the successor contractor. Where a significant portion of the predecessor Contractor's workforce is not fluent in English, the notice shall be provided in English and the language(s) with which service employees are more familiar. The written notice shall be—

(i) Posted in a conspicuous place at the worksite; or (ii) Delivered to the service employees individually. If such delivery is via email, the notification must result in an electronic delivery receipt or some other reliable confirmation that the intended recipient received the notice.

(e)(1) If required in accordance with 52.222-41(n), the predecessor Contractor shall, not less than 10 days before completion of this contract, furnish the Contracting Officer a certified list of the names of all service employees working under this contract and its subcontracts during the last month of contract performance. The list shall also contain anniversary dates of employment of each service employee under this contract and its predecessor contracts either with the current or predecessor Contractors or their subcontractors. If there are no changes to the workforce before the predecessor contract is completed, then the predecessor Contractor is not required to submit a revised list 10 days prior to completion of performance and the requirements of 52.222-41(n) are met. When there are changes to the workforce after submission of the 30-day list, the predecessor Contractor shall submit a revised certified list not less than 10 days prior to performance completion.

(2) Immediately upon receipt of the certified service employee list but not before contract award, the contracting officer shall provide the certified service employee list to the successor contractor, and, if requested, to employees of the predecessor contractor or subcontractors or their authorized representatives.

(f) The Contractor and subcontractor shall maintain the following records (regardless of format, e.g., paper or electronic) of its compliance with this clause for not less than a period of three years from the date the records were created.

(1) Copies of any written offers of employment or a contemporaneous written record of any oral offers of employment, including the date, location, and attendance roster of any service employee meeting(s) at which the offers were extended, a summary of each meeting, a copy of any written notice that may have been distributed, and the names of the service employees from the predecessor contract to whom an offer was made.

(2) A copy of any record that forms the basis for any exemption claimed under this part.

(3) A copy of the service employee list provided to or received from the contracting agency.

(4) An entry on the pay records of the amount of any retroactive payment of wages or compensation under the supervision of the Administrator of the Wage and Hour Division to each service employee, the period covered by such payment, and the date of payment, and a copy of any receipt form provided by or authorized by the Wage and Hour Division. The Contractor shall also deliver a copy of the receipt to the service employee and file the original, as evidence of payment by the Contractor and receipt by the service employee, with the Administrator or an authorized representative within 10 days after payment is made.

(g) Disputes concerning the requirements of this clause shall not be subject to the general disputes clause (52.233-1) of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set

forth in 29 CFR part 9. Disputes within the meaning of this clause include disputes between or among any of the following: The Contractor, the contracting agency, the U.S. Department of Labor, and the service employees under the contract or its predecessor contract. The Contracting Officer will refer any service employee who wishes to file a complaint, or ask questions concerning this contract clause, to the: Branch of Government Contracts Enforcement, Wage and Hour Division, U.S. Department of Labor, 200 Constitution Avenue NW., Washington, DC 20210. Contact email: displaced@dol.gov.

(h) The Contractor shall cooperate in any review or investigation by the Department of Labor into possible violations of the provisions of this clause and shall make such records requested by such official(s) available for inspection, copying, or transcription upon request.

(i) If it is determined, pursuant to regulations issued by the Secretary of Labor (Secretary), that the Contractor or its subcontractors are not in compliance with the requirements of this clause or any regulation or order of the Secretary, appropriate sanctions may be imposed and remedies invoked against the Contractor or its subcontractors, as provided in Executive Order 13495, the regulations, and relevant orders of the Secretary, or as otherwise provided by law.

(j) The Contractor shall take such action with respect to any such subcontract as may be directed by the Secretary of Labor as a means of enforcing such provisions, including the imposition of sanctions for noncompliance. However, if the Contractor, as a result of such direction, becomes involved in litigation with a subcontractor, or is threatened with such involvement, the Contractor may request that the United States, through the Secretary, enter into such litigation to protect the interests of the United States.

(k) The Contracting Officer will withhold, or cause to be withheld, from the prime Contractor under this or any other Government contract with the same prime Contractor, such sums as an authorized official of the Department of Labor requests, upon a determination by the Administrator, the Administrative Law Judge, or the Administrative Review Board, that there has been a failure to comply with the terms of this clause and that wages lost as a result of the violations are due to service employees or that other monetary relief is appropriate. If the Contracting Officer or the Administrator, upon final order of the Secretary, finds that the Contractor has failed to provide a list of the

names of service employees working under the contract, the Contracting Officer may, in his or her discretion, or upon request by the Administrator, take such action as may be necessary to cause the suspension of the payment of contract funds until such time as the list is provided to the Contracting Officer.

(l) Subcontracts. In every subcontract over the simplified acquisition threshold entered into in order to perform services under this contract, the Contractor shall include a provision that ensures—

(1) That each subcontractor will honor the requirements of paragraphs (b) through (c) of this clause with respect to the service employees of a predecessor subcontractor or subcontractors working under this contract, as well as of a predecessor Contractor and its subcontractors;

(2) That the subcontractor will provide the Contractor with the information about the service employees of the subcontractor needed by the Contractor to comply with paragraphs (d) and (e) of this clause; and

(3) The recordkeeping requirements of paragraph (f) of this clause.

52.222-21 PROHIBITION OF SEGREGATED FACILITIES (APR 2015)

(a) Definitions. As used in this clause--

Gender identity has the meaning given by the Department of Labor's Office of Federal Contract Compliance Programs, and is found at www.dol.gov/ofccp/LGBT/LGBT_FAQs.html.

Segregated facilities means any waiting rooms, work areas, rest rooms and wash rooms, restaurants and other eating areas, time clocks, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees, that are segregated by explicit directive or are in fact segregated on the basis of race, color, religion, sex, sexual orientation, gender identity, or national origin because of written or oral policies or employee custom. The term does not include separate or single-user rest rooms or necessary dressing or sleeping areas provided to assure privacy between the sexes.

Sexual orientation has the meaning given by the Department of Labor's Office of Federal Contract Compliance Programs, and is found at www.dol.gov/ofccp/LGBT/LGBT_FAQs.html.

(b) The Contractor agrees that it does not and will not maintain or provide for its employees any segregated facilities at any of its establishments, and that it does not and will not permit its employees to perform their services at any location under its control where segregated facilities are maintained. The Contractor agrees that a breach of this clause is a violation of the Equal Opportunity clause in this contract.

(c) The Contractor shall include this clause in every subcontract and purchase order that is subject to the Equal Opportunity clause of this contract.

(End of clause)

52.222-26 EQUAL OPPORTUNITY (APR 2015)

(a) Definitions. As used in this clause--

Gender identity has the meaning given by the Department of Labor's Office of Federal Contract Compliance Programs, and is found at www.dol.gov/ofccp/LGBT/LGBT_FAQs.html.

Sexual orientation has the meaning given by the Department of Labor's Office of Federal Contract Compliance Programs, and is found at www.dol.gov/ofccp/LGBT/LGBT_FAQs.html.

United States means the 50 States, the District of Columbia, Puerto Rico, the Northern Mariana Islands, American Samoa, Guam, the U.S. Virgin Islands, and Wake Island.

(b)(1) If, during any 12-month period (including the 12 months preceding the award of this contract), the Contractor has been or is awarded nonexempt Federal contracts and/or subcontracts that have an aggregate value in excess of \$10,000, the Contractor shall comply with this clause, except for work performed outside the United States by employees who were not recruited within the United States. Upon request, the Contractor shall provide information necessary to determine the applicability of this clause.

(2) If the Contractor is a religious corporation, association, educational institution, or society, the requirements of this clause do not apply with respect to the employment of individuals of a particular religion to perform work connected with the carrying on of the Contractor's activities (41 CFR 60-1.5).

(c) (1) The Contractor shall not discriminate against any employee or applicant for employment because of race, color, religion, sex, sexual orientation, gender identity, or national origin. However, it shall not be a violation of this clause for the Contractor to extend a publicly announced preference in employment to Indians living on or near an Indian reservation, in connection with employment opportunities on or near an Indian reservation, as permitted by 41 CFR 60-1.5.

(2) The Contractor shall take affirmative action to ensure that applicants are employed, and that employees are treated during employment, without regard to their race, color, religion, sex, sexual orientation, gender identity, or national origin. This shall include, but not be limited to, (i) employment, (ii) upgrading, (iii) demotion, (iv) transfer,

(v) recruitment or recruitment advertising, (vi) layoff or termination, (vii) rates of pay or other forms of compensation, and (viii) selection for training, including apprenticeship.

(3) The Contractor shall post in conspicuous places available to employees and applicants for employment the notices to be provided by the Contracting Officer that explain this clause.

(4) The Contractor shall, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, color, religion, sex, sexual orientation, gender identity, or national origin.

(5) The Contractor shall send, to each labor union or representative of workers with which it has a collective bargaining agreement or other contract or understanding, the notice to be provided by the Contracting Officer advising the labor union or workers' representative of the Contractor's commitments under this clause, and post copies of the notice in conspicuous places available to employees and applicants for employment.

(6) The Contractor shall comply with Executive Order 11246, as amended, and the rules, regulations, and orders of the Secretary of Labor.

(7) The Contractor shall furnish to the contracting agency all information required by Executive Order 11246, as amended, and by the rules, regulations, and orders of the Secretary of Labor. The Contractor shall also file Standard Form 100 (EEO-1), or any successor form, as prescribed in 41 CFR part 60-1. Unless the Contractor has filed within the 12 months preceding the date of contract award, the Contractor shall, within 30 days after contract award, apply to either the regional Office of Federal Contract Compliance Programs (OFCCP) or the local office of the Equal Employment Opportunity Commission for the necessary forms.

(8) The Contractor shall permit access to its premises, during normal business hours, by the contracting agency or the OFCCP for the purpose of conducting on-site compliance evaluations and complaint investigations. The Contractor shall permit the Government to inspect and copy any books, accounts, records (including computerized

records), and other material that may be relevant to the matter under investigation and pertinent to compliance with Executive Order 11246, as amended, and rules and regulations that implement the Executive Order.

(9) If the OFCCP determines that the Contractor is not in compliance with this clause or any rule, regulation, or order of the Secretary of Labor, this contract may be canceled, terminated, or suspended in whole or in part and the Contractor may be declared ineligible for further Government contracts, under the procedures authorized in Executive Order 11246, as amended. In addition, sanctions may be imposed and remedies invoked against the Contractor as provided in Executive Order 11246, as amended; in the rules, regulations, and orders of the Secretary of Labor; or as otherwise provided by law.

(10) The Contractor shall include the terms and conditions of this clause in every subcontract or purchase order that is not exempted by the rules, regulations, or orders of the Secretary of Labor issued under Executive Order 11246, as amended, so that these terms and conditions will be binding upon each subcontractor or vendor.

(11) The Contractor shall take such action with respect to any subcontract or purchase order as the contracting officer may direct as a means of enforcing these terms and conditions, including sanctions for noncompliance; provided, that if the Contractor becomes involved in, or is threatened with, litigation with a subcontractor or vendor as a result of any direction, the Contractor may request the United States to enter into the litigation to protect the interests of the United States.

(d) Notwithstanding any other clause in this contract, disputes relative to this clause will be governed by the procedures in 41 CFR 60-1.1.

(End of clause)

52.222-27 AFFIRMATIVE ACTION COMPLIANCE REQUIREMENTS FOR CONSTRUCTION (APR 2015)

(a) Definitions. "Covered area" means the geographical area described in the solicitation for this contract.

"Deputy Assistant Secretary" means the Deputy Assistant Secretary for Federal Contract Compliance, U.S. Department of Labor, or a designee.

"Employer's identification number" means the Federal Social Security number used on the employer's quarterly Federal tax return, U.S. Treasury Department Form 941.

"Gender identity" has the meaning given by the Department of Labor's Office of Federal Contract Compliance Programs, and is found at www.dol.gov/ofccp/LGBT/LGBT_FAQs.html.

"Minority" means --

(1) American Indian or Alaskan Native (all persons having origins in any of the original peoples of North America and maintaining identifiable tribal affiliations through membership and participation or community identification).

(2) Asian and Pacific Islander (all persons having origins in any of the original peoples of the Far East, Southeast Asia, the Indian Subcontinent, or the Pacific Islands);

(3) Black (all persons having origins in any of the black African racial groups not of Hispanic origin); and

(4) Hispanic (all persons of Mexican, Puerto Rican, Cuban, Central or South American, or other Spanish culture or origin, regardless of race).

“Sexual orientation” has the meaning given by the Department of Labor’s Office of Federal Contract Compliance Programs, and is found at www.dol.gov/ofccp/LGBT/LGBT_FAQs.html.

(b) If the Contractor, or a subcontractor at any tier, subcontracts a portion of the work involving any construction trade, each such subcontract in excess of \$10,000 shall include this clause and the Notice containing the goals for minority and female participation stated in the solicitation for this contract.

(c) If the Contractor is participating in a Hometown Plan (41 CFR 60-4) approved by the U.S. Department of Labor in a covered area, either individually or through an association, its affirmative action obligations on all work in the plan area (including goals) shall comply with the plan for those trades that have unions participating in the plan. Contractors must be able to demonstrate participation in, and compliance with, the provisions of the plan. Each Contractor or subcontractor participating in an approved plan is also required to comply with its obligations under the Equal Opportunity clause, and to make a good faith effort to achieve each goal under the plan in each trade in which it has employees. The overall good-faith performance by other Contractors or subcontractors toward a goal in an approved plan does not excuse any Contractor's or subcontractor's failure to make good-faith efforts to achieve the plan's goals.

(d) The Contractor shall implement the affirmative action procedures in subparagraphs (g)(1) through (16) of this clause. The goals stated in the solicitation for this contract are expressed as percentages of the total hours of employment and training of minority and female utilization that the Contractor should reasonably be able to achieve in each construction trade in which it has employees in the covered area. If the Contractor performs construction work in a geographical area located outside of the covered area, it shall apply the goals established for the

geographical area where that work is actually performed. The Contractor is expected to make substantially uniform progress toward its goals in each craft.

(e) Neither the terms and conditions of any collective bargaining agreement, nor the failure by a union with which the Contractor has a collective bargaining agreement, to refer minorities or women shall excuse the Contractor's obligations under this clause, Executive Order 11246, as amended, or the regulations thereunder.

(f) In order for the nonworking training hours of apprentices and trainees to be counted in meeting the goals, apprentices and trainees must be employed by the Contractor during the training period, and the Contractor must have made a commitment to employ the apprentices and trainees at the completion of their training, subject to the availability of employment opportunities. Trainees must be trained pursuant to training programs approved by the U.S. Department of Labor.

(g) The Contractor shall take affirmative action to ensure equal employment opportunity. The evaluation of the Contractor's compliance with this clause shall be based upon its effort to achieve maximum results from its actions. The Contractor shall document these efforts fully and implement affirmative action steps at least as extensive as the following:

(1) Ensure a working environment free of harassment, intimidation, and coercion at all sites and in all facilities where the Contractor's employees are assigned to work. The Contractor, if possible, will assign two or more women to each construction project. The Contractor shall ensure that foremen, superintendents, and other onsite supervisory personnel are aware of and carry out the Contractor's obligation to maintain such a working environment, with specific attention to minority or female individuals working at these sites or facilities.

(2) Establish and maintain a current list of sources for minority and female recruitment. Provide written notification to minority and female recruitment sources and community organizations when the Contractor or its unions have employment opportunities available, and maintain a record of the organizations' responses.

(3) Establish and maintain a current file of the names, addresses, and telephone numbers of each minority and female off-the-street applicant, referrals of minorities or females from unions, recruitment sources, or community organizations, and the action taken with respect to each individual. If an individual was sent to the union hiring hall for referral and not referred back to the Contractor by the union or, if referred back, not employed by the Contractor, this shall be documented in the file, along with whatever additional actions the Contractor may have taken.

(4) Immediately notify the Deputy Assistant Secretary when the union or unions with which the Contractor has a collective bargaining agreement has not referred back to the Contractor a minority or woman sent by the Contractor, or when the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its obligations.

(5) Develop on-the-job training opportunities and/or participate in training programs for the area that expressly include minorities and women, including upgrading programs and apprenticeship and trainee programs relevant to the Contractor's employment needs, especially those programs funded or approved by the Department of Labor. The Contractor shall provide notice of these programs to the sources compiled under subparagraph (g)(2) of this clause.

(6) Disseminate the Contractor's equal employment policy by--

(i) Providing notice of the policy to unions and to training, recruitment, and outreach programs, and requesting their cooperation in assisting the Contractor in meeting its contract obligations;

(ii) Including the policy in any policy manual and in collective bargaining agreements;

(iii) Publicizing the policy in the company newspaper, annual report, etc.;

(iv) Reviewing the policy with all management personnel and with all minority and female employees at least once a year; and

(v) Posting the policy on bulletin boards accessible to employees at each location where construction work is performed.

(7) Review, at least annually, the Contractor's equal employment policy and affirmative action obligations with all employees having responsibility for hiring, assignment, layoff, termination, or other employment decisions. Conduct review of this policy with all on-site supervisory personnel before initiating construction work at a job site. A written record shall be made and maintained identifying the time and place of these meetings, persons attending, subject matter discussed, and disposition of the subject matter.

(8) Disseminate the Contractor's equal employment policy externally by including it in any advertising in the news media, specifically including minority and female news media. Provide written notification to, and discuss this policy with, other Contractors and subcontractors with which the Contractor does or anticipates doing business.

(9) Direct recruitment efforts, both oral and written, to minority, female, and community organizations, to schools with minority and female students, and to minority and female recruitment and training organizations serving the Contractor's recruitment area and employment needs. Not later than 1 month before the date for acceptance of applications for apprenticeship or training by any recruitment source, send written notification to organizations such as the above, describing the openings, screening procedures, and tests to be used in the selection process.

(10) Encourage present minority and female employees to recruit minority persons and women. Where reasonable, provide after-school, summer, and vacation employment to minority and female youth both on the site and in other areas of the Contractor's workforce.

(11) Validate all tests and other selection requirements where required under 41 CFR 60-3.

(12) Conduct, at least annually, an inventory and evaluation at least of all minority and female personnel for promotional opportunities. Encourage these employees to seek or to prepare for, through appropriate training, etc., opportunities for promotion.

(13) Ensure that seniority practices, job classifications, work assignments, and other personnel practices do not have a discriminatory effect by continually monitoring all personnel and employment-related activities to ensure that the Contractor's obligations under this contract are being carried out.

(14) Ensure that all facilities and company activities are nonsegregated except that separate or single-user rest rooms and necessary dressing or sleeping areas shall be provided to assure privacy between the sexes.

(15) Maintain a record of solicitations for subcontracts for minority and female construction contractors and suppliers, including circulation of solicitations to minority and female contractor associations and other business associations.

(16) Conduct a review, at least annually, of all supervisors' adherence to and performance under the Contractor's equal employment policy and affirmative action obligations.

(h) The Contractor is encouraged to participate in voluntary associations that may assist in fulfilling one or more of the affirmative action obligations contained in subparagraphs (g)(1) through (16) of this clause. The efforts of a contractor association, joint contractor-union, contractor-community, or similar group of which the contractor is a member and participant may be asserted as fulfilling one or more of its obligations under subparagraphs (g)(1) through (16) of this clause, provided the Contractor--

(1) Actively participates in the group;

(2) Makes every effort to ensure that the group has a positive impact on the employment of minorities and women in the industry;

(3) Ensures that concrete benefits of the program are reflected in the Contractor's minority and female workforce participation;

(4) Makes a good-faith effort to meet its individual goals and timetables; and

(5) Can provide access to documentation that demonstrates the effectiveness of actions taken on behalf of the Contractor. The obligation to comply is the Contractor's, and failure of such a group to fulfill an obligation shall not be a defense for the Contractor's noncompliance.

(i) A single goal for minorities and a separate single goal for women shall be established. The Contractor is required to provide equal employment opportunity and to take affirmative action for all minority groups, both male and female, and all women, both minority and nonminority. Consequently, the Contractor may be in violation of Executive Order 11246, as amended, if a particular group is employed in a substantially disparate manner.

(j) The Contractor shall not use goals or affirmative action standards to discriminate against any person because of race, color, religion, sex, or national origin.

(k) The Contractor shall not enter into any subcontract with any person or firm debarred from Government contracts under Executive Order 11246, as amended.

(l) The Contractor shall carry out such sanctions and penalties for violation of this clause and of the Equal Opportunity clause, including suspension, termination, and cancellation of existing subcontracts, as may be imposed or ordered under Executive Order 11246, as amended, and its implementing regulations, by the OFCCP. Any failure to carry out these sanctions and penalties as ordered shall be a violation of this clause and Executive Order 11246, as amended.

(m) The Contractor in fulfilling its obligations under this clause shall implement affirmative action procedures at least as extensive as those prescribed in paragraph (g) of this clause, so as to achieve maximum results from its efforts to ensure equal employment opportunity. If the Contractor fails to comply with the requirements of Executive Order 11246, as amended, the implementing regulations, or this clause, the Deputy Assistant Secretary shall take action as prescribed in 41 CFR 60-4.8.

(n) The Contractor shall designate a responsible official to--

(1) Monitor all employment-related activity to ensure that the Contractor's equal employment policy is being carried out;

(2) Submit reports as may be required by the Government; and

(3) Keep records that shall at least include for each employee the name, address, telephone number, construction trade, union affiliation (if any), employee identification number, social security number, race, sex, status (e.g., mechanic, apprentice, trainee, helper, or laborer), dates of changes in status, hours worked per week in the indicated trade, rate of pay, and locations at which the work was performed. Records shall be maintained in an easily understandable and retrievable form; however, to the degree that existing records satisfy this requirement, separate records are not required to be maintained.

(o) Nothing contained herein shall be construed as a limitation upon the application of other laws that establish different standards of compliance or upon the requirements for the hiring of local or other area residents (e.g., those under the Public Works Employment Act of 1977 and the Community Development Block Grant Program).

(End of clause)

52.222-35 EQUAL OPPORTUNITY FOR VETERANS (OCT 2015)

(a) Definitions. As used in this clause--

``Active duty wartime or campaign badge veteran," ``Armed Forces service medal veteran," ``disabled veteran," ``protected veteran," ``qualified disabled veteran," and ``recently separated veteran" have the meanings given at FAR 22.1301.

(b) Equal opportunity clause. The Contractor shall abide by the requirements of the equal opportunity clause at 41 CFR 60-300.5(a), as of March 24, 2014. This clause prohibits discrimination against qualified protected veterans, and requires affirmative action by the Contractor to employ and advance in employment qualified protected veterans.

(c) Subcontracts. The Contractor shall insert the terms of this clause in subcontracts of \$150,000 or more unless exempted by rules, regulations, or orders of the Secretary of Labor. The Contractor shall act as specified by the Director, Office of Federal Contract Compliance Programs, to enforce the terms, including action for noncompliance. Such necessary changes in language may be made as shall be appropriate to identify properly the parties and their undertakings.

(End of clause)

52.222-36 Equal Opportunity for Workers with Disabilities (JUL 2014)

(a) Equal opportunity clause. The Contractor shall abide by the requirements of the equal opportunity clause at 41 CFR 60-741.5(a), as of March 24, 2014. This clause prohibits discrimination against qualified individuals on the basis of disability, and requires affirmative action by the Contractor to employ and advance in employment qualified individuals with disabilities.

(b) Subcontracts. The Contractor shall include the terms of this clause in every subcontract or purchase order in excess of \$15,000 unless exempted by rules, regulations, or orders of the Secretary, so that such provisions will be binding upon each subcontractor or vendor. The Contractor shall act as specified by the Director, Office of Federal Contract Compliance Programs of the U.S. Department of Labor, to enforce the terms, including action for noncompliance. Such necessary changes in language may be made as shall be appropriate to identify properly the parties and their undertakings.

(End of clause)

52.222-37 EMPLOYMENT REPORTS ON VETERANS (FEB 2016)

(a) Definitions. As used in this clause, "active duty wartime or campaign badge veteran," "Armed Forces service medal veteran," "disabled veteran," "protected veteran," and "recently separated veteran," have the meanings given in FAR 22.1301.

(b) Unless the Contractor is a State or local government agency, the Contractor shall report at least annually, as required by the Secretary of Labor, on--

(1) The total number of employees in the contractor's workforce, by job category and hiring location, who are protected veterans (i.e., active duty wartime or campaign badge veterans, Armed Forces service medal veterans, disabled veterans, and recently separated veterans);

(2) The total number of new employees hired during the period covered by the report, and of the total, the number of protected veterans (i.e., active duty wartime or campaign badge veterans, Armed Forces service medal veterans, disabled veterans, and recently separated veterans); and

(3) The maximum number and minimum number of employees of the Contractor or subcontractor at each hiring location during the period covered by the report.

(c) The Contractor shall report the above items by filing the VETS-4212 "Federal Contractor Veterans' Employment Report" (see "VETS-4212 Federal Contractor Reporting" and "Filing Your VETS-4212 Report" at <http://www.dol.gov/vets/vets4212.htm>).

(d) The Contractor shall file VETS-4212 Reports no later than September 30 of each year.

(e) The employment activity report required by paragraphs (b)(2) and (b)(3) of this clause shall reflect total new hires, and maximum and minimum number of employees, during the most recent 12-month period preceding the ending date selected for the report. Contractors may select an ending date--

(1) As of the end of any pay period between July 1 and August 31 of the year the report is due; or

(2) As of December 31, if the Contractor has prior written approval from the Equal Employment Opportunity Commission to do so for purposes of submitting the Employer Information Report EEO-1 (Standard Form 100).

(f) The number of veterans reported must be based on data known to the contractor when completing the VETS-4212. The contractor's knowledge of veterans status may be obtained in a variety of ways, including an invitation to

applicants to self-identify (in accordance with 41 CFR 60-300.42), voluntary self-disclosure by employees, or actual knowledge of veteran status by the contractor. This paragraph does not relieve an employer of liability for discrimination under 38 U.S.C. 4212.

(g) The Contractor shall insert the terms of this clause in subcontracts of \$150,000 or more unless exempted by rules, regulations, or orders of the Secretary of Labor.

(End of clause)

**52.222-40 NOTIFICATION OF EMPLOYEE RIGHTS UNDER THE NATIONAL LABOR RELATIONS ACT
(DEC 2010)**

(a) During the term of this contract, the Contractor shall post an employee notice, of such size and in such form, and containing such content as prescribed by the Secretary of Labor, in conspicuous places in and about its plants and offices where employees covered by the National Labor Relations Act engage in activities relating to the performance of the contract, including all places where notices to employees are customarily posted both physically and electronically, in the languages employees speak, in accordance with 29 CFR 471.2(d) and (f).

(1) Physical posting of the employee notice shall be in conspicuous places in and about the Contractor's plants and offices so that the notice is prominent and readily seen by employees who are covered by the National Labor Relations Act and engage in activities related to the performance of the contract.

(2) If the Contractor customarily posts notices to employees electronically, then the Contractor shall also post the required notice electronically by displaying prominently, on any Web site that is maintained by the Contractor and is

customarily used for notices to employees about terms and conditions of employment, a link to the Department of Labor's Web site that contains the full text of the poster. The link to the Department's Web site, as referenced in (b)(3) of this section, must read, "Important Notice about Employee Rights to Organize and Bargain Collectively with Their Employers."

(b) This required employee notice, printed by the Department of Labor, may be--

(1) Obtained from the Division of Interpretations and Standards, Office of Labor-Management Standards, U.S. Department of Labor, 200 Constitution Avenue, NW, Room N-5609, Washington, DC 20210, (202) 693-0123, or from any field office of the Office of Labor-Management Standards or Office of Federal Contract Compliance Programs;

(2) Provided by the Federal contracting agency if requested;

(3) Downloaded from the Office of Labor-Management Standards Web site at <http://www.dol.gov/olms/regs/compliance/EO13496.htm>; or

(4) Reproduced and used as exact duplicate copies of the Department of Labor's official poster.

(c) The required text of the employee notice referred to in this clause is located at Appendix A, Subpart A, 29 CFR Part 471.

(d) The Contractor shall comply with all provisions of the employee notice and related rules, regulations, and orders of the Secretary of Labor.

(e) In the event that the Contractor does not comply with the requirements set forth in paragraphs (a) through (d) of this clause, this contract may be terminated or suspended in whole or in part, and the Contractor may be suspended

or debarred in accordance with 29 CFR 471.14 and subpart 9.4. Such other sanctions or remedies may be imposed as are provided by 29 CFR part 471, which implements Executive Order 13496 or as otherwise provided by law.

(f) Subcontracts. (1) The Contractor shall include the substance of this clause, including this paragraph (f), in every subcontract that exceeds \$10,000 and will be performed wholly or partially in the United States, unless exempted by the rules, regulations, or orders of the Secretary of Labor issued pursuant to section 3 of Executive Order 13496 of January 30, 2009, so that such provisions will be binding upon each subcontractor.

(2) The Contractor shall not procure supplies or services in a way designed to avoid the applicability of Executive Order 13496 or this clause.

(3) The Contractor shall take such action with respect to any such subcontract as may be directed by the Secretary of Labor as a means of enforcing such provisions, including the imposition of sanctions for noncompliance.

(4) However, if the Contractor becomes involved in litigation with a subcontractor, or is threatened with such involvement, as a result of such direction, the Contractor may request the United States, through the Secretary of Labor, to enter into such litigation to protect the interests of the United States.

(End of clause)

52.222-50 COMBATING TRAFFICKING IN PERSONS (MAR 2015)

(a) Definitions. As used in this clause--

Agent means any individual, including a director, an officer, an employee, or an independent contractor, authorized to act on behalf of the organization.

Coercion means--

(1) Threats of serious harm to or physical restraint against any person;

(2) Any scheme, plan, or pattern intended to cause a person to believe that failure to perform an act would result in serious harm to or physical restraint against any person; or

(3) The abuse or threatened abuse of the legal process.

Commercially available off-the-shelf (COTS) item means--

(1) Any item of supply (including construction material) that is--

(i) A commercial item (as defined in paragraph (1) of the definition at FAR 2.101);

(ii) Sold in substantial quantities in the commercial marketplace; and

(iii) Offered to the Government, under a contract or subcontract at any tier, without modification, in the same form in which it is sold in the commercial marketplace; and

(2) Does not include bulk cargo, as defined in 46 U.S.C. 40102(4), such as agricultural products and petroleum products.

Commercial sex act means any sex act on account of which anything of value is given to or received by any person.

Debt bondage means the status or condition of a debtor arising from a pledge by the debtor of his or her personal services or of those of a person under his or her control as a security for debt, if the value of those services as reasonably assessed is not applied toward the liquidation of the debt or the length and nature of those services are not respectively limited and defined.

Employee means an employee of the Contractor directly engaged in the performance of work under the contract who has other than a minimal impact or involvement in contract performance.

Forced Labor means knowingly providing or obtaining the labor or services of a person--

- (1) By threats of serious harm to, or physical restraint against, that person or another person;
- (2) By means of any scheme, plan, or pattern intended to cause the person to believe that, if the person did not perform such labor or services, that person or another person would suffer serious harm or physical restraint; or
- (3) By means of the abuse or threatened abuse of law or the legal process.

Involuntary servitude includes a condition of servitude induced by means of--

- (1) Any scheme, plan, or pattern intended to cause a person to believe that, if the person did not enter into or continue in such conditions, that person or another person would suffer serious harm or physical restraint; or
- (2) The abuse or threatened abuse of the legal process.

Severe forms of trafficking in persons means--

- (1) Sex trafficking in which a commercial sex act is induced by force, fraud, or coercion, or in which the person induced to perform such act has not attained 18 years of age; or
- (2) The recruitment, harboring, transportation, provision, or obtaining of a person for labor or services, through the use of force, fraud, or coercion for the purpose of subjection to involuntary servitude, peonage, debt bondage, or slavery.

Sex trafficking means the recruitment, harboring, transportation, provision, or obtaining of a person for the purpose of a commercial sex act.

Subcontract means any contract entered into by a subcontractor to furnish supplies or services for performance of a prime contract or a subcontract.

Subcontractor means any supplier, distributor, vendor, or firm that furnishes supplies or services to or for a prime contractor or another subcontractor.

United States means the 50 States, the District of Columbia, and outlying areas.

(b) Policy. The United States Government has adopted a policy prohibiting trafficking in persons including the trafficking-related activities of this clause. Contractors, contractor employees, and their agents shall not--

- (1) Engage in severe forms of trafficking in persons during the period of performance of the contract;
- (2) Procure commercial sex acts during the period of performance of the contract;
- (3) Use forced labor in the performance of the contract;

(4) Destroy, conceal, confiscate, or otherwise deny access by an employee to the employee's identity or immigration documents, such as passports or drivers' licenses, regardless of issuing authority;

(5)(i) Use misleading or fraudulent practices during the recruitment of employees or offering of employment, such as failing to disclose, in a format and language accessible to the worker, basic information or making material misrepresentations during the recruitment of employees regarding the key terms and conditions of employment, including wages and fringe benefits, the location of work, the living conditions, housing and associated costs (if employer or agent provided or arranged), any significant cost to be charged to the employee, and, if applicable, the hazardous nature of the work;

(ii) Use recruiters that do not comply with local labor laws of the country in which the recruiting takes place;

(6) Charge employees recruitment fees;

(7)(i) Fail to provide return transportation or pay for the cost of return transportation upon the end of employment--

(A) For an employee who is not a national of the country in which the work is taking place and who was brought into that country for the purpose of working on a U.S. Government contract or subcontract (for portions of contracts performed outside the United States); or

(B) For an employee who is not a United States national and who was brought into the United States for the purpose of working on a U.S. Government contract or subcontract, if the payment of such costs is required under existing temporary worker programs or pursuant to a written agreement with the employee (for portions of contracts performed inside the United States); except that--

(ii) The requirements of paragraphs (b)(7)(i) of this clause shall not apply to an employee who is--

(A) Legally permitted to remain in the country of employment and who chooses to do so; or

(B) Exempted by an authorized official of the contracting agency from the requirement to provide return transportation or pay for the cost of return transportation;

(iii) The requirements of paragraph (b)(7)(i) of this clause are modified for a victim of trafficking in persons who is seeking victim services or legal redress in the country of employment, or for a witness in an enforcement action related to trafficking in persons. The contractor shall provide the return transportation or pay the cost of return transportation in a way that does not obstruct the victim services, legal redress, or witness activity. For example, the contractor shall not only offer return transportation to a witness at a time when the witness is still needed to testify. This paragraph does not apply when the exemptions at paragraph (b)(7)(ii) of this clause apply.

(8) Provide or arrange housing that fails to meet the host country housing and safety standards; or

(9) If required by law or contract, fail to provide an employment contract, recruitment agreement, or other required work document in writing. Such written work document shall be in a language the employee understands. If the employee must relocate to perform the work, the work document shall be provided to the employee at least five days prior to the employee relocating. The employee's work document shall include, but is not limited to, details about work description, wages, prohibition on charging recruitment fees, work location(s), living accommodations and associated costs, time off, roundtrip transportation arrangements, grievance process, and the content of applicable laws and regulations that prohibit trafficking in persons.

(c) Contractor requirements. The Contractor shall--

(1) Notify its employees and agents of--

(i) The United States Government's policy prohibiting trafficking in persons, described in paragraph (b) of this clause; and

(ii) The actions that will be taken against employees or agents for violations of this policy. Such actions for employees may include, but are not limited to, removal from the contract, reduction in benefits, or termination of employment; and

(2) Take appropriate action, up to and including termination, against employees, agents, or subcontractors that violate the policy in paragraph (b) of this clause.

(d) Notification. (1) The Contractor shall inform the Contracting Officer and the agency Inspector General immediately of--

(i) Any credible information it receives from any source (including host country law enforcement) that alleges a Contractor employee, subcontractor, subcontractor employee, or their agent has engaged in conduct that violates the policy in paragraph (b) of this clause (see also 18 U.S.C. 1351, Fraud in Foreign Labor Contracting, and 52.203-13(b)(3)(i)(A), if that clause is included in the solicitation or contract, which requires disclosure to the agency Office of the Inspector General when the Contractor has credible evidence of fraud); and

(ii) Any actions taken against a Contractor employee, subcontractor, subcontractor employee, or their agent pursuant to this clause.

(2) If the allegation may be associated with more than one contract, the Contractor shall inform the contracting officer for

the contract with the highest dollar value.

(e) Remedies. In addition to other remedies available to the Government, the Contractor's failure to comply with the requirements of paragraphs (c), (d), (g), (h), or (i) of this clause may result in--

(1) Requiring the Contractor to remove a Contractor employee or employees from the performance of the contract;

(2) Requiring the Contractor to terminate a subcontract;

(3) Suspension of contract payments until the Contractor has taken appropriate remedial action;

(4) Loss of award fee, consistent with the award fee plan, for the performance period in which the Government determined Contractor non-compliance;

(5) Declining to exercise available options under the contract;

(6) Termination of the contract for default or cause, in accordance with the termination clause of this contract; or

(7) Suspension or debarment.

(f) Mitigating and aggravating factors. When determining remedies, the Contracting Officer may consider the following:

(1) Mitigating factors. The Contractor had a Trafficking in Persons compliance plan or an awareness program at the time of the violation, was in compliance with the plan, and has taken appropriate remedial actions for the violation, that may include reparation to victims for such violations.

(2) Aggravating factors. The Contractor failed to abate an alleged violation or enforce the requirements of a compliance plan, when directed by the Contracting Officer to do so.

(g) Full cooperation. (1) The Contractor shall, at a minimum--

(i) Disclose to the agency Inspector General information sufficient to identify the nature and extent of an offense and the individuals responsible for the conduct;

(ii) Provide timely and complete responses to Government auditors' and investigators' requests for documents;

(iii) Cooperate fully in providing reasonable access to its facilities and staff (both inside and outside the U.S.) to allow contracting agencies and other responsible Federal agencies to conduct audits, investigations, or other actions to ascertain compliance with the Trafficking Victims Protection Act of 2000 (22 U.S.C. chapter 78), E.O. 13627, or any other applicable law or regulation establishing restrictions on trafficking in persons, the procurement of commercial sex acts, or the use of forced labor; and

(iv) Protect all employees suspected of being victims of or witnesses to prohibited activities, prior to returning to the country from which the employee was recruited, and shall not prevent or hinder the ability of these employees from cooperating fully with Government authorities.

(2) The requirement for full cooperation does not foreclose any Contractor rights arising in law, the FAR, or the terms of the contract. It does not--

(i) Require the Contractor to waive its attorney-client privilege or the protections afforded by the attorney work product doctrine;

(ii) Require any officer, director, owner, employee, or agent of the Contractor, including a sole proprietor, to waive his or her attorney client privilege or Fifth Amendment rights; or

(iii) Restrict the Contractor from--

(A) Conducting an internal investigation; or

(B) Defending a proceeding or dispute arising under the contract or related to a potential or disclosed violation.

(h) Compliance plan. (1) This paragraph (h) applies to any portion of the contract that--

(i) Is for supplies, other than commercially available off-the-shelf items, acquired outside the United States, or services to be performed outside the United States; and

(ii) Has an estimated value that exceeds \$500,000.

(2) The Contractor shall maintain a compliance plan during the performance of the contract that is appropriate--

(i) To the size and complexity of the contract; and

(ii) To the nature and scope of the activities to be performed for the Government, including the number of non-United States citizens expected to be employed and the risk that the contract or subcontract will involve services or supplies susceptible to trafficking in persons.

(3) Minimum requirements. The compliance plan must include, at a minimum, the following:

(i) An awareness program to inform contractor employees about the Government's policy prohibiting trafficking-related activities described in paragraph (b) of this clause, the activities prohibited, and the actions that will be taken against the employee for violations. Additional information about Trafficking in Persons and examples of awareness programs can be found at the Web site for the Department of State's Office to Monitor and Combat Trafficking in Persons at <http://www.state.gov/j/tip/>.

(ii) A process for employees to report, without fear of retaliation, activity inconsistent with the policy prohibiting trafficking in persons, including a means to make available to all employees the hotline phone number of the Global Human Trafficking Hotline at 1-844-888-FREE and its email address at help@befree.org.

(iii) A recruitment and wage plan that only permits the use of recruitment companies with trained employees, prohibits charging recruitment fees to the employee, and ensures that wages meet applicable host-country legal requirements or explains any variance.

(iv) A housing plan, if the Contractor or subcontractor intends to provide or arrange housing, that ensures that the housing meets host-country housing and safety standards.

(v) Procedures to prevent agents and subcontractors at any tier and at any dollar value from engaging in trafficking in persons (including activities in paragraph (b) of this clause) and to monitor, detect, and terminate any agents, subcontracts, or subcontractor employees that have engaged in such activities.

(4) Posting. (i) The Contractor shall post the relevant contents of the compliance plan, no later than the initiation of contract performance, at the workplace (unless the work is to be performed in the field or not in a fixed location) and on the Contractor's Web site (if one is maintained). If posting at the workplace or on the Web site is impracticable, the Contractor shall provide the relevant contents of the compliance plan to each worker in writing.

(ii) The Contractor shall provide the compliance plan to the Contracting Officer upon request.

(5) Certification. Annually after receiving an award, the Contractor shall submit a certification to the Contracting Officer that--

(i) It has implemented a compliance plan to prevent any prohibited activities identified at paragraph (b) of this clause and to monitor, detect, and terminate any agent, subcontract or subcontractor employee engaging in prohibited activities; and

(ii) After having conducted due diligence, either--

(A) To the best of the Contractor's knowledge and belief, neither it nor any of its agents, subcontractors, or their agents is engaged in any such activities; or

(B) If abuses relating to any of the prohibited activities identified in paragraph (b) of this clause have been found, the Contractor or subcontractor has taken the appropriate remedial and referral actions.

(i) Subcontracts. (1) The Contractor shall include the substance of this clause, including this paragraph (i), in all subcontracts and in all contracts with agents. The requirements in paragraph (h) of this clause apply only to any portion of the subcontract that--

(A) Is for supplies, other than commercially available off-the-shelf items, acquired outside the United States, or services to be performed outside the United States; and

(B) Has an estimated value that exceeds \$500,000.

(2) If any subcontractor is required by this clause to submit a certification, the Contractor shall require submission prior to the award of the subcontract and annually thereafter. The certification

(End of clause)

52.222-54 – Employment Eligibility Verification.

(a) Definitions. As used in this clause—

“Commercially available off-the-shelf (COTS) item”—

(1) Means any item of supply that is—

(i) A commercial item (as defined in paragraph (1) of the definition at 2.101);

(ii) Sold in substantial quantities in the commercial marketplace; and

(iii) Offered to the Government, without modification, in the same form in which it is sold in the commercial marketplace; and

(2) Does not include bulk cargo, as defined in 46 U.S.C. 40102(4) such as agricultural products and petroleum products. Per 46 CFR 525.1(c)(2), “bulk cargo” means cargo that is loaded and carried in bulk onboard ship without mark or count, in a loose unpackaged form, having homogenous characteristics. Bulk cargo loaded into intermodal equipment, except LASH or Seabee barges, is subject to mark and count and, therefore, ceases to be bulk cargo.

“Employee assigned to the contract” means an employee who was hired after November 6, 1986 (after November 27, 2009, in the Commonwealth of the Northern Mariana Islands), who is directly performing work, in the United States, under a contract that is required to include the clause prescribed at 22.1803. An employee is not considered to be directly performing work under a contract if the employee—

(1) Normally performs support work, such as indirect or overhead functions; and

(2) Does not perform any substantial duties applicable to the contract.

“Subcontract” means any contract, as defined in 2.101, entered into by a subcontractor to furnish supplies or services for performance of a prime contract or a subcontract. It includes but is not limited to purchase orders, and changes and modifications to purchase orders.

“Subcontractor” means any supplier, distributor, vendor, or firm that furnishes supplies or services to or for a prime Contractor or another subcontractor.

“United States,” as defined in 8 U.S.C. 1101(a)(38), means the 50 States, the District of Columbia, Puerto Rico, Guam, the Commonwealth of the Northern Mariana Islands, and the U.S. Virgin Islands.

(b) Enrollment and verification requirements.

(1) If the Contractor is not enrolled as a Federal Contractor in E-Verify at time of contract award, the Contractor shall—

(i) Enroll. Enroll as a Federal Contractor in the E-Verify program within 30 calendar days of contract award;

(ii) Verify all new employees. Within 90 calendar days of enrollment in the E-Verify program, begin to use E-Verify to initiate verification of employment eligibility of all new hires of the Contractor, who are working in the United

States, whether or not assigned to the contract, within 3 business days after the date of hire (but see paragraph (b)(3) of this section); and

(iii) Verify employees assigned to the contract. For each employee assigned to the contract, initiate verification within 90 calendar days after date of enrollment or within 30 calendar days of the employee's assignment to the contract, whichever date is later (but see paragraph (b)(4) of this section).

(2) If the Contractor is enrolled as a Federal Contractor in E-Verify at time of contract award, the Contractor shall use E-Verify to initiate verification of employment eligibility of—

(i) All new employees.

(A) Enrolled 90 calendar days or more. The Contractor shall initiate verification of all new hires of the Contractor, who are working in the United States, whether or not assigned to the contract within 3 business days after the date of hire (but see paragraph (b)(3) of this section); or

(B) Enrolled less than 90 calendar days. Within 90 calendar days after enrollment as a Federal Contractor in E-Verify, the Contractor shall initiate verification of all new hires of the Contractor, who are working in the United States, whether or not assigned to the contract, within 3 business days after the date of hire (but see paragraph (b)(3) of this section); or

(ii) Employees assigned to the contract. For each employee assigned to the contract, the Contractor shall initiate verification within 90 calendar days after date of contract award or within 30 days after assignment to the contract, whichever date is later (but see paragraph (b)(4) of this section).

(3) If the Contractor is an institution of higher education (as defined at 20 U.S.C. 1001(a)); a State or local government or the government of a Federally recognized Indian tribe; or a surety performing under a takeover agreement entered into with a Federal agency pursuant to a performance bond, the Contractor may choose to verify only employees assigned to the contract, whether existing employees or new hires. The Contractor shall follow the applicable verification requirements at (b)(1) or (b)(2), respectively, except that any requirement for verification of new employees applies only to new employees assigned to the contract.

(4) Option to verify employment eligibility of all employees. The Contractor may elect to verify all existing employees hired after November 6, 1986 (after November 27, 2009, in the Commonwealth of the Northern Mariana Islands), rather than just those employees assigned to the contract. The Contractor shall initiate verification for each existing employee working in the United States who was hired after November 6, 1986 (after November 27, 2009, in the Commonwealth of the Northern Mariana Islands), within 180 calendar days of—

(i) Enrollment in the E-Verify program; or

(ii) Notification to E-Verify Operations of the Contractor's decision to exercise this option, using the contact information provided in the E-Verify program Memorandum of Understanding (MOU).

(5) The Contractor shall comply, for the period of performance of this contract, with the requirement of the E-Verify program MOU.

(i) The Department of Homeland Security (DHS) or the Social Security Administration (SSA) may terminate the Contractor's MOU and deny access to the E-Verify system in accordance with the terms of the MOU. In such case, the Contractor will be referred to a suspension or debarment official.

(ii) During the period between termination of the MOU and a decision by the suspension or debarment official whether to suspend or debar, the Contractor is excused from its obligations under paragraph (b) of this clause. If the suspension or debarment official determines not to suspend or debar the Contractor, then the Contractor must reenroll in E-Verify.

(c) Web site. Information on registration for and use of the E-Verify program can be obtained via the Internet at the Department of Homeland Security Web site: <http://www.dhs.gov/E-Verify> .

(d) Individuals previously verified. The Contractor is not required by this clause to perform additional employment verification using E-Verify for any employee—

(1) Whose employment eligibility was previously verified by the Contractor through the E-Verify program;

(2) Who has been granted and holds an active U.S. Government security clearance for access to confidential, secret, or top secret information in accordance with the National Industrial Security Program Operating Manual; or

(3) Who has undergone a completed background investigation and been issued credentials pursuant to Homeland Security Presidential Directive (HSPD) -12, Policy for a Common Identification Standard for Federal Employees and Contractors.

(e) Subcontracts. The contractor shall include the requirements of this clause, including this paragraph (e) (appropriately modified for identification of the parties), in each subcontract that—

(1) Is for—

(i) Commercial or noncommercial services (except for commercial services that are part of the purchase of a COTS item (or an item that would be a COTS item, but for minor modifications), performed by the COTS provider, and are normally provided for that COTS item); or

(ii) Construction;

(2) Has a value of more than \$3,500; and

(3) Includes work performed in the United States.

(End of Clause)

52.222-55 Minimum Wages Under Executive Order 13658 (DEC 2015)

(a) Definitions. As used in this clause--

``United States" means the 50 states and the District of Columbia.

``Worker"--

(1) Means any person engaged in performing work on, or in connection with, a contract covered by Executive Order 13658, and --

(i) Whose wages under such contract are governed by the Fair Labor Standards Act (29 U.S.C. chapter 8), the Service Contract Labor Standards statute (41 U.S.C. chapter 67), or the Wage Rate Requirements (Construction) statute (40 U.S.C. chapter 31, subchapter IV);

(ii) Other than individuals employed in a bona fide executive, administrative, or professional capacity, as those terms are defined in 29 CFR part 541;

(iii) Regardless of the contractual relationship alleged to exist between the individual and the employer.

(2) Includes workers performing on, or in connection with, the contract whose wages are calculated pursuant to special certificates issued under 29 U.S.C. 214(c).

(3) Also includes any person working on, or in connection with, the contract and individually registered in a bona fide apprenticeship or training program registered with the Department of Labor's Employment and Training Administration, Office of Apprenticeship, or with a State Apprenticeship Agency recognized by the Office of Apprenticeship.

(b) Executive Order minimum wage rate. (1) The Contractor shall pay to workers, while performing in the United States, and performing on, or in connection with, this contract, a minimum hourly wage rate of \$10.10 per hour beginning January 1, 2015.

(2) The Contractor shall adjust the minimum wage paid, if necessary, beginning January 1, 2016, and annually thereafter, to meet the applicable annual E.O. minimum wage. The Administrator of the Department of Labor's Wage and Hour Division (the Administrator) will publish annual determinations in the Federal Register no later than 90 days before the effective date of the new E.O. minimum wage rate. The Administrator will also publish the applicable E.O. minimum wage on www.wdol.gov (or any successor Web site), and a general notice on all wage determinations issued under the Service Contract Labor Standards statute or the Wage Rate Requirements (Construction) statute, that will provide information on the E.O. minimum wage and how to obtain annual updates. The applicable published E.O. minimum wage is incorporated by reference into this contract.

(3)(i) The Contractor may request a price adjustment only after the effective date of the new annual E.O. minimum wage determination. Prices will be adjusted only for increased labor costs (including subcontractor labor costs) as a result of an increase in the annual E.O. minimum wage, and for associated labor costs (including those for subcontractors). Associated labor costs shall include increases or decreases that result from changes in social security and unemployment taxes and workers' compensation insurance, but will not otherwise include any amount for general and administrative costs, overhead, or profit.

(ii) Subcontractors may be entitled to adjustments due to the new minimum wage, pursuant to paragraph (b)(2). Contractors shall consider any subcontractor requests for such price adjustment.

(iii) The Contracting Officer will not adjust the contract price under this clause for any costs other than those identified in paragraph (b)(3)(i) of this clause, and will not provideduplicate price adjustments with any price adjustment under clauses implementing the Service Contract Labor Standards statute or the Wage Rate Requirements (Construction) statute.

(4) The Contractor warrants that the prices in this contract do not include allowance for any contingency to cover increased costs for which adjustment is provided under this clause.

(5) A pay period under this clause may not be longer than semi-monthly, but may be shorter to comply with any applicable law or other requirement under this contract establishing a shorter pay period. Workers shall be paid no later than one pay period following the end of the regular pay period in which such wages were earned or accrued.

(6) The Contractor shall pay, unconditionally to each worker, all wages due free and clear without subsequent rebate or kickback. The Contractor may make deductions that reduce a worker's wages below the E.O. minimum wage rate only if done in accordance with 29 CFR 10.23, Deductions.

(7) The Contractor shall not discharge any part of its minimum wage obligation under this clause by furnishing fringe benefits or, with respect to workers whose wages are governed by the Service Contract Labor Standards statute, the cash equivalent thereof.

(8) Nothing in this clause shall excuse the Contractor from compliance with any applicable Federal or State prevailing wage law or any applicable law or municipal ordinance establishing a minimum wage higher than the E.O. minimum wage. However, wage increases under such other laws or municipal ordinances are not subject to price adjustment under this subpart.

(9) The Contractor shall pay the E.O. minimum wage rate whenever it is higher than any applicable collective bargaining agreement(s) wage rate.

(10) The Contractor shall follow the policies and procedures in 29 CFR 10.24(b) and 10.28 for treatment of workers engaged in an occupation in which they customarily and regularly receive more than \$30 a month in tips.

(c)(1) This clause applies to workers as defined in paragraph (a). As provided in that definition--

(i) Workers are covered regardless of the contractual relationship alleged to exist between the contractor or subcontractor and the worker;

(ii) Workers with disabilities whose wages are calculated pursuant to special certificates issued under 29 U.S.C. 214(c) are covered; and

(iii) Workers who are registered in a bona fide apprenticeship program or training program registered with the Department of Labor's Employment and Training Administration, Office of Apprenticeship, or with a State Apprenticeship Agency recognized by the Office of Apprenticeship, are covered.

(2) This clause does not apply to--

(i) Fair Labor Standards Act (FLSA)-covered individuals performing in connection with contracts covered by the E.O., i.e. those individuals who perform duties necessary to the performance of the contract, but who are not directly engaged in performing the specific work called for by the contract, and who spend less than 20 percent of their hours worked in a particular workweek performing in connection with such contracts;

(ii) Individuals exempted from the minimum wage requirements of the FLSA under 29 U.S.C. 213(a) and 214(a) and (b), unless otherwise covered by the Service Contract Labor Standards statute, or the Wage Rate Requirements (Construction) statute. These individuals include but are not limited to--

(A) Learners, apprentices, or messengers whose wages are calculated pursuant to special certificates issued under 29 U.S.C. 214(a).

(B) Students whose wages are calculated pursuant to special certificates issued under 29 U.S.C. 214(b).

(C) Those employed in a bona fide executive, administrative, or professional capacity (29 U.S.C. 213(a)(1) and 29 CFR part 541).

(d) Notice. The Contractor shall notify all workers performing work on, or in connection with, this contract of the applicable E.O. minimum wage rate under this clause. With respect to workers covered by the Service Contract Labor Standards statute or the Wage Rate Requirements (Construction) statute, the Contractor may meet this requirement by posting, in a prominent and accessible place at the worksite, the applicable wage determination under those statutes. With respect to workers whose wages are governed by the FLSA, the Contractor shall post notice, utilizing the poster provided by the Administrator, which can be obtained at www.dol.gov/whd/govcontracts, in a prominent and accessible place at the worksite. Contractors that customarily post notices to workers electronically may post the notice electronically provided the electronic posting is displayed prominently on any

Web site that is maintained by the contractor, whether external or internal, and customarily used for notices to workers about terms and conditions of employment.

(e) Payroll Records. (1) The Contractor shall make and maintain records, for three years after completion of the work, containing the following information for each worker:

- (i) Name, address, and social security number;
- (ii) The worker's occupation(s) or classification(s);
- (iii) The rate or rates of wages paid;
- (iv) The number of daily and weekly hours worked by each worker;
- (v) Any deductions made; and
- (vi) Total wages paid.

(2) The Contractor shall make records pursuant to paragraph (e)(1) of this clause available for inspection and transcription by authorized representatives of the Administrator. The Contractor shall also make such records available upon request of the Contracting Officer.

(3) The Contractor shall make a copy of the contract available, as applicable, for inspection or transcription by authorized representatives of the Administrator.

(4) Failure to comply with this paragraph (e) shall be a violation of 29 CFR 10.26 and this contract. Upon direction of the Administrator or upon the Contracting Officer's own action, payment shall be withheld until such time as the noncompliance is corrected.

(5) Nothing in this clause limits or otherwise modifies the Contractor's payroll and recordkeeping obligations, if any, under the Service Contract Labor Standards statute, the Wage Rate Requirements (Construction) statute, the Fair Labor Standards Act, or any other applicable law.

(f) Access. The Contractor shall permit authorized representatives of the Administrator to conduct investigations, including interviewing workers at the worksite during normal working hours.

(g) Withholding. The Contracting Officer, upon his or her own action or upon written request of the Administrator, will withhold funds or cause funds to be withheld, from the Contractor under this or any other Federal contract with the same Contractor, sufficient to pay workers the full amount of wages required by this clause.

(h) Disputes. Department of Labor has set forth in 29 CFR 10.51, Disputes concerning contractor compliance, the procedures for resolving disputes concerning a contractor's compliance with Department of Labor regulations at 29 CFR part 10. Such disputes shall be resolved in accordance with those procedures and not the Disputes clause of this contract. These disputes include disputes between the Contractor (or any of its subcontractors) and the contracting agency, the Department of Labor, or the workers or their representatives.

(i) Antiretaliation. The Contractor shall not discharge or in any other manner discriminate against any worker because such worker has filed any complaint or instituted or caused to be instituted any proceeding under or related to compliance with the E.O. or this clause, or has testified or is about to testify in any such proceeding.

(j) Subcontractor compliance. The Contractor is responsible for subcontractor compliance with the requirements of this clause and may be held liable for unpaid wages due subcontractor workers.

(k) Subcontracts. The Contractor shall include the substance of this clause, including this paragraph (k) in all subcontracts, regardless of dollar value, that are subject to the Service Contract Labor Standards statute or the Wage Rate Requirements (Construction) statute, and are to be performed in whole or in part in the United States.

52.222-62 Paid Sick Leave Under Executive Order 13706 (JAN 2017)

(a) Definitions. As used in this clause (in accordance with 29 CFR 13.2)--

Child, domestic partner, and domestic violence have the meaning given in 29 CFR 13.2.

Employee--(1)(i) Means any person engaged in performing work on or in connection with a contract covered by Executive Order (E.O.) 13706; and

(A) Whose wages under such contract are governed by the Service Contract Labor Standards statute (41 U.S.C. chapter 67), the Wage Rate Requirements (Construction) statute (40 U.S.C. chapter 31, subchapter IV), or the Fair Labor Standards Act (29 U.S.C. chapter 8);

(B) Including employees who qualify for an exemption from the Fair Labor Standards Act's minimum wage and overtime provisions;

(C) Regardless of the contractual relationship alleged to exist between the individual and the employer; and

(ii) Includes any person performing work on or in connection with the contract and individually registered in a bona fide apprenticeship or training program registered with the Department of Labor's Employment and Training Administration, Office of Apprenticeship, or with a State Apprenticeship Agency recognized by the Office of Apprenticeship.

(2)(i) An employee performs "on" a contract if the employee directly performs the specific services called for by the contract; and

(ii) An employee performs "in connection with" a contract if the employee's work activities are necessary to the performance of a contract but are not the specific services called for by the contract.

Individual related by blood or affinity whose close association with the employee is the equivalent of a family relationship has the meaning given in 29 CFR 13.2.

Multiemployer plan means a plan to which more than one employer is required to contribute and which is maintained pursuant to one or more collective bargaining agreements between one or more employee organizations and more than one employer.

Paid sick leave means compensated absence from employment that is required by E.O. 13706 and 29 CFR part 13.

Parent, sexual assault, spouse, and stalking have the meaning given in 29 CFR 13.2.

United States means the 50 States and the District of Columbia.

(b) Executive Order 13706. (1) This contract is subject to E.O. 13706 and the regulations issued by the Secretary of Labor in 29 CFR part 13 pursuant to the E.O.

(2) If this contract is not performed wholly within the United States, this clause only applies with respect to that part of the contract that is performed within the United States.

(c) Paid sick leave. The Contractor shall--

(1) Permit each employee engaged in performing work on or in connection with this contract to earn not less than 1 hour of paid sick leave for every 30 hours worked;

- (2) Allow accrual and use of paid sick leave as required by E.O. 13706 and 29 CFR part 13;
 - (3) Comply with the accrual, use, and other requirements set forth in 29 CFR 13.5 and 13.6, which are incorporated by reference in this contract;
 - (4) Provide paid sick leave to all employees when due free and clear and without subsequent deduction (except as otherwise provided by 29 CFR 13.24), rebate, or kickback on any account;
 - (5) Provide pay and benefits for paid sick leave used no later than one pay period following the end of the regular pay period in which the paid sick leave was taken; and
 - (6) Be responsible for the compliance by any subcontractor with the requirements of E.O. 13706, 29 CFR part 13, and this clause.
- (d) Contractors may fulfill their obligations under E.O. 13706 and 29 CFR part 13 jointly with other contractors through a multiemployer plan, or may fulfill their obligations through an individual fund, plan, or program (see 29 CFR 13.8).
- (e) Withholding. The Contracting Officer will, upon his or her own action or upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the Contractor under this or any other Federal contract with the same Contractor, so much of the accrued payments or advances as may be considered necessary to pay employees the full amount owed to compensate for any violation of the requirements of E.O. 13706, 29 CFR part 13, or this clause, including--
- (1) Any pay and/or benefits denied or lost by reason of the violation;
 - (2) Other actual monetary losses sustained as a direct result of the violation; and
 - (3) Liquidated damages.
- (f) Payment suspension/contract termination/contractor debarment. (1) In the event of a failure to comply with E.O. 13706, 29 CFR part 13, or this clause, the contracting agency may, on its own action or after authorization or by direction of the Department of Labor and written notification to the Contractor take action to cause suspension of any further payment, advance, or guarantee of funds until such violations have ceased.
- (2) Any failure to comply with the requirements of this clause may be grounds for termination for default or cause.
 - (3) A breach of the contract clause may be grounds for debarment as a contractor and subcontractor as provided in 29 CFR 13.52.
- (g) The paid sick leave required by E.O. 13706, 29 CFR part 13, and this clause is in addition to the Contractor's obligations under the Service Contract Labor Standards statute and Wage Rate Requirements (Construction) statute, and the Contractor may not receive credit toward its prevailing wage or fringe benefit obligations under those Acts for any paid sick leave provided in satisfaction of the requirements of E.O. 13706 and 29 CFR part 13.
- (h) Nothing in E.O. 13706 or 29 CFR part 13 shall excuse noncompliance with or supersede any applicable Federal or State law, any applicable law or municipal ordinance, or a collective bargaining agreement requiring greater paid sick leave or leave rights than those established under E.O. 13706 and 29 CFR part 13.
- (i) Recordkeeping. (1) The Contractor shall make and maintain, for no less than three (3) years from the completion of the work on the contract, records containing the following information for each employee, which the Contractor shall make available upon request for inspection, copying, and transcription by authorized representatives of the Administrator of the Wage and Hour Division of the Department of Labor:

(i) Name, address, and social security number of each employee.

(ii) The employee's occupation(s) or classification(s).

(iii) The rate or rates of wages paid (including all pay and benefits provided).

(iv) The number of daily and weekly hours worked.

(v) Any deductions made.

(vi) The total wages paid (including all pay and benefits provided) each pay period.

(vii) A copy of notifications to employees of the amount of paid sick leave the employee has accrued, as required under 29 CFR 13.5(a)(2).

(viii) A copy of employees' requests to use paid sick leave, if in writing, or, if not in writing, any other records reflecting such employee requests.

(ix) Dates and amounts of paid sick leave taken by employees (unless the Contractor's paid time off policy satisfies the requirements of E.O. 13706 and 29 CFR part 13 as described in 29 CFR 13.5(f)(5), leave shall be designated in records as paid sick leave pursuant to E.O. 13706).

(x) A copy of any written responses to employees' requests to use paid sick leave, including explanations for any denials of such requests, as required under 29 CFR 13.5(d)(3).

(xi) Any records reflecting the certification and documentation the Contractor may require an employee to provide under 29 CFR 13.5(e), including copies of any certification or documentation provided by an employee.

(xii) Any other records showing any tracking of or calculations related to an employee's accrual or use of paid sick leave.

(xiii) The relevant contract.

(xiv) The regular pay and benefits provided to an employee for each use of paid sick leave.

(xv) Any financial payment made for unused paid sick leave upon a separation from employment intended, pursuant to 29 CFR 13.5(b)(5), to relieve the Contractor from the obligation to reinstate such paid sick leave as otherwise required by 29 CFR 13.5(b)(4).

(2)(i) If the Contractor wishes to distinguish between an employee's covered and noncovered work, the Contractor shall keep records or other proof reflecting such distinctions. Only if the Contractor adequately segregates the employee's time will time spent on noncovered work be excluded from hours worked counted toward the accrual of paid sick leave. Similarly, only if the Contractor adequately segregates the employee's time may the Contractor properly refuse an employee's request to use paid sick leave on the ground that the employee was scheduled to perform noncovered work during the time he or she asked to use paid sick leave.

(ii) If the Contractor estimates covered hours worked by an employee who performs work in connection with contracts covered by the E.O. pursuant to 29 CFR 13.5(a)(1)(i) or (iii), the Contractor shall keep records or other proof of the verifiable information on which such estimates are reasonably based. Only if the Contractor relies on an estimate that is reasonable and based on verifiable information will an employee's time spent in connection with noncovered work be excluded from hours worked counted toward the accrual of paid sick leave. If the Contractor estimates the amount of time an employee spends performing in connection with contracts covered by the E.O., the Contractor shall permit the employee to use his or her paid sick leave during any work time for the Contractor.

(3) In the event the Contractor is not obligated by the Service Contract Labor Standards statute, the Wage Rate Requirements (Construction) statute, or the Fair Labor Standards Act to keep records of an employee's hours worked, such as because the employee is exempt from the Fair Labor Standards Act's minimum wage and overtime requirements, and the Contractor chooses to use the assumption permitted by 29 CFR 13.5(a)(1)(iii), the Contractor is excused from the requirement in paragraph (i)(1)(iv) of this clause and 29 CFR 13.25(a)(4) to keep records of the employee's number of daily and weekly hours worked.

(4)(i) Records relating to medical histories or domestic violence, sexual assault, or stalking, created for purposes of E.O. 13706, whether of an employee or an employee's child, parent, spouse, domestic partner, or other individual related by blood or affinity whose close association with the employee is the equivalent of a family relationship, shall be maintained as confidential records in separate files/records from the usual personnel files.

(ii) If the confidentiality requirements of the Genetic Information Nondiscrimination Act of 2008 (GINA), section 503 of the Rehabilitation Act of 1973, and/or the Americans with Disabilities Act (ADA) apply to records or documents created to comply with the recordkeeping requirements in this contract clause, the records and documents shall also be maintained in compliance with the confidentiality requirements of the GINA, section 503 of the Rehabilitation Act of 1973, and/or ADA as described in 29 CFR 1635.9, 41 CFR 60-741.23(d), and 29 CFR 1630.14(c)(1), respectively.

(iii) The Contractor shall not disclose any documentation used to verify the need to use 3 or more consecutive days of paid sick leave for the purposes listed in 29 CFR 13.5(c)(1)(iv) (as described in 29 CFR 13.5(e)(1)(ii)) and shall maintain confidentiality about any domestic abuse, sexual assault, or stalking, unless the employee consents or when disclosure is required by law.

(5) The Contractor shall permit authorized representatives of the Wage and Hour Division to conduct interviews with employees at the worksite during normal working hours.

(6) Nothing in this contract clause limits or otherwise modifies the Contractor's recordkeeping obligations, if any, under the Service Contract Labor Standards statute, the Wage Rate Requirements (Construction) statute, the Fair Labor Standards Act, the Family and Medical Leave Act, E.O. 13658, their respective implementing regulations, or any other applicable law.

(j) Interference/discrimination.

(1) The Contractor shall not in any manner interfere with an employee's accrual or use of paid sick leave as required by E.O. 13706 or 29 CFR part 13. Interference includes, but is not limited to--

(i) Miscalculating the amount of paid sick leave an employee has accrued;

(ii) Denying or unreasonably delaying a response to a proper request to use paid sick leave;

(iii) Discouraging an employee from using paid sick leave;

(iv) Reducing an employee's accrued paid sick leave by more than the amount of such leave used;

(v) Transferring an employee to work on contracts not covered by the E.O. to prevent the accrual or use of paid sick leave;

(vi) Disclosing confidential information contained in certification or other documentation provided to verify the need to use paid sick leave; or

(vii) Making the use of paid sick leave contingent on the employee's finding a replacement worker or the fulfillment of the Contractor's operational needs.

(2) The Contractor shall not discharge or in any other manner discriminate against any employee for--

- (i) Using, or attempting to use, paid sick leave as provided for under E.O. 13706 and 29 CFR part 13;
 - (ii) Filing any complaint, initiating any proceeding, or otherwise asserting any right or claim under E.O. 13706 and 29 CFR part 13;
 - (iii) Cooperating in any investigation or testifying in any proceeding under E.O. 13706 and 29 CFR part 13; or
 - (iv) Informing any other person about his or her rights under E.O. 13706 and 29 CFR part 13.
- (k) Notice. The Contractor shall notify all employees performing work on or in connection with a contract covered by the E.O. of the paid sick leave requirements of E.O. 13706, 29 CFR part 13, and this clause by posting a notice provided by the Department of Labor in a prominent and accessible place at the worksite so it may be readily seen by employees. Contractors that customarily post notices to employees electronically may post the notice electronically, provided such electronic posting is displayed prominently on any Web site that is maintained by the Contractor, whether external or internal, and customarily used for notices to employees about terms and conditions of employment.
- (l) Disputes concerning labor standards. Disputes related to the application of E.O. 13706 to this contract shall not be subject to the general disputes clause of the contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR part 13. Disputes within the meaning of this contract clause include disputes between the Contractor (or any of its subcontractors) and the contracting agency, the Department of Labor, or the employees or their representatives.
- (m) Subcontracts. The Contractor shall insert the substance of this clause, including this paragraph (m), in all subcontracts, regardless of dollar value, that are subject to the Service Contract Labor Standards statute or the Wage Rate Requirements (Construction) statute, and are to be performed in whole or in part in the United States.

(End of clause)

52.223-2 AFFIRMATIVE PROCUREMENT OF BIOBASED PRODUCTS UNDER SERVICE AND CONSTRUCTION CONTRACTS (DEVIATION) (SEP 2013)

- (a) In the performance of this contract, the contractor shall make maximum use of biobased products that are United States Department of Agriculture (USDA)-designated items unless--
- (1) The product cannot be acquired--
 - (i) Competitively within a time frame providing for compliance with the contract performance schedule;
 - (ii) Meeting contract performance requirements; or
 - (iii) At a reasonable price.
 - (2) The product is to be used in an application covered by a USDA categorical exemption (see 7 CFR 3201.3(e)). For example, all USDA-designated items are exempt from the preferred procurement requirement for the following:
 - (i) Spacecraft system and launch support equipment.
 - (ii) Military equipment, i.e., a product or system designed or procured for combat or combat-related missions.
- (b) Information about this requirement and these products is available at <http://www.biopreferredgov>.
- (c) In the performance of this contract, the Contractor shall--
- (1) Report to <http://www.sam.gov>, with a copy to the Contracting Officer, on the product types and dollar value of any USDA-designated biobased products purchased by the Contractor during the previous Government fiscal year, between October 1 and September 30; and
 - (2) Submit this report no later than--

(ii) At the end of contract performance.

(End of clause)

52.223-5 -- Pollution Prevention and Right-to-Know Information.

(a) Definitions. As used in this clause—

“Toxic chemical” means a chemical or chemical category in listed in 40 CFR 372.65.

(b) Federal facilities are required to comply with the provisions of the Emergency Planning and Community Right-to-Know Act of 1986 (EPCRA) (42 U.S.C. 11001-11050), and the Pollution Prevention Act of 1990 (PPA) (42 U.S.C. 13101-13109).

(c) The Contractor shall provide all information needed by the Federal facility to comply with the following:

(1) The emergency planning reporting requirements of Section 302 of EPCRA.

(2) The emergency notice requirements of Section 304 of EPCRA

(3) The list of Material Safety Data Sheets required by Section 311 of EPCRA

(4) The emergency and hazardous chemical inventory forms of Section 312 of EPCRA

(5) The toxic chemical release inventory of Section 313 of EPCRA, which includes the reduction and recycling information required by Section 6607 of PPA

(6) The toxic chemical and hazardous substance release and use reduction goals of section 2(e) of Executive Order 13423 and of Executive Order 13514.

(End of Clause)

52.223-6 DRUG-FREE WORKPLACE (MAY 2001)

(a) Definitions. As used in this clause --

"Controlled substance" means a controlled substance in schedules I through V of section 202 of the Controlled Substances Act (21 U.S.C. 812) and as further defined in regulation at 21 CFR 1308.11 - 1308.15.

"Conviction" means a finding of guilt (including a plea of nolo contendere) or imposition of sentence, or both, by any judicial body charged with the responsibility to determine violations of the Federal or State criminal drug statutes.

"Criminal drug statute" means a Federal or non-Federal criminal statute involving the manufacture, distribution, dispensing, possession, or use of any controlled substance.

"Drug-free workplace" means the site(s) for the performance of work done by the Contractor in connection with a specific contract at which employees of the Contractor are prohibited from engaging in the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance.

"Employee" means an employee of a Contractor directly engaged in the performance of work under a Government contract. "Directly engaged" is defined to include all direct cost employees and any other Contractor employee who

has other than a minimal impact or involvement in contract performance.

"Individual" means an offeror/contractor that has no more than one employee including the offeror/contractor.

(b) The Contractor, if other than an individual, shall-- within 30 days after award (unless a longer period is agreed to in writing for contracts of 30 days or more performance duration), or as soon as possible for contracts of less than 30 days performance duration--

(1) Publish a statement notifying its employees that the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance is prohibited in the Contractor's workplace and specifying the actions that will be taken against employees for violations of such prohibition;

(2) Establish an ongoing drug-free awareness program to inform such employees about--

(i) The dangers of drug abuse in the workplace;

(ii) The Contractor's policy of maintaining a drug-free workplace;

(iii) Any available drug counseling, rehabilitation, and employee assistance programs; and

(iv) The penalties that may be imposed upon employees for drug abuse violations occurring in the workplace;

(3) Provide all employees engaged in performance of the contract with a copy of the statement required by subparagraph (b)(1) of this clause;

(4) Notify such employees in writing in the statement required by subparagraph (b)(1) of this clause that, as a condition of continued employment on this contract, the employee will--

(i) Abide by the terms of the statement; and

(ii) Notify the employer in writing of the employee's conviction under a criminal drug statute for a violation occurring in the workplace no later than 5 days after such conviction.

(5) Notify the Contracting Officer in writing within 10 days after receiving notice under subdivision (b)(4)(ii) of this clause, from an employee or otherwise receiving actual notice of such conviction. The notice shall include the position title of the employee;

(6) Within 30 days after receiving notice under subdivision (b)(4)(ii) of this clause of a conviction, take one of the following actions with respect to any employee who is convicted of a drug abuse violation occurring in the workplace:

(i) Taking appropriate personnel action against such employee, up to and including termination; or

(ii) Require such employee to satisfactorily participate in a drug abuse assistance or rehabilitation program approved for such purposes by a Federal, State, or local health, law enforcement, or other appropriate agency; and

(7) Make a good faith effort to maintain a drug-free workplace through implementation of subparagraphs (b)(1) through (b)(6) of this clause.

(c) The Contractor, if an individual, agrees by award of the contract or acceptance of a purchase order, not to engage in the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance while performing this contract.

(d) In addition to other remedies available to the Government, the Contractor's failure to comply with the requirements of paragraph (b) or (c) of this clause may, pursuant to FAR 23.506, render the Contractor subject to

suspension of contract payments, termination of the contract for default, and suspension or debarment.

(End of clause)

52.223-15 – Energy Efficiency in Energy-Consuming Products.

(a) Definition. As used in this clause--

“Energy-efficient product”—

(1) Means a product that—

(i) Meets Department of Energy and Environmental Protection Agency criteria for use of the Energy Star trademark label; or

(ii) Is in the upper 25 percent of efficiency for all similar products as designated by the Department of Energy’s Federal Energy Management Program.

(2) The term “product” does not include any energy-consuming product or system designed or procured for combat or combat-related missions (42 U.S.C. 8259b).

(b) The Contractor shall ensure that energy-consuming products are energy efficient products (i.e., ENERGY STAR® products or FEMP-designated products) at the time of contract award, for products that are—

(1) Delivered;

(2) Acquired by the Contractor for use in performing services at a Federally-controlled facility;

(3) Furnished by the Contractor for use by the Government; or

(4) Specified in the design of a building or work, or incorporated during its construction, renovation, or maintenance.

(c) The requirements of paragraph (b) apply to the Contractor (including any subcontractor) unless—

(1) The energy-consuming product is not listed in the ENERGY STAR® Program or FEMP; or

(2) Otherwise approved in writing by the Contracting Officer.

(d) Information about these products is available for—

(1) ENERGY STAR® at <http://www.energystar.gov/products>; and

(2) FEMP at http://www1.eere.energy.gov/femp/procurement/eeep_requirements.html.

(End of clause)

52.223-17 – Affirmative Procurement of EPA-Designated Items in Service and Construction Contracts.

(a) In the performance of this contract, the Contractor shall make maximum use of products containing recovered materials that are EPA-designated items unless the product cannot be acquired—

(1) Competitively within a timeframe providing for compliance with the contract performance schedule;

(2) Meeting contract performance requirements; or

(3) At a reasonable price.

(b) Information about this requirement is available at EPA's Comprehensive Procurement Guidelines web site, <http://www.epa.gov/cpg/>. The list of EPA-designate items is available at <http://www.epa.gov/cpg/products.htm>.

(End of clause)

**52.223-18 ENCOURAGING CONTRACTOR POLICIES TO BAN TEXT MESSAGING WHILE DRIVING
(AUG 2011)**

(a) Definitions. As used in this clause--

Driving—

(1) Means operating a motor vehicle on an active roadway with the motor running, including while temporarily stationary because of traffic, a traffic light, stop sign, or otherwise.

(2) Does not include operating a motor vehicle with or without the motor running when one has pulled over to the side of, or off, an active roadway and has halted in a location where one can safely remain stationary.

Text messaging means reading from or entering data into any handheld or other electronic device, including for the purpose of short message service texting, e-mailing, instant messaging, obtaining navigational information, or engaging in any other form of electronic data retrieval or electronic data communication. The term does not include glancing at or listening to a navigational device that is secured in a commercially designed holder affixed to the vehicle, provided that the destination and route are programmed into the device either before driving or while stopped in a location off the roadway where it is safe and legal to park.

(b) This clause implements Executive Order 13513, Federal Leadership on Reducing Text Messaging while Driving, dated October 1, 2009.

(c) The Contractor is encouraged to--

(1) Adopt and enforce policies that ban text messaging while driving--

(i) Company-owned or -rented vehicles or Government-owned vehicles; or

(ii) Privately-owned vehicles when on official Government business or when performing any work for or on behalf of the Government.

(2) Conduct initiatives in a manner commensurate with the size of the business, such as--

(i) Establishment of new rules and programs or re-evaluation of existing programs to prohibit text messaging while driving; and

(ii) Education, awareness, and other outreach to employees about the safety risks associated with texting while driving.

(d) Subcontracts. The Contractor shall insert the substance of this clause, including this paragraph (d), in all subcontracts that exceed the micro-purchase threshold.

(End of clause)

(a) Definitions. As used in this clause--

“Commercially available off-the-shelf (COTS) item”—

(1) Means any item of supply (including construction material) that is—

(i) A commercial item (as defined in paragraph (1) of the definition at FAR 2.101);

(ii) Sold in substantial quantities in the commercial marketplace; and

(iii) Offered to the Government, under a contract or subcontract at any tier, without modification, in the same form in which it is sold in the commercial marketplace; and

(2) Does not include bulk cargo, as defined in 46 U.S.C. 40102(4), such as agricultural products and petroleum products.

“Component” means an article, material, or supply incorporated directly into a construction material.

“Construction material” means an article, material, or supply brought to the construction site by the Contractor or a subcontractor for incorporation into the building or work. The term also includes an item brought to the site preassembled from articles, materials, or supplies. However, emergency life safety systems, such as emergency lighting, fire alarm, and audio evacuation systems, that are discrete systems incorporated into a public building or work and that are produced as complete systems, are evaluated as a single and distinct construction material regardless of when or how the individual parts or components of those systems are delivered to the construction site. Materials purchased directly by the Government are supplies, not construction material.

“Cost of components” means--

(1) For components purchased by the Contractor, the acquisition cost, including transportation costs to the place of incorporation into the construction material (whether or not such costs are paid to a domestic firm), and any applicable duty (whether or not a duty-free entry certificate is issued); or

(2) For components manufactured by the Contractor, all costs associated with the manufacture of the component, including transportation costs as described in paragraph (1) of this definition, plus allocable overhead costs, but excluding profit. Cost of components does not include any costs associated with the manufacture of the construction material.

“Domestic construction material” means—

(1) An unmanufactured construction material mined or produced in the United States;

(2) A construction material manufactured in the United States, if—

(i) The cost of its components mined, produced, or manufactured in the United States exceeds 50 percent of the cost of all its components. Components of foreign origin of the same class or kind for which nonavailability determinations have been made are treated as domestic; or

(ii) The construction material is a COTS item.

“Foreign construction material” means a construction material other than a domestic construction material.

“United States” means the 50 States, the District of Columbia, and outlying areas.

(b) Domestic preference.

(1) This clause implements the 41 U.S.C. chapter 83, Buy American, by providing a preference for domestic construction material. In accordance with 41 U.S.C. 1907, the component test of the Buy American statute is waived for construction material that is a COTS item. (See FAR 12.505(a)(2)). The Contractor shall use only domestic construction material in performing this contract, except as provided in paragraphs (b)(2) and (b)(3) of this clause.

(2) This requirement does not apply to information technology that is a commercial item or to the construction materials or components listed by the Government as follows: _____ [Contracting Officer to list applicable excepted materials or indicate "none"]

(3) The Contracting Officer may add other foreign construction material to the list in paragraph (b)(2) of this clause if the Government determines that

(i) The cost of domestic construction material would be unreasonable. The cost of a particular domestic construction material subject to the requirements of the Buy American statute is unreasonable when the cost of such material exceeds the cost of foreign material by more than 6 percent;

(ii) The application of the restriction of the Buy American statute to a particular construction material would be impracticable or inconsistent with the public interest; or

(iii) The construction material is not mined, produced, or manufactured in the United States in sufficient and reasonably available commercial quantities of a satisfactory quality.

(c) Request for determination of inapplicability of the Buy American statute.

(1)

(i) Any Contractor request to use foreign construction material in accordance with paragraph (b)(3) of this clause shall include adequate information for Government evaluation of the request, including--

(A) A description of the foreign and domestic construction materials;

(B) Unit of measure;

(C) Quantity;

(D) Price;

(E) Time of delivery or availability;

(F) Location of the construction project;

(G) Name and address of the proposed supplier; and

(H) A detailed justification of the reason for use of foreign construction materials cited in accordance with paragraph (b)(3) of this clause.

(ii) A request based on unreasonable cost shall include a reasonable survey of the market and a completed price comparison table in the format in paragraph (d) of this clause.

(iii) The price of construction material shall include all delivery costs to the construction site and any applicable duty (whether or not a duty-free certificate may be issued).

(iv) Any Contractor request for a determination submitted after contract award shall explain why the Contractor could not reasonably foresee the need for such determination and could not have requested the determination before contract award. If the Contractor does not submit a satisfactory explanation, the Contracting Officer need not make a determination.

(2) If the Government determines after contract award that an exception to the Buy American statute applies and the Contracting Officer and the Contractor negotiate adequate consideration, the Contracting Officer will modify the contract to allow use of the foreign construction material. However, when the basis for the exception is the unreasonable price of a domestic construction material, adequate consideration is not less than the differential established in paragraph (b)(3)(i) of this clause.

(3) Unless the Government determines that an exception to the Buy American statute applies, use of foreign construction material is noncompliant with the Buy American statute.

(d) Data. To permit evaluation of requests under paragraph (c) of this clause based on unreasonable cost, the Contractor shall include the following information and any applicable supporting data based on the survey of suppliers:

Foreign and Domestic Construction Materials Price Comparison

Construction material description

Unit of measure

Quantity

Price (dollars) *

Item 1

Foreign construction material

Domestic construction material

Item 2

Foreign construction material

Domestic construction material

[List name, address, telephone number, and contact for suppliers surveyed. Attach copy of response; if oral, attach summary.]

[Include other applicable supporting information.]

[*Include all delivery costs to the construction site and any applicable duty (whether or not a duty-free entry certificate is issued).]

(End of Clause)

52.225-12 NOTICE OF BUY AMERICAN REQUIREMENT-- CONSTRUCTION MATERIALS UNDER TRADE AGREEMENTS (MAY 2014)

(a) Definitions. "Commercially available off-the-shelf (COTS) item," "construction material," "designated country construction material," "domestic construction material," and "foreign construction material," as used in this provision, are defined in the clause of this solicitation entitled "Buy American -- Construction Materials Under Trade Agreements" (Federal Acquisition Regulation (FAR) clause 52.225-11).

(b) Requests for determination of inapplicability. An offeror requesting a determination regarding the inapplicability of the Buy American statute should submit the request to the Contracting Officer in time to allow a determination before submission of offers. The offeror shall include the information and applicable supporting data required by paragraphs (c) and (d) of FAR clause 52.225-11 in the request. If an offeror has not requested a determination regarding the inapplicability of the Buy American statute before submitting its offer, or has not received a response to a previous request, the offeror shall include the information and supporting data in the offer.

(c) Evaluation of offers. (1) The Government will evaluate an offer requesting exception to the requirements of the Buy American statute, based on claimed unreasonable cost of domestic construction materials, by adding to the offered price the appropriate percentage of the cost of such foreign construction material, as specified in paragraph (b)(4)(i) of FAR clause 52.225-11.

(2) If evaluation results in a tie between an offeror that requested the substitution of foreign construction material based on unreasonable cost and an offeror that did not request an exception, the Contracting Officer will award to the offeror that did not request an exception based on unreasonable cost.

(d) Alternate offers. (1) When an offer includes foreign construction material, other than designated country construction material, that is not listed by the Government in this solicitation in paragraph (b)(3) of FAR clause 52.225-11, the offeror also may submit an alternate offer based on use of equivalent domestic or designated country construction material.

(2) If an alternate offer is submitted, the offeror shall submit a separate Standard Form 1442 for the alternate offer, and a separate price comparison table prepared in accordance with paragraphs (c) and (d) of FAR clause 52.225-11 for the offer that is based on the use of any foreign construction material for which the Government has not yet determined an exception applies.

(3) If the Government determines that a particular exception requested in accordance with paragraph (c) of FAR clause 52.225-11 does not apply, the Government will evaluate only those offers based on use of the equivalent domestic or designated country construction material, and the offeror shall be required to furnish such domestic or designated country construction material. An offer based on use of the foreign construction material for which an exception was requested-- (i) Will be rejected as nonresponsive if this acquisition is conducted by sealed bidding; or

(ii) May be accepted if revised during negotiations.

(End of provision)

52.225-13 RESTRICTIONS ON CERTAIN FOREIGN PURCHASES (JUN 2008)

(a) Except as authorized by the Office of Foreign Assets Control (OFAC) in the Department of the Treasury, the Contractor shall not acquire, for use in the performance of this contract, any supplies or services if any proclamation, Executive order, or statute administered by OFAC, or if OFAC's implementing regulations at 31 CFR chapter V, would prohibit such a transaction by a person subject to the jurisdiction of the United States.

(b) Except as authorized by OFAC, most transactions involving Cuba, Iran, and Sudan are prohibited, as are most imports from Burma or North Korea, into the United States or its outlying areas. Lists of entities and individuals subject to economic sanctions are included in OFAC's List of Specially Designated Nationals and Blocked Persons at [TerList1.html](http://terlist1.html). More information about these restrictions, as well as updates, is available in the OFAC's regulations at 31 CFR chapter V and/or on OFAC's Web site at <http://www.treas.gov/offices/enforcement/ofac/>.

(c) The Contractor shall insert this clause, including this paragraph (c), in all subcontracts.

(End of clause)

52.226-1 UTILIZATION OF INDIAN ORGANIZATIONS AND INDIAN-OWNED ECONOMIC ENTERPRISES (JUN 2000)

(a) Definitions. As used in this clause:

"Indian" means any person who is a member of any Indian tribe, band, group, pueblo or community that is recognized by the Federal Government as eligible for services from the Bureau of Indian Affairs (BIA) in accordance with 25 U.S.C. 1452(c) and any "Native" as defined in the Alaska Native Claims Settlement Act (43 U.S.C. 1601).

"Indian organization" means the governing body of any Indian tribe or entity established or recognized by the governing body of an Indian tribe for the purposes of 25 U.S.C., chapter 17.

"Indian-owned economic enterprise" means any Indian-owned (as determined by the Secretary of the Interior) commercial, industrial, or business activity established or organized for the purpose of profit, provided that Indian ownership constitute a not less than 51 percent of the enterprise.

"Indian tribe" means any Indian tribe, band, group, pueblo or community, including native villages and native groups (including corporations organized by Kenai, Juneau, Sitka, and Kodiak) as defined in the Alaska Native Claims Settlement Act, that is recognized by the Federal Government as eligible for services from BIA in accordance with 25 U.S.C. 1542(c).

"Interested party" means a prime contractor or an actual or prospective offeror whose direct economic interest would be affected by the award of a subcontract or by the failure to award a subcontract.

(b) The Contractor shall use its best efforts to give Indian organizations and Indian-owned economic enterprises (25 U.S.C. 1544) the maximum practicable opportunity to participate in the subcontracts it awards to the fullest extent consistent with efficient performance of its contract.

(1) The Contracting Officer and the Contractor, acting in good faith, may rely on the representation of an Indian organization or Indian-owned economic enterprise as to its eligibility, unless an interested party challenges its status or the Contracting Officer has independent reason to question that status. In the event of a challenge to the representation of a subcontractor, the Contracting Officer will refer the matter to the U.S. Department of the Interior, Bureau of Indian Affairs (BIA), Attn: Chief, Division of Contracting and Grants Administration, 1849 C Street, NW., MS 2626-MIB, Washington, DC 20240-4000.

The BIA will determine the eligibility and notify the Contracting Officer. No incentive payment will be made within 50 working days of subcontract award or while a challenge is pending. If a subcontractor is determined to be an ineligible participant, no incentive payment will be made under the Indian Incentive Program.

(2) The Contractor may request an adjustment under the Indian Incentive Program to the following:

(i) The estimated cost of a cost-type contract.

(ii) The target cost of a cost-plus-incentive-fee prime contract.

(iii) The target cost and ceiling price of a fixed-price incentive prime contract.

(iv) The price of a firm-fixed-price prime contract.

(3) The amount of the adjustment to the prime contract is 5 percent of the estimated cost, target cost, or firm-fixed-price included in the subcontract initially awarded to the Indian organization or Indian-owned economic enterprise.

(4) The Contractor has the burden of proving the amount claimed and must assert its request for an adjustment prior to completion of contract performance.

(c) The Contracting Officer, subject to the terms and conditions of the contract and the availability of funds, will authorize an incentive payment of 5 percent of the amount paid to the subcontractor. The Contracting Officer will seek funding in accordance with agency procedures.

(End of clause)

52.227-1 AUTHORIZATION AND CONSENT (DEC 2007)

(a) The Government authorizes and consents to all use and manufacture, in performing this contract or any subcontract at any tier, of any invention described in and covered by a United States patent--

(1) Embodied in the structure or composition of any article the delivery of which is accepted by the Government under this contract; or

(2) Used in machinery, tools, or methods whose use necessarily results from compliance by the Contractor or a subcontractor with (i) specifications or written provisions forming a part of this contract or (ii) specific written instructions given by the Contracting Officer directing the manner of performance. The entire liability to the Government for infringement of a United States patent shall be determined solely by the provisions of the indemnity clause, if any, included in this contract or any subcontract hereunder (including any lower-tier subcontract), and the Government assumes liability for all other infringement to the extent of the authorization and consent hereinabove granted.

(b) The Contractor shall include the substance of this clause, including this paragraph (b), in all subcontracts that are expected to exceed the simplified acquisition threshold. However, omission of this clause from any subcontract, including those at or below the simplified acquisition threshold, does not affect this authorization and consent.

(End of clause)

52.227-2 NOTICE AND ASSISTANCE REGARDING PATENT AND COPYRIGHT INFRINGEMENT (DEC 2007)

(a) The Contractor shall report to the Contracting Officer, promptly and in reasonable written detail, each notice or claim of patent or copyright infringement based on the performance of this contract of which the Contractor has knowledge.

(b) In the event of any claim or suit against the Government on account of any alleged patent or copyright infringement arising out of the performance of this contract or out of the use of any supplies furnished or work or services performed under this contract, the Contractor shall furnish to the Government, when requested by the Contracting Officer, all evidence and information in the Contractor's possession pertaining to such claim or suit.

Such evidence and information shall be furnished at the expense of the Government except where the Contractor has agreed to indemnify the Government.

(c) The Contractor shall include the substance of this clause, including this paragraph (c), in all subcontracts that are expected to exceed the simplified acquisition threshold.

(End of clause)

52.227-4 PATENT INDEMNITY--CONSTRUCTION CONTRACTS (DEC 2007)

Except as otherwise provided, the Contractor shall indemnify the Government and its officers, agents, and employees against liability, including costs and expenses, for infringement of any United States patent (except a patent issued upon an application that is now or may hereafter be withheld from issue pursuant to a Secrecy Order under 35 U.S.C. 181) arising out of performing this contract or out of the use or disposal by or for the account of the Government of supplies furnished or work performed under this contract.

(End of clause)

52.228-1 BID GUARANTEE (SEP 1996)

(a) Failure to furnish a bid guarantee in the proper form and amount, by the time set for opening of bids, may be cause for rejection of the bid.

(b) The bidder shall furnish a bid guarantee in the form of a firm commitment, e.g., bid bond supported by good and sufficient surety or sureties acceptable to the Government, postal money order, certified check, cashier's check, irrevocable letter of credit, or, under Treasury Department regulations, certain bonds or notes of the United States. The Contracting Officer will return bid guarantees, other than bid bonds, (1) to unsuccessful bidders as soon as practicable after the opening of bids, and (2) to the successful bidder upon execution of contractual documents and bonds (including any necessary coinsurance or reinsurance agreements), as required by the bid as accepted.-

(c) The amount of the bid guarantee shall be **twenty (20%)** percent of the bid price or **\$3,000,000.00**, whichever is less.-

(d) If the successful bidder, upon acceptance of its bid by the Government within the period specified for acceptance, fails to execute all contractual documents or furnish executed bond(s) within 10 days after receipt of the forms by the bidder, the Contracting Officer may terminate the contract for default.-

(e) In the event the contract is terminated for default, the bidder is liable for any cost of acquiring the work that exceeds the amount of its bid, and the bid guarantee is available to offset the difference.

(End of provision)

52.228-2 ADDITIONAL BOND SECURITY (OCT 1997)

The Contractor shall promptly furnish additional security required to protect the Government and persons supplying labor or materials under this contract if--

(a) Any surety upon any bond, or issuing financial institution for other security, furnished with this contract becomes unacceptable to the Government.

(b) Any surety fails to furnish reports on its financial condition as required by the Government;

(c) The contract price is increased so that the penal sum of any bond becomes inadequate in the opinion of the Contracting Officer; or

(d) An irrevocable letter of credit (ILC) used as security will expire before the end of the period of required security. If the Contractor does not furnish an acceptable extension or replacement ILC, or other acceptable substitute, at least 30 days before an ILC's scheduled expiration, the Contracting officer has the right to immediately draw on the ILC.

(End of clause)

52.228-5 INSURANCE--WORK ON A GOVERNMENT INSTALLATION (JAN 1997)

(a) The Contractor shall, at its own expense, provide and maintain during the entire performance of this contract, at least the kinds and minimum amounts of insurance required in the Schedule or elsewhere in the contract.

(b) Before commencing work under this contract, the Contractor shall notify the Contracting Officer in writing that the required insurance has been obtained. The policies evidencing required insurance shall contain an endorsement to the effect that any cancellation or any material change adversely affecting the Government's interest shall not be effective (1) for such period as the laws of the State in which this contract is to be performed prescribe, or (2) until 30 days after the insurer or the Contractor gives written notice to the Contracting Officer, whichever period is longer.

(c) The Contractor shall insert the substance of this clause, including this paragraph (c), in subcontracts under this contract that require work on a Government installation and shall require subcontractors to provide and maintain the insurance required in the Schedule or elsewhere in the contract. The Contractor shall maintain a copy of all subcontractors' proofs of required insurance, and shall make copies available to the Contracting Officer upon request.

(End of clause)

52.228-11 PLEDGES OF ASSETS (JAN 2012)

(a) Offerors shall obtain from each person acting as an individual surety on a bid guarantee, a performance bond, or a payment bond--

(1) Pledge of assets; and

(2) Standard Form 28, Affidavit of Individual Surety.

(b) Pledges of assets from each person acting as an individual surety shall be in the form of--

(1) Evidence of an escrow account containing cash, certificates of deposit, commercial or Government securities, or other assets described in FAR 28.203-2 (except see 28.203-2(b)(2) with respect to Government securities held in book entry form); and/or

(2) A recorded lien on real estate. The offeror will be required to provide--

(i) A mortgagee title insurance policy, in an insurance amount equal to the amount of the lien, or other evidence of title that is consistent with the requirements of Section 2 of the United States Department of Justice Title Standards

at http://www.justice.gov/enrd/ENRD_Assets/Title_Standards_2001.pdf. This title evidence must show fee simple title vested in the surety along with any concurrent owners; whether any real estate taxes are due and payable; and

any recorded encumbrances against the property, including the lien filed in favor of the Government as required by FAR 28.203-3(d);

(ii) Evidence of the amount due under any encumbrance shown in the evidence of title;

(iii) A copy of the current real estate tax assessment of the property or a current appraisal dated no earlier than 6 months prior to the date of the bond, prepared by a professional appraiser who certifies that the appraisal has been conducted in accordance with the generally accepted appraisal standards as reflected in the Uniform Standards of Professional Appraisal Practice, as promulgated by the Appraisal Foundation.

(End of clause)

52.228-12 Prospective Subcontractor Requests for Bonds. (MAY 2014)

In accordance with section 806(a)(3) of Pub. L. 102-190, as amended by sections 2091 and 8105 of Pub. L. 103-355 (10 U.S.C. 2302 note), upon the request of a prospective subcontractor or supplier offering to furnish labor or material for the performance of this contract for which a payment bond has been furnished to the Government pursuant to 40 U.S.C. chapter 31, subchapter III, Bonds, the Contractor shall promptly provide a copy of such payment bond to the requester.

(End of clause)

52.228-14 IRREVOCABLE LETTER OF CREDIT (NOV 2014)

(a) "Irrevocable letter of credit" (ILC), as used in this clause, means a written commitment by a federally insured financial institution to pay all or part of a stated amount of money, until the expiration date of the letter, upon presentation by the Government (the beneficiary) of a written demand therefor. Neither the financial institution nor the offeror/Contractor can revoke or condition the letter of credit.

(b) If the offeror intends to use an ILC in lieu of a bid bond, or to secure other types of bonds such as performance and payment bonds, the letter of credit and letter of confirmation formats in paragraphs (e) and (f) of this clause shall be used.

(c) The letter of credit shall be irrevocable, shall require presentation of no document other than a written demand and the ILC (including confirming letter, if any), shall be issued/confirmed by an acceptable federally insured financial institution as provided in paragraph (d) of this clause, and--

(1) If used as a bid guarantee, the ILC shall expire no earlier than 60 days after the close of the bid acceptance period;

(2) If used as an alternative to corporate or individual sureties as security for a performance or payment bond, the offeror/Contractor may submit an ILC with an initial expiration date estimated to cover the entire period for which financial security is required or may submit an ILC with an initial expiration date that is a minimum period of one year from the date of issuance. The ILC shall provide that, unless the issuer provides the beneficiary written notice of non-renewal at least 60 days in advance of the current expiration date, the ILC is automatically extended without amendment for one year from the expiration date, or any future expiration date, until the period of required coverage is completed and the Contracting Officer provides the financial institution with a written statement waiving the right to payment. The period of required coverage shall be:

(i) For contracts subject to 40 U.S.C. chapter 31, subchapter III, Bonds, the later of--

(A) One year following the expected date of final payment;

(B) For performance bonds only, until completion of any warranty period; or

(C) For payment bonds only, until resolution of all claims filed against the payment bond during the one-year period following final payment.

(ii) For contracts not subject to the Miller Act, the later of--

(A) 90 days following final payment; or

(B) For performance bonds only, until completion of any warranty period.

(d)(1) Only federally insured financial institutions rated investment grade by a commercial rating service shall issue or confirm the ILC.

(2) Unless the financial institution issuing the ILC had letter of credit business of at least \$25 million in the past year, ILCs over \$5 million must be confirmed by another acceptable financial institution that had letter of credit business of at least \$25 million in the past year.

(3) The Offeror/Contractor shall provide the Contracting Officer a credit rating that indicates the financial institutions have the required credit rating as of the date of issuance of the ILC.

(4) The current rating for a financial institution is available through any of the following rating services registered with the U.S. Securities and Exchange Commission (SEC) as a Nationally Recognized Statistical Rating Organization (NRSRO). NRSRO's can be located at the Web site <http://www.sec.gov/answers/nrsro.htm> maintained by the SEC.

(e) The following format shall be used by the issuing financial institution to create an ILC:

[Issuing Financial Institution's Letterhead or Name and Address]

Issue Date ____

IRREVOCABLE LETTER OF CREDIT NO. ____

Account party's name ____

Account party's address ____

For Solicitation No. ____ (for reference only)

TO: [____ U.S. Government agency]

[____ U.S. Government agency's address]

1. We hereby establish this irrevocable and transferable Letter of Credit in your favor for one or more drawings up to United States \$ ____ . This Letter of Credit is payable at [issuing financial institution's and, if any, confirming financial institution's] office at [____ issuing financial institution's address and, if any, confirming financial institution's address] and expires with our close of business on ____ , or any automatically extended expiration date.

2. We hereby undertake to honor your or the transferee's sight draft(s) drawn on the issuing or, if any, the confirming financial institution, for all or any part of this credit if presented with this Letter of Credit and confirmation, if any, at the office specified in paragraph 1 of this Letter of Credit on or before the expiration date or

3. [This paragraph is omitted if used as a bid guarantee, and subsequent paragraphs are renumbered.] It is a condition of this Letter of Credit that it is deemed to be automatically extended without amendment for one year from the expiration date hereof, or any future expiration date, unless at least 60 days prior to any expiration date, we notify you or the transferee by registered mail, or other receipted means of delivery, that we elect not to consider this Letter of Credit renewed for any such additional period. At the time we notify you, we also agree to notify the account party (and confirming financial institution, if any) by the same means of delivery.

4. This Letter of Credit is transferable. Transfers and assignments of proceeds are to be effected without charge to either the beneficiary or the transferee/assignee of proceeds. Such transfer or assignment shall be only at the written direction of the Government (the beneficiary) in a form satisfactory to the issuing financial institution and the confirming financial institution, if any.

5. This Letter of Credit is subject to the Uniform Customs and Practice (UCP) for Documentary Credits, International Chamber of Commerce Publication No. ____ -- (Insert version in effect at the time of ILC issuance, e.g., "Publication 600, 2006 edition") and to the extent not inconsistent therewith, to the laws of ____ --[State of confirming financial institution, if any, otherwise State of issuing financial institution].

6. If this credit expires during an interruption of business of this financial institution as described in Article 17 of the UCP, the financial institution specifically agrees to effect payment if this credit is drawn against within 30 days after the resumption of our business.

Sincerely,

[____ Issuing financial institution]

(f) The following format shall be used by the financial institution to confirm an ILC:

____ [Confirming Financial Institution's Letterhead or Name and Address]

(Date) ____

Our Letter of Credit Advice Number ____

Beneficiary: ____ [U.S. Government agency]

Issuing Financial Institution: ____

Issuing Financial Institution's LC No.: ____

Gentlemen:

1. We hereby confirm the above indicated Letter of Credit, the original of which is attached, issued by ____ [name of issuing financial institution] for drawings of up to United States dollars ____ /U.S. \$ ____ and expiring with our close of business on ____ [the expiration date], or any automatically extended expiration date.

2. Draft(s) drawn under the Letter of Credit and this Confirmation are payable at our office located at ____ .

3. We hereby undertake to honor sight draft(s) drawn under and presented with the Letter of Credit and this Confirmation at our offices as specified herein.

4. [This paragraph is omitted if used as a bid guarantee, and subsequent paragraphs are renumbered.] It is a

IDIQ CONTRACT FOR RENTAL OF HOPPER
DREDGE WITH ATTENDANT PLANT AND
OPERATORS FOR MAINTENANCE DREDGING IN
ALABAMA, MISSISSIPPI, FLORIDA

W91278-17-B-0002

condition of this confirmation that it be deemed automatically extended without amendment for one year from the expiration date hereof, or any automatically extended expiration date, unless:

(a) At least 60 days prior to any such expiration date, we shall notify the Contracting Officer, or the transferee and the issuing financial institution, by registered mail or other receipted means of delivery, that we elect not to consider this confirmation extended for any such additional period; or

(b) The issuing financial institution shall have exercised its right to notify you or the transferee, the account party, and ourselves, of its election not to extend the expiration date of the Letter of Credit.

5. This confirmation is subject to the Uniform Customs and Practice (UCP) for Documentary Credits, International Chamber of Commerce Publication No. ____ -- (Insert version in effect at the time of ILC issuance, e.g., ``Publication 600, 2006 edition") and to the extent not inconsistent therewith, to the laws of ____ --[State of confirming financial institution].

6. If this confirmation expires during an interruption of business of this financial institution as described in Article 17 of the UCP, we specifically agree to effect payment if this credit is drawn against within 30 days after the resumption of our business.

Sincerely,

[Confirming financial institution]

(g) The following format shall be used by the Contracting Officer for a sight draft to draw on the Letter of Credit:

SIGHT DRAFT

[City, State]

(Date) ____

[Name and address of financial institution]

Pay to the order of ____ [Beneficiary Agency] ____ the sum of United States ____ This draft is drawn under Irrevocable Letter of Credit No. ____

____ [Beneficiary Agency]

By: ____

(End of clause)

52.228-15 Performance and Payment Bonds--Construction (OCT 2010)

(a) Definitions. As used in this clause--

Original contract price means the award price of the contract; or, for requirements contracts, the price payable for the estimated total quantity; or, for indefinite-quantity contracts, the price payable for the specified minimum quantity. Original contract price does not include the price of any options, except those options exercised at the time of contract award.

(b) Amount of required bonds. Unless the resulting contract price is \$150,000 or less, the successful offeror shall furnish performance and payment bonds to the Contracting Officer as follows:

(1) Performance bonds (Standard Form 25). The penal amount of performance bonds at the time of contract award shall be 100 percent of the original contract price.

(2) Payment Bonds (Standard Form 25-A). The penal amount of payment bonds at the time of contract award shall be 100 percent of the original contract price.

(3) Additional bond protection. (i) The Government may require additional performance and payment bond protection if the contract price is increased. The increase in protection generally will equal 100 percent of the increase in contract price.

(ii) The Government may secure the additional protection by directing the Contractor to increase the penal amount of the existing bond or to obtain an additional bond.

(c) Furnishing executed bonds. The Contractor shall furnish all executed bonds, including any necessary reinsurance agreements, to the Contracting Officer, within the time period specified in the Bid Guarantee provision of the solicitation, or otherwise specified by the Contracting Officer, but in any event, before starting work.

(d) Surety or other security for bonds. The bonds shall be in the form of firm commitment, supported by corporate sureties whose names appear on the list contained in Treasury Department Circular 570, individual sureties, or by other acceptable security such as postal money order, certified check, cashier's check, irrevocable letter of credit, or, in accordance with Treasury Department regulations, certain bonds or notes of the United States. Treasury Circular 570 is published in the Federal Register or may be obtained from the U.S. Department of the Treasury, Financial Management Service, Surety Bond Branch, 3700 East West Highway, Room 6F01, Hyattsville, MD 20782. Or via the internet at <http://www.fms.treas.gov/c570/>.

(e) Notice of subcontractor waiver of protection (40 U.S.C. 3133(c)). Any waiver of the right to sue on the payment bond is void unless it is in writing, signed by the person whose right is waived, and executed after such person has first furnished labor or material for use in the performance of the contract.

(End of clause)

52.229-3 FEDERAL, STATE, AND LOCAL TAXES (FEB 2013)

(a) As used in this clause—

“After-imposed Federal tax” means any new or increased Federal excise tax or duty, or tax that was exempted or excluded on the contract date but whose exemption was later revoked or reduced during the contract period, on the transactions or property covered by this contract that the Contractor is required to pay or bear as the result of legislative, judicial, or administrative action taking effect after the contract date. It does not include social security tax or other employment taxes.

“After-relieved Federal tax” means any amount of Federal excise tax or duty, except social security or other employment taxes, that would otherwise have been payable on the transactions or property covered by this contract, but which the Contractor is not required to pay or bear, or for which the Contractor obtains a refund or drawback, as the result of legislative, judicial, or administrative action taking effect after the contract date.

“All applicable Federal, State, and local taxes and duties” means all taxes and duties, in effect on the contract date, that the taxing authority is imposing and collecting on the transactions or property covered by this contract.

“Contract date” means the date set for bid opening or, if this is a negotiated contract or a modification, the effective date of this contract or modification.

“Local taxes” includes taxes imposed by a possession or territory of the United States, Puerto Rico, or the Northern Mariana Islands, if the contract is performed wholly or partly in any of those areas.

(b)(1) The contract price includes all applicable Federal, State, and local taxes and duties, except as provided in subparagraph (b)(2)(i) of this clause.

(2) Taxes imposed under 26 U.S.C. 5000C may not be—

(i) Included in the contract price; nor

(ii) Reimbursed.

(c) The contract price shall be increased by the amount of any after-imposed Federal tax, provided the Contractor warrants in writing that no amount for such newly imposed Federal excise tax or duty or rate increase was included in the contract price, as a contingency reserve or otherwise.

(d) The contract price shall be decreased by the amount of any after-relieved Federal tax.

(e) The contract price shall be decreased by the amount of any Federal excise tax or duty, except social security or other employment taxes, that the Contractor is required to pay or bear, or does not obtain a refund of, through the Contractor’s fault, negligence, or failure to follow instructions of the Contracting Officer.

(f) No adjustment shall be made in the contract price under this clause unless the amount of the adjustment exceeds \$250.

(g) The Contractor shall promptly notify the Contracting Officer of all matters relating to any Federal excise tax or duty that reasonably may be expected to result in either an increase or decrease in the contract price and shall take appropriate action as the Contracting Officer directs.

(h) The Government shall, without liability, furnish evidence appropriate to establish exemption from any Federal, State, or local tax when the Contractor requests such evidence and a reasonable basis exists to sustain the exemption.

(End of clause)

52.232-5 PAYMENTS UNDER FIXED-PRICE CONSTRUCTION CONTRACTS (MAY 2014)

(a) Payment of price. The Government shall pay the Contractor the contract price as provided in this contract.

(b) Progress payments. The Government shall make progress payments monthly as the work proceeds, or at more frequent intervals as determined by the Contracting Officer, on estimates of work accomplished which meets the standards of quality established under the contract, as approved by the Contracting Officer.

(1) The Contractor's request for progress payments shall include the following substantiation:

(i) An itemization of the amounts requested, related to the various elements of work required by the contract covered by the payment requested.

(ii) A listing of the amount included for work performed by each subcontractor under the contract.

(iii) A listing of the total amount of each subcontract under the contract.

(iv) A listing of the amounts previously paid to each such subcontractor under the contract.

(v) Additional supporting data in a form and detail required by the Contracting Officer.

(2) In the preparation of estimates, the Contracting Officer may authorize material delivered on the site and preparatory work done to be taken into consideration. Material delivered to the Contractor at locations other than the site also may be taken into consideration if--

(i) Consideration is specifically authorized by this contract; and

(ii) The Contractor furnishes satisfactory evidence that it has acquired title to such material and that the material will be used to perform this contract.

(c) Contractor certification. Along with each request for progress payments, the Contractor shall furnish the following certification, or payment shall not be made: (However, if the Contractor elects to delete paragraph (c)(4) from the certification, the certification is still acceptable.)

I hereby certify, to the best of my knowledge and belief, that--

(1) The amounts requested are only for performance in accordance with the specifications, terms, and conditions of the contract;

(2) All payments due to subcontractors and suppliers from previous payments received under the contract have been made, and timely payments will be made from the proceeds of the payment covered by this certification, in accordance with subcontract agreements and the requirements of chapter 39 of Title 31, United States Code;

(3) This request for progress payments does not include any amounts which the prime contractor intends to withhold or retain from a subcontractor or supplier in accordance with the terms and conditions of the subcontract; and

(4) This certification is not to be construed as final acceptance of a subcontractor's performance.

(Name)

(Title)

(Date)

(d) Refund of unearned amounts. If the Contractor, after making a certified request for progress payments, discovers that a portion or all of such request constitutes a payment for performance by the Contractor that fails to conform to

the specifications, terms, and conditions of this contract (hereinafter referred to as the "unearned amount"), the

- (1) Notify the Contracting Officer of such performance deficiency; and
- (2) Be obligated to pay the Government an amount (computed by the Contracting Officer in the manner provided in paragraph (j) of this clause) equal to interest on the unearned amount from the 8th day after the date of receipt of the unearned amount until--
 - (i) The date the Contractor notifies the Contracting Officer that the performance deficiency has been corrected; or
 - (ii) The date the Contractor reduces the amount of any subsequent certified request for progress payments by an amount equal to the unearned amount.
- (e) Retainage. If the Contracting Officer finds that satisfactory progress was achieved during any period for which a progress payment is to be made, the Contracting Officer shall authorize payment to be made in full. However, if satisfactory progress has not been made, the Contracting Officer may retain a maximum of 10 percent of the amount of the payment until satisfactory progress is achieved. When the work is substantially complete, the Contracting Officer may retain from previously withheld funds and future progress payments that amount the Contracting Officer considers adequate for protection of the Government and shall release to the Contractor all the remaining withheld funds. Also, on completion and acceptance of each separate building, public work, or other division of the contract, for which the price is stated separately in the contract, payment shall be made for the completed work without retention of a percentage.
- (f) Title, liability, and reservation of rights. All material and work covered by progress payments made shall, at the time of payment, become the sole property of the Government, but this shall not be construed as--
 - (1) Relieving the Contractor from the sole responsibility for all material and work upon which payments have been made or the restoration of any damaged work; or
 - (2) Waiving the right of the Government to require the fulfillment of all of the terms of the contract.
- (g) Reimbursement for bond premiums. In making these progress payments, the Government shall, upon request, reimburse the Contractor for the amount of premiums paid for performance and payment bonds (including coinsurance and reinsurance agreements, when applicable) after the Contractor has furnished evidence of full payment to the surety. The retainage provisions in paragraph (e) of this clause shall not apply to that portion of progress payments attributable to bond premiums.
- (h) Final payment. The Government shall pay the amount due the Contractor under this contract after--
 - (1) Completion and acceptance of all work;
 - (2) Presentation of a properly executed voucher; and
 - (3) Presentation of release of all claims against the Government arising by virtue of this contract, other than claims, in stated amounts, that the Contractor has specifically excepted from the operation of the release. A release may also be required of the assignee if the Contractor's claim to amounts payable under this contract has been assigned under the Assignment of Claims Act of 1940 (31 U.S.C. 3727 and 41 U.S.C. 6305).
- (i) Limitation because of undefinitized work. Notwithstanding any provision of this contract, progress payments shall not exceed 80 percent on work accomplished on undefinitized contract actions. A "contract action" is any action resulting in a contract, as defined in FAR Subpart 2.1, including contract modifications for additional supplies or services, but not including contract modifications that are within the scope and under the terms of the contract, such as contract modifications issued pursuant to the Changes clause, or funding and other administrative changes.
- (j) Interest computation on unearned amounts. In accordance with 31 U.S.C. 3903(c)(1), the amount payable under

(1) Computed at the rate of average bond equivalent rates of 91-day Treasury bills auctioned at the most recent auction of such bills prior to the date the Contractor receives the unearned amount; and

(2) Deducted from the next available payment to the Contractor.

(End of clause)

52.232-13 NOTICE OF PROGRESS PAYMENTS (APR 1984)

The need for customary progress payments conforming to the regulations in Subpart 32.5 of the Federal Acquisition Regulation (FAR) will not be considered as a handicap or adverse factor in the award of the contract. The Progress Payments clause included in this solicitation will be included in any resulting contract, modified or altered if necessary in accordance with subsection 52.232-16 and its Alternate I of the FAR. Even though the clause is included in the contract, the clause shall be inoperative during any time the contractor's accounting system and controls are determined by the Government to be inadequate for segregation and accumulation of contract costs.

(End of clause)

52.232-16 PROGRESS PAYMENTS (APR 2012)

The Government will make progress payments to the Contractor when requested as work progresses, but not more frequently than monthly, in amounts of \$2,500 or more approved by the Contracting Officer, under the following conditions:

(a) Computation of amounts. (1) Unless the Contractor requests a smaller amount, the Government will compute each progress payment as 80 percent of the Contractor's total costs incurred under this contract whether or not actually paid, plus financing payments to subcontractors (see paragraph (j) of this clause), less the sum of all previous progress payments made by the Government under this contract. The Contracting Officer will consider cost of money that would be allowable under FAR 31.205-10 as an incurred cost for progress payment purposes.

(2) The amount of financing and other payments for supplies and services purchased directly for the contract are limited to the amounts that have been paid by cash, check, or other forms of payment, or that are determined due and will be paid to subcontractors--

(i) In accordance with the terms and conditions of a subcontract or invoice; and

(ii) Ordinarily within 30 days of the submission of the Contractor's payment request to the Government.

(3) The Government will exclude accrued costs of Contractor contributions under employee pension plans until actually paid unless--

(i) The Contractor's practice is to make contributions to the retirement fund quarterly or more frequently; and

(ii) The contribution does not remain unpaid 30 days after the end of the applicable quarter or shorter payment period (any contribution remaining unpaid shall be excluded from the Contractor's total costs for progress payments until paid).

(4) The Contractor shall not include the following in total costs for progress payment purposes in paragraph (a)(1) of this clause:

(i) Costs that are not reasonable, allocable to this contract, and consistent with sound and generally accepted accounting principles and practices.

(ii) Costs incurred by subcontractors or suppliers.

(iii) Costs ordinarily capitalized and subject to depreciation or amortization except for the properly depreciated or amortized portion of such costs.

(iv) Payments made or amounts payable to subcontractors or suppliers, except for --

(A) Completed work, including partial deliveries, to which the Contractor has acquired title; and

(B) Work under cost-reimbursement or time-and-material subcontracts to which the Contractor has acquired title.

(5) The amount of unliquidated progress payments may exceed neither (i) the progress payments made against incomplete work (including allowable unliquidated progress payments to subcontractors) nor

(ii) the value, for progress payment purposes, of the incomplete work. Incomplete work shall be considered to be the supplies and services required by this contract, for which delivery and invoicing by the Contractor and acceptance by the Government are incomplete.

(6) The total amount of progress payments shall not exceed 80 percent of the total contract price.

(7) If a progress payment or the unliquidated progress payments exceed the amounts permitted by subparagraphs (a)(4) or (a)(5) of this clause, the Contractor shall repay the amount of such excess to the Government on demand.

(8) Notwithstanding any other terms of the contract, the Contractor agrees not to request progress payments in dollar amounts of less than \$2,500. The Contracting Officer may make exceptions.

(9) The costs applicable to items delivered, invoiced, and accepted shall not include costs in excess of the contract price of the items.

(b) Liquidation. Except as provided in the Termination for Convenience of the Government clause, all progress payments shall be liquidated by deducting from any payment under this contract, other than advance or progress payments, the unliquidated progress payments, or 80 percent of the amount invoiced, whichever is less. The Contractor shall repay to the Government any amounts required by a retroactive price reduction, after computing liquidations and payments on past invoices at the reduced prices and adjusting the unliquidated progress payments accordingly. The Government reserves the right to unilaterally change from the ordinary liquidation rate to an alternate rate when deemed appropriate for proper contract financing.

(c) Reduction or suspension. The Contracting Officer may reduce or suspend progress payments, increase the rate of liquidation, or take a combination of these actions, after finding on substantial evidence any of the following conditions:

(1) The Contractor failed to comply with any material requirement of this contract (which includes paragraphs (f) and (g) of this clause).

(2) Performance of this contract is endangered by the Contractor's --

(i) Failure to make progress or

(ii) Unsatisfactory financial condition.

(3) Inventory allocated to this contract substantially exceeds reasonable requirements.

(4) The Contractor is delinquent in payment of the costs of performing this contract in the ordinary course of business.

(5) The fair value of the undelivered work is less than the amount of unliquidated progress payments for that work.

(6) The Contractor is realizing less profit than that reflected in the establishment of any alternate liquidation rate in paragraph (b) of this clause, and that rate is less than the progress payment rate stated in subparagraph (a)(1) of this clause.

(d) Title.

(1) Title to the property described in this paragraph (d) shall vest in the Government. Vestiture shall be immediately upon the date of this contract, for property acquired or produced before that date. Otherwise, vestiture shall occur when the property is or should have been allocable or properly chargeable to this contract.

(2) "Property," as used in this clause, includes all of the below-described items acquired or produced by the Contractor that are or should be allocable or properly chargeable to this contract under sound and generally accepted accounting principles and practices.

(i) Parts, materials, inventories, and work in process;

(ii) Special tooling and special test equipment to which the Government is to acquire title;

(iii) Nondurable (i.e., noncapital) tools, jigs, dies, fixtures, molds, patterns, taps, gauges, test equipment, and other similar manufacturing aids, title to which would not be obtained as special tooling under paragraph (d) (2)(ii) of this clause; and

(iv) Drawings and technical data, to the extent the Contractor or subcontractors are required to deliver them to the Government by other clauses of this contract.

(3) Although title to property is in the Government under this clause, other applicable clauses of this contract; e.g., the termination clauses, shall determine the handling and disposition of the property.

(4) The Contractor may sell any scrap resulting from production under this contract without requesting the Contracting Officer's approval, but the proceeds shall be credited against the costs of performance.

(5) To acquire for its own use or dispose of property to which title is vested in the Government under this clause, the Contractor must obtain the Contracting Officer's advance approval of the action and the terms. The Contractor shall (i) exclude the allocable costs of the property from the costs of contract performance, and (ii) repay to the Government any amount of unliquidated progress payments allocable to the property. Repayment may be by cash or credit memorandum.

(6) When the Contractor completes all of the obligations under this contract, including liquidation of all progress payments, title shall vest in the Contractor for all property (or the proceeds thereof) not--

(i) Delivered to, and accepted by, the Government under this contract; or

(ii) Incorporated in supplies delivered to, and accepted by, the Government under this contract and to which title is vested in the Government under this clause.

(7) The terms of this contract concerning liability for Government-furnished property shall not apply to property to which the Government acquired title solely under this clause.

(e) Risk of loss. Before delivery to and acceptance by the Government, the Contractor shall bear the risk of loss for property, the title to which vests in the Government under this clause, except to the extent the Government expressly assumes the risk. The Contractor shall repay the Government an amount equal to the unliquidated progress payments that are based on costs allocable to property that is lost (see 45.101).

(f) Control of costs and property. The Contractor shall maintain an accounting system and controls adequate for the proper administration of this clause.

(g) Reports, forms, and access to records. (1) The Contractor shall promptly furnish reports, certificates, financial statements, and other pertinent information (including estimates to complete) reasonably requested by the Contracting Officer for the administration of this clause. Also, the Contractor shall give the Government reasonable opportunity to examine and verify the Contractor's books, records, and accounts.

(2) The Contractor shall furnish estimates to complete that have been developed or updated within six months of the date of the progress payment request. The estimates to complete shall represent the Contractor's best estimate of total costs to complete all remaining contract work required under the contract. The estimates shall include sufficient detail to permit Government verification.

(3) Each Contractor request for progress payment shall:

(i) Be submitted on Standard Form 1443, Contractor's Request for Progress Payment, or the electronic equivalent as required by agency regulations, in accordance with the form instructions and the contract terms; and

(ii) Include any additional supporting documentation requested by the Contracting Officer.

(h) Special terms regarding default. If this contract is terminated under the Default clause, (i) the Contractor shall, on demand, repay to the Government the amount of unliquidated progress payments and (ii) title shall vest in the Contractor, on full liquidation of progress payments, for all property for which the Government elects not to require delivery under the Default clause. The Government shall be liable for no payment except as provided by the Default clause.

(i) Reservations of rights.

(1) No payment or vesting of title under this clause shall --

(i) Excuse the Contractor from performance of obligations under this contract or

(ii) Constitute a waiver of any of the rights or remedies of the parties under the contract.

(2) The Government's rights and remedies under this clause

(i) Shall not be exclusive but rather shall be in addition to any other rights and remedies provided by law or this contract and

(ii) Shall not be affected by delayed, partial, or omitted exercise of any right, remedy, power, or privilege, nor shall such exercise or any single exercise preclude or impair any further exercise under this clause or the exercise of any other right, power, or privilege of the Government.

(j) Financing payments to subcontractors. The financing payments to subcontractors mentioned in paragraphs (a)(1) and (a)(2) of this clause shall be all financing payments to subcontractors or divisions, if the following conditions are met:

(1) The amounts included are limited to--

(i) The unliquidated remainder of financing payments made; plus

(ii) Any unpaid subcontractor requests for financing payments.

(2) The subcontract or interdivisional order is expected to involve a minimum of approximately 6 months between the beginning of work and the first delivery; or, if the subcontractor is a small business concern, 4 months.

(3) If the financing payments are in the form of progress payments, the terms of the subcontract or interdivisional order concerning progress payments--

(i) Are substantially similar to the terms of this clause for any subcontractor that is a large business concern, or this clause with its Alternate I for any subcontractor that is a small business concern;

(ii) Are at least as favorable to the Government as the terms of this clause;

(iii) Are not more favorable to the subcontractor or division than the terms of this clause are to the Contractor;

(iv) Are in conformance with the requirements of FAR 32.504(e); and

(v) Subordinate all subcontractor rights concerning property to which the Government has title under the subcontract to the Government's right to require delivery of the property to the Government if--

(A) The Contractor defaults; or

(B) The subcontractor becomes bankrupt or insolvent.

(4) If the financing payments are in the form of performance-based payments, the terms of the subcontract or interdivisional order concerning payments--

(i) Are substantially similar to the Performance-Based Payments clause at FAR 52.232-32 and meet the criteria for, and definition of, performance-based payments in FAR Part 32;

(ii) Are in conformance with the requirements of FAR 32.504(f); and

(iii) Subordinate all subcontractor rights concerning property to which the Government has title under the subcontract to the Government's right to require delivery of the property to the Government if--

(A) The Contractor defaults; or

(B) The subcontractor becomes bankrupt or insolvent.

(5) If the financing payments are in the form of commercial item financing payments, the terms of the subcontract or interdivisional order concerning payments--

(i) Are constructed in accordance with FAR 32.206(c) and included in a subcontract for a commercial item purchase that meets the definition and standards for acquisition of commercial items in FAR Parts 2 and 12;

(ii) Are in conformance with the requirements of FAR 32.504(g); and

(iii) Subordinate all subcontractor rights concerning property to which the Government has title under the subcontract to the Government's right to require delivery of the property to the Government if--

(A) The Contractor defaults; or

(B) The subcontractor becomes bankrupt or insolvent.

(6) If financing is in the form of progress payments, the progress payment rate in the subcontract is the customary rate used by the contracting agency, depending on whether the subcontractor is or is not a small business concern.

(7) Concerning any proceeds received by the Government for property to which title has vested in the Government under the subcontract terms, the parties agree that the proceeds shall be applied to reducing any unliquidated financing payments by the Government to the Contractor under this contract.

(8) If no unliquidated financing payments to the Contractor remain, but there are unliquidated financing payments that the Contractor has made to any subcontractor, the Contractor shall be subrogated to all the rights the Government obtained through the terms required by this clause to be in any subcontract, as if all such rights had been assigned and transferred to the Contractor.

(9) To facilitate small business participation in subcontracting under this contract, the Contractor shall provide financing payments to small business concerns, in conformity with the standards for customary contract financing payments stated in Subpart 32.113. The Contractor shall not consider the need for such financing payments as a handicap or adverse factor in the award of subcontracts.

(k) Limitations on undefinitized contract actions. Notwithstanding any other progress payment provisions in this contract, progress payments may not exceed 80 percent of costs incurred on work accomplished under undefinitized contract actions. A "contract action" is any action resulting in a contract, as defined in Subpart 2.1, including contract modifications for additional supplies or services, but not including contract modifications that are within the scope and under the terms of the contract, such as contract modifications issued pursuant to the Changes clause, or funding and other administrative changes. This limitation shall apply to the costs incurred, as computed in accordance with paragraph (a) of this clause, and shall remain in effect until the contract action is definitized. Costs incurred which are subject to this limitation shall be segregated on Contractor progress payment requests and invoices from those costs eligible for higher progress payment rates. For purposes of progress payment liquidation, as described in paragraph (b) of this clause, progress payments for undefinitized contract actions shall be liquidated at 80 percent of the amount invoiced for work performed under the undefinitized contract action as long as the contract action remains undefinitized. The amount of unliquidated progress payments for undefinitized contract actions shall not exceed 80 percent of the maximum liability of the Government under the undefinitized contract action or such lower limit specified elsewhere in the contract. Separate limits may be specified for separate actions.

(l) Due date. The designated payment office will make progress payments on the (identified per Task Order) day after the designated billing office receives a proper progress payment request. In the event that the Government requires an audit or other review of a specific progress payment request to ensure compliance with the terms and conditions of the contract, the designated payment office is not compelled to make payment by the specified due date. Progress payments are considered contract financing and are not subject to the interest penalty provisions of the Prompt Payment Act.

(m) Progress payments under indefinite--delivery contracts. The Contractor shall account for and submit progress payment requests under individual orders as if the order constituted a separate contract, unless otherwise specified in this contract.

(End of clause)

52.232-17 INTEREST (MAY 2014)

(a) Except as otherwise provided in this contract under a Price Reduction for Defective Certified Cost or Pricing Data clause or a Cost Accounting Standards clause, all amounts that become payable by the Contractor to the Government under this contract shall bear simple interest from the date due until paid unless paid within 30 days of

becoming due. The interest rate shall be the interest rate established by the Secretary of the Treasury as provided in 41 U.S.C. 7109, which is applicable to the period in which the amount becomes due, as provided in paragraph (e) of this clause, and then at the rate applicable for each six-month period as fixed by the Secretary until the amount is paid.

(b) The Government may issue a demand for payment to the Contractor upon finding a debt is due under the contract.

(c) Final Decisions. The Contracting Officer will issue a final decision as required by 33.211 if--

(1) The Contracting Officer and the Contractor are unable to reach agreement on the existence or amount of a debt in a timely manner;

(2) The Contractor fails to liquidate a debt previously demanded by the Contracting Officer within the timeline specified in the demand for payment unless the amounts were not repaid because the Contractor has requested an installment payment agreement; or

(3) The Contractor requests a deferment of collection on a debt previously demanded by the Contracting Officer (see 32.607-2).

(d) If a demand for payment was previously issued for the debt, the demand for payment included in the final decision shall identify the same due date as the original demand for payment.

(e) Amounts shall be due at the earliest of the following dates:

(1) The date fixed under this contract.

(2) The date of the first written demand for payment, including any demand for payment resulting from a default termination.

(f) The interest charge shall be computed for the actual number of calendar days involved beginning on the due date and ending on--

(1) The date on which the designated office receives payment from the Contractor;

(2) The date of issuance of a Government check to the Contractor from which an amount otherwise payable has been withheld as a credit against the contract debt; or

(3) The date on which an amount withheld and applied to the contract debt would otherwise have become payable to the Contractor.

(g) The interest charge made under this clause may be reduced under the procedures prescribed in 32.608-2 of the Federal Acquisition Regulation in effect on the date of this contract.

(End of clause)

52.232-23 ASSIGNMENT OF CLAIMS (MAY 2014)

(a) The Contractor, under the Assignment of Claims Act, as amended, 31 U.S.C. 3727, 41 U.S.C. 6305 (hereafter referred to as "the Act"), may assign its rights to be paid amounts due or to become due as a result of the performance of this contract to a bank, trust company, or other financing institution, including any Federal lending agency. The assignee under such an assignment may thereafter further assign or reassign its right under the original assignment to any type of financing institution described in the preceding sentence.

(b) Any assignment or reassignment authorized under the Act and this clause shall cover all unpaid amounts payable under this contract, and shall not be made to more than one party, except that an assignment or reassignment may be made to one party as agent or trustee for two or more parties participating in the financing of this contract.

(c) The Contractor shall not furnish or disclose to any assignee under this contract any classified document (including this contract) or information related to work under this contract until the Contracting Officer authorizes such action in writing.

(End of clause)

52.232-27 PROMPT PAYMENT FOR CONSTRUCTION CONTRACTS (MAY 2014)

Notwithstanding any other payment terms in this contract, the Government will make invoice payments under the terms and conditions specified in this clause. The Government considers payment as being made on the day a check is dated or the date of an electronic funds transfer. Definitions of pertinent terms are set forth in sections 2.101, 32.001, and 32.902 of the Federal Acquisition Regulation. All days referred to in this clause are calendar days, unless otherwise specified. (However, see paragraph (a)(3) concerning payments due on Saturdays, Sundays, and legal holidays.)

(a) Invoice payments--(1) Types of invoice payments. For purposes of this clause, there are several types of invoice payments that may occur under this contract, as follows:

(i) Progress payments, if provided for elsewhere in this contract, based on Contracting Officer approval of the estimated amount and value of work or services performed, including payments for reaching milestones in any project.

(A) The due date for making such payments is 14 days after the designated billing office receives a proper payment request. If the designated billing office fails to annotate the payment request with the actual date of receipt at the time of receipt, the payment due date is the 14th day after the date of the Contractor's payment request, provided the designated billing office receives a proper payment request and there is no disagreement over quantity, quality, or Contractor compliance with contract requirements.

(B) The due date for payment of any amounts retained by the Contracting Officer in accordance with the clause at 52.232-5, Payments Under Fixed-Price Construction Contracts, is as specified in the contract or, if not specified, 30 days after approval by the Contracting Officer for release to the Contractor.

(ii) Final payments based on completion and acceptance of all work and presentation of release of all claims against the Government arising by virtue of the contract, and payments for partial deliveries that have been accepted by the Government (e.g., each separate building, public work, or other division of the contract for which the price is stated separately in the contract).

(A) The due date for making such payments is the later of the following two events:

(1) The 30th day after the designated billing office receives a proper invoice from the Contractor.

(2) The 30th day after Government acceptance of the work or services completed by the Contractor. For a final invoice when the payment amount is subject to contract settlement actions (e.g., release of claims), acceptance is deemed to occur on the effective date of the contract settlement.

(B) If the designated billing office fails to annotate the invoice with the date of actual receipt at the time of receipt, the invoice payment due date is the 30th day after the date of the Contractor's invoice, provided the designated

billing office receives a proper invoice and there is no disagreement over quantity, quality, or Contractor compliance with contract requirements.

(2) Contractor's invoice. The Contractor shall prepare and submit invoices to the designated billing office specified in the contract. A proper invoice must include the items listed in paragraphs (a)(2)(i) through (a)(2)(xi) of this clause. If the invoice does not comply with these requirements, the designated billing office must return it within 7 days after receipt, with the reasons why it is not a proper invoice. When computing any interest penalty owed the Contractor, the Government will take into account if the Government notifies the Contractor of an improper invoice in an untimely manner.

(i) Name and address of the Contractor.

(ii) Invoice date and invoice number. (The Contractor should date invoices as close as possible to the date of mailing or transmission.)

(iii) Contract number or other authorization for work or services performed (including order number and contract line item number).

(iv) Description of work or services performed.

(v) Delivery and payment terms (e.g., discount for prompt payment terms).

(vi) Name and address of Contractor official to whom payment is to be sent (must be the same as that in the contract or in a proper notice of assignment).

(vii) Name (where practicable), title, phone number, and mailing address of person to notify in the event of a defective invoice.

(viii) For payments described in paragraph (a)(1)(i) of this clause, substantiation of the amounts requested and certification in accordance with the requirements of the clause at 52.232-5, Payments Under Fixed-Price Construction Contracts.

(ix) Taxpayer Identification Number (TIN). The Contractor shall include its TIN on the invoice only if required elsewhere in this contract.

(x) Electronic funds transfer (EFT) banking information.

(A) The Contractor shall include EFT banking information on the invoice only if required elsewhere in this contract.

(B) If EFT banking information is not required to be on the invoice, in order for the invoice to be a proper invoice, the Contractor shall have submitted correct EFT banking information in accordance with the applicable solicitation provision (e.g., 52.232-38, Submission of Electronic Funds Transfer Information with Offer), contract clause (e.g., 52.232-33, Payment by Electronic Funds Transfer--System for Award Management, or 52.232-34, Payment by Electronic Funds Transfer--Other Than System for Award Management), or applicable agency procedures.

(C) EFT banking information is not required if the Government waived the requirement to pay by EFT.

(xi) Any other information or documentation required by the contract.

(3) Interest penalty. The designated payment office will pay an interest penalty automatically, without request from the Contractor, if payment is not made by the due date and the conditions listed in paragraphs (a)(3)(i) through (a)(3)(iii) of this clause are met, if applicable. However, when the due date falls on a Saturday, Sunday, or legal holiday, the designated payment office may make payment on the following working day without incurring a late payment interest penalty.

(i) The designated billing office received a proper invoice.

(ii) The Government processed a receiving report or other Government documentation authorizing payment and there was no disagreement over quantity, quality, Contractor compliance with any contract term or condition, or requested progress payment amount.

(iii) In the case of a final invoice for any balance of funds due the Contractor for work or services performed, the amount was not subject to further contract settlement actions between the Government and the Contractor.

(4) Computing penalty amount. The Government will compute the interest penalty in accordance with the Office of Management and Budget prompt payment regulations at 5 CFR part 1315.

(i) For the sole purpose of computing an interest penalty that might be due the Contractor for payments described in paragraph (a)(1)(ii) of this clause, Government acceptance or approval is deemed to occur constructively on the 7th day after the Contractor has completed the work or services in accordance with the terms and conditions of the contract. If actual acceptance or approval occurs within the constructive acceptance or approval period, the Government will base the determination of an interest penalty on the actual date of acceptance or approval. Constructive acceptance or constructive approval requirements do not apply if there is a disagreement over quantity, quality, or Contractor compliance with a contract provision. These requirements also do not compel Government officials to accept work or services, approve Contractor estimates, perform contract administration functions, or make payment prior to fulfilling their responsibilities.

(ii) The prompt payment regulations at 5 CFR 1315.10(c) do not require the Government to pay interest penalties if payment delays are due to disagreement between the Government and the Contractor over the payment amount or other issues involving contract compliance, or on amounts temporarily withheld or retained in accordance with the terms of the contract. The Government and the Contractor shall resolve claims involving disputes, and any interest that may be payable in accordance with the clause at FAR 52.233-1, Disputes.

(5) Discounts for prompt payment. The designated payment office will pay an interest penalty automatically, without request from the Contractor, if the Government takes a discount for prompt payment improperly. The Government will calculate the interest penalty in accordance with the prompt payment regulations at 5 CFR part 1315.

(6) Additional interest penalty. (i) The designated payment office will pay a penalty amount, calculated in accordance with the prompt payment regulations at 5 CFR part 1315 in addition to the interest penalty amount only if--

(A) The Government owes an interest penalty of \$1 or more;

(B) The designated payment office does not pay the interest penalty within 10 days after the date the invoice amount is paid; and

(C) The Contractor makes a written demand to the designated payment office for additional penalty payment, in accordance with paragraph (a)(6)(ii) of this clause, postmarked not later than 40 days after the date the invoice amount is paid.

(ii)(A) The Contractor shall support written demands for additional penalty payments with the following data. The Government will not request any additional data. The Contractor shall--

(1) Specifically assert that late payment interest is due under a specific invoice, and request payment of all overdue late payment interest penalty and such additional penalty as may be required;

(2) Attach a copy of the invoice on which the unpaid late payment interest was due; and

(3) State that payment of the principal has been received, including the date of receipt.

(B) If there is no postmark or the postmark is illegible--

(1) The designated payment office that receives the demand will annotate it with the date of receipt provided the demand is received on or before the 40th day after payment was made; or

(2) If the designated payment office fails to make the required annotation, the Government will determine the demand's validity based on the date the Contractor has placed on the demand, provided such date is no later than the 40th day after payment was made.

(b) Contract financing payments. If this contract provides for contract financing, the Government will make contract financing payments in accordance with the applicable contract financing clause.

(c) Subcontract clause requirements. The Contractor shall include in each subcontract for property or services (including a material supplier) for the purpose of performing this contract the following:

(1) Prompt payment for subcontractors. A payment clause that obligates the Contractor to pay the subcontractor for satisfactory performance under its subcontract not later than 7 days from receipt of payment out of such amounts as are paid to the Contractor under this contract.

(2) Interest for subcontractors. An interest penalty clause that obligates the Contractor to pay to the subcontractor an interest penalty for each payment not made in accordance with the payment clause--

(i) For the period beginning on the day after the required payment date and ending on the date on which payment of the amount due is made; and

(ii) Computed at the rate of interest established by the Secretary of the Treasury, and published in the Federal Register, for interest payments under 41 U.S.C. 7109 in effect at the time the Contractor accrues the obligation to pay an interest penalty.

(3) Subcontractor clause flow down. A clause requiring each subcontractor to use:

(i) Include a payment clause and an interest penalty clause conforming to the standards set forth in paragraphs (c)(1) and (c)(2) of this clause in each of its subcontracts; and

(ii) Require each of its subcontractors to include such clauses in their subcontracts with each lower-tier subcontractor or supplier.

(d) Subcontract clause interpretation. The clauses required by paragraph (c) of this clause shall not be construed to impair the right of the Contractor or a subcontractor at any tier to negotiate, and to include in their subcontract, provisions that--

(1) Retainage permitted. Permit the Contractor or a subcontractor to retain (without cause) a specified percentage of each progress payment otherwise due to a subcontractor for satisfactory performance under the subcontract without incurring any obligation to pay a late payment interest penalty, in accordance with terms and conditions agreed to by the parties to the subcontract, giving such recognition as the parties deem appropriate to the ability of a subcontractor to furnish a performance bond and a payment bond;

(2) Withholding permitted. Permit the Contractor or subcontractor to make a determination that part or all of the subcontractor's request for payment may be withheld in accordance with the subcontract agreement; and

(3) Withholding requirements. Permit such withholding without incurring any obligation to pay a late payment penalty if--

(i) A notice conforming to the standards of paragraph (g) of this clause previously has been furnished to the subcontractor; and

(ii) The Contractor furnishes to the Contracting Officer a copy of any notice issued by a Contractor pursuant to paragraph (d)(3)(i) of this clause.

(e) Subcontractor withholding procedures. If a Contractor, after making a request for payment to the Government but before making a payment to a subcontractor for the subcontractor's performance covered by the payment request, discovers that all or a portion of the payment otherwise due such subcontractor is subject to withholding from the subcontractor in accordance with the subcontract agreement, then the Contractor shall--

(1) Subcontractor notice. Furnish to the subcontractor a notice conforming to the standards of paragraph (g) of this clause as soon as practicable upon ascertaining the cause giving rise to a withholding, but prior to the due date for subcontractor payment;

(2) Contracting Officer notice. Furnish to the Contracting Officer, as soon as practicable, a copy of the notice furnished to the subcontractor pursuant to paragraph (e)(1) of this clause;

(3) Subcontractor progress payment reduction. Reduce the subcontractor's progress payment by an amount not to exceed the amount specified in the notice of withholding furnished under paragraph (e)(1) of this clause;

(4) Subsequent subcontractor payment. Pay the subcontractor as soon as practicable after the correction of the identified subcontract performance deficiency, and--

(i) Make such payment within--

(A) Seven days after correction of the identified subcontract performance deficiency (unless the funds therefor must be recovered from the Government because of a reduction under paragraph (e)(5)(i)) of this clause; or

(B) Seven days after the Contractor recovers such funds from the Government; or

(ii) Incur an obligation to pay a late payment interest penalty computed at the rate of interest established by the Secretary of the Treasury, and published in the Federal Register, for interest payments under 41 U.S.C. 7109 in effect at the time the Contractor accrues the obligation to pay an interest penalty;

(5) Notice to Contracting Officer. Notify the Contracting Officer upon--

(i) Reduction of the amount of any subsequent certified application for payment; or

(ii) Payment to the subcontractor of any withheld amounts of a progress payment, specifying--

(A) The amounts withheld under paragraph (e)(1) of this clause; and

(B) The dates that such withholding began and ended; and

(6) Interest to Government. Be obligated to pay to the Government an amount equal to interest on the withheld payments (computed in the manner provided in 31 U.S.C. 3903(c)(1)), from the 8th day after receipt of the withheld amounts from the Government until--

(i) The day the identified subcontractor performance deficiency is corrected; or

(ii) The date that any subsequent payment is reduced under paragraph (e)(5)(i) of this clause.

(1) Withholding from subcontractor. If a Contractor, after making payment to a first-tier subcontractor, receives from a supplier or subcontractor of the first-tier subcontractor (hereafter referred to as a “second-tier subcontractor”) a written notice in accordance with 40 U.S.C. 3133, asserting a deficiency in such first-tier subcontractor's performance under the contract for which the Contractor may be ultimately liable, and the Contractor determines that all or a portion of future payments otherwise due such first-tier subcontractor is subject to withholding in accordance with the subcontract agreement, the Contractor may, without incurring an obligation to pay an interest penalty under paragraph (e)(6) of this clause--

(i) Furnish to the first-tier subcontractor a notice conforming to the standards of paragraph (g) of this clause as soon as practicable upon making such determination; and

(ii) Withhold from the first-tier subcontractor's next available progress payment or payments an amount not to exceed the amount specified in the notice of withholding furnished under paragraph (f)(1)(i) of this clause.

(2) Subsequent payment or interest charge. As soon as practicable, but not later than 7 days after receipt of satisfactory written notification that the identified subcontract performance deficiency has been corrected, the Contractor shall--

(i) Pay the amount withheld under paragraph (f)(1)(ii) of this clause to such first-tier subcontractor; or

(ii) Incur an obligation to pay a late payment interest penalty to such first-tier subcontractor computed at the rate of interest established by the Secretary of the Treasury, and published in the Federal Register, for interest payments under section 12 of 41 U.S.C. 7109 in effect at the time the Contractor accrues the obligation to pay an interest penalty.

(g) Written notice of subcontractor withholding. The Contractor shall issue a written notice of any withholding to a subcontractor (with a copy furnished to the Contracting Officer), specifying--

(1) The amount to be withheld;

(2) The specific causes for the withholding under the terms of the subcontract; and

(3) The remedial actions to be taken by the subcontractor in order to receive payment of the amounts withheld.

(h) Subcontractor payment entitlement. The Contractor may not request payment from the Government of any amount withheld or retained in accordance with paragraph (d) of this clause until such time as the Contractor has determined and certified to the Contracting Officer that the subcontractor is entitled to the payment of such amount.

(i) Prime-subcontractor disputes. A dispute between the Contractor and subcontractor relating to the amount or entitlement of a subcontractor to a payment or a late payment interest penalty under a clause included in the subcontract pursuant to paragraph (c) of this clause does not constitute a dispute to which the Government is a party. The Government may not be interpleaded in any judicial or administrative proceeding involving such a dispute.

(j) Preservation of prime-subcontractor rights. Except as provided in paragraph (i) of this clause, this clause shall not limit or impair any contractual, administrative, or judicial remedies otherwise available to the Contractor or a subcontractor in the event of a dispute involving late payment or nonpayment by the Contractor or deficient subcontract performance or nonperformance by a subcontractor.

(k) Non-recourse for prime contractor interest penalty. The Contractor's obligation to pay an interest penalty to a subcontractor pursuant to the clauses included in a subcontract under paragraph (c) of this clause shall not be construed to be an obligation of the Government for such interest penalty. A cost-reimbursement claim may not include any amount for reimbursement of such interest penalty.

(l) Overpayments. If the Contractor becomes aware of a duplicate contract financing or invoice payment or that the Government has otherwise overpaid on a contract financing or invoice payment, the Contractor shall--

(1) Remit the overpayment amount to the payment office cited in the contract along with a description of the overpayment including the--

(i) Circumstances of the overpayment (e.g., duplicate payment, erroneous payment, liquidation errors, date(s) of overpayment);

(ii) Affected contract number and delivery order number if applicable;

(iii) Affected contract line item or subline item, if applicable; and

(iv) Contractor point of contact.

(2) Provide a copy of the remittance and supporting documentation to the Contracting Officer.

(End of clause)

52.232-33 PAYMENT BY ELECTRONIC FUNDS TRANSFER—SYSTEM FOR AWARD MANAGEMENT (JULY 2013)

(a) Method of payment. (1) All payments by the Government under this contract shall be made by electronic funds transfer (EFT), except as provided in paragraph (a)(2) of this clause. As used in this clause, the term "EFT" refers to the funds transfer and may also include the payment information transfer.

(2) In the event the Government is unable to release one or more payments by EFT, the Contractor agrees to either--

(i) Accept payment by check or some other mutually agreeable method of payment; or

(ii) Request the Government to extend the payment due date until such time as the Government can make payment by EFT (but see paragraph (d) of this clause).

(b) Contractor's EFT information. The Government shall make payment to the Contractor using the EFT information contained in the System for Award Management (SAM) database. In the event that the EFT information changes, the Contractor shall be responsible for providing the updated information to the SAM database.

(c) Mechanisms for EFT payment. The Government may make payment by EFT through either the Automated Clearing House (ACH) network, subject to the rules of the National Automated Clearing House Association, or the Fedwire Transfer System. The rules governing Federal payments through the ACH are contained in 31 CFR part 210.

(d) Suspension of payment. If the Contractor's EFT information in the SAM database is incorrect, then the Government need not make payment to the Contractor under this contract until correct EFT information is entered into the SAM database; and any invoice or contract financing request shall be deemed not to be a proper invoice for the purpose of prompt payment under this contract. The prompt payment terms of the contract regarding notice of an improper invoice and delays in accrual of interest penalties apply.

(e) Liability for uncompleted or erroneous transfers. (1) If an uncompleted or erroneous transfer occurs because the Government used the Contractor's EFT information incorrectly, the Government remains responsible for--

(i) Making a correct payment;

(ii) Paying any prompt payment penalty due; and

(iii) Recovering any erroneously directed funds.

(2) If an uncompleted or erroneous transfer occurs because the Contractor's EFT information was incorrect, or was revised within 30 days of Government release of the EFT payment transaction instruction to the Federal Reserve System, and--

(i) If the funds are no longer under the control of the payment office, the Government is deemed to have made payment and the Contractor is responsible for recovery of any erroneously directed funds; or

(ii) If the funds remain under the control of the payment office, the Government shall not make payment, and the provisions of paragraph (d) of this clause shall apply.

(f) EFT and prompt payment. A payment shall be deemed to have been made in a timely manner in accordance with the prompt payment terms of this contract if, in the EFT payment transaction instruction released to the Federal Reserve System, the date specified for settlement of the payment is on or before the prompt payment due date, provided the specified payment date is a valid date under the rules of the Federal Reserve System.

(g) EFT and assignment of claims. If the Contractor assigns the proceeds of this contract as provided for in the assignment of claims terms of this contract, the Contractor shall require as a condition of any such assignment, that the assignee shall register separately in the SAM database and shall be paid by EFT in accordance with the terms of this clause. Notwithstanding any other requirement of this contract, payment to an ultimate recipient other than the Contractor, or a financial institution properly recognized under an assignment of claims pursuant to subpart 32.8, is not permitted. In all respects, the requirements of this clause shall apply to the assignee as if it were the Contractor. EFT information that shows the ultimate recipient of the transfer to be other than the Contractor, in the absence of a proper assignment of claims acceptable to the Government, is incorrect EFT information within the meaning of paragraph (d) of this clause.

(h) Liability for change of EFT information by financial agent. The Government is not liable for errors resulting from changes to EFT information made by the Contractor's financial agent.

(i) Payment information. The payment or disbursing office shall forward to the Contractor available payment information that is suitable for transmission as of the date of release of the EFT instruction to the Federal Reserve System. The Government may request the Contractor to designate a desired format and method(s) for delivery of payment information from a list of formats and methods the payment office is capable of executing. However, the Government does not guarantee that any particular format or method of delivery is available at any particular payment office and retains the latitude to use the format and delivery method most convenient to the Government. If the Government makes payment by check in accordance with paragraph (a) of this clause, the Government shall mail the payment information to the remittance address contained in the SAM database.

(End of Clause)

52.232-39 Unenforceability of Unauthorized Obligations (JUN 2013)

(a) Except as stated in paragraph (b) of this clause, when any supply or service acquired under this contract is subject to any End User License Agreement (EULA), Terms of Service (TOS), or similar legal instrument or agreement, that includes any clause requiring the Government to indemnify the Contractor or any person or entity for damages, costs, fees, or any other loss or liability that would create an Anti-Deficiency Act violation (31 U.S.C. 1341), the following shall govern:

(1) Any such clause is unenforceable against the Government.

(2) Neither the Government nor any Government authorized end user shall be deemed to have agreed to such clause by virtue of it appearing in the EULA, TOS, or similar legal instrument or agreement. If the EULA, TOS, or similar legal instrument or agreement is invoked through an "I agree" click box or other comparable mechanism (e.g., "click-wrap" or "browse-wrap" agreements), execution does not bind the Government or any Government authorized end user to such clause.

(3) Any such clause is deemed to be stricken from the EULA, TOS, or similar legal instrument or agreement.

(b) Paragraph (a) of this clause does not apply to indemnification by the Government that is expressly authorized by statute and specifically authorized under applicable agency regulations and procedures.

(End of clause)

52.232-40 PROVIDING ACCELERATED PAYMENTS TO SMALL BUSINESS SUBCONTRACTORS (DEC 2013)

(a) Upon receipt of accelerated payments from the Government, the Contractor shall make accelerated payments to its small business subcontractors under this contract, to the maximum extent practicable and prior to when such payment is otherwise required under the applicable contract or subcontract, after receipt of a proper invoice and all other required documentation from the small business subcontractor.

(b) The acceleration of payments under this clause does not provide any new rights under the Prompt Payment Act.

(c) Include the substance of this clause, including this paragraph (c), in all subcontracts with small business concerns, including subcontracts with small business concerns for the acquisition of commercial items.

(End of clause)

52.233-1 DISPUTES. (MAY 2014) -- ALTERNATE I (DEC 1991)

(a) This contract is subject to 41 U.S.C. chapter 71, Contract Disputes.

(b) Except as provided in 41 U.S.C. chapter 71, all disputes arising under or relating to this contract shall be resolved under this clause.

(c) Claim, as used in this clause, means a written demand or written assertion by one of the contracting parties seeking, as a matter of right, the payment of money in a sum certain, the adjustment or interpretation of contract terms, or other relief arising under or relating to this contract. However, a written demand or written assertion by the Contractor seeking the payment of money exceeding \$100,000 is not a claim under 41 U.S.C. chapter 71 until certified. A voucher, invoice, or other routine request for payment that is not in dispute when submitted is not a claim under 41 U.S.C. chapter 71. The submission may be converted to a claim under 41 U.S.C. chapter 71, by complying with the submission and certification requirements of this clause, if it is disputed either as to liability or amount or is not acted upon in a reasonable time.

(d)(1) A claim by the Contractor shall be made in writing and, unless otherwise stated in this contract, submitted within 6 years after accrual of the claim to the Contracting Officer for a written decision. A claim by the Government against the Contractor shall be subject to a written decision by the Contracting Officer.

(2) (i) Contractors shall provide the certification specified in subparagraph (d)(2)(iii) of this clause when submitting any claim exceeding \$100,000.

(ii) The certification requirement does not apply to issues in controversy that have not been submitted as all or part of a claim.

(iii) The certification shall state as follows: "I certify that the claim is made in good faith; that the supporting data are accurate and complete to the best of my knowledge and belief; that the amount requested accurately reflects the contract adjustment for which the Contractor believes the Government is liable; and that I am authorized to certify the claim on behalf of the Contractor.

(3) The certification may be executed by any person authorized to bind the Contractor with respect to the claim.

(e) For Contractor claims of \$100,000 or less, the Contracting Officer must, if requested in writing by the Contractor, render a decision within 60 days of the request. For Contractor-certified claims over \$100,000, the Contracting Officer must, within 60 days, decide the claim or notify the Contractor of the date by which the decision will be made.

(f) The Contracting Officer's decision shall be final unless the Contractor appeals or files a suit as provided in 41 U.S.C. chapter 71.

(g) If the claim by the Contractor is submitted to the Contracting Officer or a claim by the Government is presented to the Contractor, the parties, by mutual consent, may agree to use ADR. If the Contractor refuses an offer for alternative disputes resolution, the Contractor shall inform the Contracting Officer, in writing, of the Contractor's specific reasons for rejecting the request. When using arbitration conducted pursuant to 5 U.S.C. 575-580, or when using any other ADR technique that the agency elects to handle in accordance with the ADRA, any claim, regardless of amount, shall be accompanied by the certification described in subparagraph (d)(2)(iii) of this clause, and executed in accordance with subparagraph (d)(3) of this clause.

(h) The Government shall pay interest on the amount found due and unpaid from (1) the date the Contracting Officer receives the claim (certified, if required); or (2) the date that payment otherwise would be due, if that date is later, until the date of payment. With regard to claims having defective certifications, as defined in (FAR) 48 CFR 33.201, interest shall be paid from the date that the Contracting Officer initially receives the claim. Simple interest on claims shall be paid at the rate, fixed by the Secretary of the Treasury as provided in the Act, which is applicable to the period during which the Contracting Officer receives the claim and then at the rate applicable for each 6-month period as fixed by the Treasury Secretary during the pendency of the claim.

(i) The Contractor shall proceed diligently with performance of this contract, pending final resolution of any request for relief, claim, appeal, or action arising under or relating to the contract, and comply with any decision of the Contracting Officer.

(End of clause)

52.233-3 PROTEST AFTER AWARD (AUG. 1996)

(a) Upon receipt of a notice of protest (as defined in FAR 33.101) or a determination that a protest is likely (see FAR 33.102(d)), the Contracting Officer may, by written order to the Contractor, direct the Contractor to stop performance of the work called for by this contract. The order shall be specifically identified as a stop-work order issued under this clause. Upon receipt of the order, the Contractor shall immediately comply with its terms and take

all reasonable steps to minimize the incurrence of costs allocable to the work covered by the order during the period of work stoppage. Upon receipt of the final decision in the protest, the Contracting Officer shall either--

(1) Cancel the stop-work order; or

(2) Terminate the work covered by the order as provided in the Default, or the Termination for Convenience of the Government, clause of this contract.

(b) If a stop-work order issued under this clause is canceled either before or after a final decision in the protest, the Contractor shall resume work. The Contracting Officer shall make an equitable adjustment in the delivery schedule or contract price, or both, and the contract shall be modified, in writing, accordingly, if--

(1) The stop-work order results in an increase in the time required for, or in the Contractor's cost properly allocable to, the performance of any part of this contract; and

(2) The Contractor asserts its right to an adjustment within 30 days after the end of the period of work stoppage; provided, that if the Contracting Officer decides the facts justify the action, the Contracting Officer may receive and act upon a proposal at any time before final payment under this contract.

(c) If a stop-work order is not canceled and the work covered by the order is terminated for the convenience of the Government, the Contracting Officer shall allow reasonable costs resulting from the stop-work order in arriving at the termination settlement.

(d) If a stop-work order is not canceled and the work covered by the order is terminated for default, the Contracting Officer shall allow, by equitable adjustment or otherwise, reasonable costs resulting from the stop-work order.

(e) The Government's rights to terminate this contract at any time are not affected by action taken under this clause.

(f) If, as the result of the Contractor's intentional or negligent misstatement, misrepresentation, or miscertification, a protest related to this contract is sustained, and the Government pays costs, as provided in FAR 33.102(b)(2) or 33.104(h)(1), the Government may require the Contractor to reimburse the Government the amount of such costs. In addition to any other remedy available, and pursuant to the requirements of Subpart 32.6, the Government may collect this debt by offsetting the amount against any payment due the Contractor under any contract between the Contractor and the Government.

(End of clause)

52.233-4 APPLICABLE LAW FOR BREACH OF CONTRACT CLAIM (OCT 2004)

United States law will apply to resolve any claim of breach of this contract.

(End of clause)

52.236-1 PERFORMANCE OF WORK BY THE CONTRACTOR (APR 1984)

The Contractor shall perform on the site, and with its own organization, work equivalent to at least **forty (40%)** percent of the total amount of work to be performed under the contract. This percentage may be reduced by a supplemental agreement to this contract if, during performing the work, the Contractor requests a reduction and the Contracting Officer determines that the reduction would be to the advantage of the Government.

(End of clause)

52.236-2 DIFFERING SITE CONDITIONS (APR 1984)

(a) The Contractor shall promptly, and before the conditions are disturbed, give a written notice to the Contracting Officer of

(1) subsurface or latent physical conditions at the site which differ materially from those indicated in this contract, or

(2) unknown physical conditions at the site, of an unusual nature, which differ materially from those ordinarily encountered and generally recognized as inhering in work of the character provided for in the contract.

(b) The Contracting Officer shall investigate the site conditions promptly after receiving the notice. If the conditions do materially so differ and cause an increase or decrease in the Contractor's cost of, or the time required for, performing any part of the work under this contract, whether or not changed as a result of the conditions, an equitable adjustment shall be made under this clause and the contract modified in writing accordingly.

(c) No request by the Contractor for an equitable adjustment to the contract under this clause shall be allowed, unless the Contractor has given the written notice required; provided, that the time prescribed in (a) above for giving written notice may be extended by the Contracting Officer.

(d) No request by the Contractor for an equitable adjustment to the contract for differing site conditions shall be allowed if made after final payment under this contract.

(End of clause)

52.236-3 SITE INVESTIGATION AND CONDITIONS AFFECTING THE WORK (APR 1984)

(a) The Contractor acknowledges that it has taken steps reasonably necessary to ascertain the nature and location of the work, and that it has investigated and satisfied itself as to the general and local conditions which can affect the work or its cost, including but not limited to

(1) conditions bearing upon transportation, disposal, handling, and storage of materials;

(2) the availability of labor, water, electric power, and roads;

(3) uncertainties of weather, river stages, tides, or similar physical conditions at the site;

(4) the conformation and conditions of the ground; and (5) the character of equipment and facilities needed preliminary to and during work performance. The Contractor also acknowledges that it has satisfied itself as to the character, quality, and quantity of surface and subsurface materials or obstacles to be encountered insofar as this information is reasonably ascertainable from an inspection of the site, including all exploratory work done by the Government, as well as from the drawings and specifications made a part of this contract. Any failure of the Contractor to take the actions described and acknowledged in this paragraph will not relieve the Contractor from responsibility for estimating properly the difficulty and cost of successfully performing the work, or for proceeding to successfully perform the work without additional expense to the Government.

(b) The Government assumes no responsibility for any conclusions or interpretations made by the Contractor based on the information made available by the Government. Nor does the Government assume responsibility for any understanding reached or representation made concerning conditions which can affect the work by any of its officers or agents before the execution of this contract, unless that understanding or representation is expressly stated in this contract.

(End of clause)

52.236-4 PHYSICAL DATA (APR 1984)

Data and information furnished or referred to below is for the Contractor's information. The Government shall not be responsible for any interpretation of or conclusion drawn from the data or information by the Contractor.

(a) The indications of physical conditions on the drawings and in the specifications are the result of site investigations by [insert a description of investigational methods used, such as surveys, auger borings,

(b) Weather conditions (insert a summary of weather records and warnings).

(c) Transportation facilities (insert a summary of transportation facilities providing access from the site, including information about their availability and limitations.

(d) (insert other pertinent information).

(End of clause)

52.236-5 MATERIAL AND WORKMANSHIP (APR 1984)

(a) All equipment, material, and articles incorporated into the work covered by this contract shall be new and of the most suitable grade for the purpose intended, unless otherwise specifically provided in this contract. References in the specifications to equipment, material, articles, or patented processes by trade name, make, or catalog number, shall be regarded as establishing a standard of quality and shall not be construed as limiting competition. The Contractor may, at its option, use any equipment, material, article, or process that, in the judgment of the Contracting Officer, is equal to that named in the specifications, unless otherwise specifically provided in this contract.

(b) The Contractor shall obtain the Contracting Officer's approval of the machinery and mechanical and other equipment to be incorporated into the work. When requesting approval, the Contractor shall furnish to the Contracting Officer the name of the manufacturer, the model number, and other information concerning the performance, capacity, nature, and rating of the machinery and mechanical and other equipment. When required by this contract or by the Contracting Officer, the Contractor shall also obtain the Contracting Officer's approval of the material or articles which the Contractor contemplates incorporating into the work. When requesting approval, the Contractor shall provide full information concerning the material or articles. When directed to do so, the Contractor shall submit samples for approval at the Contractor's expense, with all shipping charges prepaid. Machinery, equipment, material, and articles that do not have the required approval shall be installed or used at the risk of subsequent rejection.

(c) All work under this contract shall be performed in a skillful and workmanlike manner. The Contracting Officer may require, in writing, that the Contractor remove from the work any employee the Contracting Officer deems incompetent, careless, or otherwise objectionable.

(End of clause)

52.236-6 SUPERINTENDENCE BY THE CONTRACTOR (APR 1984)

At all times during performance of this contract and until the work is completed and accepted, the Contractor shall directly superintend the work or assign and have on the worksite a competent superintendent who is satisfactory to the Contracting Officer and has authority to act for the Contractor.

(End of clause)

52.236-7 PERMITS AND RESPONSIBILITIES (NOV 1991)

The Contractor shall, without additional expense to the Government, be responsible for obtaining any necessary licenses and permits, and for complying with any Federal, State, and municipal laws, codes, and regulations applicable to the performance of the work. The Contractor shall also be responsible for all damages to persons or

property that occur as a result of the Contractor's fault or negligence. The Contractor shall also be responsible for all materials delivered and work performed until completion and acceptance of the entire work, except for any completed unit of work which may have been accepted under the contract.

(End of clause)

52.236-8 OTHER CONTRACTS (APR 1984)

The Government may undertake or award other contracts for additional work at or near the site of the work under this contract. The Contractor shall fully cooperate with the other contractors and with Government employees and shall carefully adapt scheduling and performing the work under this contract to accommodate the additional work, heeding any direction that may be provided by the Contracting Officer. The Contractor shall not commit or permit any act that will interfere with the performance of work by any other contractor or by Government employees.

(End of clause)

52.236-9 PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS (APR 1984)

(a) The Contractor shall preserve and protect all structures, equipment, and vegetation (such as trees, shrubs, and grass) on or adjacent to the work site, which are not to be removed and which do not unreasonably interfere with the work required under this contract. The Contractor shall only remove trees when specifically authorized to do so, and shall avoid damaging vegetation that will remain in place. If any limbs or branches of trees are broken during contract performance, or by the careless operation of equipment, or by workmen, the Contractor shall trim those limbs or branches with a clean cut and paint the cut with a tree-pruning compound as directed by the Contracting Officer.

(b) The Contractor shall protect from damage all existing improvements and utilities

(1) at or near the work site, and

(2) on adjacent property of a third party, the locations of which are made known to or should be known by the Contractor. The Contractor shall repair any damage to those facilities, including those that are the property of a third party, resulting from failure to comply with the requirements of this contract or failure to exercise reasonable care in performing the work. If the Contractor fails or refuses to repair the damage promptly, the Contracting Officer may have the necessary work performed and charge the cost to the Contractor.

(End of clause)

52.236-10 OPERATIONS AND STORAGE AREAS (APR 1984)

(a) The Contractor shall confine all operations (including storage of materials) on Government premises to areas authorized or approved by the Contracting Officer. The Contractor shall hold and save the Government, its officers and agents, free and harmless from liability of any nature occasioned by the Contractor's performance.

(b) Temporary buildings (e.g., storage sheds, shops, offices) and utilities may be erected by the Contractor only with

the approval of the Contracting Officer and shall be built with labor and materials furnished by the Contractor without expense to the Government. The temporary buildings and utilities shall remain the property of the Contractor and shall be removed by the Contractor at its expense upon completion of the work. With the written consent of the Contracting Officer, the buildings and utilities may be abandoned and need not be removed.

(c) The Contractor shall, under regulations prescribed by the Contracting Officer, use only established roadways, or use temporary roadways constructed by the Contractor when and as authorized by the Contracting Officer. When materials are transported in prosecuting the work, vehicles shall not be loaded beyond the loading capacity recommended by the manufacturer of the vehicle or prescribed by any Federal, State, or local law or regulation. When it is necessary to cross curbs or sidewalks, the Contractor shall protect them from damage. The Contractor shall repair or pay for the repair of any damaged curbs, sidewalks, or roads.

(End of clause)

52.236-11 USE AND POSSESSION PRIOR TO COMPLETION (APR 1984)

(a) The Government shall have the right to take possession of or use any completed or partially completed part of the work. Before taking possession of or using any work, the Contracting Officer shall furnish the Contractor a list of items of work remaining to be performed or corrected on those portions of the work that the Government intends to take possession of or use. However, failure of the Contracting Officer to list any item of work shall not relieve the Contractor of responsibility for complying with the terms of the contract. The Government's possession or use shall not be deemed an acceptance of any work under the contract.

(b) While the Government has such possession or use, the Contractor shall be relieved of the responsibility for the loss of or damage to the work resulting from the Government's possession or use, notwithstanding the terms of the clause in this contract entitled "Permits and Responsibilities." If prior possession or use by the Government delays the progress of the work or causes additional expense to the Contractor, an equitable adjustment shall be made in the contract price or the time of completion, and the contract shall be modified in writing accordingly.

(End of clause)

52.236-12 CLEANING UP (APR 1984)

The Contractor shall at all times keep the work area, including storage areas, free from accumulations of waste materials. Before completing the work, the Contractor shall remove from the work and premises any rubbish, tools, scaffolding, equipment, and materials that are not the property of the Government. Upon completing the work, the Contractor shall leave the work area in a clean, neat, and orderly condition satisfactory to the Contracting Officer.

(End of clause)

52.236-13 ACCIDENT PREVENTION (NOV 1991)

(a) The Contractor shall provide and maintain work environments and procedures which will

(1) safeguard the public and Government personnel, property, materials, supplies, and equipment exposed to Contractor operations and activities;

(2) avoid interruptions of Government operations and delays in project completion dates; and

(3) control costs in the performance of this contract.

(b) For these purposes on contracts for construction or dismantling, demolition, or removal of improvements, the Contractor shall-

(1) Provide appropriate safety barricades, signs, and signal lights;

(2) Comply with the standards issued by the Secretary of Labor at 29 CFR Part 1926 and 29 CFR Part 1910; and

(3) Ensure that any additional measures the Contracting Officer determines to be reasonably necessary for the purposes are taken.

(c) If this contract is for construction or dismantling, demolition or removal of improvements with any Department of Defense agency or component, the Contractor shall comply with all pertinent provisions of the latest version of U.S. Army Corps of Engineers Safety and Health Requirements Manual, EM 385-1-1, in effect on the date of the solicitation.

(d) Whenever the Contracting Officer becomes aware of any noncompliance with these requirements or any condition which poses a serious or imminent danger to the health or safety of the public or Government personnel, the Contracting Officer shall notify the Contractor orally, with written confirmation, and request immediate initiation of corrective action. This notice, when delivered to the Contractor or the Contractor's representative at the work site, shall be deemed sufficient notice of the noncompliance and that corrective action is required. After receiving the notice, the Contractor shall immediately take corrective action. If the Contractor fails or refuses to promptly take corrective action, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. The Contractor shall not be entitled to any equitable adjustment of the contract price or extension of the performance schedule on any stop work order issued under this clause.

(e) The Contractor shall insert this clause, including this paragraph (e), with appropriate changes in the designation of the parties, in subcontracts.

(End of clause)

52.236-15 SCHEDULES FOR CONSTRUCTION CONTRACTS (APR 1984)

(a) The Contractor shall, within five days after the work commences on the contract or another period of time determined by the Contracting Officer, prepare and submit to the Contracting Officer for approval three copies of a practicable schedule showing the order in which the Contractor proposes to perform the work, and the dates on which the Contractor contemplates starting and completing the several salient features of the work (including acquiring materials, plant, and equipment). The schedule shall be in the form of a progress chart of suitable scale to indicate appropriately the percentage of work scheduled for completion by any given date during the period. If the Contractor fails to submit a schedule within the time prescribed, the Contracting Officer may withhold approval of progress payments until the Contractor submits the required schedule.

(b) The Contractor shall enter the actual progress on the chart as directed by the Contracting Officer, and upon doing

so shall immediately deliver three copies of the annotated schedule to the Contracting Officer. If, in the opinion of the Contracting Officer, the Contractor falls behind the approved schedule, the Contractor shall take steps necessary to improve its progress, including those that may be required by the Contracting Officer, without additional cost to the Government. In this circumstance, the Contracting Officer may require the Contractor to increase the number of shifts, overtime operations, days of work, and/or the amount of construction plant, and to submit for approval any supplementary schedule or schedules in chart form as the Contracting Officer deems necessary to demonstrate how the approved rate of progress will be regained.

(c) Failure of the Contractor to comply with the requirements of the Contracting Officer under this clause shall be grounds for a determination by the Contracting Officer that the Contractor is not prosecuting the work with sufficient diligence to ensure completion within the time specified in the contract. Upon making this determination, the Contracting Officer may terminate the Contractor's right to proceed with the work, or any separable part of it, in accordance with the default terms of this contract.

(End of clause)

52.236-21 SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION (FEB 1997)

(a) The Contractor shall keep on the work site a copy of the drawings and specifications and shall at all times give the Contracting Officer access thereto. Anything mentioned in the specifications and not shown on the drawings, or shown on the drawings and not mentioned in the specifications, shall be of like effect as if shown or mentioned in both. In case of difference between drawings and specifications, the specifications shall govern. In case of discrepancy in the figures, in the drawings, or in the specifications, the matter shall be promptly submitted to the Contracting Officer, who shall promptly make a determination in writing. Any adjustment by the Contractor without such a determination shall be at its own risk and expense. The Contracting Officer shall furnish from time to time such detailed drawings and other information as considered necessary, unless otherwise provided.

(b) Wherever in the specifications or upon the drawings the words "directed", "required", "ordered", "designated", "prescribed", or words of like import are used, it shall be understood that the "direction", "requirement", "order", "designation", or "prescription", of the Contracting Officer is intended and similarly the words "approved", "acceptable", "satisfactory", or words of like import shall mean "approved by," or "acceptable to", or "satisfactory to" the Contracting Officer, unless otherwise expressly stated.

(c) Where "as shown," "as indicated", "as detailed", or words of similar import are used, it shall be understood that the reference is made to the drawings accompanying this contract unless stated otherwise. The word "provided" as used herein shall be understood to mean "provide complete in place," that is "furnished and installed".

(d) Shop drawings means drawings, submitted to the Government by the Contractor, subcontractor, or any lower tier subcontractor pursuant to a construction contract, showing in detail (1) the proposed fabrication and assembly of structural elements, and (2) the installation (i.e., fit, and attachment details) of materials or equipment. It includes drawings, diagrams, layouts, schematics, descriptive literature, illustrations, schedules, performance and test data, and similar materials furnished by the contractor to explain in detail specific portions of the work required by the contract. The Government may duplicate, use, and disclose in any manner and for any purpose shop drawings delivered under this contract.

(e) If this contract requires shop drawings, the Contractor shall coordinate all such drawings, and review them for accuracy, completeness, and compliance with contract requirements and shall indicate its approval thereon as evidence of such coordination and review. Shop drawings submitted to the Contracting Officer without evidence of the Contractor's approval may be returned for resubmission. The Contracting Officer will indicate an approval or disapproval of the shop drawings and if not approved as submitted shall indicate the Government's reasons therefor. Any work done before such approval shall be at the Contractor's risk. Approval by the Contracting Officer shall not relieve the Contractor from responsibility for any errors or omissions in such drawings, nor from responsibility for complying with the requirements of this contract, except with respect to variations described and approved in accordance with (f) below.

(f) If shop drawings show variations from the contract requirements, the Contractor shall describe such variations in writing, separate from the drawings, at the time of submission. If the Contracting Officer approves any such variation, the Contracting Officer shall issue an appropriate contract modification, except that, if the variation is minor or does not involve a change in price or in time of performance, a modification need not be issued.

(g) The Contractor shall submit to the Contracting Officer for approval four copies (unless otherwise indicated) of all shop drawings as called for under the various headings of these specifications. Three sets (unless otherwise

indicated) of all shop drawings, will be retained by the Contracting Officer and one set will be returned to the Contractor.

(End of clause)

52.242-13 BANKRUPTCY (JUL 1995)

In the event the Contractor enters into proceedings relating to bankruptcy, whether voluntary or involuntary, the Contractor agrees to furnish, by certified mail or electronic commerce method authorized by the contract, written notification of the bankruptcy to the Contracting Officer responsible for administering the contract. This notification shall be furnished within five days of the initiation of the proceedings relating to bankruptcy filing. This notification shall include the date on which the bankruptcy petition was filed, the identity of the court in which the bankruptcy petition was filed, and a listing of Government contract numbers and contracting offices for all Government contracts against which final payment has not been made. This obligation remains in effect until final payment under this contract.

(End of clause)

52.242-14 SUSPENSION OF WORK (APR 1984)

(a) The Contracting Officer may order the Contractor, in writing, to suspend, delay, or interrupt all or any part of the work of this contract for the period of time that the Contracting Officer determines appropriate for the convenience of the Government.

(b) If the performance of all or any part of the work is, for an unreasonable period of time, suspended, delayed, or interrupted (1) by an act of the Contracting Officer in the administration of this contract, or (2) by the Contracting Officer's failure to act within the time specified in this contract (or within a reasonable time if not specified), an adjustment shall be made for any increase in the cost of performance of this contract (excluding profit) necessarily caused by the unreasonable suspension, delay, or interruption, and the contract modified in writing accordingly. However, no adjustment shall be made under this clause for any suspension, delay, or interruption to the extent that performance would have been so suspended, delayed, or interrupted by any other cause, including the fault or negligence of the Contractor, or for which an equitable adjustment is provided for or excluded under any other term or condition of this contract.

(c) A claim under this clause shall not be allowed—

(1) For any costs incurred more than 20 days before the Contractor shall have notified the Contracting Officer in writing of the act or failure to act involved (but this requirement shall not apply as to a claim resulting from a suspension order); and

(2) Unless the claim, in an amount stated, is asserted in writing as soon as practicable after the termination of the suspension, delay, or interruption, but not later than the date of final payment under the contract.

(End of clause)

52.243-4 CHANGES (JUN 2007)

(a) The Contracting Officer may, at any time, without notice to the sureties, if any, by written order designated or indicated to be a change order, make changes in the work within the general scope of the contract, including changes--

- (1) In the specifications (including drawings and designs);
- (2) In the method or manner of performance of the work;
- (3) In the Government-furnished property or services; or
- (4) Directing acceleration in the performance of the work.

(b) Any other written or oral order (which, as used in this paragraph (b), includes direction, instruction, interpretation, or determination) from the Contracting Officer that causes a change shall be treated as a change order under this clause; provided, that the Contractor gives the Contracting Officer written notice stating

- (1) the date, circumstances, and source of the order and
- (2) that the Contractor regards the order as a change order.

(c) Except as provided in this clause, no order, statement, or conduct of the Contracting Officer shall be treated as a change under this clause or entitle the Contractor to an equitable adjustment.

(d) If any change under this clause causes an increase or decrease in the Contractor's cost of, or the time required for, the performance of any part of the work under this contract, whether or not changed by any such order, the Contracting Officer shall make an equitable adjustment and modify the contract in writing. However, except for an adjustment based on defective specifications, no adjustment for any change under paragraph (b) of this clause shall be made for any costs incurred more than 20 days before the Contractor gives written notice as required. In the case of defective specifications for which the Government is responsible, the equitable adjustment shall include any increased cost reasonably incurred by the Contractor in attempting to comply with the defective specifications.

(e) The Contractor must assert its right to an adjustment under this clause within 30 days after

(1) receipt of a written change order under paragraph (a) of this clause or (2) the furnishing of a written notice under paragraph (b) of this clause, by submitting to the Contracting Officer a written statement describing the general nature and amount of the proposal, unless this period is extended by the Government. The statement of proposal for adjustment may be included in the notice under paragraph (b) above.

(f) No proposal by the Contractor for an equitable adjustment shall be allowed if asserted after final payment under this contract.

(End of clause)

52.244-6 SUBCONTRACTS FOR COMMERCIAL ITEMS (FEB 2016)

(a) Definitions.

"Commercial item", has the meaning contained in Federal Acquisition Regulation 2.101, Definitions.

"Subcontract", includes a transfer of commercial items between divisions, subsidiaries, or affiliates of the Contractor or subcontractor at any tier.

(b) To the maximum extent practicable, the Contractor shall incorporate, and require its subcontractors at all tiers to incorporate, commercial items or nondevelopmental items as components of items to be supplied under this contract.

(c) (1) The Contractor shall insert the following clauses in subcontracts for commercial items:

(i) 52.203-13, Contractor Code of Business Ethics and Conduct (Oct 2015) (41 U.S.C. 3509), if the subcontract exceeds \$5.5 million and has a performance period of more than 120 days. In altering this clause to identify the appropriate parties, all disclosures of violation of the civil False Claims Act or of Federal criminal law shall be directed to the agency Office of the Inspector General, with a copy to the Contracting Officer.

(ii) 52.203-15, Whistleblower Protections Under the American Recovery and Reinvestment Act of 2009 (Jun 2010) (Section 1553 of Pub. L. 111-5), if the subcontract is funded under the Recovery Act.

(iii) 52.219-8, Utilization of Small Business Concerns (OCT 2014) (15 U.S.C. 637(d)(2) and (3)), if the subcontract offers further subcontracting opportunities. If the subcontract (except subcontracts to small business concerns) exceeds \$700,000 (\$1.5 million for construction of any public facility), the subcontractor must include 52.219-8 in lower tier subcontracts that offer subcontracting opportunities.

(iv) 52.222-21, Prohibition of Segregated Facilities (Apr 2015).

(v) 52.222-26, Equal Opportunity (Apr 2015) (E.O. 11246).

(vi) 52.222-35, Equal Opportunity for Veterans (Oct 2015)(38 U.S.C. 4212(a));

(vii) 52.222-36, Equal Opportunity for Workers with Disabilities (Jul 2014) (29 U.S.C. 793).

(viii) 52.222-37, Employment Reports on Veterans (Feb 2016)(38 U.S.C. 4212).

(ix) 52.222-40, Notification of Employee Rights Under the National Labor Relations Act (Dec 2010) (E.O. 13496), if flow down is required in accordance with paragraph (f) of FAR clause 52.222-40.

(x) (A) 52.222-50, Combating Trafficking in Persons (March 2, 2015) (22 U.S.C. chapter 78 and E.O. 13627).

(B) Alternate I (March 2, 2015) of 52.222-50 (22 U.S.C. chapter 78 and E.O. 13627).

(xi) 52.222-55, Minimum Wages under Executive Order 13658 (DEC 2015).

(xii) 52.225-26, Contractors Performing Private Security Functions Outside the United States (Jul 2013) (Section 862, as amended, of the National Defense Authorization Act for Fiscal Year 2008; 10 U.S.C. 2302 Note).

(xiii) 52.232-40, Providing Accelerated Payments to Small Business Subcontractors (Dec 2013), if flow down is required in accordance with paragraph (c) of FAR clause 52.232-40.

(xiv) 52.247-64, Preference for Privately Owned U.S.-Flag Commercial Vessels (Feb 2006) (46 U.S.C. App. 1241 and 10 U.S.C. 2631), if flow down is required in accordance with paragraph (d) of FAR clause 52.247-64.

(2) While not required, the Contractor may flow down to subcontracts for commercial items a minimal number of additional clauses necessary to satisfy its contractual obligations.

(d) The Contractor shall include the terms of this clause, including this paragraph (d), in subcontracts awarded under this contract.

(End of clause)

52.246-12 INSPECTION OF CONSTRUCTION (AUG 1996)

(a) Definition. "Work" includes, but is not limited to, materials, workmanship, and manufacture and fabrication of components.

(b) The Contractor shall maintain an adequate inspection system and perform such inspections as will ensure that the work performed under the contract conforms to contract requirements. The Contractor shall maintain complete inspection records and make them available to the Government. All work shall be conducted under the general direction of the Contracting Officer and is subject to Government inspection and test at all places and at all reasonable times before acceptance to ensure strict compliance with the terms of the contract.

(c) Government inspections and tests are for the sole benefit of the Government and do not--

(1) Relieve the Contractor of responsibility for providing adequate quality control measures;

(2) Relieve the Contractor of responsibility for damage to or loss of the material before acceptance;

(3) Constitute or imply acceptance; or

(4) Affect the continuing rights of the Government after acceptance of the completed work under paragraph (i) of this section.

(d) The presence or absence of a Government inspector does not relieve the Contractor from any contract requirement, nor is the inspector authorized to change any term or condition of the specification without the Contracting Officer's written authorization.

(e) The Contractor shall promptly furnish, at no increase in contract price, all facilities, labor, and material reasonably needed for performing such safe and convenient inspections and tests as may be required by the Contracting Officer. The Government may charge to the Contractor any additional cost of inspection or test when work is not ready at the time specified by the Contractor for inspection or test, or when prior rejection makes reinspection or retest necessary. The Government shall perform all inspections and tests in a manner that will not unnecessarily delay the work. Special, full size, and performance tests shall be performed as described in the contract.

(f) The Contractor shall, without charge, replace or correct work found by the Government not to conform to

contract requirements, unless in the public interest the Government consents to accept the work with an appropriate adjustment in contract price. The Contractor shall promptly segregate and remove rejected material from the premises.

(g) If the Contractor does not promptly replace or correct rejected work, the Government may (1) by contract or otherwise, replace or correct the work and charge the cost to the Contractor or (2) terminate for default the Contractor's right to proceed.

(h) If, before acceptance of the entire work, the Government decides to examine already completed work by removing it or tearing it out, the Contractor, on request, shall promptly furnish all necessary facilities, labor, and material. If the work is found to be defective or nonconforming in any material respect due to the fault of the Contractor or its subcontractors, the Contractor shall defray the expenses of the examination and of satisfactory reconstruction. However, if the work is found to meet contract requirements, the Contracting Officer shall make an equitable adjustment for the additional services involved in the examination and reconstruction, including, if completion of the work was thereby delayed, an extension of time.

(i) Unless otherwise specified in the contract, the Government shall accept, as promptly as practicable after completion and inspection, all work required by the contract or that portion of the work the Contracting Officer determines can be accepted separately. Acceptance shall be final and conclusive except for latent defects, fraud, gross mistakes amounting to fraud, or the Government's rights under any warranty or guarantee.

(End of clause)

52.247-63 PREFERENCE FOR U.S.-FLAG AIR CARRIERS (JUN 2003)

(a) Definitions. As used in this clause--

International air transportation means transportation by air between a place in the United States and a place outside the United States or between two places both of which are outside the United States.

United States means the 50 States, the District of Columbia, and outlying areas.

U.S.-flag air carrier means an air carrier holding a certificate under 49 U.S.C. Chapter 411.

(b) Section 5 of the International Air Transportation Fair Competitive Practices Act of 1974 (49 U.S.C. 40118) (Fly America Act) requires that all Federal agencies and Government contractors and subcontractors use U.S.-flag air carriers for U.S. Government-financed international air transportation of personnel (and their personal effects) or property, to the extent that service by those carriers is available. It requires the Comptroller General of the United States, in the absence of satisfactory proof of the necessity for foreign-flag air transportation, to disallow expenditures from funds, appropriated or otherwise established for the account of the United States, for international air transportation secured aboard a foreign-flag air carrier if a U.S.-flag air carrier is available to provide such services.

(c) If available, the Contractor, in performing work under this contract, shall use U.S.-flag carriers for international air transportation of personnel (and their personal effects) or property.

(d) In the event that the Contractor selects a carrier other than a U.S.-flag air carrier for international air transportation, the Contractor shall include a statement on vouchers involving such transportation essentially as follows:

STATEMENT OF UNAVAILABILITY OF U.S.-FLAG AIR CARRIERS

International air transportation of persons (and their personal effects) or property by U.S.-flag air carrier was not available or it was necessary to use foreign-flag air carrier service for the following reasons (see section 47.403 of the Federal Acquisition Regulation): [State reasons]: _____

(End of statement)

(e) The Contractor shall include the substance of this clause, including this paragraph (e), in each subcontract or purchase under this contract that may involve international air transportation.

(End of clause)

52.248-3 VALUE ENGINEERING--CONSTRUCTION (OCT 2015)

(a) General. The Contractor is encouraged to develop, prepare, and submit value engineering change proposals (VECP's) voluntarily. The Contractor shall share in any instant contract savings realized from accepted VECP's, in accordance with paragraph (f) below.

(b) Definitions. "Collateral costs," as used in this clause, means agency costs of operation, maintenance, logistic support, or Government-furnished property.

"Collateral savings," as used in this clause, means those measurable net reductions resulting from a VECP in the agency's overall projected collateral costs, exclusive of acquisition savings, whether or not the acquisition cost changes.

"Contractor's development and implementation costs," as used in this clause, means those costs the Contractor incurs on a VECP specifically in developing, testing, preparing, and submitting the VECP, as well as those costs the Contractor incurs to make the contractual changes required by Government acceptance of a VECP.

"Government costs," as used in this clause, means those agency costs that result directly from developing and implementing the VECP, such as any net increases in the cost of testing, operations, maintenance, and logistic support. The term does not include the normal administrative costs of processing the VECP.

"Instant contract savings," as used in this clause, means the estimated reduction in Contractor cost of performance resulting from acceptance of the VECP, minus allowable Contractor's development and implementation costs, including subcontractors' development and implementation costs (see paragraph (h) below).

"Value engineering change proposal (VECP)" means a proposal that--

(1) Requires a change to this, the instant contract, to implement; and

(2) Results in reducing the contract price or estimated cost without impairing essential functions or characteristics; provided, that it does not involve a change--

(i) In deliverable end item quantities only; or

(ii) To the contract type only.

(c) VECP preparation. As a minimum, the Contractor shall include in each VECP the information described in subparagraphs(c) (1) through (7) below. If the proposed change is affected by contractually required configuration management or similar procedures, the instructions in those procedures relating to format, identification, and priority assignment shall govern VECP preparation. The VECP shall include the following:

(1) A description of the difference between the existing contract requirement and that proposed, the comparative advantages and disadvantages of each, a justification when an item's function or characteristics are being altered, and the effect of the change on the end item's performance.

(2) A list and analysis of the contract requirements that must be changed if the VECP is accepted, including any suggested specification revisions.

(3) A separate, detailed cost estimate for

(i) the affected portions of the existing contract requirement and

(ii) the VECP. The cost reduction associated with the VECP shall take into account the Contractor's allowable development and implementation costs, including any amount attributable to subcontracts under paragraph (h) below.

(4) A description and estimate of costs the Government may incur in implementing the VECP, such as test and evaluation and operating and support costs.

(5) A prediction of any effects the proposed change would have on collateral costs to the agency.

(6) A statement of the time by which a contract modification accepting the VECP must be issued in order to achieve the maximum cost reduction, noting any effect on the contract completion time or delivery schedule.

(7) Identification of any previous submissions of the VECP, including the dates submitted, the agencies and contract numbers involved, and previous Government actions, if known.

(d) Submission. The Contractor shall submit VECP's to the Resident Engineer at the worksite, with a copy to the Contracting Officer.

(e) Government action.

(1) The Contracting Officer will notify the Contractor of the status of the VECP within 45 calendar days after the contracting office receives it. If additional time is required, the Contracting Officer will notify the Contractor within the 45-day period and provide the reason for the delay and the expected date of the decision. The Government will process VECP's expeditiously; however, it shall not be liable for any delay in acting upon a VECP.

If the VECP is not accepted, the Contracting Officer will notify the Contractor in writing, explaining the reasons for rejection. The Contractor may withdraw any VECP, in whole or in part, at any time before it is accepted by the Government. The Contracting Officer may require that the Contractor provide written notification before undertaking significant expenditures for VECP effort.

Any VECP may be accepted, in whole or in part, by the Contracting Officer's award of a modification to this contract citing this clause. The Contracting Officer may accept the VECP, even though an agreement on price reduction has not been reached, by issuing the Contractor a notice to proceed with the change. Until a notice to proceed is issued or a contract modification applies a VECP to this contract, the Contractor shall perform in accordance with the existing contract. The decision to accept or reject all or part of any VECP is a unilateral decision made solely at the discretion of the Contracting Officer.

(f) Sharing.

(1) Rates. The Government's share of savings is determined by subtracting Government costs from instant contract savings and multiplying the result by

(i) 45 percent for fixed-price contracts or

(ii) 75 percent for cost-reimbursement contracts.

(2) Payment. Payment of any share due the Contractor for use of a VECP on this contract shall be authorized by a modification to this contract to--

(i) Accept the VECP;

(ii) Reduce the contract price or estimated cost by the amount of instant contract savings; and

(iii) Provide the Contractor's share of savings by adding the amount calculated to the contract price or fee.

(g) Collateral savings. If a VECP is accepted, the Contracting Officer will increase the instant contract amount by 20 percent of any projected collateral savings determined to be realized in a typical year of use after subtracting any Government costs not previously offset. However, the Contractor's share of collateral savings will not exceed the contract's firm-fixed-price or estimated cost, at the time the VECP is accepted, or \$100,000, whichever is greater. The Contracting Officer is the sole determiner of the amount of collateral savings.

(h) Subcontracts. The Contractor shall include an appropriate value engineering clause in any subcontract of \$70,000 or more and may include one in subcontracts of lesser value. In computing any adjustment in this contract's price under paragraph (f) above, the Contractor's allowable development and implementation costs shall include any subcontractor's allowable development and implementation costs clearly resulting from a VECP accepted by the Government under this contract, but shall exclude any value engineering incentive payments to a subcontractor. The Contractor may choose any arrangement for subcontractor value engineering incentive payments; provided, that these payments shall not reduce the Government's share of the savings resulting from the VECP.

(i) Data. The Contractor may restrict the Government's right to use any part of a VECP or the supporting data by marking the following legend on the affected parts:

"These data, furnished under the Value Engineering-- Construction clause of contract , shall not be disclosed outside the Government or duplicated, used, or disclosed, in whole or in part, for any purpose other than to evaluate a value engineering change proposal submitted under the clause. This restriction does not limit the Government's right to use information contained in these data if it has been obtained or is otherwise available from the Contractor or from another source without limitations." If a VECP is accepted, the Contractor hereby grants the Government unlimited rights in the VECP and supporting data, except that, with respect to data qualifying and submitted as limited rights technical data, the Government shall have the rights specified in the contract modification implementing the VECP and shall appropriately mark the data. (The terms "unlimited rights" and "limited rights" are defined in Part 27 of the Federal Acquisition Regulation.)

(End of clause)

52.249-2 TERMINATION FOR CONVENIENCE OF THE GOVERNMENT (FIXED-PRICE) (APR 2012)

(a) The Government may terminate performance of work under this contract in whole or, from time to time, in part if the Contracting Officer determines that a termination is in the Government's interest. The Contracting Officer shall terminate by delivering to the Contractor a Notice of Termination specifying the extent of termination and the effective date.

(b) After receipt of a Notice of Termination, and except as directed by the Contracting Officer, the Contractor shall immediately proceed with the following obligations, regardless of any delay in determining or adjusting any amounts due under this clause:

(1) Stop work as specified in the notice.

(2) Place no further subcontracts or orders (referred to as subcontracts in this clause) for materials, services, or facilities, except as necessary to complete the continued portion of the contract.

(3) Terminate all subcontracts to the extent they relate to the work terminated.

(4) Assign to the Government, as directed by the Contracting Officer, all right, title, and interest of the Contractor under the subcontracts terminated, in which case the Government shall have the right to settle or to pay any termination settlement proposal arising out of those terminations.

(5) With approval or ratification to the extent required by the Contracting Officer, settle all outstanding liabilities and termination settlement proposals arising from the termination of subcontracts; the approval or ratification will be final for purposes of this clause.

(6) As directed by the Contracting Officer, transfer title and deliver to the Government (i) the fabricated or unfabricated parts, work in process, completed work, supplies, and other material produced or acquired for the work terminated, and (ii) the completed or partially completed plans, drawings, information, and other property that, if the contract had been completed, would be required to be furnished to the Government.

(7) Complete performance of the work not terminated.

(8) Take any action that may be necessary, or that the Contracting Officer may direct, for the protection and preservation of the property related to this contract that is in the possession of the Contractor and in which the Government has or may acquire an interest.

(9) Use its best efforts to sell, as directed or authorized by the Contracting Officer, any property of the types referred to in subparagraph (b)(6) of this clause; provided, however, that the Contractor (i) is not required to extend credit to any purchaser and (ii) may acquire the property under the conditions prescribed by, and at prices approved by, the Contracting Officer. The proceeds of any transfer or disposition will be applied to reduce any payments to be made by the Government under this contract, credited to the price or cost of the work, or paid in any other manner directed by the Contracting Officer.

(c) The Contractor shall submit complete termination inventory schedules no later than 120 days from the effective date of termination, unless extended in writing by the Contracting Officer upon written request of the Contractor within this 120-day period.

(d) After expiration of the plant clearance period as defined in Subpart 49.001 of the Federal Acquisition Regulation, the Contractor may submit to the Contracting Officer a list, certified as to quantity and quality, of termination inventory not previously disposed of, excluding items authorized for disposition by the Contracting Officer. The Contractor may request the Government to remove those items or enter into an agreement for their storage. Within 15 days, the Government will accept title to those items and remove them or enter into a storage agreement. The Contracting Officer may verify the list upon removal of the items, or if stored, within 45 days from submission of the list, and shall correct the list, as necessary, before final settlement.

(e) After termination, the Contractor shall submit a final termination settlement proposal to the Contracting Officer in the form and with the certification prescribed by the Contracting Officer. The Contractor shall submit the proposal promptly, but no later than 1 year from the effective date of termination, unless extended in writing by the Contracting Officer upon written request of the Contractor within this 1-year period. However, if the Contracting Officer determines that the facts justify it, a termination settlement proposal may be received and acted on after 1 year or any extension. If the Contractor fails to submit the proposal within the time allowed, the Contracting Officer may determine, on the basis of information available, the amount, if any, due the Contractor because of the termination and shall pay the amount determined.

(f) Subject to paragraph (e) of this clause, the Contractor and the Contracting Officer may agree upon the whole or any part of the amount to be paid or remaining to be paid because of the termination. The amount may include a

reasonable allowance for profit on work done. However, the agreed amount, whether under this paragraph (g) or paragraph (g) of this clause, exclusive of costs shown in subparagraph (g)(3) of this clause, may not exceed the total contract price as reduced by (1) the amount of payments previously made and (2) the contract price of work not terminated. The contract shall be modified, and the Contractor paid the agreed amount. Paragraph (g) of this clause shall not limit, restrict, or affect the amount that may be agreed upon to be paid under this paragraph.

(g) If the Contractor and the Contracting Officer fail to agree on the whole amount to be paid because of the termination of work, the Contracting Officer shall pay the Contractor the amounts determined by the Contracting Officer as follows, but without duplication of any amounts agreed on under paragraph (f) of this clause:

(1) The contract price for completed supplies or services accepted by the Government (or sold or acquired under subparagraph (b)(9) of this clause) not previously paid for, adjusted for any saving of freight and other charges.

(2) The total of--

(i) The costs incurred in the performance of the work terminated, including initial costs and preparatory expense allocable thereto, but excluding any costs attributable to supplies or services paid or to be paid under subparagraph (f)(1) of this clause;

(ii) The cost of settling and paying termination settlement proposals under terminated subcontracts that are properly chargeable to the terminated portion of the contract if not included in subdivision (g)(2)(i) of this clause; and

(iii) A sum, as profit on subdivision (g)(2)(i) of this clause, determined by the Contracting Officer under 49.202 of the Federal Acquisition Regulation, in effect on the date of this contract, to be fair and reasonable; however, if it appears that the Contractor would have sustained a loss on the entire contract had it been completed, the Contracting Officer shall allow no profit under this subdivision (iii) and shall reduce the settlement to reflect the indicated rate of loss.

(3) The reasonable costs of settlement of the work terminated, including--

(i) Accounting, legal, clerical, and other expenses reasonably necessary for the preparation of termination settlement proposals and supporting data;

(ii) The termination and settlement of subcontracts (excluding the amounts of such settlements); and

(iii) Storage, transportation, and other costs incurred, reasonably necessary for the preservation, protection, or disposition of the termination inventory.

(h) Except for normal spoilage, and except to the extent that the Government expressly assumed the risk of loss, the Contracting Officer shall exclude from the amounts payable to the Contractor under paragraph (g) of this clause, the fair value as determined by the Contracting Officer, for the loss of the Government property.

(i) The cost principles and procedures of Part 31 of the Federal Acquisition Regulation, in effect on the date of this contract, shall govern all costs claimed, agreed to, or determined under this clause.

(j) The Contractor shall have the right of appeal, under the Disputes clause, from any determination made by the Contracting Officer under paragraph (e), (g), or (l) of this clause, except that if the Contractor failed to submit the termination settlement proposal or request for equitable adjustment within the time provided in paragraph (e) or (l), respectively, and failed to request a time extension, there is no right of appeal.

(k) In arriving at the amount due the Contractor under this clause, there shall be deducted--

(1) All unliquidated advance or other payments to the Contractor under the terminated portion of this contract;

(2) Any claim which the Government has against the Contractor under this contract; and

(3) The agreed price for, or the proceeds of sale of, materials, supplies, or other things acquired by the Contractor or sold under the provisions of this clause and not recovered by or credited to the Government.

(l) If the termination is partial, the Contractor may file a proposal with the Contracting Officer for an equitable adjustment of the price(s) of the continued portion of the contract. The Contracting Officer shall make any equitable adjustment agreed upon. Any proposal by the Contractor for an equitable adjustment under this clause shall be requested within 90 days from the effective date of termination unless extended in writing by the Contracting Officer.

(m)(1) The Government may, under the terms and conditions it prescribes, make partial payments and payments against costs incurred by the Contractor for the terminated portion of the contract, if the Contracting Officer believes the total of these payments will not exceed the amount to which the Contractor will be entitled.

(2) If the total payments exceed the amount finally determined to be due, the Contractor shall repay the excess to the Government upon demand, together with interest computed at the rate established by the Secretary of the Treasury under 50 U.S.C. App. 1215(b)(2). Interest shall be computed for the period from the date the excess payment is received by the Contractor to the date the excess is repaid. Interest shall not be charged on any excess payment due to a reduction in the Contractor's termination settlement proposal because of retention or other disposition of termination inventory until 10 days after the date of the retention or disposition, or a later date determined by the Contracting Officer because of the circumstances.

(n) Unless otherwise provided in this contract or by statute, the Contractor shall maintain all records and documents relating to the terminated portion of this contract for 3 years after final settlement. This includes all books and other evidence bearing on the Contractor's costs and expenses under this contract. The Contractor shall make these records and documents available to the Government, at the Contractor's office, at all reasonable times, without any direct charge. If approved by the Contracting Officer, photographs, microphotographs, or other authentic reproductions may be maintained instead of original records and documents.

(End of clause)

52.249-10 DEFAULT (FIXED-PRICE CONSTRUCTION) (APR 1984)

(a) If the Contractor refuses or fails to prosecute the work or any separable part, with the diligence that will insure its completion within the time specified in this contract including any extension, or fails to complete the work within this time, the Government may, by written notice to the Contractor, terminate the right to proceed with the work (or the separable part of the work) that has been delayed. In this event, the Government may take over the work and complete it by contract or otherwise, and may take possession of and use any materials, appliances, and plant on the work site necessary for completing the work. The Contractor and its sureties shall be liable for any damage to the Government resulting from the Contractor's refusal or failure to complete the work within the specified time, whether or not the Contractor's right to proceed with the work is terminated. This liability includes any increased costs incurred by the Government in completing the work.

(b) The Contractor's right to proceed shall not be terminated nor the Contractor charged with damages under this clause, if—

(1) The delay in completing the work arises from unforeseeable causes beyond the control and without the fault or negligence of the Contractor. Examples of such causes include—

(i) Acts of God or of the public enemy,

(ii) Acts of the Government in either its sovereign or contractual capacity,

(iii) Acts of another Contractor in the performance of a contract with the Government,

(iv) Fires,

(v) Floods,

(vi) Epidemics,

(vii) Quarantine restrictions,

(viii) Strikes,

(ix) Freight embargoes,

(x) Unusually severe weather, or

(xi) Delays of subcontractors or suppliers at any tier arising from unforeseeable causes beyond the control and without the fault or negligence of both the Contractor and the subcontractors or suppliers; and

(2) The Contractor, within 10 days from the beginning of any delay (unless extended by the Contracting Officer), notifies the Contracting Officer in writing of the causes of delay. The Contracting Officer shall ascertain the facts and the extent of delay. If, in the judgment of the Contracting Officer, the findings of fact warrant such action, the time for completing the work shall be extended. The findings of the Contracting Officer shall be final and conclusive on the parties, but subject to appeal under the Disputes clause.

(c) If, after termination of the Contractor's right to proceed, it is determined that the Contractor was not in default, or that the delay was excusable, the rights and obligations of the parties will be the same as if the termination had been issued for the convenience of the Government.

(d) The rights and remedies of the Government in this clause are in addition to any other rights and remedies provided by law or under this contract.

(End of clause)

52.253-1 COMPUTER GENERATED FORMS (JAN 1991)

(a) Any data required to be submitted on a Standard or Optional Form prescribed by the Federal Acquisition Regulation (FAR) may be submitted on a computer generated version of the form, provided there is no change to the name, content, or sequence of the data elements on the form, and provided the form carries the Standard or Optional Form number and edition date.

(b) Unless prohibited by agency regulations, any data required to be submitted on an agency unique form prescribed by an agency supplement to the FAR may be submitted on a computer generated version of the form provided there is no change to the name, content, or sequence of the data elements on the form and provided the form carries the agency form number and edition date.

(c) If the Contractor submits a computer generated version of a form that is different than the required form, then the rights and obligations of the parties will be determined based on the content of the required form.

(End of clause)

252.201-7000 CONTRACTING OFFICER'S REPRESENTATIVE (DEC 1991)

(a) "Definition. Contracting officer's representative" means an individual designated in accordance with subsection 201.602-2 of the Defense Federal Acquisition Regulation Supplement and authorized in writing by the contracting officer to perform specific technical or administrative functions.

(b) If the Contracting Officer designates a contracting officer's representative (COR), the Contractor will receive a copy of the written designation. It will specify the extent of the COR's authority to act on behalf of the contracting officer. The COR is not authorized to make any commitments or changes that will affect price, quality, quantity, delivery, or any other term or condition of the contract.

(End of clause)

252.203-7000 REQUIREMENTS RELATING TO COMPENSATION OF FORMER DOD OFFICIALS (SEP 2011)

(a) Definition. Covered DoD official, as used in this clause, means an individual that--

(1) Leaves or left DoD service on or after January 28, 2008; and

(2)(i) Participated personally and substantially in an acquisition as defined in 41 U.S.C. 131 with a value in excess of \$10 million, and serves or served--

(A) In an Executive Schedule position under subchapter II of chapter 53 of Title 5, United States Code;

(B) In a position in the Senior Executive Service under subchapter VIII of chapter 53 of Title 5, United States Code; or

(C) In a general or flag officer position compensated at a rate of pay for grade O-7 or above under section 201 of Title 37, United States Code; or

(ii) Serves or served in DoD in one of the following positions: Program manager, deputy program manager, procuring contracting officer, administrative contracting officer, source selection authority, member of the source selection evaluation board, or chief of a financial or technical evaluation team for a contract in an amount in excess of \$10 million.

(b) The Contractor shall not knowingly provide compensation to a covered DoD official within 2 years after the official leaves DoD service, without first determining that the official has sought and received, or has not received after 30 days of seeking, a written opinion from the appropriate DoD ethics counselor regarding the applicability of post-employment restrictions to the activities that the official is expected to undertake on behalf of the Contractor.

(c) Failure by the Contractor to comply with paragraph (b) of this clause may subject the Contractor to rescission of this contract, suspension, or debarment in accordance with 41 U.S.C. 2105(c).

(End of clause)

252.203-7001 PROHIBITION ON PERSONS CONVICTED OF FRAUD OR OTHER DEFENSE-CONTRACT-RELATED FELONIES (DEC 2008)

(a) Definitions. As used in this clause—

(1) “Arising out of a contract with the DoD” means any act in connection with—

(i) Attempting to obtain;

(ii) Obtaining, or

(iii) Performing a contract or first-tier subcontract of any agency, department, or component of the Department of Defense (DoD).

(2) “Conviction of fraud or any other felony” means any conviction for fraud or a felony in violation of state or Federal criminal statutes, whether entered on a verdict or plea, including a plea of nolo contendere, for which sentence has been imposed.

(3) “Date of conviction” means the date judgment was entered against the individual.

(b) Any individual who is convicted after September 29, 1988, of fraud or any other felony arising out of a contract with the DoD is prohibited from serving--

(1) In a management or supervisory capacity on this contract;

(2) On the board of directors of the Contractor;

(3) As a consultant, agent, or representative for the Contractor; or

(4) In any other capacity with the authority to influence, advise, or control the decisions of the Contractor with regard to this contract.

(c) Unless waived, the prohibition in paragraph (b) of this clause applies for not less than 5 years from the date of conviction.

(d) 10 U.S.C. 2408 provides that the Contractor shall be subject to a criminal penalty of not more than \$500,000 if convicted of knowingly--

(1) Employing a person under a prohibition specified in paragraph (b) of this clause; or

(2) Allowing such a person to serve on the board of directors of the contractor or first-tier subcontractor.

(e) In addition to the criminal penalties contained in 10 U.S.C. 2408, the Government may consider other available remedies, such as—

(1) Suspension or debarment;

(2) Cancellation of the contract at no cost to the Government; or

(3) Termination of the contract for default.

(f) The Contractor may submit written requests for waiver of the prohibition in paragraph (b) of this clause to the Contracting Officer. Requests shall clearly identify—

- (1) The person involved;
 - (2) The nature of the conviction and resultant sentence or punishment imposed;
 - (3) The reasons for the requested waiver; and
 - (4) An explanation of why a waiver is in the interest of national security.
- (g) The Contractor agrees to include the substance of this clause, appropriately modified to reflect the identity and relationship of the parties, in all first-tier subcontracts exceeding the simplified acquisition threshold in Part 2 of the Federal Acquisition Regulation, except those for commercial items or components.
- (h) Pursuant to 10 U.S.C. 2408(c), defense contractors and subcontractors may obtain information as to whether a particular person has been convicted of fraud or any other felony arising out of a contract with the DoD by contacting The Office of Justice Programs, The Denial of Federal Benefits Office, U.S. Department of Justice, telephone 301-937-1542; www.ojp.usdoj.gov/BJA/grant/DPFC.html".
- (End of clause)

252.203-7002 REQUIREMENT TO INFORM EMPLOYEES OF WHISTLEBLOWER RIGHTS (SEP 2013)

- (a) The Contractor shall inform its employees in writing, in the predominant native language of the workforce, of contractor employee whistleblower rights and protections under 10 U.S.C. 2409, as described in subpart 203.9 of the Defense Federal Acquisition Regulation Supplement.
- (b) The Contractor shall include the substance of this clause, including this paragraph (b), in all subcontracts.
- (End of clause)

252.203-7003 AGENCY OFFICE OF THE INSPECTOR GENERAL (DEC 2012)

The agency office of the Inspector General referenced in paragraphs (c) and (d) of FAR clause 52.203-13, Contractor Code of Business Ethics and Conduct, is the DoD Office of Inspector General at the following address:

Department of Defense Office of Inspector General, Investigative Policy and Oversight, Contractor Disclosure Program, 4800 Mark Center Drive, Suite 11H25, Alexandria, VA 22350-1500.

Toll Free Telephone: 866-429-8011.

(End of clause)

252.204-7000 Disclosure of Information.

- (a) The Contractor shall not release to anyone outside the Contractor's organization any unclassified information, regardless of medium (e.g., film, tape, document), pertaining to any part of this contract or any program related to this contract, unless—
- (1) The Contracting Officer has given prior written approval;

(2) The information is otherwise in the public domain before the date of release; or

(3) The information results from or arises during the performance of a project

that involves no covered defense information (as defined in the clause at DFARS 252.204-7012) and has been scoped and negotiated by the contracting activity with the

contractor and research performer and determined in writing by the contracting officer

to be fundamental research (which by definition cannot involve any covered defense information), in accordance with National Security Decision Directive 189, National

Policy on the Transfer of Scientific, Technical and Engineering Information, in effect on

the date of contract award and the Under Secretary of Defense (Acquisition, Technology, and Logistics) memoranda on Fundamental Research, dated May 24, 2010,

and on Contracted Fundamental Research, dated June 26, 2008 (available at DFARS PGI 204.4).

(b) Requests for approval under paragraph (a)(1) shall identify the specific information to be released, the medium to be used, and the purpose for the release. The Contractor shall submit its request to the Contracting Officer at least 10 business days before the proposed date for release.

(c) The Contractor agrees to include a similar requirement, including this paragraph (c), in each subcontract under this contract. Subcontractors shall submit requests for authorization to release through the prime contractor to the Contracting Officer.

(End of clause)

252.204-7003 CONTROL OF GOVERNMENT PERSONNEL WORK PRODUCT (APR 1992)

The Contractor's procedures for protecting against unauthorized disclosure of information shall not require Department of Defense employees or members of the Armed Forces to relinquish control of their work products, whether classified or not, to the contractor.

(End of clause)

252.204-7009 Limitations on the Use or Disclosure of Third-Party Contractor Reported Cyber Incident Information.

CONTRACTOR REPORTED CYBER INCIDENT INFORMATION (OCT 2016)

(a) Definitions. As used in this clause—

“Compromise” means disclosure of information to unauthorized persons, or a violation of the security policy of a system, in which unauthorized intentional or unintentional disclosure, modification, destruction, or loss of an object, or the copying of information to unauthorized media may have occurred.

“Controlled technical information” means technical information with military or space application that is subject to controls on the access, use, reproduction, modification, performance, display, release, disclosure, or dissemination. Controlled technical information would meet the criteria, if disseminated, for distribution statements B through F

using the criteria set forth in DoD Instruction 5230.24, Distribution Statements on Technical Documents. The term does not include information that is lawfully publicly available without restrictions.

“Covered defense information” means unclassified controlled technical information or other information (as described in the Controlled Unclassified Information (CUI) Registry at <http://www.archives.gov/cui/registry/category-list.html>) that requires safeguarding or dissemination controls pursuant to and consistent with law, regulations, and Governmentwide policies, and is—

(1) Marked or otherwise identified in the contract, task order, or delivery order and provided to the contractor by or on behalf of DoD in support of the performance of the contract; or

(2) Collected, developed, received, transmitted, used, or stored by or on behalf of the contractor in support of the performance of the contract.

“Cyber incident” means actions taken through the use of computer networks that result in a compromise or an actual or potentially adverse effect on an information system and/or the information residing therein.

“Information system” means a discrete set of information resources organized for the collection, processing, maintenance, use, sharing, dissemination, or disposition of information.

“Media” means physical devices or writing surfaces including, but is not limited to, magnetic tapes, optical disks, magnetic disks, large-scale integration memory chips, and printouts onto which covered defense information is recorded, stored, or printed within a covered contractor information system.

“Technical information” means technical data or computer software, as those terms are defined in the clause at DFARS 252.227-7013, Rights in Technical Data-Noncommercial Items, regardless of whether or not the clause is incorporated in this solicitation or contract. Examples of technical information include research and engineering data, engineering drawings, and associated lists, specifications, standards, process sheets, manuals, technical reports, technical orders, catalog-item identifications, data sets, studies and analyses and related information, and computer software executable code and source code.

(b) Restrictions. The Contractor agrees that the following conditions apply to any information it receives or creates in the performance of this contract that is information obtained from a third-party’s reporting of a cyber incident pursuant to DFARS clause 252.204-7012, Safeguarding Covered Defense Information and Cyber Incident Reporting (or derived from such information obtained under that clause):

(1) The Contractor shall access and use the information only for the purpose of furnishing advice or technical assistance directly to the Government in support of the Government’s activities related to clause 252.204-7012, and shall not be used for any other purpose.

(2) The Contractor shall protect the information against unauthorized release or disclosure.

(3) The Contractor shall ensure that its employees are subject to use and non-disclosure obligations consistent with this clause prior to the employees being provided access to or use of the information.

(4) The third-party contractor that reported the cyber incident is a third-party beneficiary of the non-disclosure agreement between the Government and Contractor, as required by paragraph (b)(3) of this clause.

(5) A breach of these obligations or restrictions may subject the Contractor to—

(i) Criminal, civil, administrative, and contractual actions in law and equity for penalties, damages, and other appropriate remedies by the United States; and

(ii) Civil actions for damages and other appropriate remedies by the third party that reported the cyber incident, as a third party beneficiary of this clause.

(c) Subcontracts. The Contractor shall include this clause, including this paragraph (c), in subcontracts, or similar contractual instruments, for services that include support for the Government's activities related to safeguarding covered defense information and cyber incident reporting, including subcontracts for commercial items, without alteration, except to identify the parties.

(End of clause)

252.204-7012 Safeguarding Covered Defense Information and Cyber Incident Reporting (DEC 2015)

(a) Definitions. As used in this clause--

Adequate security means protective measures that are commensurate with the consequences and probability of loss, misuse, or unauthorized access to, or modification of information.

Compromise means disclosure of information to unauthorized persons, or a violation of the security policy of a system, in which unauthorized intentional or unintentional disclosure, modification, destruction, or loss of an object, or the copying of information to unauthorized media may have occurred.

Contractor attributional/proprietary information means information that identifies the contractor(s), whether directly or indirectly, by the grouping of information that can be traced back to the contractor(s) (e.g., program description, facility locations), personally identifiable information, as well as trade secrets, commercial or financial information, or other commercially sensitive information that is not customarily shared outside of the company.

Contractor information system means an information system belonging to, or operated by or for, the Contractor.

Controlled technical information means technical information with military or space application that is subject to controls on the access, use, reproduction, modification, performance, display, release, disclosure, or dissemination. Controlled technical information would meet the criteria, if disseminated, for distribution statements B through F using the criteria set forth in DoD Instruction 5230.24, Distribution Statements on Technical Documents. The term does not include information that is lawfully publicly available without restrictions.

Covered contractor information system means an information system that is owned, or operated by or for, a contractor and that processes, stores, or transmits covered defense information.

Covered defense information means unclassified information that--

(i) Is--

(A) Provided to the contractor by or on behalf of DoD in connection with the performance of the contract; or

(B) Collected, developed, received, transmitted, used, or stored by or on behalf of the contractor in support of the performance of the contract; and

(ii) Falls in any of the following categories:

(A) Controlled technical information.

(B) Critical information (operations security). Specific facts identified through the Operations Security process about friendly intentions, capabilities, and activities vitally needed by adversaries for them to plan and act

effectively so as to guarantee failure or unacceptable consequences for friendly mission accomplishment (part of Operations Security process).

(C) Export control. Unclassified information concerning certain items, commodities, technology, software, or other information whose export could reasonably be expected to adversely affect the United States national security and nonproliferation objectives. To include dual use items; items identified in export administration regulations, international traffic in arms regulations and munitions list; license applications; and sensitive nuclear technology information.

(D) Any other information, marked or otherwise identified in the contract, that requires safeguarding or dissemination controls pursuant to and consistent with law, regulations, and Government wide policies (e.g., privacy, proprietary business information).

Cyber incident means actions taken through the use of computer networks that result in a compromise or an actual or potentially adverse effect on an information system and/or the information residing therein.

Forensic analysis means the practice of gathering, retaining, and analyzing computer-related data for investigative purposes in a manner that maintains the integrity of the data.

Malicious software means computer software or firmware intended to perform an unauthorized process that will have adverse impact on the confidentiality, integrity, or availability of an information system. This definition includes a virus, worm, Trojan horse, or other code-based entity that infects a host, as well as spyware and some forms of adware.

Media means physical devices or writing surfaces including, but is not limited to, magnetic tapes, optical disks, magnetic disks, large-scale integration memory chips, and printouts onto which information is recorded, stored, or printed within an information system.

Operationally critical support means supplies or services designated by the Government as critical for airlift, sealift, intermodal transportation services, or logistical support that is essential to the mobilization, deployment, or sustainment of the Armed Forces in a contingency operation.

Rapid(ly) report(ing) means within 72 hours of discovery of any cyber incident.

Technical information means technical data or computer software, as those terms are defined in the clause at DFARS 252.227-7013, Rights in Technical Data-Non Commercial Items, regardless of whether or not the clause is incorporated in this solicitation or contract. Examples of technical information include research and engineering data, engineering drawings, and associated lists, specifications, standards, process sheets, manuals, technical reports, technical orders, catalog-item identifications, data sets, studies and analyses and related information, and computer software executable code and source code.

(b) Adequate security. The Contractor shall provide adequate security for all covered defense information on all covered contractor information systems that support the performance of work under this contract. To provide adequate security, the Contractor shall--

(1) Implement information systems security protections on all covered contractor information systems including, at a minimum--

(i) For covered contractor information systems that are part of an Information Technology (IT) service or system operated on behalf of the Government--

(A) Cloud computing services shall be subject to the security requirements specified in the clause 252.239-7010, Cloud Computing Services, of this contract; and

(B) Any other such IT service or system (i.e., other than cloud computing) shall be subject to the security requirements specified elsewhere in this contract; or

(ii) For covered contractor information systems that are not part of an IT service or system operated on behalf of the Government and therefore are not subject to the security requirement specified at paragraph (b)(1)(i) of this clause--

(A) The security requirements in National Institute of Standards and Technology (NIST) Special Publication (SP) 800-171, "Protecting Controlled Unclassified Information in Nonfederal Information Systems and Organizations," <http://dx.doi.org/10.6028/NIST.SP.800-171> that is in effect at the time the solicitation is issued or as authorized by the Contracting Officer, as soon as practical, but not later than December 31, 2017. The Contractor shall notify the DoD CIO, via email at osd.dibcsia@mail.mil, within 30 days of contract award, of any security requirements specified by NIST SP 800-171 not implemented at the time of contract award; or

(B) Alternative but equally effective security measures used to compensate for the inability to satisfy a particular requirement and achieve equivalent protection accepted in writing by an authorized representative of the DoD CIO; and

(2) Apply other security measures when the Contractor reasonably determines that such measures, in addition to those identified in paragraph (b)(1) of this clause, may be required to provide adequate security in a dynamic environment based on an assessed risk or vulnerability.

(c) Cyber incident reporting requirement.

(1) When the Contractor discovers a cyber incident that affects a covered contractor information system or the covered defense information residing therein, or that affects the contractor's ability to perform the requirements of the contract that are designated as operationally critical support, the Contractor shall--

(i) Conduct a review for evidence of compromise of covered defense information, including, but not limited to, identifying compromised computers, servers, specific data, and user accounts. This review shall also include analyzing covered contractor information system(s) that were part of the cyber incident, as well as other information systems on the Contractor's network(s), that may have been accessed as a result of the incident in order to identify compromised covered defense information, or that affect the Contractor's ability to provide operationally critical support; and

(ii) Rapidly report cyber incidents to DoD at <http://dibnet.dod.mil>.

(2) Cyber incident report. The cyber incident report shall be treated as information created by or for DoD and shall include, at a minimum, the required elements at <http://dibnet.dod.mil>.

(3) Medium assurance certificate requirement. In order to report cyber incidents in accordance with this clause, the Contractor or subcontractor shall have or acquire a DoD-approved medium assurance certificate to report cyber incidents. For information on obtaining a DoD-approved medium assurance certificate, see <http://iase.disa.mil/pki/eca/Pages/index.aspx>.

(d) Malicious software. The Contractor or subcontractors that discover and isolate malicious software in connection with a reported cyber incident shall submit the malicious software in accordance with instructions provided by the Contracting Officer.

(e) Media preservation and protection. When a Contractor discovers a cyber incident has occurred, the Contractor shall preserve and protect images of all known affected information systems identified in paragraph (c)(1)(i) of this clause and all relevant monitoring/packet capture data for at least 90 days from the submission of the cyber incident report to allow DoD to request the media or decline interest.

(f) Access to additional information or equipment necessary for forensic analysis. Upon request by DoD, the Contractor shall provide DoD with access to additional information or equipment that is necessary to conduct a forensic analysis.

(g) Cyber incident damage assessment activities. If DoD elects to conduct a damage assessment, the Contracting Officer will request that the Contractor provide all of the damage assessment information gathered in accordance with paragraph (e) of this clause.

(h) DoD safeguarding and use of contractor attributional/proprietary information. The Government shall protect against the unauthorized use or release of information obtained from the contractor (or derived from information obtained from the contractor) under this clause that includes contractor attributional/proprietary information, including such information submitted in accordance with paragraph (c). To the maximum extent practicable, the Contractor shall identify and mark attributional/proprietary information. In making an authorized release of such information, the Government will implement appropriate procedures to minimize the contractor attributional/proprietary information that is included in such authorized release, seeking to include only that information that is necessary for the authorized purpose(s) for which the information is being released.

(i) Use and release of contractor attributional/proprietary information not created by or for DoD. Information that is obtained from the contractor (or derived from information obtained from the contractor) under this clause that is not created by or for DoD is authorized to be released outside of DoD--

(1) To entities with missions that may be affected by such information;

(2) To entities that may be called upon to assist in the diagnosis, detection, or mitigation of cyber incidents;

(3) To Government entities that conduct counterintelligence or law enforcement investigations;

(4) For national security purposes, including cyber situational awareness and defense purposes (including with Defense Industrial Base (DIB) participants in the program at 32 CFR part 236); or

(5) To a support services contractor ("recipient") that is directly supporting Government activities under a contract that includes the clause at 252.204-7009, Limitations on the Use or Disclosure of Third-Party Contractor Reported Cyber Incident Information.

(j) Use and release of contractor attributional/proprietary information created by or for DoD. Information that is obtained from the contractor (or derived from information obtained from the contractor) under this clause that is created by or for DoD (including the information submitted pursuant to paragraph (c) of this clause) is authorized to be used and released outside of DoD for purposes and activities authorized by paragraph (i) of this clause, and for any other lawful Government purpose or activity, subject to all applicable statutory, regulatory, and policy based restrictions on the Government's use and release of such information.

(k) The Contractor shall conduct activities under this clause in accordance with applicable laws and regulations on the interception, monitoring, access, use, and disclosure of electronic communications and data.

(l) Other safeguarding or reporting requirements. The safeguarding and cyber incident reporting required by this clause in no way abrogates the Contractor's responsibility for other safeguarding or cyber incident reporting pertaining to its unclassified information systems as required by other applicable clauses of this contract, or as a result of other applicable U.S. Government statutory or regulatory requirements.

(m) Subcontracts. The Contractor shall--

(1) Include this clause, including this paragraph (m), in subcontracts, or similar contractual instruments, for operationally critical support, or for which subcontract performance will involve a covered contractor information system, including subcontracts for commercial items, without alteration, except to identify the parties;

and

(2) When this clause is included in a subcontract, require subcontractors to rapidly report cyber incidents directly to DoD at <http://dibnet.dod.mil> and the prime Contractor. This includes providing the incident report number, automatically assigned by DoD, to the prime Contractor (or next higher-tier subcontractor) as soon as practicable.

(End of clause)

252.204-7015 Notice of Authorized Disclosure of Information for Litigation Support.

(a) Definitions. As used in this clause—

“Computer software” means computer programs, source code, source code listings, object code listings, design details, algorithms, processes, flow charts, formulae, and related material that would enable the software to be reproduced, recreated, or recompiled. Computer software does not include computer data bases or computer software documentation.

“Litigation support” means administrative, technical, or professional services provided in support of the Government during or in anticipation of litigation.

"Litigation support contractor" means a contractor (including its experts, technical consultants, subcontractors, and suppliers) providing litigation support under a contract that contains the clause at 252.204-7014, Limitations on the Use or Disclosure of Information by Litigation Support Contractors.

“Sensitive information” means controlled unclassified information of a commercial,

financial, proprietary, or privileged nature. The term includes technical data and computer software, but does not include information that is lawfully, publicly available without restriction.

“Technical data” means recorded information, regardless of the form or method of the recording, of a scientific or technical nature (including computer software documentation). The term does not include computer software or data incidental to contract administration, such as financial and/or management information.

(b) Notice of authorized disclosures. Notwithstanding any other provision of this

solicitation or contract, the Government may disclose to a litigation support contractor, for the sole purpose of litigation support activities, any information, including sensitive information, received--

(1) Within or in connection with a quotation or offer; or

(2) In the performance of or in connection with a contract.

(c) Flowdown. Include the substance of this clause, including this paragraph (c), in all subcontracts, including subcontracts for commercial items.

(End of clause)

252.205-7000 PROVISION OF INFORMATION TO COOPERATIVE AGREEMENT HOLDERS (DEC 1991)

(a) Definition.

"Cooperative agreement holder" means a State or local government; a private, nonprofit organization; a tribal organization (as defined in section 4(c) of the Indian Self-Determination and Education Assistance Act (Pub. L. 93-268; 25 U.S.C. 450 (c))); or an economic enterprise (as defined in section 3(e) of the Indian Financing Act of 1974 (Pub. L. 93-362; 25 U.S.C. 1452(e))) whether such economic enterprise is organized for profit or nonprofit purposes; which has an agreement with the Defense Logistics Agency to furnish procurement technical assistance to business entities.

(b) The Contractor shall provide cooperative agreement holders, upon their request, with a list of those appropriate employees or offices responsible for entering into subcontracts under defense contracts. The list shall include the business address, telephone number, and area of responsibility of each employee or office.

(c) The Contractor need not provide the listing to a particular cooperative agreement holder more frequently than once a year.

(End of clause)

252.209-7004 SUBCONTRACTING WITH FIRMS THAT ARE OWNED OR CONTROLLED BY THE GOVERNMENT OF A COUNTRY THAT IS A STATE SPONSOR OF TERRORISM (OCT 2015)

(a) Unless the Government determines that there is a compelling reason to do so, the Contractor shall not enter into any subcontract in excess of \$35,000 with a firm, or a subsidiary of a firm, that is identified in the Exclusions section of the System for Award Management System (SAM Exclusions) as being ineligible for the award of Defense contracts or subcontracts because it is owned or controlled by the government of a country that is a state sponsor of terrorism.

(b) A corporate officer or a designee of the Contractor shall notify the Contracting Officer, in writing, before entering into a subcontract with a party that is identified, in SAM Exclusions, as being ineligible for the award of Defense contracts or subcontracts because it is owned or controlled by the government of a country that is a state sponsor of terrorism. The notice must include the name of the proposed subcontractor and the compelling reason(s) for doing business with the subcontractor notwithstanding its inclusion in SAM Exclusions.

(End of clause)

252.216-7006 ORDERING (MAY 2011)

(a) Any supplies and services to be furnished under this contract shall be ordered by issuance of delivery orders or task orders by the individuals or activities designated in the contract schedule. Such orders may be issued from a **period of fourteen (14) months after award date of the contract.**

(b) All delivery orders or task orders are subject to the terms and conditions of this contract. In the event of conflict between a delivery order or task order and this contract, the contract shall control.

(c)(1) If issued electronically, the order is considered ``issued" when a copy has been posted to the Electronic Document Access system, and notice has been sent to the Contractor.

(2) If mailed or transmitted by facsimile, a delivery order or task order is considered ``issued" when the Government deposits the order in the mail or transmits by facsimile. Mailing includes transmittal by U.S. mail or private delivery services.

(3) Orders may be issued orally only if authorized in the schedule.

(End of Clause)

252.219-7003 SMALL BUSINESS SUBCONTRACTING PLAN (DOD CONTRACTS) (OCT 2014)

This clause supplements the Federal Acquisition Regulation 52.219-9, Small Business Subcontracting Plan, clause of this contract.

(a) Definitions. As used in this clause--

Historically black colleges and universities means institutions determined by the Secretary of Education to meet the requirements of 34 CFR Section 608.2. The term also means any nonprofit research institution that was an integral part of such a college or university before November 14, 1986.

Minority institutions means institutions meeting the requirements of Section 1046(3) of the Higher Education Act of 1965 (20 U.S.C. 1135d-5(3)). The term also includes Hispanic-serving institutions as defined in Section 316(b)(1) of such Act (20 U.S.C. 1059c(b)(1)).

Summary Subcontract Report (SSR) Coordinator, as used in this clause, means the individual at the department or agency level who is registered in eSRS and is responsible for acknowledging receipt or rejecting SSRs in eSRS for the department or agency.

(b) Subcontracts awarded to workshops approved by the Committee for Purchase from People Who are Blind or Severely Disabled (41 U.S.C. 8502-8504), may be counted toward the Contractor's small business subcontracting goal.

(c) A mentor firm, under the Pilot Mentor-Protege Program established under section 831 of Public Law 101-510, as amended, may count toward its small disadvantaged business goal, subcontracts awarded to--

(1) Protege firms which are qualified organizations employing the severely disabled; and

(2) Former protege firms that meet the criteria in Section 831(g)(4) of Public Law 101-510.

(d) The master plan is approved by the Contractor's cognizant contract administration activity.

(e) In those subcontracting plans which specifically identify small businesses, the Contractor shall notify the Administrative Contracting Officer of any substitutions of firms that are not small business firms, for the small business firms specifically identified in the subcontracting plan. Notifications shall be in writing and shall occur within a reasonable period of time after award of the subcontract. Contractor-specified formats shall be acceptable.

(f)(1) For DoD, the Contractor shall submit reports in eSRS as follows:

(i) The Individual Subcontract Report (ISR) shall be submitted to the contracting officer at the procuring contracting office, even when contract administration has been delegated to the Defense Contract Management Agency.

(ii) An SSR for other than a commercial subcontracting plan, or construction and related maintenance repair contracts, shall be submitted in eSRS to the department or agency within DoD that administers the majority of the Contractor's individual subcontracting plans. An example would be Defense Finance and Accounting Service or Missile Defense Agency.

(2) For DoD, the authority to acknowledge receipt or reject reports in eSRS is as follows:

(i) The authority to acknowledge receipt or reject the ISR resides with the contracting officer who receives it, as described in paragraph (f)(1)(i) of this clause.

(ii) Except as provided in (f)(2)(iii), the authority to acknowledge receipt or reject SSRs in eSRS resides with the SSR Coordinator at the department or agency that administers the majority of the Contractor's individual subcontracting plans.

(iii) The authority to acknowledge receipt or reject SSRs for construction and related maintenance and repair contracts resides with the SSR Coordinator for each department or agency.

(End of clause)

252.222-7006 RESTRICTIONS ON THE USE OF MANDATORY ARBITRATION AGREEMENTS (DEC 2010)

(a) Definitions. As used in this clause--

Covered subcontractor means any entity that has a subcontract valued in excess of \$1 million, except a subcontract for the acquisition of commercial items, including commercially available off-the-shelf items.

Subcontract means any contract, as defined in Federal Acquisition Regulation subpart 2.1, to furnish supplies or services for performance of this contract or a higher-tier subcontract thereunder.

(b) The Contractor--

(1) Agrees not to--

(i) Enter into any agreement with any of its employees or independent contractors that requires, as a condition of employment, that the employee or independent contractor agree to resolve through arbitration--

(A) Any claim under title VII of the Civil Rights Act of 1964; or

(B) Any tort related to or arising out of sexual assault or harassment, including assault and battery, intentional infliction of emotional distress, false imprisonment, or negligent hiring, supervision, or retention; or

(ii) Take any action to enforce any provision of an existing agreement with an employee or independent contractor that mandates that the employee or independent contractor resolve through arbitration--

(A) Any claim under title VII of the Civil Rights Act of 1964; or

(B) Any tort related to or arising out of sexual assault or harassment, including assault and battery, intentional infliction of emotional distress, false imprisonment, or negligent hiring, supervision, or retention; and

(2) Certifies, by signature of the contract, that it requires each covered subcontractor to agree not to enter into, and not to take any action to enforce, any provision of any existing agreements, as described in paragraph (b)(1) of this clause, with respect to any employee or independent contractor performing work related to such subcontract.

(c) The prohibitions of this clause do not apply with respect to a contractor's or subcontractor's agreements with employees or independent contractors that may not be enforced in a court of the United States.

(d) The Secretary of Defense may waive the applicability of the restrictions of paragraph (b) of this clause in accordance with Defense Federal Acquisition Regulation Supplement 222.7404.

(End of clause)

252.223-7004 DRUG-FREE WORK FORCE (SEP 1988)

(a) Definitions.

(1) "Employee in a sensitive position," as used in this clause, means an employee who has been granted access to classified information; or employees in other positions that the Contractor determines involve national security; health or safety, or functions other than the foregoing requiring a high degree of trust and confidence.

(2) "Illegal drugs," as used in this clause, means controlled substances included in Schedules I and II, as defined by section 802(6) of title 21 of the United States Code, the possession of which is unlawful under chapter 13 of that Title. The term "illegal drugs" does not mean the use of a controlled substance pursuant to a valid prescription or other uses authorized by law.

(b) The Contractor agrees to institute and maintain a program for achieving the objective of a drug-free work force. While this clause defines criteria for such a program, contractors are encouraged to implement alternative approaches comparable to the criteria in paragraph (c) that are designed to achieve the objectives of this clause.

(c) Contractor programs shall include the following, or appropriate alternatives:

(1) Employee assistance programs emphasizing high level direction, education, counseling, rehabilitation, and coordination with available community resources;

(2) Supervisory training to assist in identifying and addressing illegal drug use by Contractor employees;

(3) Provision for self-referrals as well as supervisory referrals to treatment with maximum respect for individual confidentiality consistent with safety and security issues;

(4) Provision for identifying illegal drug users, including testing on a controlled and carefully monitored basis. Employee drug testing programs shall be established taking account of the following:

(i) The Contractor shall establish a program that provides for testing for the use of illegal drugs by employees in sensitive positions. The extent of and criteria for such testing shall be determined by the Contractor based on considerations that include the nature of the work being performed under the contract, the employee's duties, and efficient use of Contractor resources, and the risks to health, safety, or national security that could result from the failure of an employee adequately to discharge his or her position.

(ii) In addition, the Contractor may establish a program for employee drug testing--

(A) When there is a reasonable suspicion that an employee uses illegal drugs; or

(B) When an employees has been involved in an accident or unsafe practice;

(C) As part of or as a follow-up to counseling or rehabilitation for illegal drug use;

(D) As part of a voluntary employee drug testing program.

(iii) The Contractor may establish a program to test applicants for employment for illegal drug use.

(iv) For the purpose of administering this clause, testing for illegal drugs may be limited to those substances for which testing is prescribed by section 2.1 of subpart B of the "Mandatory Guidelines for Federal Workplace Drug Testing Programs" (53 FR 11980 (April 11, 1988), issued by the Department of Health and Human Services.

(d) Contractors shall adopt appropriate personnel procedures to deal with employees who are found to be using drugs illegally. Contractors shall not allow any employee to remain on duty or perform in a sensitive position who is found to use illegal drugs until such times as the Contractor, in accordance with procedures established by the Contractor, determines that the employee may perform in such a position.

(e) The provisions of this clause pertaining to drug testing program shall not apply to the extent that are inconsistent with state or local law, or with an existing collective bargaining agreement; provided that with respect to the latter, the Contractor agrees those issues that are in conflict will be a subject of negotiation at the next collective bargaining session.

(End of clause)

252.223-7006 PROHIBITION ON STORAGE, TREATMENT, AND DISPOSAL OF TOXIC OR HAZARDOUS MATERIALS--BASIC (SEP 2014)

(a) Definitions. As used in this clause--

Storage means a non-transitory, semi-permanent or permanent holding, placement, or leaving of material. It does not include a temporary accumulation of a limited quantity of a material used in or a waste generated or resulting from authorized activities, such as servicing, maintenance, or repair of Department of Defense (DoD) items, equipment, or facilities.

Toxic or hazardous materials means--

(i) Materials referred to in section 101(14) of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980 (42 U.S.C. 9601(14)) and materials designated under section 102 of CERCLA (42 U.S.C. 9602) (40 CFR Part 302);

(ii) Materials that are of an explosive, flammable, or pyrotechnic nature; or

(iii) Materials otherwise identified by the Secretary of Defense as specified in DoD regulations.

(b) In accordance with 10 U.S.C. 2692, the Contractor is prohibited from storing, treating, or disposing of toxic or hazardous materials not owned by DoD on a DoD installation, except to the extent authorized by a statutory exception to 10 U.S.C. 2692 or as authorized by the Secretary of Defense. A charge may be assessed for any storage or disposal authorized under any of the exceptions to 10 U.S.C. 2692. If a charge is to be assessed, then such assessment shall be identified elsewhere in the contract with payment to the Government on a reimbursable cost basis.

(c) The Contractor shall include the substance of this clause, including this paragraph (c), in all subcontracts that require, may require, or permit a subcontractor access to a DoD installation, at any subcontract tier.

(End of clause)

252.223-7008 Prohibition of Hexavalent Chromium (JUN 2013)

(a) Definitions. As used in this clause--

Homogeneous material means a material that cannot be mechanically disjointed into different materials and is of uniform composition throughout.

(1) Examples of homogeneous materials include individual types of plastics, ceramics, glass, metals, alloys, paper, board, resins, and surface coatings.

(2) Homogeneous material does not include conversion coatings that chemically modify the substrate.

Mechanically disjointed means that the materials can, in principle, be separated by mechanical actions such as unscrewing, cutting, crushing, grinding, and abrasive processes.

(b) Prohibition.

(1) Unless otherwise specified by the Contracting Officer, the Contractor shall not provide any deliverable or construction material under this contract that--

(i) Contains hexavalent chromium in a concentration greater than 0.1 percent by weight in any homogenous material; or

(ii) Requires the removal or reapplication of hexavalent chromium materials during subsequent sustainment phases of the deliverable or construction material.

(2) This prohibition does not apply to hexavalent chromium produced as a by-product of manufacturing processes.

(c) If authorization for incorporation of hexavalent chromium in a deliverable or construction material is required, the Contractor shall submit a request to the Contracting Officer.

(d) Subcontracts. The Contractor shall include the substance of this clause, including this paragraph (d), in all subcontracts, including subcontracts for commercial items, that are for supplies, maintenance and repair services, or construction materials.

(End of clause)

[252.225-7012](#) PREFERENCE FOR CERTAIN DOMESTIC COMMODITIES (FEB 2013)

(a) Definitions. As used in this clause--

Component means any item supplied to the Government as part of an end product or of another component.

End product means supplies delivered under a line item of this contract.

Qualifying country means a country with a reciprocal defense procurement memorandum of understanding or international agreement with the United States in which both countries agree to remove barriers to purchases of supplies produced in the other country or services performed by sources of the other country, and the memorandum or agreement complies, where applicable, with the requirements of section 36 of the Arms Export Control Act (22 U.S.C. 2776) and with 10 U.S.C. 2457. Accordingly, the following are qualifying countries:

Australia
Austria
Belgium
Canada
Czech Republic
Denmark

Germany
Greece
Israel
Italy
Luxembourg
Netherlands
Norway
Poland
Portugal
Spain
Sweden
Switzerland
Turkey
United Kingdom of Great Britain and Northern Ireland.

Structural component of a tent--

(i) Means a component that contributes to the form and stability of the tent (e.g., poles, frames, flooring, guy ropes, pegs);

(ii) Does not include equipment such as heating, cooling, or lighting.

United States means the 50 States, the District of Columbia, and outlying areas.

U.S.-flag vessel means a vessel of the United States or belonging to the United States, including any vessel registered or having national status under the laws of the United States.

(b) The Contractor shall deliver under this contract only such of the following items, either as end products or components, that have been grown, reprocessed, reused, or produced in the United States:

(1) Food.

(2) Clothing and the materials and components thereof, other than sensors, electronics, or other items added to, and not normally associated with, clothing and the materials and components thereof. Clothing includes items such as outerwear, headwear, underwear, nightwear, footwear, hosiery, handwear, belts, badges, and insignia.

(3) (i) Tents and structural components of tents;

(ii) Tarpaulins; or

(iii) Covers.

(4) Cotton and other natural fiber products.

(5) Woven silk or woven silk blends.

(6) Spun silk yarn for cartridge cloth.

(7) Synthetic fabric, and coated synthetic fabric, including all textile fibers and yarns that are for use in such fabrics.

(8) Canvas products.

(9) Wool (whether in the form of fiber or yarn or contained in fabrics, materials, or manufactured articles).

(10) Any item of individual equipment (Federal Supply Class 8465) manufactured from or containing fibers, yarns, fabrics, or materials listed in this paragraph (b).

(c) This clause does not apply--

(1) To items listed in section 25.104(a) of the Federal Acquisition Regulation (FAR), or other items for which the Government has determined that a satisfactory quality and sufficient quantity cannot be acquired as and when needed at U.S. market prices;

(2) To incidental amounts of cotton, other natural fibers, or wool incorporated in an end product, for which the estimated value of the cotton, other natural fibers, or wool--

(i) Is not more than 10 percent of the total price of the end product; and (ii) Does not exceed the simplified acquisition threshold in FAR part 2;

(3) To waste and byproducts of cotton or wool fiber for use in the production of propellants and explosives;

(4) To foods, other than fish, shellfish, or seafood, that have been manufactured or processed in the United States, regardless of where the foods (and any component if applicable) were grown or produced. Fish, shellfish, or seafood manufactured or processed in the United States and fish, shellfish, or seafood contained in foods manufactured or processed in the United States shall be provided in accordance with paragraph (d) of this clause;

(5) To chemical warfare protective clothing produced in a qualifying country; or

(6) To fibers and yarns that are for use in synthetic fabric or coated synthetic fabric (but does apply to the synthetic or coated synthetic fabric itself), if--

(i) The fabric is to be used as a component of an end product that is not a textile product. Examples of textile products, made in whole or in part of fabric, include--

(A) Draperies, floor coverings, furnishings, and bedding (Federal Supply Group 72, Household and Commercial Furnishings and Appliances);

(B) Items made in whole or in part of fabric in Federal Supply Group 83, Textile/leather/furs/apparel/findings/tents/flags, or Federal Supply Group 84, Clothing, Individual Equipment and Insignia;

(C) Upholstered seats (whether for household, office, or other use); and

(D) Parachutes (Federal Supply Class 1670); or

(ii) The fibers and yarns are para-aramid fibers and continuous filament para-aramid yarns manufactured in a qualifying country.

(d)(1) Fish, shellfish, and seafood delivered under this contract, or contained in foods delivered under this contract--

(i) Shall be taken from the sea by U.S.-flag vessels; or

(ii) If not taken from the sea, shall be obtained from fishing within the United States; and

(2) Any processing or manufacturing of the fish, shellfish, or seafood shall be performed on a U.S.-flag vessel or in the United States.

(End of clause)

252.225-7048 Export-Controlled Items (June 2013)

(a) Definition. "Export-controlled items," as used in this clause, means items subject to the Export Administration Regulations (EAR) (15 CFR Parts 730-774) or the International Traffic in Arms Regulations (ITAR) (22 CFR Parts 120-130). The term includes--

(1) "Defense items," defined in the Arms Export Control Act, 22 U.S.C. 2778(j)(4)(A), as defense articles, defense services, and related technical data, and further defined in the ITAR, 22 CFR Part 120; and

(2) "Items," defined in the EAR as "commodities", "software", and "technology," terms that are also defined in the EAR, 15 CFR 772.1.

(b) The Contractor shall comply with all applicable laws and regulations regarding export-controlled items, including, but not limited to, the requirement for contractors to register with the Department of State in accordance with the ITAR. The Contractor shall consult with the Department of State regarding any questions relating to compliance with the ITAR and shall consult with the Department of Commerce regarding any questions relating to compliance with the EAR.

(c) The Contractor's responsibility to comply with all applicable laws and regulations regarding export-controlled items exists independent of, and is not established or limited by, the information provided by this clause.

(d) Nothing in the terms of this contract adds, changes, supersedes, or waives any of the requirements of applicable Federal laws, Executive orders, and regulations, including but not limited to—

(1) The Export Administration Act of 1979, as amended (50 U.S.C. App. 2401, et seq.);

(2) The Arms Export Control Act (22 U.S.C. 2751, et seq.);

(3) The International Emergency Economic Powers Act (50 U.S.C. 1701, et seq.);

(4) The Export Administration Regulations (15 CFR Parts 730-774);

(5) The International Traffic in Arms Regulations (22 CFR Parts 120-130); and

(6) Executive Order 13222, as extended.

(e) The Contractor shall include the substance of this clause, including this paragraph (e), in all subcontracts.

(End of clause)

252.227-7000 Non-estoppel. (OCT 1966)

The Government reserves the right at any time to contest the enforceability, validity, scope of, or the title to any patent or patent application herein licensed without waiving or forfeiting any right under this contract.

(End of clause)

252.232-7003 Electronic Submission of Payment Requests and Receiving Reports.

(a) Definitions. As used in this clause—

(1) “Contract financing payment” and “invoice payment” have the meanings given in section 32.001 of the Federal Acquisition Regulation.

(2) “Electronic form” means any automated system that transmits information electronically from the initiating system to all affected systems. Facsimile, e-mail, and scanned documents are not acceptable electronic forms for submission of payment requests. However, scanned documents are acceptable when they are part of a submission of a payment request made using Wide Area WorkFlow (WAWF) or another electronic form authorized by the Contracting Officer.

(3) “Payment request” means any request for contract financing payment or invoice payment submitted by the Contractor under this contract.

(4) “Receiving report” means the data required by the clause at 252.246-7000, Material Inspection and Receiving Report.

(b) Except as provided in paragraph (c) of this clause, the Contractor shall submit payment requests and receiving reports using WAWF, in one of the following electronic formats that WAWF accepts: Electronic Data Interchange, Secure File Transfer Protocol, or World Wide Web input. Information regarding WAWF is available on the Internet at <https://wawf.eb.mil/>.

(c) The Contractor may submit a payment request and receiving report using other than WAWF only when—

(1) The Contracting Officer administering the contract for payment has determined, in writing, that electronic submission would be unduly burdensome to the Contractor. In such cases, the Contractor shall include a copy of the Contracting Officer’s determination with each request for payment;

(2) DoD makes payment for commercial transportation services provided under a Government rate tender or a contract for transportation services using a DoD-approved electronic third party payment system or other exempted vendor payment/invoicing system (e.g., PowerTrack, Transportation Financial Management System, and Cargo and Billing System);

(3) DoD makes payment for rendered health care services using the TRICARE Encounter Data System (TEDS) as the electronic format; or

(4) When the Governmentwide commercial purchase card is used as the method of payment, only submission of the receiving report in electronic form is required.

(d) The Contractor shall submit any non-electronic payment requests using the method or methods specified in Section G of the contract.

(e) In addition to the requirements of this clause, the Contractor shall meet the requirements of the appropriate payment clauses in this contract when submitting payment requests.

(End of clause)

252.232-7010 LEVIES ON CONTRACT PAYMENTS (DEC 2006)

(a) 26 U.S.C. 6331(h) authorizes the Internal Revenue Service (IRS) to continuously levy up to 100 percent of contract payments, up to the amount of tax debt.

(b) When a levy is imposed on a payment under this contract and the Contractor believes that the levy may result in an inability to perform the contract, the Contractor shall promptly notify the Procuring Contracting Officer in writing, with a copy to the Administrative Contracting Officer, and shall provide--

(1) The total dollar amount of the levy;

(2) A statement that the Contractor believes that the levy may result in an inability to perform the contract, including rationale and adequate supporting documentation; and

(3) Advice as to whether the inability to perform may adversely affect national security, including rationale and adequate supporting documentation.

(c) DoD shall promptly review the Contractor's assessment, and the Procuring Contracting Officer shall provide a written notification to the Contractor including--

(1) A statement as to whether DoD agrees that the levy may result in an inability to perform the contract; and

(2)(i) If the levy may result in an inability to perform the contract and the lack of performance will adversely affect national security, the total amount of the monies collected that should be returned to the Contractor; or

(ii) If the levy may result in an inability to perform the contract but will not impact national security, a recommendation that the Contractor promptly notify the IRS to attempt to resolve the tax situation.

(d) Any DoD determination under this clause is not subject to appeal under the Contract Disputes Act.

(End of clause)

252.236-7000 MODIFICATION PROPOSALS - PRICE BREAKDOWN. (DEC 1991)

(a) The Contractor shall furnish a price breakdown, itemized as required and within the time specified by the Contracting Officer, with any proposal for a contract modification.

(b) The price breakdown --

(1) Must include sufficient detail to permit an analysis of profit, and of all costs for --

(i) Material;

(ii) Labor;

(iii) Equipment;

(iv) Subcontracts; and

(v) Overhead; and

(2) Must cover all work involved in the modification, whether the work was deleted, added, or changed.

(c) The Contractor shall provide similar price breakdowns to support any amounts claimed for subcontracts.

(d) The Contractor's proposal shall include a justification for any time extension proposed.

252.236-7001 CONTRACT DRAWINGS AND SPECIFICATIONS (AUG 2000)

(a) The Government will provide to the Contractor, without charge, one set of contract drawings and specifications, except publications incorporated into the technical provisions by reference, in electronic or paper media as chosen by the Contracting Officer.

(b) The Contractor shall--

- (1) Check all drawings furnished immediately upon receipt;
- (2) Compare all drawings and verify the figures before laying out the work;
- (3) Promptly notify the Contracting Officer of any discrepancies;
- (4) Be responsible for any errors that might have been avoided by complying with this paragraph (b); and
- (5) Reproduce and print contract drawings and specifications as needed.

(c) In general--

- (1) Large-scale drawings shall govern small-scale drawings; and
- (2) The Contractor shall follow figures marked on drawings in preference to scale measurements.

(d) Omissions from the drawings or specifications or the misdescription of details of work that are manifestly necessary to carry out the intent of the drawings and specifications, or that are customarily performed, shall not relieve the Contractor from performing such omitted or misdescribed details of the work. The Contractor shall perform such details as if fully and correctly set forth and described in the drawings and specifications.

(e) The work shall conform to the specifications and the contract drawings identified on the following index of drawings:

(End of clause)

252.236-7002 OBSTRUCTION OF NAVIGABLE WATERWAYS. (DEC 1991)

(a) The Contractor shall --

- (1) Promptly recover and remove any material, plant, machinery, or appliance which the contractor loses, dumps, throws overboard, sinks, or misplaces, and which, in the opinion of the Contracting Officer, may be dangerous to or obstruct navigation;
- (2) Give immediate notice, with description and locations of any such obstructions, to the Contracting Officer; and
- (3) When required by the Contracting Officer, mark or buoy such obstructions until the same are removed.

(b) The Contracting Officer may --

- (1) Remove the obstructions by contract or otherwise should the Contractor refuse, neglect, or delay compliance with paragraph (a) of this clause; and
- (2) Deduct the cost of removal from any monies due or to become due to the Contractor; or
- (3) Recover the cost of removal under the Contractor's bond.

(c) The Contractor's liability for the removal of a vessel wrecked or sunk without fault or negligence is limited to that provided in sections 15, 19, and 20 of the River and Harbor Act of March 3, 1899 (33 U.S.C. 410 et. seq.).

252.236-7004 PAYMENT FOR MOBILIZATION AND DEMOBILIZATION (DEC 1991)

(a) The Government will pay all costs for the mobilization and demobilization of all of the Contractor's plant and equipment at the contract lump sum price for this item.

(1) **Sixty (60%)** percent of the lump sum price upon completion of the contractor's mobilization at the work site.

(2) The remaining **Forty (40%)** percent upon completion of demobilization.

(b) The Contracting Officer may require the Contractor to furnish cost data to justify this portion of the bid if the Contracting Officer believes that the percentages in paragraphs (a) (1) and (2) of this clause do not bear a reasonable relation to the cost of the work in this contract.

(1) Failure to justify such price to the satisfaction of the Contracting Officer will result in payment, as determined by the Contracting Officer, of --

(i) Actual mobilization costs at completion of mobilization;

(ii) Actual demobilization costs at completion of demobilization; and

(iii) The remainder of this item in the final payment under this contract.

(2) The Contracting Officer's determination of the actual costs in paragraph (b)(1) of this clause is not subject to appeal.

252.236-7008 CONTRACT PRICES - BIDDING SCHEDULES. (DEC 1991)

(a) The Government's payment for the items listed in the Bidding Schedule shall constitute full compensation to the Contractor for --

(1) Furnishing all plant, labor, equipment, appliances, and materials; and

(2) Performing all operations required to complete the work in conformity with the drawings and specifications.

(b) The Contractor shall include in the prices for the items listed in the Bidding Schedule all costs for work in the specifications, whether or not specifically listed in the Bidding Schedule.

252.242-7004 MATERIAL MANAGEMENT AND ACCOUNTING SYSTEM (MAY 2011)

(a) Definitions. As used in this clause--

(1) Material management and accounting system (MMAS) means the Contractor's system or systems for planning, controlling, and accounting for the acquisition, use, issuing, and disposition of material. Material management and accounting systems may be manual or automated. They may be stand-alone systems or they may be integrated with planning, engineering, estimating, purchasing, inventory, accounting, or other systems.

(2) Valid time-phased requirements means material that is--

(i) Needed to fulfill the production plan, including reasonable quantities for scrap, shrinkage, yield, etc.; and

(ii) Charged/billed to contracts or other cost objectives in a manner consistent with the need to fulfill the production plan.

(3) Contractor means a business unit as defined in section 31.001 of the Federal Acquisition Regulation (FAR).

(4) Acceptable material management and accounting system means a MMAS that generally complies with the system criteria in paragraph (d) of this clause.

(5) Significant deficiency means a shortcoming in the system that materially affects the ability of officials of the Department of Defense to rely upon information produced by the system that is needed for management purposes.

(b) General. The Contractor shall--

(1) Maintain an MMAS that--

(i) Reasonably forecasts material requirements;

(ii) Ensures that costs of purchased and fabricated material charged or allocated to a contract are based on valid time-phased requirements; and

(iii) Maintains a consistent, equitable, and unbiased logic for costing of material transactions; and

(2) Assess its MMAS and take reasonable action to comply with the MMAS standards in paragraph (e) of this clause.

(c) Disclosure and maintenance requirements. The Contractor shall--

(1) Have policies, procedures, and operating instructions that adequately describe its MMAS;

(2) Provide to the Administrative Contracting Officer (ACO), upon request, the results of internal reviews that it has conducted to ensure compliance with established MMAS policies, procedures, and operating instructions; and

(3) Disclose significant changes in its MMAS to the ACO at least 30 days prior to implementation.

(d) System criteria. The MMAS shall have adequate internal controls to ensure system and data integrity, and shall--

(1) Have an adequate system description including policies, procedures, and operating instructions that comply with the Federal Acquisition Regulation and Defense Federal Acquisition Regulation Supplement;

(2) Ensure that costs of purchased and fabricated material charged or allocated to a contract are based on valid time-phased requirements as impacted by minimum/economic order quantity restrictions.

(i) A 98 percent bill of material accuracy and a 95 percent master production schedule accuracy are desirable as a goal in order to ensure that requirements are both valid and appropriately time-phased.

(ii) If systems have accuracy levels below these, the Contractor shall provide adequate evidence that--

(A) There is no material harm to the Government due to lower accuracy levels; and

(B) The cost to meet the accuracy goals is excessive in relation to the impact on the Government;

(3) Provide a mechanism to identify, report, and resolve system control weaknesses and manual override. Systems should identify operational exceptions, such as excess/residual inventory, as soon as known;

(4) Provide audit trails and maintain records (manual and those in machine-readable form) necessary to evaluate system logic and to verify through transaction testing that the system is operating as desired;

(5) Establish and maintain adequate levels of record accuracy, and include reconciliation of recorded inventory quantities to physical inventory by part number on a periodic basis. A 95 percent accuracy level is desirable. If systems have an accuracy level below 95 percent, the Contractor shall provide adequate evidence that--

(i) There is no material harm to the Government due to lower accuracy levels; and

(ii) The cost to meet the accuracy goal is excessive in relation to the impact on the Government;

(6) Provide detailed descriptions of circumstances that will result in manual or system generated transfers of parts;

(7) Maintain a consistent, equitable, and unbiased logic for costing of material transactions as follows:

(i) The Contractor shall maintain and disclose written policies describing the transfer methodology and the loan/pay-back technique.

(ii) The costing methodology may be standard or actual cost, or any of the inventory costing methods in 48 CFR 9904.411-50(b). The Contractor shall maintain consistency across all contract and customer types, and from accounting period to accounting period for initial charging and transfer charging.

(iii) The system should transfer parts and associated costs within the same billing period. In the few instances where this may not be appropriate, the Contractor may accomplish the material transaction using a loan/pay-back technique. The "loan/pay-back technique" means that the physical part is moved temporarily from the contract, but the cost of the part remains on the contract. The procedures for the loan/pay-back technique must be approved by the ACO. When the technique is used, the Contractor shall have controls to ensure--

(A) Parts are paid back expeditiously;

(B) Procedures and controls are in place to correct any overbilling that might occur;

(C) Monthly, at a minimum, identification of the borrowing contract and the date the part was borrowed; and

(D) The cost of the replacement part is charged to the borrowing contract;

(8) Where allocations from common inventory accounts are used, have controls (in addition to those in paragraphs (d)(2) and (7) of this clause) to ensure that--

(i) Reallocations and any credit due are processed no less frequently than the routine billing cycle;

(ii) Inventories retained for requirements that are not under contract are not allocated to contracts; and

(iii) Algorithms are maintained based on valid and current data;

(9) Have adequate controls to ensure that physically commingled inventories that may include material for which costs are charged or allocated to fixed-price, cost-reimbursement, and commercial contracts do not compromise requirements of any of the standards in paragraphs (d)(1) through (8) of this clause. Government-furnished material shall not be--

(i) Physically commingled with other material; or

(ii) Used on commercial work; and

(10) Be subjected to periodic internal reviews to ensure compliance with established policies and procedures.

(e) Significant deficiencies.

(1) The Contracting Officer will provide an initial determination to the Contractor, in writing, of any significant deficiencies. The initial determination will describe the deficiency in sufficient detail to allow the Contractor to understand the deficiency.

(2) The Contractor shall respond within 30 days to a written initial determination from the Contracting Officer that identifies significant deficiencies in the Contractor's MMAS. If the Contractor disagrees with the initial determination, the Contractor shall state, in writing, its rationale for disagreeing.

(3) The Contracting Officer will evaluate the Contractor's response and notify the Contractor, in writing, of the Contracting Officer's final determination concerning--

(i) Remaining significant deficiencies;

(ii) The adequacy of any proposed or completed corrective action; and

(iii) System disapproval if the Contracting Officer determines that one or more significant deficiencies remain.

(f) If the Contractor receives the Contracting Officer's final determination of significant deficiencies, the Contractor

shall, within 45 days of receipt of the final determination, either correct the significant deficiencies or submit an acceptable corrective action plan showing milestones and actions to eliminate the significant deficiencies.

(g) Withholding payments. If the Contracting Officer makes a final determination to disapprove the Contractor's MMAS, and the contract includes the clause at 252.242-7005, Contractor Business Systems, the Contracting Officer will withhold payments in accordance with that clause.

(End of clause)

252.242-7005 Contractor Business Systems.

(a) This clause only applies to covered contracts that are subject to the Cost Accounting Standards under 41 U.S.C. chapter 15, as implemented in regulations found at 48 CFR 9903.201-1 (see the FAR Appendix).

(b) Definitions. As used in this clause—

“Acceptable contractor business systems” means contractor business systems that comply with the terms and conditions of the applicable business system clauses listed in the definition of "contractor business systems" in this clause.

“Contractor business systems” means—

(1) Accounting system, if this contract includes the clause at 252.242-7006, Accounting System Administration;

(2) Earned value management system, if this contract includes the clause at 252.234-7002, Earned Value Management System;

(3) Estimating system, if this contract includes the clause at 252.215-7002, Cost Estimating System Requirements;

(4) Material management and accounting system, if this contract includes the clause at 252.242-7004, Material

(5) Property management system, if this contract includes the clause at 252.245-7003, Contractor Property Management System Administration; and

(6) Purchasing system, if this contract includes the clause at 252.244-7001, Contractor Purchasing System Administration.

“Significant deficiency,” in the case of a contractor business system, means a shortcoming in the system that materially affects the ability of officials of the Department of Defense to rely upon information produced by the system that is needed for management purposes.

(c) General. The Contractor shall establish and maintain acceptable business systems in accordance with the terms and conditions of this contract.

(d) Significant deficiencies. (1) The Contractor shall respond, in writing, within 30 days to an initial determination that there are one or more significant deficiencies in one or more of the Contractor’s business systems.

(2) The Contracting Officer will evaluate the Contractor's response and notify the Contractor, in writing, of the final determination as to whether the Contractor’s business system contains significant deficiencies. If the Contracting Officer determines that the Contractor’s business system contains significant deficiencies, the final determination will include a notice to withhold payments.

(e) Withholding payments. (1) If the Contracting Officer issues the final determination with a notice to withhold payments for significant deficiencies in a contractor business system required under this contract, the Contracting Officer will withhold five percent of amounts due from progress payments and performance-based payments, and direct the Contractor, in writing, to withhold five percent from its billings on interim cost vouchers on cost-reimbursement, labor-hour, and time-and-materials contracts until the Contracting Officer has determined that the Contractor has corrected all significant deficiencies as directed by the Contracting Officer’s final determination. The Contractor shall, within 45 days of receipt of the notice, either correct the deficiencies or submit an acceptable corrective action plan showing milestones and actions to eliminate the deficiencies.

(2) If the Contractor submits an acceptable corrective action plan within 45 days of receipt of a notice of the Contracting Officer’s intent to withhold payments, and the Contracting Officer, in consultation with the auditor or functional specialist, determines that the Contractor is effectively implementing such plan, the Contracting Officer will reduce withholding directly related to the significant deficiencies covered under the corrective action plan, to two percent from progress payments and performance-based payments, and direct the Contractor, in writing, to reduce the percentage withheld on interim cost vouchers to two percent until the Contracting Officer determines the Contractor has corrected all significant deficiencies as directed by the Contracting Officer’s final determination. However, if at any time, the Contracting Officer determines that the Contractor has failed to follow the accepted corrective action plan, the Contracting Officer will increase withholding from progress payments and performance-based payments, and direct the Contractor, in writing, to increase the percentage withheld on interim cost vouchers to the percentage initially withheld, until the Contracting Officer determines that the Contractor has corrected all significant deficiencies as directed by the Contracting Officer’s final determination.

(3) Payment withhold percentage limits.

(i) The total percentage of payments withheld on amounts due under each progress payment, performance-based payment, or interim cost voucher, on this contract shall not exceed--

(A) Five percent for one or more significant deficiencies in any single contractor business system; and

(B) Ten percent for significant deficiencies in multiple contractor business systems.

(ii) If this contract contains pre-existing withholds, and the application of any subsequent payment withholds will

cause withholding under this clause to exceed the payment withhold percentage limits in paragraph (e)(3)(i) of this clause, the Contracting Officer will reduce the payment withhold percentage in the final determination to an amount that will not exceed the payment withhold percentage limits.

(4) For the purpose of this clause, payment means any of the following payments authorized under this contract:

(i) Interim payments under—

(A) Cost-reimbursement contracts;

(B) Incentive type contracts;

(C) Time-and-materials contracts;

(D) Labor-hour contracts.

(ii) Progress payments.

(iii) Performance-based payments.

(5) Payment withholding shall not apply to payments on fixed-price line items where performance is complete and the items were accepted by the Government.

(6) The withholding of any amount or subsequent payment to the Contractor shall not be construed as a waiver of any rights or remedies the Government has under this contract.

(7) Notwithstanding the provisions of any clause in this contract providing for interim, partial, or other payment withholding on any basis, the Contracting Officer may withhold payment in accordance with the provisions of this clause.

(8) The payment withholding authorized in this clause is not subject to the interest-penalty provisions of the Prompt Payment Act.

(f) Correction of deficiencies. (1) The Contractor shall notify the Contracting Officer, in writing, when the Contractor has corrected the business system's deficiencies.

(2) Once the Contractor has notified the Contracting Officer that all deficiencies have been corrected, the Contracting Officer will take one of the following actions:

(i) If the Contracting Officer determines that the Contractor has corrected all significant deficiencies as directed by the Contracting Officer's final determination, the Contracting Officer will, as appropriate, discontinue the withholding of progress payments and performance-based payments, and direct the Contractor, in writing, to discontinue the payment withholding from billings on interim cost vouchers under this contract associated with the Contracting Officer's final determination, and authorize the Contractor to bill for any monies previously withheld that are not also being withheld due to other significant deficiencies. Any payment withholding under this contract due to other significant deficiencies, will remain in effect until the Contracting Officer determines that those significant deficiencies are corrected.

(ii) If the Contracting Officer determines that the Contractor still has significant deficiencies, the Contracting Officer will continue the withholding of progress payments and performance-based payments, and the Contractor shall continue withholding amounts from its billings on interim cost vouchers in accordance with paragraph (e) of this clause, and not bill for any monies previously withheld.

(iii) If the Contracting Officer determines, based on the evidence submitted by the Contractor, that there is a reasonable expectation that the corrective actions have been implemented and are expected to correct the significant

deficiencies, the Contracting Officer will discontinue withholding payments, and release any payments previously withheld directly related to the significant deficiencies identified in the Contractor notification, and direct the Contractor, in writing, to discontinue the payment withholding from billings on interim cost vouchers associated with the Contracting Officer's final determination, and authorize the Contractor to bill for any monies previously withheld.

(iv) If, within 90 days of receipt of the Contractor notification that the Contractor has corrected the significant deficiencies, the Contracting Officer has not made a determination in accordance with paragraphs (f)(2)(i), (ii), or (iii) of this clause, the Contracting Officer will reduce withholding directly related to the significant deficiencies identified in the Contractor notification by at least 50 percent of the amount being withheld from progress payments and performance-based payments, and direct the Contractor, in writing, to reduce the payment withholding from billings on interim cost vouchers directly related to the significant deficiencies identified in the Contractor notification by a specified percentage that is at least 50 percent, but not authorize the Contractor to bill for any monies previously withheld until the Contracting Officer makes a determination in accordance with paragraphs (f)(2)(i), (ii), or (iii) of this clause.

(v) At any time after the Contracting Officer reduces or discontinues the withholding of progress payments and performance-based payments, or directs the Contractor to reduce or discontinue the payment withholding from billings on interim cost vouchers under this contract, if the Contracting Officer determines that the Contractor has failed to correct the significant deficiencies identified in the Contractor's notification, the Contracting Officer will reinstate or increase withholding from progress payments and performance-based payments, and direct the Contractor, in writing, to reinstate or increase the percentage withheld on interim cost vouchers to the percentage initially withheld, until the Contracting Officer determines that the Contractor has corrected all significant deficiencies as directed by the Contracting Officer's final determination.

(End of clause)

252.242-7006 ACCOUNTING SYSTEM ADMINISTRATION (FEB 2012)

(a) Definitions. As used in this clause--

(1) Acceptable accounting system means a system that complies with the system criteria in paragraph (c) of this clause to provide reasonable assurance that--

(i) Applicable laws and regulations are complied with;

(ii) The accounting system and cost data are reliable;

(iii) Risk of misallocations and mischarges are minimized; and

(iv) Contract allocations and charges are consistent with billing procedures.

(2) Accounting system means the Contractor's system or systems for accounting methods, procedures, and controls established to gather, record, classify, analyze, summarize, interpret, and present accurate and timely financial data for reporting in compliance with applicable laws, regulations, and management decisions, and may include subsystems for specific areas such as indirect and other direct costs, compensation, billing, labor, and general information technology.

(3) Significant deficiency means a shortcoming in the system that materially affects the ability of officials of the Department of Defense to rely upon information produced by the system that is needed for management purposes.

(b) General. The Contractor shall establish and maintain an acceptable accounting system. Failure to maintain an acceptable accounting system, as defined in this clause, shall result in the withholding of payments if the contract includes the clause at 252.242-7005, Contractor Business Systems, and also may result in disapproval of the system.

(c) System criteria. The Contractor's accounting system shall provide for--

- (1) A sound internal control environment, accounting framework, and organizational structure;
- (2) Proper segregation of direct costs from indirect costs;
- (3) Identification and accumulation of direct costs by contract;
- (4) A logical and consistent method for the accumulation and allocation of indirect costs to intermediate and final cost objectives;
- (5) Accumulation of costs under general ledger control;
- (6) Reconciliation of subsidiary cost ledgers and cost objectives to general ledger;
- (7) Approval and documentation of adjusting entries;
- (8) Management reviews or internal audits of the system to ensure compliance with the Contractor's established policies, procedures, and accounting practices;
- (9) A timekeeping system that identifies employees' labor by intermediate or final cost objectives;
- (10) A labor distribution system that charges direct and indirect labor to the appropriate cost objectives;
- (11) Interim (at least monthly) determination of costs charged to a contract through routine posting of books of account;
- (12) Exclusion from costs charged to Government contracts of amounts which are not allowable in terms of Federal Acquisition Regulation (FAR) part 31, Contract Cost Principles and Procedures, and other contract provisions;
- (13) Identification of costs by contract line item and by units (as if each unit or line item were a separate contract), if required by the contract;
- (14) Segregation of preproduction costs from production costs, as applicable;
- (15) Cost accounting information, as required--
 - (i) By contract clauses concerning limitation of cost (FAR 52.232-20), limitation of funds (FAR 52.232-22), or allowable cost and payment (FAR 52.216-7); and
 - (ii) To readily calculate indirect cost rates from the books of accounts;
- (16) Billings that can be reconciled to the cost accounts for both current and cumulative amounts claimed and comply with contract terms;
- (17) Adequate, reliable data for use in pricing follow-on acquisitions; and
- (18) Accounting practices in accordance with standards promulgated by the Cost Accounting Standards Board, if applicable, otherwise, Generally Accepted Accounting Principles.

(1) The Contracting Officer will provide an initial determination to the Contractor, in writing, on any significant deficiencies. The initial determination will describe the deficiency in sufficient detail to allow the Contractor to understand the deficiency.

(2) The Contractor shall respond within 30 days to a written initial determination from the Contracting Officer that identifies significant deficiencies in the Contractor's accounting system. If the Contractor disagrees with the initial determination, the Contractor shall state, in writing, its rationale for disagreeing.

(3) The Contracting Officer will evaluate the Contractor's response and notify the Contractor, in writing, of the Contracting Officer's final determination concerning--

(i) Remaining significant deficiencies;

(ii) The adequacy of any proposed or completed corrective action; and

(iii) System disapproval, if the Contracting Officer determines that one or more significant deficiencies remain.

(e) If the Contractor receives the Contracting Officer's final determination of significant deficiencies, the Contractor shall, within 45 days of receipt of the final determination, either correct the significant deficiencies or submit an acceptable corrective action plan showing milestones and actions to eliminate the significant deficiencies.

(f) Withholding payments. If the Contracting Officer makes a final determination to disapprove the Contractor's accounting system, and the contract includes the clause at 252.242-7005, Contractor Business Systems, the Contracting Officer will withhold payments in accordance with that clause.

(End of clause)

252.243-7001 PRICING OF CONTRACT MODIFICATIONS (DEC 1991)

When costs are a factor in any price adjustment under this contract, the contract cost principles and procedures in FAR part 31 and DFARS part 231, in effect on the date of this contract, apply.

(End of clause)

252.243-7002 REQUESTS FOR EQUITABLE ADJUSTMENT (DEC 2012)

(a) The amount of any request for equitable adjustment to contract terms shall accurately reflect the contract adjustment for which the Contractor believes the Government is liable. The request shall include only costs for performing the change, and shall not include any costs that already have been reimbursed or that have been separately claimed. All indirect costs included in the request shall be properly allocable to the change in accordance with applicable acquisition regulations.

(b) In accordance with 10 U.S.C. 2410(a), any request for equitable adjustment to contract terms that exceeds the simplified acquisition threshold shall bear, at the time of submission, the following certificate executed by an individual authorized to certify the request on behalf of the Contractor:

I certify that the request is made in good faith, and that the supporting data are accurate and complete to the best of my knowledge and belief.

(Title)

(c) The certification in paragraph (b) of this clause requires full disclosure of all relevant facts, including--

(1) Certified cost or pricing data if required in accordance with subsection 15.403-4 of the Federal Acquisition Regulation (FAR); and

(2) Data other than certified cost or pricing data, in accordance with subsection 15.403-3 of the FAR, including actual cost data and data to support any estimated costs, even if certified cost or pricing data are not required.

(d) The certification requirement in paragraph (b) of this clause does not apply to----

(1) Requests for routine contract payments; for example, requests for payment for accepted supplies and services, routine vouchers under a cost-reimbursement type contract, or progress payment invoices; or

(2) Final adjustment under an incentive provision of the contract.

252.244-7000 SUBCONTRACTS FOR COMMERCIAL ITEMS (JUN 2013)

(a) The Contractor is not required to flow down the terms of any Defense Federal Acquisition Regulation Supplement (DFARS) clause in subcontracts for commercial items at any tier under this contract, unless so specified in the particular clause.

(b) While not required, the Contractor may flow down to subcontracts for commercial items a minimal number of additional clauses necessary to satisfy its contractual obligation.

(c) The Contractor shall include the terms of this clause, including this paragraph (c), in subcontracts awarded under this contract, including subcontracts for the acquisition of commercial items.

(End of clause)

252.247-7023 TRANSPORTATION OF SUPPLIES BY SEA (APR 2014)

(a) Definitions. As used in this clause --

"Components" means articles, materials, and supplies incorporated directly into end products at any level of manufacture, fabrication, or assembly by the Contractor or any subcontractor.

"Department of Defense" (DoD) means the Army, Navy, Air Force, Marine Corps, and defense agencies.

"Foreign-flag vessel" means any vessel that is not a U.S.-flag vessel.

"Ocean transportation" means any transportation aboard a ship, vessel, boat, barge, or ferry through international waters.

"Subcontractor" means a supplier, materialman, distributor, or vendor at any level below the prime contractor whose contractual obligation to perform results from, or is conditioned upon, award of the prime contract and who is performing any part of the work or other requirement of the prime contract.

"Supplies" means all property, except land and interests in land, that is clearly identifiable for eventual use by or owned by the DoD at the time of transportation by sea.

(i) An item is clearly identifiable for eventual use by the DoD if, for example, the contract documentation contains a reference to a DoD contract number or a military destination.

(ii) "Supplies" includes (but is not limited to) public works; buildings and facilities; ships; floating equipment and vessels of every character, type, and description, with parts, subassemblies, accessories, and equipment; machine tools; material; equipment; stores of all kinds; end items; construction materials; and components of the foregoing.

"U.S.-flag vessel" means a vessel of the United States or belonging to the United States, including any vessel registered or having national status under the laws of the United States.

(b)(1) The Contractor shall use U.S.-flag vessels when transporting any supplies by sea under this contract.

(2) A subcontractor transporting supplies by sea under this contract shall use U.S.-flag vessels if--

(i) This contract is a construction contract; or

(ii) The supplies being transported are--

(A) Noncommercial items; or

(B) Commercial items that--

(1) The Contractor is reselling or distributing to the Government without adding value (generally, the Contractor does not add value to items that it contracts for f.o.b. destination shipment);

(2) Are shipped in direct support of U.S. military contingency operations, exercises, or forces deployed in humanitarian or peacekeeping operations; or

(3) Are commissary or exchange cargoes transported outside of the Defense Transportation System in accordance with 10 U.S.C. 2643.

(c) The Contractor and its subcontractors may request that the Contracting Officer authorize shipment in foreign-flag vessels, or designate available U.S.-flag vessels, if the Contractor or a subcontractor believes that --

(1) U.S.-flag vessels are not available for timely shipment;

(2) The freight charges are inordinately excessive or unreasonable; or

(3) Freight charges are higher than charges to private persons for transportation of like goods.

(d) The Contractor must submit any request for use of foreign-flag vessels in writing to the Contracting Officer at least 45 days prior to the sailing date necessary to meet its delivery schedules. The Contracting Officer will process requests submitted after such date(s) as expeditiously as possible, but the Contracting Officer's failure to grant approvals to meet the shipper's sailing date will not of itself constitute a compensable delay under this or any other clause of this contract. Requests shall contain at a minimum --

(1) Type, weight, and cube of cargo;

(2) Required shipping date;

(3) Special handling and discharge requirements;

(4) Loading and discharge points;

(5) Name of shipper and consignee;

(6) Prime contract number; and

(7) A documented description of efforts made to secure U.S.-flag vessels, including points of contact (with names and telephone numbers) with at least two U.S.-flag carriers contacted. Copies of telephone notes, telegraphic and facsimile message or letters will be sufficient for this purpose.

(e) The Contractor shall, within 30 days after each shipment covered by this clause, provide the Contracting Officer and the Maritime Administration, Office of Cargo Preference, U.S. Department of Transportation, 400 Seventh Street SW., Washington, DC 20590, one copy of the rated on board vessel operating carrier's ocean bill of lading, which shall contain the following information:

(1) Prime contract number;

(2) Name of vessel;

(3) Vessel flag of registry;

(4) Date of loading;

(5) Port of loading;

(6) Port of final discharge;

(7) Description of commodity;

(8) Gross weight in pounds and cubic feet if available;

(9) Total ocean freight in U.S. dollars; and

(10) Name of the steamship company.

(f) If this contract exceeds the simplified acquisition threshold, the Contractor shall provide with its final invoice under this contract a representation that to the best of its knowledge and belief--

(1) No ocean transportation was used in the performance of this contract;

(2) Ocean transportation was used and only U.S.-flag vessels were used for all ocean shipments under the contract;

(3) Ocean transportation was used, and the Contractor had the written consent of the Contracting Officer for all foreign-flag ocean transportation; or

(4) Ocean transportation was used and some or all of the shipments were made on foreign-flag vessels without the written consent of the Contracting Officer. The Contractor shall describe these shipments in the following format:

ITEM DESCRIPTION	CONTRACT LINE ITEMS	QUANTITY
---------------------	------------------------	----------

(g) If this contract exceeds the simplified acquisition threshold and the final invoice does not include the required representation, the Government will reject and return it to the Contractor as an improper invoice for the purposes of the Prompt Payment clause of this contract. In the event there has been unauthorized use of foreign-flag vessels in the performance of this contract, the Contracting Officer is entitled to equitably adjust the contract, based on the unauthorized use.

(h) In the award of subcontracts for the types of supplies described in paragraph (b)(2) of this clause, including subcontracts for commercial items, the Contractor shall flow down the requirements of this clause as follows:

(1) The Contractor shall insert the substance of this clause, including this paragraph (h), in subcontracts that exceed the simplified acquisition threshold in part 2 of the Federal Acquisition Regulation.

(2) The Contractor shall insert the substance of paragraphs (a) through (e) of this clause, and this paragraph (h), in subcontracts that are at or below the simplified acquisition threshold in part 2 of the Federal Acquisition Regulation.

(End of clause)

[252.247-7024 Notification of Transportation of Supplies by Sea \(MAR 2000\)](#)

(a) The Contractor has indicated by the response to the solicitation provision, Representation of Extent of Transportation by Sea, that it did not anticipate transporting by sea any supplies. If, however, after the award of this contract, the Contractor learns that supplies, as defined in the Transportation of Supplies by Sea clause of this contract, will be transported by sea, the Contractor --

(1) Shall notify the Contracting Officer of that fact; and

(2) Hereby agrees to comply with all the terms and conditions of the Transportation of Supplies by Sea clause of this contract.

(b) The Contractor shall include this clause; including this paragraph (b), revised as necessary to reflect the relationship of the contracting parties--

(1) In all subcontracts under this contract, if this contract is a construction contract; or

(2) If this contract is not a construction contract, in all subcontracts under this contract that are for--

(i) Noncommercial items; or

(ii) Commercial items that--

(A) The Contractor is reselling or distributing to the Government without adding value (generally, the Contractor does not add value to items that it subcontracts for f.o.b. destination shipment);

(B) Are shipped in direct support of U.S. military contingency operations, exercises, or forces deployed in humanitarian or peacekeeping operations; or

(C) Are commissary or exchange cargoes transported outside of the Defense Transportation System in accordance with 10 U.S.C. 2643.

(End of clause)

Section 00800 – Special Contract Requirements

Clause No.	Title	Page No.
UAI 5152.236-9009 Partnering		2
UAI 5152.249-9000 Basis for Settlement of Proposals		2

UAI 5152.236-9009 Partnering

As prescribed in 5136.570-100(j) , insert the following clause:

PARTNERING (FEB 2000)

In order to most effectively accomplish this contract, the Government proposes to form a partnership with the Contractor to develop a cohesive building team. It is anticipated that this partnership would involve the *US Army Engineer District Mobile*, and the Contractor, primary subcontractors and designers, and the Corps of Engineers. This partnership would strive to develop a cooperative management team drawing on the strengths of each team member in an effort to achieve a quality project within budget and on schedule. This partnership would be bilateral in membership and participation will be completely voluntary. Any cost associated with effectuating this partnership, excluding travel and lodging cost of Government personnel, will be borne by TBD. The partnering meetings shall be held in TDB.
(End of clause)

UAI 5152.249-9000 Basis for Settlement of Proposals

As prescribed in 5149.505(d), insert the following clause:

BASIS FOR SETTLEMENT OF PROPOSALS (MAR 2009)

Actual costs will be used to determine equipment costs for a settlement proposal submitted on the total cost basis under Federal Acquisition Regulation (FAR) 49.206-2(b). In evaluating a termination settlement proposal using the total cost basis, the following principles will be applied to determine allowable equipment costs:

- (a) Actual costs for each piece of equipment, or groups of similar serial or series equipment, need not be available in the contractor's accounting records to determine total actual equipment costs.
- (b) If equipment costs have been allocated to a contract using predetermined rates, those charges will be adjusted to actual costs.
- (c) Recorded job costs adjusted for unallowable expenses will be used to determine equipment operating expenses.
- (d) Ownership costs (depreciation) will be determined using the contractor's depreciation schedule (subject to the provisions of Federal Acquisition Regulation (FAR) 31.205-11).
- (e) License, taxes, storage and insurance costs are normally recovered as an indirect expense and unless the contractor charges these costs directly to contracts, they will be recovered through the indirect expense rate.

(End of clause)

SECTION 01 00 00

SPECIFICATIONS

INDEX

1. SCOPE OF WORK
2. PRE-AWARD INSPECTION OF PLANT
3. DELIVERY OF PLANT
4. ORDER OF WORK
5. COMPLETION OF ASSIGNMENTS
6. SERVICES TO BE FURNISHED TO THE GOVERNMENT
7. LOCATION OF SUBMERGED OBJECTS
8. LAYOUT OF WORK
9. DATUM AND BENCH MARKS
10. EQUIPMENT OWNERSHIP AND OPERATING EXPENSE SCHEDULE
11. RADIO / INTERNET
12. DESIGNATED REPRESENTATIVE OF THE CONTRACTING OFFICER
13. PHYSICAL DATA
14. PRECONSTRUCTION CONFERENCE
15. DREDGE AND ATTENDANT PLANT REQUIREMENTS
16. PLANT MANAGEMENT
17. DREDGING (EXCAVATING OF SHOALS)
18. COMPANY REPRESENTATIVE
19. REPORTING REQUIREMENT
20. NOTICES
21. GENERAL SAFETY REQUIREMENTS
22. PAYMENT
23. NAVIGATION AIDS
24. QUALITY CONTROL
25. TASK ORDERS, DELIVERY, COMMENCEMENT, PROSECUTION AND COMPLETION OF WORK
26. POTABLE WATER
27. PERFORMANCE EVALUATION OF CONTRACTOR

SECTION 01 00 00

STATEMENT OF WORK - SPECIFICATIONS

1. SCOPE OF WORK:

1.1. **GENERAL:** The scope of work to be covered by the intended contract is to perform maintenance dredging in navigation channels in Alabama, Mississippi, and Florida. All work will occur only as directed (assigned) by the Contracting Officer's Representative (COR). There is no guarantee as to the amount of work. If the Contracting Officer determines that the shoaling in the channels is greater than that which can be removed under this contract in a timely manner, contracts for additional dredges may be procured to work concurrently in the same general locations. Should any of the channels of the projects listed above require dredging, it is in the scope of this contract to negotiate with the successful bidder on an hourly rate for the services of another hopper dredge(s) or for unit cost dredging as negotiated with the low bidder.

1.2. **RENTAL OF DREDGE (Bid Item No. 2):** The work to be performed under this portion of the contract will consist of the removal and satisfactory disposal of all material lying above project depth (or as directed by the COR), MLLW, over the bottom widths (full and/or partial) and applicable side slopes, at specific work location(s) all within the specified dredging limits of this contract. The COR will furnish the specific work location(s) (in advance) within those limits of the project during the contract life. All material excavated from the assigned channel segments will be transported and deposited into the assigned disposal area as discussed later in this specification.

1.2.1. **RENTAL DREDGE PLANT:** The work to be performed under this contract consists of furnishing and operating a hopper dredge with pump discharge of not less than 24-inch diameter nor more than 38-inch diameter complete with all necessary materials, supplies, labor, and transportation including fuel, power, and water for excavation operations as specified in the above paragraph. General excavation limits include all federally maintained channels in Alabama, Mississippi, and Florida, however, specific locations will be as directed by the Government within the total contract limits. More specific dredge and attendant plant requirements are discussed below.

1.3. **GENERAL:** All work, material and services not expressly called for in these specifications which may be necessary for complete and proper operations to carry out the contract in good faith shall be performed, furnished and installed by the Contractor at no increase in cost to the Government.

2. PRE-AWARD INSPECTION OF PLANT:

a. The apparent low bidder shall make his dredge and attendant plant available for inspection, to determine compliance with these specifications, as soon as practicable after bids are opened, and prior to contract award. If deficiencies are found during the inspection, the bidder will be notified by email or FAX. Upon receipt of such notice, the bidder shall correct all deficiencies at least two days in advance of the projected contract award date.

b. Two days before the projected award date, or upon notification by the bidder that the deficiencies have been corrected, a Government representative will re-inspect the dredge or plant. At that time, if the dredge and attendant plant do not meet the requirements of these specifications, then the bid will be rejected as non-responsive.

c. The Government may choose to waive the pre-award inspection, if such waiver is in the best interest of the Government. Waiver of the pre-award inspection does not relieve the bidder from the requirement to provide a dredge and attendant plant in full compliance with the specifications.

d. A post-award inspection will also be performed, in accordance with the clause "DELIVERY OF PLANT". Performance or waiver of the pre-award inspection will not affect the performance of a post-award inspection.

3. DELIVERY OF PLANT:

Delivery of the hopper dredge and attendant plant shall be completed within the time prescribed on the Standard Form 1442. For bidding purposes, the mobilization site will be the Mobile Bay Channel and Theodore Ship Channel intersection. Upon arrival of the dredge and attendant plant at the delivery site, the dredge will be inspected by Government personnel to determine whether any deficiencies have developed subsequent to the time the plant was brought into compliance pursuant to the pre-award inspection. The Contractor will be notified of acceptance or rejection of the dredge and attendant plant. If accepted, the dredge will be given an assignment immediately.

4. ORDER OF WORK:

a. The order of work to be performed under this contract cannot be determined except as the work progresses. Successive dredging location assignments may be either upstream or downstream from the previous assignments, and may not be at consecutive or contiguous locations. Repetitive assignments may also be required at a given location.

b. Dredging assignments shall be determined by the Contracting Officer or his representative, and will be given to the Contractor's representative aboard the plant who is in charge of the operations. Assignments may be changed at any time without any prior notice. The Contractor may also be required to stop work at any time without completing an assignment. There is no guarantee of specific work assignments or quantities under this contract.

c. The Contractor shall endeavor to meet the schedule of dredging operations as determined by the Contracting Officer. Operations shall be performed 24 hours a day, 7 days a week, including those days which have been declared by Congress to be legal holidays for per diem employees of the Federal Government.

5. COMPLETION OF ASSIGNMENTS:

As soon as the Contractor can determine the estimated completion time for the present assignment, he shall notify the Contracting Officer or COR of his best estimated completion time, during normal District working hours and not later than noon on Friday. The COR will determine the next assignment prior to the estimated completion time of the present assignment.

6. SERVICES TO BE FURNISHED TO THE GOVERNMENT:

a. The Contractor will be required to furnish, on the request of the COR or any inspector:

1. The use of such boats, boatmen, laborers, and material forming a part of the ordinary and usual equipment and crew of the floating plant, as may be reasonably necessary in inspecting and supervising the work.

2. Suitable transportation between the worksite and all points on shore designated by the Contracting Officer's representative, by means of the survey boat/inspector boat described in the technical specifications of the contract.

b. Equipment which fails to perform because of insufficient power or other mechanical difficulties or due to inexperienced operators shall be replaced, or the operator replaced, as appropriate, within 24 hours after the Contractor is directed to do so.

c. Should the Contractor refuse, neglect, or delay compliance with these requirements, the specific facilities may be furnished and maintained by the Contracting Officer, and the cost will be deducted from any amounts due or to become due the Contractor.

7. LOCATION OF SUBMERGED OBJECTS:

a. If the Contractor should locate a submerged object within the area of work, which endangers dredging operations or poses a hazard to general navigation, he shall note the location of the object, as determined from the electronic positioning system aboard the vessel. This location shall be reported to the Government inspector. Dredging in the immediate vicinity of the reported object shall be curtailed until the nature of the object and the degree of hazard can be determined. Dredging shall resume at the location of the reported object when the Contracting Officer determines that a hazard no longer exists.

b. If the Contractor issues a false report of a sunken object, the cost of the investigation shall be deducted from any amounts due, or to become due, the Contractor.

c. This clause applies in the case of submerged objects or hazards which are created by others. Submerged objects or other hazards created by the Contractor shall be considered as misplaced materials.

8. LAYOUT OF WORK (1965 APR OCE):

The Contractor shall lay out the work assignments from the Government-established monuments, ranges, and gages indicated on the drawings (if furnished in Advertisement) and shall be responsible for all measurements in connection therewith. The Contractor shall furnish, at his own expense, all stakes, templates, platforms, equipment, range markers and labor as may be required in laying out any part of the work from the ranges and gages established by the government. The Contractor will be held responsible for the execution of the work to such lines and grades as may be established or indicated by the Contracting Officer. It shall be the responsibility of the Contractor to maintain and preserve all stakes and other marks established by the Contracting Officer until authorized to remove them. If such marks are destroyed by the Contractor or through his negligence prior to their authorized removal, they may be replaced by the Contracting Officer at his discretion. The expense of replacement will be deducted from any amounts due, or to become due the Contractor.

9. DATUM AND BENCH MARKS:

The plane of reference of Mean Lower Low Water (MLLW) as used in these specifications is that determined by monuments, bench marks and tide gages as shown on the contract drawings (if furnished in Advertisement) or as are on record in the office of the Site Manager, Irvington Site Office, Phone 251-957-6019 or Panama City Site office, Phone 850-784-9780. The Contractor should take note that there will be specific tide gages designated for specific tangents of the project work.

10. EQUIPMENT OWNERSHIP AND OPERATING EXPENSE SCHEDULE (MAR 95):

a. This statement shall become operative only for negotiated contracts where cost or pricing data is requested, and for modification to sealed bid or negotiated contracts where cost or pricing data is requested. This clause does not apply to terminations. See 52.231-5000, Basis for settlement of proposals, and FAR Part 49.

b. Allowable costs for construction and marine plant and equipment in sound workable condition owned or controlled and furnished by a contractor or subcontractor at any tier shall be based on actual cost data for each piece of equipment or groups of similar serial and series for

which the Government can determine both ownership and operating costs from the contractor's accounting records. When both ownership and operating costs cannot be determined for any piece of equipment or groups of similar serial or series equipment from the contractor's accounting records, costs for that equipment shall be based upon the applicable provisions of EP 1110-1-8, "Construction Equipment Ownership and Operating Expense Schedule," Region III. Working conditions shall be considered to be average for determining equipment rates using the schedule unless specified otherwise by the contracting officer. For retroactive pricing, the schedule in effect at of the time work was performed shall apply.

c. Equipment rental costs are allowable, subject to the provisions of FAR 31.105(d) (ii) and FAR 31.205-36. Rates for equipment rented from an organization under common control, lease-purchase arrangements, and sale-leaseback arrangements, will be determined using the schedule, except that actual rates will be used for equipment leased from an organization under common control that has an established practice of leasing the same or similar equipment to unaffiliated lessees.

d. When actual equipment costs are proposed and the total amount of the pricing action exceeds the small purchase threshold, the contracting officer shall request the contractor to submit either certified cost or pricing data, or partial/limited data, as appropriate. The data shall be submitted on Standard Form 1411, "Contract Pricing Proposal Cover Sheet".

11. RADIO / INTERNET:

The Contractor shall furnish and maintain the following radios for communication with the Corps of Engineers, the United States Coast Guard, and other vessels: Radio(s) must be certified as being operable on the specified frequencies and powers by a licensed radio technician. A copy of the certification must be furnished to the Contracting Officer prior to final acceptance of the dredging plant.

- a. A Marine VHF Radio, FCC type accepted with the following channels: Channel 16, (156.8 MHZ), Channel 13, (156.65 MHZ), Channel 12, (156.6 MHZ), Channel 14, (156.7 MHZ), and Channels 26 and 28 for public correspondence. A separate receiver must be provided on Channel 13, (156.6 MHZ) in compliance with Public Law 92-63.

- b. The Contractor shall furnish and maintain an internet service so RMS/QAS, CE DREDGE and DQM can be accessed on the dredge for the government inspector's use.

12. DESIGNATION OF AUTHORIZED REPRESENTATIVE OF THE CONTRACTING OFFICER:

Effective the date of award and pursuant to AFARS 42.9001, The ARCO, is delegated authority

to act as the Authorized Representative of the Contracting Officer, without power of re-delegation, for the purpose of discharging the following duty of the Contracting Officer on this contract:

- a. Order work when and as required during the contract period.
- b. Determine acceptability of work performed.
- c. Inspect all equipment furnished by the Contractor for use on the project and determine that it is suitable for use as required by the contract.
- d. To approve payments.

The following delegated title will be used when signing any contractual document pursuant to this authority.

EXAMPLE: John Doe
Authorized Representative of the Contracting Officer

This delegation will remain in effect until completion of the contract unless sooner rescinded in writing by the Contracting Officer or his successor.

12.1. ADMINISTRATION OF CONTRACT: After award, this contract will be administered by the A-E and Construction Branch (CT), U.S. Army Corps of Engineers, Mobile district, P.O. Box 2288, Mobile, Alabama 36628-0001, telephone (251) 441-6161.

13. PHYSICAL DATA (APR 1984):

Information and data furnished or referred to below are furnished for the Contractor's information. However, it is expressly understood that the Government will not be responsible for any interpretation or conclusion drawn therefrom by the Contractor.

- a. General: The physical conditions indicated on the drawings (if furnished in Advertisement) and in the specifications are the result of site investigations and surveys.
- b. Location: The main location of work (excavation or dredging) to be done under these specifications is located in the existing Mobile Harbor project channels in the southwestern part of the State of Alabama, and approximately 80 miles by water from Pensacola Harbor, Florida, on the east and 61 miles by water from Pascagoula Harbor, Mississippi, on the west. Another area of work will be Pascagoula Bar Channel. Other potential areas of work under these specifications are in the existing federal channels located in Pensacola and Gulfport.

c. Subsurface Investigations:

(1) Mobile River, Bay and Bar Channels: Subsurface cable, pipeline and tunnel crossings are as indicated on the contract drawings (if drawings furnished in Advertisement). The Contractor shall be responsible for any damage, due to his negligence, to the cables, pipelines and tunnels occasioned by his dredging operations.

(2) Contractor's Investigation Responsibility: The Contractor should make his own investigation of submerged, surface and overhead structures in the work area and other locations he finds necessary to traverse. The exact location, depths and height of all submarine cables, pipes, high lines, docks, piers, bulkheads bridges, etc. (as applicable), are not known and it will be necessary for the Contractor to ascertain interference problems and notify the respective owners in advance of dredging operations. The Contractor shall make all arrangements with the respective owners of the structure to assure satisfactory completion of dredging in the vicinity with a minimum interruption of service, and shall perform his operations in such a manner as will avoid damage to these facilities.

(3) No dredging will be done within 100 feet (horizontally) of any marine structures, wharves, or bulkheads in order that such structures will not sustain damage or be undermined by the dredging operations. Any such damaged structures, due to the negligence of the Contractor, shall be repaired or replaced by the Contractor at no expense to the Government.

d. Weather Conditions: The sites of the work are exposed to local disturbances in the Mobile Harbor, which may cause suspension of the work for short unknown periods of time. During tropical hurricanes which may occur from June to December, inclusive, the project channels do not afford a safe refuge for floating plant. There are no unusual currents except during floods, when velocities of 2 to 4 miles per hour may be expected; however, the Contractor should investigate all sites of work and determine for himself the requirements of the work. Under ordinary conditions, the Mean Tidal Range is 1.2 feet. The working season extends over the entire year. Tides in Mobile Harbor are affected by extended periods of strong north or south winds.

e. Transportation Facilities: Rail and highway transportation is available to Mobile, Alabama. Water transportation is available to the site of the work.

f. Channel Traffic: The traffic using the Mobile Bay and Bar Channel is considered large, including several lines of freight steamers, ore carriers, tankers, tugs, fishing and passenger boats. There is ample width in this channel to accommodate traffic without undue interference with the dredging operations specified herein. CAUTION: When navigation conditions become hazardous due to inclement weather (fog, storm, etc.) or other circumstances, the dredge and related equipment shall be moved to provide the maximum possible channel width (even full

channel) for safe passage of any impending project traffic. The Contractor shall maintain appropriate communication with project traffic during such hazardous conditions. The Contractor shall particularly comply with all U.S. Coast Guard regulations pertaining to proper activation of fog (and any other) signaling devices (sound, light, etc.).

g. Obstruction of Channel: The Government will not undertake to keep the area and channel free from vessels or other obstructions, except to the extent of such regulations, if any, as may be prescribed by the Secretary of the Army, in accordance with the provisions of Section 7 of the River and Harbor Act approved 8 August 1917. The Contractor will be required to conduct the work in such manner as to obstruct navigation as little as possible, and in case the Contractor's plant so obstructs the channel as to make difficult or endanger the passage of vessels, said plant shall be promptly moved on the approach of any vessel to such an extent as may be necessary to afford a practicable passage. The Contractor is emphatically placed on notice that the work areas of this contract is a very heavy marine industrial, congested area. The Contractor must layout his work (and equipment) in such a way not to restrict the docks, piers, bulkheads, etc. of the bank occupants. Upon the completion of the work, the Contractor shall promptly remove his plant, including ranges, buoys, piles, and other marks placed by him under the contract in navigable waters or on shore.

h. Character of Material: The material to be removed is predominantly the normal maintenance shoaling (silts and sands) and will have some debris (wood, metal, etc. as is normally found in a heavy marine industrial harbor environment). For the purposes of this solicitation, the material to be dredged shall be considered as unclassified. Some new work dredging could be encountered by the dredge plant.

14. PRECONSTRUCTION CONFERENCE:

a. A preconstruction conference will be arranged by the COR after award of contract and before commencement of work. The COR will notify the Contractor of the time and date set for the meeting. At this conference, the Contractor shall be oriented with respect to Government procedures and line of authority, contractual, administrative, and construction matters. Additionally, a schedule of required submittals will be discussed.

b. The Contractor shall bring to this conference all items listed in Section 01330, 1.3.

15. DREDGE AND ATTENDANT PLANT REQUIREMENTS (Bid Item No. 2):

15.1. DREDGE REQUIREMENTS: The dredge offered shall be capable of continuous operation and of sufficient size (not less than a 24-inch nor more than a 38-inch discharge) and with dragarm(s) of an appropriate length and construction to work efficiently in depths of up to 52 feet. The Contractor shall have available for use at all times a variety of serviceable interchangeable pump impellers (2 minimum), a spare pump case, and a spare serviceable

draghead to permit the dredge to operate efficiently under varying conditions described in the paragraph entitled (PHYSICAL DATA). The dredge shall be capable of dredging upstream as well as downstream and will so operate as directed by the Contracting Officer. The following information was obtained from history and data banks from Operations Division, Mobile District Office:

Pump Disch. Diam. (inches)	Hopper Size (CY)	Base Hours	
*24	3600	4397	Isle 1
**24	3600	4101	Isle 2
27	4000	4286	RNWeeks
26	4000	3708	Newport
24	4387	2989	Columbia
28	4000	3471	Lindholm
33.5	6400	2146	Terrapin Island
33.5	11147	1464	Stuyvesant
28.5	4830	2923	Bayport
31.5	6466	1895	Liberty Island
38	13572	875	Glenn Edwards

* Normal powered dredge for this size category

** Turbo charged dredge for this size category

15.1.1. BIDDING: The bidder shall use the above chart to select the hours to be inserted into the appropriate Bid Schedule from the class of dredge he intends to use. The total amount of hours to be inserted into Bid Items No. 2 shall be that shown above for the class of dredge to be used by the Contractor.

15.1.2. EVALUATION OF BIDS:

a. It is the intent of the Government to secure a dredge and/or dredges meeting the requirements set forth in these specifications and having a main pump discharge of not less than 24 inch diameter nor more than 38 inch diameter.

b. Hourly quantities have been determined based on the estimated quantity of shoal

material to be removed, the size of the dredge pump and the operating characteristics of the hopper dredge, to provide fair competition between dredges of dissimilar sizes and production rates. Award will be to the lowest responsive, responsible bidder.

15.2. ATTENDANT PLANT:

a. Transport Vessel/Survey Boat: The contractor shall provide one transport vessel/survey boat, with twin propellers, not less than 40 feet in overall length, with enclosed space for three or more passengers after installation of all required contractor furnished survey equipment and survey party crew (Survey Equipment/Personnel defined elsewhere), to adequately operate and survey in the federal navigation channels, ocean disposal area, open water D/As and the area enroute to the ocean D/A. This vessel must have an operator on site at all times; capable of traveling at a speed of 20 knots (23 MPH) or greater in good weather and capable of traveling safely at night and in intense fog; (such vessel shall meet or exceed US Coast Guard regulations for vessels 65 feet or less in length and have Certificate of Inspection (COI) or be inspected by a licensed Marine Surveyor, as applicable). This vessel shall be for the primary use of Government Inspector shift changes and government directed hydrographic surveying. The use of this vessel for contractor crew changes, or any other use of this vessel by the contractor shall be secondary to Government Inspector shift changes and government directed hydrographic surveys. This vessel shall be equipped with the following at a minimum: built in fuel tanks with correctly operating fuel gauges; marine and company radios; windshield wipers, running and spot lights; and all required survey equipment. The contractor shall secure a satisfactory landing location in the vicinity of the current assignment for this vessel. This location will vary depending on the assignment.

b. Survey Party: The Contractor shall furnish one full survey party available for 12 hr/day survey operations 7 days a week. The minimum full-time crew for the survey boat shall be one qualified survey boat operator for the daylight shift, plus up to a 4 man survey party to perform surveys to support the entire dredging process. Also, a person responsible for processing and plotting of surveys shall be on board the dredge during the daylight shift. The survey party shall have a sufficient number of qualified personnel in order to adequately survey under any condition. The minimum qualifications for the chief surveyor shall be one of the following: Hydrographer Certification by American Congress of Surveying and Mapping or a minimum of 3 years of experience performing hydrographic surveys as the primary systems operator within the last 5 years. The party shall survey the current conditions of the area being dredged and continue surveying for shoals for future dredging while the prior survey is being processed on board the dredge. This survey party will perform the survey assignments, operating all necessary electronic positioning and computer equipment.

c. Survey Equipment: The Contractor furnished survey equipment must meet or exceed all requirements listed below as well as any other requirements referred to in these specifications:

(1) Positioning System: The positioning system must be capable of providing positional accuracies of the vessel within three meters or less. This system must have a proven track record and have the manufacturer's written backing stating the accuracy thereof. The system utilized must be capable of providing twenty-four hours, seven days a week positional coverage within the above stated accuracies, anywhere within the scope of work area without interruption of positional location. Both the dredge and survey vessel shall be equipped with a complete positional system. These systems shall be fully operational at all times. Any failure of said system will be corrected within 8 hours. If not corrected within said time frame the vessel with failed system may be directed to cease operations until corrected. The contractor, if properly equipped with a Global Positioning System, may utilize such a system as long as the accuracies are confirmed and documented during the use of the system. The positioning system and survey software will have the capability of providing visual guidance to the vessel operator and acquire positioning and guidance updates on no less than one second time increments.

(2) Sounding Equipment: The sounding equipment will consist of a sounding machine/device capable of providing updated soundings on no more than 1/20 second intervals and have an accuracy rating ± 0.5 feet. Sounding device will have analog charting (real time) within the device and will have all the capabilities of calibrating to a bar check utilizing the Norfolk Method of bar checking. All depths acquired will consist of dual frequency soundings utilizing a high operating 208 kHz frequency transducer and a low operating 24/41 kHz frequency transducer (any frequencies other than those listed must be approved by the Authorized Representative of the Contracting Officer prior to use). Sounding data will be digitally acquired from both the high and low frequency transducers. The 24/41 kHz soundings will be shown in conjunction with the 208 kHz soundings on the analog chart of the sounding device. All soundings will be acquired on a continuous basis. Plotting of data shall be on the scale and size of the plot requirements as specified by the Authorized Representative in clearly legible print. These plots shall reflect the data gathered by the 208 kHz frequency unless otherwise requested by the Authorized Representative of the Contracting Officer. Any additional plotted data requested would be that data acquired by the 24/41 kHz. Volumes shall be computed from the 208 kHz frequency unless otherwise requested by the Authorized Representative. These plots along with all digitally acquired data (for both 208 and 24/41 kHz) shall be provided to the Government as specified below.

(3) Acquired and Processed Data: The survey system will require a computer and software capable of handling all required data points and plotting of those data points. This system shall be capable of acquiring or converting all, unedited raw data (horizontal and vertical) to an IBM, ASCII compatible format prior to submittal to the Government. The ASCII format shall be compatible with the MS DOS Operation system. If the Contractor is utilizing HYPACK to perform his required surveys, the Contractor shall use the Government provided channel files. The Contractor shall submit the HYPACK project files for the specific survey performed. These files contain all the files that make up the survey including raw and edited, line, log, and tide files associated with each survey among others. Otherwise the Contractor shall use a system

capable of acquiring and converting all unedited raw data (horizontal and vertical) to an IBM, ASCII compatible format prior to submittal to the Government. The ASCII format shall be compatible with the DOS operating system. Sounding files shall contain single line records. Each record shall contain the easting, northing, depth, date and time for one sounding. Each item in the record shall be separated by a space character (ASCII 32 (10)) and the record shall be terminated by a line feed with carriage return. Sounding files shall be no greater than 1.2 MB in size and shall contain the data for no more than 99 section lines. All records shall conform to the format shown below.

<u>East</u>	<u>North</u>	<u>Depth</u>	<u>Date</u>	<u>Time</u>
123456.78	876543.21	-42.3	01/15/07	14:22:13.3

Said survey system will provide a means of plotting all data points for submittal in hard copy form according to the following requirements: All plots submitted shall be provided on full size 22" x 34" (ANSI 'D' size) plot paper (half size, 11" x 17" if approved by the Authorized Representative) and delineate no less than the following: all nav. aids; north arrow; station annotation; channel limits (toe & center line); edited sounding data (corrected to MLLW); date of survey; grid ticks; surveyor's name; survey vessel name; contract number; and any other pertinent information. Scale of plan view plots shall be 1" = 200' and cross-sectional plots shall be plotted at a 1" = 100' horizontal scale unless otherwise specified by the Authorized Representative. Plan view plots for vessel tracking will delineate actual vessel track along the specific route taken and print depths acquired along the route on a scale clearly legible; cross-sectional plots will be plotted on hard copies which delineate the channel dimensions in a template format and plot all acquired sounding data points thereon; a plan view plot will be plotted in three different colors which will determine the depths above and below project depth. Colors will be determined by the Authorized Representative. A contour line drawn at the project depth, which will be given by the Authorized Representative, will be drawn showing said contour, all data acquired by the system will be provided on a CD-Rom in the format previously specified and in unedited form. All hard copy submittals shall consist of edited data and all supporting field notes.

d. Dredge Electronic Tracking Position: The Contractor shall be able to visually display continuous real time positioning of the dredge, by track plot or CRT screen, in relation to both the before-dredging surveyed shoals and at the disposal area. Dredge location accuracy shall meet the requirement of the Corps' "Manual of Survey Instructions". A written discussion of the method the Contractor intends to use in order to satisfy these requirements shall be included in the Contractor's bidding schedule discussions.

e. Government Work Station: The Contractor shall furnish a computer workstation for use by the Government Inspector on board the vessel. An identical dredge electronic tracking system as mentioned in the paragraph above shall be provided to the Government inspector and equipped in the inspector's office.

16. PLANT MANAGEMENT:

16.1. **GENERAL:** Upon initiation of work, the Contractor shall execute the work assigned diligently, and at all times endeavor to meet the schedule of excavation (dredging) and disposal operations as determined by the Contracting Officer. The Contractor shall be expected to conduct excavation dredging and disposal operations seven days per week, twenty-four hours per day. The order of work to be performed cannot be determined except as the work progresses. The Contractor shall bear all direct, overhead and collateral expenses incident to the operation, upkeep and repair of all items of plant. He shall maintain the plant in a good state of repair, shall arrange for a supply of renewal parts to be on hand when needed for all plant and shall provide and maintain efficient personnel for each item of plant employed in connection with the work. Equipment will be in condition to render efficient, economical and continuous service and shall be equipped with all mechanical devices and equipment required by Federal, State and local authorities, provided that nothing in the paragraph shall be construed to limit the authority of the Contracting Officer to prohibit the use of any piece of equipment which, in the opinion of the Contracting Officer, is mechanically unsafe for use. Equipment which the Contracting Officer or his authorized representative considers does not perform in a satisfactory or efficient manner shall be repaired or replaced by the Contractor at the Contractor's expense within 24 hours after notification by the Contracting Officer or his authorized representative. Failure of the equipment to perform to the satisfaction of the Contracting Officer, and failure by the Contractor to effect timely replacement of the unsatisfactory equipment, shall be sufficient cause for the Government to procure replacement equipment and charge the Contractor for any excess costs associated therewith. The equipment shall be registered by the Contractor with all Federal, State and local authorities requiring registration, and registration plates or other evidence of registration shall be displayed in accordance with the requirements of the registering authority.

16.1.1. **ORDER OF WORK AND INSPECTION:** The work will be conducted as directed by the Contracting Officer and will be directed by Inspectors appointed by him who will enforce a strict compliance with the terms of the contract. The Inspectors will keep a record of the work done and see that the gages, ranges, and other marks are kept in proper order; but the presence of the Inspector shall not relieve the Contractor or his responsible agent of any responsibility for the proper execution of the work in accordance with the contract and directives of the Contracting Officer issued thereunder. The Contractor will be required (notwithstanding contract requirements at other points).

a. To furnish on the request of the Inspectors the use of such boats, boatmen, laborers, and material forming a part of the ordinary and usual equipment and personnel of the plant as may be reasonably necessary in directing the work.

b. To furnish on the request of the Contracting Officer or his authorized representative suitable transportation from all points on shore designated by the Contracting Officer to and from

the various pieces of plant and to and from the disposal areas. Should the Contractor refuse, neglect or delay compliance with these requirements, the specific facilities may be furnished and maintained by the Contracting Officer and the cost thereof will be deducted from any amounts due or to become due to the Contractor.

16.2. INSPECTION OF PLANT: The dredge plant will be inspected by the Contracting Officer or his representative to ensure total dredging plant required under the contract has been mobilized and is in safe working condition.

a. Contractor's Obligation to Inspect. Before any machinery or mechanized equipment is placed in service it shall be inspected and tested by contractor and certified to be in safe operating condition using Safety Survey Checklist for Floating Plant and Safety Inspection Checklist for Mobile Construction Equipment forms as prescribed by EM 385-1-1. Records of these tests and inspections shall be provided to the Government prior to Government inspection and shall be maintained at the site by the contractor.

b. Safety Inspection. Upon completion of mobilization, before starting work, and after the checklist forms are provided to the government, a safety inspection will be conducted by the Government. The safety inspection will be conducted using the checklist as a guide to denote any deficiencies.

c. Clearance to Begin Work. Upon completion of the safety inspection a list of deficiencies will be compiled and copies given to the contractor for corrective action as required. If in the opinion of the Contracting Officer the plant is unsafe or does not meet the terms of the specifications clearance to begin work will not be given. In the absence of any deficiencies, the plant will be put to work. Failure of the Contractor to provide dredge plant complying with requirements of the contract specifications or safety deficiencies preventing commencement of work could be cause for termination for default.

d. Inspections. Inspections performed by the Government does not relieve the contractor of his responsibility to perform his own inspections of plant to assure a safe working environment at all times in accordance with contract specifications, the latest version of EM 385-1-1 and his Accident Prevention Plan.

e. Hopper Leakage Test. During the safety inspection the dredge will be required to take on water equivalent to the hopper capacity as rated in the above table. In order for the dredge to begin work it must have no more than a 5% loss in a one hour (1 hr) period. This test may be performed again at any time during the contract when an indication of leakage exists. Should the dredge fail said test the dredge will be on 0% pay for the entire test period and until leakage is repaired; if the dredge passes said test it will be paid at a 70% rate for the time to perform leakage test.

16.3. TERMINATION OF WORK: It is anticipated that upon completion of the excavation assignment(s) all the plant will be released to the Contractor. However, the Contracting Officer, by written notice, may terminate this contract, in whole or in part, when it is in the Government's interest. If this contract is terminated, the Government shall be liable only for payment under the payment provisions of this contract for services rendered before the effective date of termination.

16.4. DREDGE SUSPENSION AND WORK FOR OTHERS:

16.4.1. PRIVATE WORK RELEASE: By mutual agreement of both the Contractor and the Contracting Officer, the dredge may be released from this contract (with Government approval) for short periods of time to perform work for others in the same vicinity. The dredge shall, however, be returned to operations under this contract within 48 hours after notice by the Contracting Officer to resume such contract work.

16.4.2. DREDGE SUSPENSION/RELEASE: The Contracting Officer may suspend the dredge for extended periods of time to allow the Contractor to perform work for other Corps Districts. The Contractor may request to be released or the Contracting Officer may unilaterally suspend work to allow the dredge release. The dredge shall remain on 10-day call by the Contracting Officer during the suspension/release period. Regardless of the pay status of the dredge at the time it is released, the dredge will immediately go to a non-pay status, and remain so until it is recalled to work. Demobilization at the time of release, and mobilization at the time of recall, will not be paid. Payment will cease when the last load is dumped prior to release. Payment will resume if the dredge is recalled to an assignment under this contract and when the dredged material starts flowing into the hopper. The return from the dump will be estimated and paid for, based on return time from loads previous to demobilization. The contract may be terminated during the suspension/release time period if the Contracting Officer determines that termination is in the best interest of the Government.

16.5. WORK LAYOUT: Dredging limits will be designated at each assignment by coordinates and/or channel centerline station. The Contractor shall furnish, at its own expense, all stakes, pipe, equipment, range markers and labor as may be required to maintain any part of the work from the ranges and gages established by the Government and to check for verification starting and stopping points on each shoal area. It shall be the responsibility of the Contractor to maintain and preserve all stakes and other marks established by the Contracting Officer until authorized to remove them, and if such works are destroyed by the Contractor through his negligence prior to their authorized removal, they may be replaced by the Contracting Officer at his discretion. The expense of replacement will be deducted from any amounts due or to become due to the Contractor.

17. DREDGING (EXCAVATING OF SHOALS):

17.1. General: The shoals removed during this contract shall be transported and satisfactorily

deposited into a designated ocean dredged material disposal area or open water site. The specific location of the disposal area shall be furnished at the Preconstruction Conference or as necessary during this contract.

17.2. Dredge (excavation) Plant Instrumentation: All dredge (excavation) plant utilized on this contract shall be instrumented to monitor the location of the dredge during excavation and disposal as specified herein. The data produced by this instrumentation will be collected by automated (computer-digitized) means and stored in an IBM compatible format, DOS Operating System, ASCII format. The Contractor's initial submittal shall include written instructions to explain the data format used. All data will be tied to the date and real time of day with data point intervals not greater than five (5) minutes. The data will be submitted to the Government weekly on CD Rom.

17.2.1. As stated in section 35 20 23.23 DQM, the following elements will be monitored, as a minimum:

- a. Dredge I.D. designation.
- b. Dredge location by coordinates and by cut(s), i.e. east, west, center, 1, 2, 3, etc. and whether first cut or redredge and stationing of current assignment.
- c. Dredge deposition horizontal location.

17.2.2. The Dredge Plant Instrumentation is a part of the dredge plant and must be functional at all times. If failure of any part thereof occurs the Contractor will be expected to repair the failed part within the next 36 hours restoring full operations. If failure to repair does not occur in that period, the particular plant affected will be considered non-responsive to the contract requirement and will either be replaced or a redundancy part added to render the plant fully operational to include the monitored data, all at no additional increased price or time to the contract.

17.3. Disposal of Excavated Material: Excavated material shall be transported to and disposed of in the proper disposal area as described below and as depicted on the contract drawings (if provided). The Contractor will develop his disposal procedures based on these requirements/restrictions. The Contractor will submit a DEPOSITION PLAN to the Contracting Officer for approval prior to disposal of any dredged material under this contract. The Contractor's DEPOSITION PLAN shall be completely explanatory and include all assumptions, statements of fact, computations and a narrative to fully explain the procedures that the Contractor will follow during the contract. The Contractor's DEPOSITION PLAN will address each different disposal situation.

17.4. The Government will be monitoring turbidity throughout the life of the contract to ensure the Contractor complies with permit requirements for this contract. The Contractor shall provide a turbidity meter equivalent to a HACH 2100 Portable Turbidimeter. Turbidity shall not exceed

the limits specified in the Water Quality Certification for the project. If turbidity resulting from the project exceeds these levels, the Contractor will cease dredging and notify the COR.

17.5. **Misplaced Dredged Material:** Any dredged material deposited at locations other than in areas designated or approved by the Contracting Officer will be considered misplaced material and will not be paid for until the Contractor, at his own expense, removes and redeposits the misplaced material. Any necessary disposal site restoration work shall not be the basis for a time extension or additional compensation under this contract.

18. **COMPANY REPRESENTATIVE:** With reference to the paragraph entitled PLANT MANAGEMENT and section 01 45 01, the Contractor's Representative shall be on the actual work site (dredge) at all times. The Government Representative shall issue work instructions to the Contractor's Representative. The Contractor's Representative will direct the actual performance of the equipment. No definable feature of work shall be performed without the Contractor's Representative being present.

19. **REPORTING REQUIREMENT:** The Contractor will be required to prepare and submit a Daily Report of Operations, ENG Form 27A, for all dredging work activities (as appropriate). The Contractor will also be required to attach a copy of the Mate's Log pages which cover the 24 hour period being reported to the ENG Form 27A. The original Mate's Log must be given to the Government's Representative at the completion of the project. Contractor shall also submit daily report SAM Form 696 (See paragraph 24.2.b). All reports must be submitted on a daily basis and not in groups. A reduced sample of each form for recording the required information is bound herein. In addition to the two (2) daily dredging reports required, the Contractor shall prepare a Monthly Report of Operations for each month or partial month's dredging work on ENG Form 27A. The monthly report is to be submitted to the Contracting Officer's Authorized Representative on or before the 7th of each month, consolidating the previous month's work. Further instructions on the preparation of the reports will be furnished at a Preconstruction Conference. Upon completion of the job, the Contractor shall submit a consolidated job report, combining the monthly reports, within seven calendar days of contract completion. The Contractor shall submit the original and one copy of each report to the Contracting Officer's Authorized Representative.

20. **NOTICES:**

a. The Contractor shall give the Contracting Officer 5 days advance written notice of the date he plans to commence work under this contract in order that Government required actions may be commenced sufficiently in advance of the Contractor's operations and that baselines and other controls may be adequately installed.

b. The Contractor shall work on holidays, week-ends, etc., 24 hours per day, 7 days per week. Adequate lighting for thorough inspection of night operations will be provided by the

Contractor at his expense.

21. GENERAL SAFETY REQUIREMENTS: Contract Clause entitled, ACCIDENT PREVENTION, requires an accident prevention program which incorporates safety features and procedures from EM 385-1-1, (latest edition), entitled "U.S. Army Corps of Engineers Safety and Health Requirements Manual" that are applicable to all aspects of Contractor dredging operations. In addition to these features, the following safety requirements shall be incorporated into the Contractor's accident prevention program:

21.1. The Contractor shall designate a "plant fleeting area" in which all non-used portions of plant shall be stored. Such area shall have "hazardous area" buoys which are properly placed and marked with reflective tape to give the boating public adequate warning of the fleeting area while traveling at night. Additionally, a prominent lighted warning sign (as specified in EM 385-1-1) shall be displayed on the equipment in the fleeting area. Such signs shall have reflective borders and shall be well lighted.

21.2. All plant, used or idle, shall be inspected at least once per shift by the contractor and government inspector (if inspector is on shift) to assure that buoys, signs, and lights are in place and that all lights operate properly. Daily reports of both the contractor and government inspector shall identify the inspectors and reflect the time of the inspection of plant in use and of plant at the fleeting area. An adequate number of reserve batteries and lights shall be stored on the dredge at all times in order to restore non-functioning lights.

21.3. At all public boat marinas within 10 miles of dredging operations or moored equipment, a sturdy and prominent warning sign shall be displayed, (reference drawing of example sign at end of this advertisement entitled: "Warning Sign"). The Contractor will be responsible for keeping this sign current with respect to his dredging operations or equipment. Such sign shall have red lettering and castles on white background with a red reflective border. Adequate spacing should be provided to allow for listing of two work sites. A map showing the location of all Warning Signs shall be submitted to the Government. Final Payment will be withheld until all warning signs are removed.

21.4. The Contractor shall increase public awareness of potential hazards presented by dredge plant equipment stating: location, date of construction, equipment mooring, marshalling areas, etc., by: Ensuring that an announcement of the beginning of the dredging operation receives publicity in local newspapers/radios/television/waterway users association/etc. Periodic updates/status announcements should be made at intervals (suggest monthly) throughout the contract life.

22. PAYMENT:

22.1. Mobilization and Demobilization of Dredge and Attendant Plant (Bid Item No. 1.): (See

Special Contract Requirements.) All cost associated with mobilization and demobilization of all dredge plant and dredge attendant plant under Bid Item No. 2 will be included in the contract lump sum price for Mobilization and Demobilization, Bid Item No. 1. This shall include any and all costs to adapt, modify, reconstruct, and/or reconfigure the dredge plant and/or the attendant plant to such a configuration capable of conducting this contract work. No separate payment shall be made for any such configuration preparations and payment of this Bid Item is considered complete compensation for such actions. The Contractor will be entitled to invoice for 60% of the mobilization and demobilization line item after all required equipment is delivered to the designated work site and material is passing through the dredge. The remaining 40% will be due after all equipment is removed from the work site and proper receipt is received by the Government.

22.2. Dredging 100% Pay Time (Bid Item No. 2.): 100% Pay time shall begin on the date and hour when the dredge actually commences dredging operations (defined as shoal material moving through pump and deposited into the hopper) on the initial assignment. There is no eligible 70% Pay Time or 40% Pay Time prior to eligible 100% Pay Time. The actual number of hours of work required may be more or less than the estimated amount shown in the contract. Payment for work on an assignment will stop upon completion of the work assignment as determined by the COR.

22.2.1. 100% Pay Time (Bid Item No. 2.): Actual time of dredging when the dredge is under operation, with the dredge's pump system satisfactorily moving material, and such material is being properly deposited into the hopper. This item will include applicable turning time that facilitates loadings operations at the shoal (dredging) assignment. Also time involved in round trip transport of material from location of excavation to and through the disposal site and back to the excavation location or new assigned location if so directed by the Government; the disposal process (dropping of hopper load into D/A or pumping out into open water site) will be included in the payment under this bid item. During the movement periods, the Contractor shall at all times maintain the average operating strengths of each watch and be ready to commence preparing the dredge before and after a movement between work locations. Payment will be made monthly at the contract price per hour calculated to the nearest one sixtieth (1/60) hour.

22.2.2. 70% Pay Time: The following time will be paid for monthly at 70% of the contract price per hour calculated to the nearest one sixtieth (1/60) hour:

a. Actual time lost due to traffic in ALL areas. This excessive time shall be calculated by using the following method: Subtract the reduced speed from the full speed to determine the reduction in speed. Multiply the reduction in speed by the duration of the reduction and divide the resulting distance by the full speed of the dredge to calculate the time lost. The full speed rate and the reduced speed rate can be obtained either by using the DQM data and/or the mate's noted observations.

b. Actual time lost up to but not in excess of four hours due to dredge shut-downs authorized by the Contracting Officer, for the purpose of replacing the pump impeller with either a different diameter impeller or an impeller of a different number of vanes than that of the impeller being used. The intent of payment for delays authorized by the Contracting Officer to permit the Contractor to change pump impellers is to obtain the greatest efficiency of pump operations under changing conditions, such as, varying materials, but it is not the intent to pay for replacing worn out impellers or impellers that have lost their efficiency because of wear of either impellers or pump liners.

c. Actual time lost due to removal of logs, driftwood, etc. from the draghead, pump, pipeline, etc.

d. Actual time for moving between work assignment locations will be made under this bid item and will continue until material is passing through the pump(s) at which time the payment will revert back to 100% payment for Bid Item No. 2. If moving to the new work assignment requires travel through the previous work assignment, 70% payment will begin at the north end of the previous work assignment until material is passing through the pump(s) at which time the payment will revert back to 100% payment for Bid Item No. 2, unless the new assignment is connected to the previous assignment. If moving to the new work assignment requires travel to a different project location (i.e. from Mobile Bay to Pascagoula Sound) then 70% payment will begin from the previous work assignment designated Disposal Area until material is passing through the pump(s) at which time the payment will revert back to 100% payment for Bid Item No. 2.

e. When weather conditions, i.e. fog, storm, hurricane, are of such intensity as to require cessation of dredging operations is further clarified hereby. If the cessation of dredging operations results in the dredge plant standing by at, or near, the work site (anchored) and the full crew remains on duty, then payment will continue at the 70% pay rate for the duration of the cessation. If the cessation of operations results in the dredge plant being moved to a point of dockage or safe harbor (if so directed by the Authorized Representative of the Contracting Officer) where the dredge is shut down except for a required fire watch and other minimum crew for necessary operations, then the payment will be: at the 70% pay rate, to and from the work area and designated dockage point, and at the 40% pay rate while at the dockage point.

f. Time lost when the dredge's speed is reduced due to adverse weather conditions. This excessive time shall be calculated as detailed for traffic delays in paragraph 22.2.2 a.

g. Time incurred during a successfully passed leak test as required by paragraph 16.2.e.

22.2.3. 40% Pay Time: When weather conditions are such that they will preclude economical and efficient dredging operations, the Contracting Officer may elect to place the total dredge plant in a standby status until conditions are favorable for economical and efficient dredging

operations. When the Contracting Officer directs that the total dredge plant be placed in a standby status, the Contractor will cease dredging operations and/or preparations for dredging operations, and will secure the total dredge in a location approved by the Contracting Officer. This may be a directed long term docking of the vessel by the Government for reasons other than that caused by the Contractor. Actual time lost due to circumstances uncontrollable by the Contractor. If the dredge is damaged, while on 40% pay time due to the weather conditions, the dredge will be placed on 0% pay time until the repairs are made and the dredge becomes fully operational at which time the dredge will be placed back on the applicable pay status.

22.2.3.1. The standby status will be measured and paid for by the hour measured to the nearest 1/60th of an hour at the rate of 40% of the 100% pay time rate for effective dredging.

22.2.4. 0% Pay Time: Payment will not be made for:

22.2.4.1. Lay time after arrival at a new work location when such time is incurred at the direction of the Contractor's representative or when, through the negligence of the Contractor, part of the necessary equipment needed to prepare the plant before and after a given move is not available, no payment will be made for the period of delay.

a. Time incurred during a failed leak test as required by paragraph 16.2.e.

b. Time lost due to stoppage of work due to safety violations.

c. Time of the complete cycle during which the material is placed outside of the assigned disposal area.

22.2.4.2. Shutdowns to stop leaks in pipeline, repair to dredge, pull a line together when the joints open up, replace damaged pontoons, except when pontoons are damaged by drift. Discharge line must be in use for conditions to apply.

22.2.4.3. Any time or purpose other than that enumerated above, except for mobilization and demobilization, including cleaning plugged line, removing misplaced material, dredging for others, shutdowns due to safety, shutdowns due to refueling, insufficient crew size, etc.

22.2.4.4. Any time the dredge is moved from the site of work at the Contractor's convenience.

22.2.4.5. Hours of darkness when the contractor chooses not to work. If the contractor chooses to place both crew shifts on daytime hours, the contractor will be 0% pay status at night.

22.3. Mobilization and Demobilization Trawler (Bid Item No. 3): All cost associated with mobilization and demobilization of all necessary man power and equipment to perform trawling operations as described in the SECTION 01 57 20.00 10. For estimation purposes assume the

mobilization site to be the Pascagoula Bar Channel.

22.4. Sea Turtle/Gulf Sturgeon Trawling (Bid Item No. 4):

Payment will include all costs associated with providing the trawler, sea turtle/gulf sturgeon observers and all items necessary to comply with the specifications, all environmental permits and the Regional Biological Opinion.

22.9. Reduced Percentage of Payment: Should any portion of the dredge plant become inoperable with the dredge still able to operate at a reduced rate of performance, the hourly rate of payment will be reduced by the same percentage as the reduction in dredge performance as compared to the fully operational dredge performance. See section entitled "PLANT MANAGEMENT" for other provisions regarding time allowed for repair.

23. NAVIGATION AIDS: Navigation aids located within or near the areas required to be dredged will be removed, if necessary, by the U.S. Coast Guard in advance of dredging operations. The Contractor will notify the Contracting Officer of any aids which will be required to be relocated to facilitate dredging. The Contracting Officer will then request the U.S. Coast Guard to relocate the aids.

24. QUALITY CONTROL:

24.1. Electronic positioning: While performing all excavation (dredging) work under this contract the contractor shall control the horizontal positioning of the dredge and make all required surveys with electronic positioning equipment. The dredge's electronic positioning equipment shall be installed and operated at all times.

24.2. The contractor shall establish and maintain quality control for operations under this section to assure compliance with contractual requirements and maintain records of his quality control for qualification of survey personnel, and accuracy and completeness of required survey work, including but not limited to the following:

a. Survey work shall be performed by survey personnel in accordance with "Manual of Survey Instructions", copies of which are available for review at the Mobile District Office. All responsibilities for accuracy, completeness and verification of survey work so performed shall remain with the Contractor.

b. Daily reports shall be made by the Contractor and shall be prepared using SAM Form 696 and 27A, attached hereto. All reports shall be prepared daily and signed by the Contractor's authorized representative and submitted to the Government's representative on the next duty day following the surveying activity. Said reports shall include, but not be limited to: equipment used; location, description, and type work performed; inspections of said work; verbal instructions received and actions taken; safety; and causes for delays.

c. The Contractor shall be responsible for protection of all vegetation and/or property within surveying areas. Should any portion of said survey work require tree trimming, or in anyway, use of private property or facilities, specific written consent shall be obtained by the Contractor from the affected owner prior to said survey action.

d. All survey work is subject to periodic inspection and/or verification by the Government during or after such work. Should any portion of the surveys be found to be in error it shall be the responsibility of the Contractor, at no cost to the Government, to correct such errors. Presence of the Government Representative on the work site does not release the Contractor of his responsibility for providing quality control of the required survey work and does not release the Contractor from the responsibility of taking necessary corrective action should errors be found. The determination of acceptable and unacceptable dredged channel remains the responsibility of the COR.

24.3. All surveys for open water disposal areas, baselines, hydroranges, cutting ranges and all other necessary survey work are to be performed by standard survey methods as referenced in Paragraph 24.2.a. Soundings shall be made at such intervals specified by the Government and to an accuracy of ± 0.5 foot. Tide will be observed and recorded every half hour, in addition to the beginning and ending of the survey. Tide heights will be read and recorded to the nearest 0.1 foot. All baselines and all markers, whether land or water based, shall be tied to existing land based survey markers using channel center line coordinates furnished by the Government. Then such survey work shall be clearly and completely recorded in standard field books, and shall be made available for inspection and/or verification by representatives of the Government. Said books shall, upon or before completion of the requirements of this contract, become the property of the Government. All poles, stakes, flagging, books, and/or other survey materials shall be furnished by the Contractor.

25. TASK ORDERS, DELIVERY, COMMENCEMENT, PROSECUTION AND COMPLETION OF WORK:

a. Task Orders will be issued continuously, however, after the dredge has been released, additional task orders may be issued if the dredge is available for additional work.

b. In the event that the Contractor has a conflict of schedules due to other Government contracts either with this district or other Corps districts, the Contracting Officer may elect to allow a substitute dredge to perform work during the interim time prior to the arrival of the originally proposed dredge. This substitution will only be allowed if the substitute dredge meets all the requirements of this solicitation and it is determined that the substitution is in the best interest of the Government. Any substitution will be by contract modification and the Contractor may experience delays or down time as a result of the required modification process. Any delay will be at the contractor's expense. There will be no increase in contract price by said

modification but the unit hourly rate may be adjusted by the percentage variation between the evaluation chart's hours for each dredge as listed in the contract. The Contractor is still required to meet both the percentages stated in the paragraph entitled Performance of Work by the Contractor and the commencement and prosecution times stated below.

c. The Government reserves the right to suspend operations whenever, in the opinion of the Contracting Officer, conditions will make dredging operations and disposal impracticable or uneconomical. If during the period of suspension ordered by the Contracting Officer, the dredge and attendant plant are removed at the convenience of the Contractor from the site of assignment from which operations were suspended, the plant shall be returned to operations under the contract within ten (10) calendar days after receipt by the Contractor of notice to resume operations.

d. In the event of suspension as outlined in subparagraph "c" above, the dredge and attendant plant shall not be removed from the site of work or from the area in which standing by, unless expressly consented to by the Contracting Officer.

e. Failure of the Contractor to comply with the requirements of the contract specifications will be cause for termination for default. Termination for default will be immediate, by written notice.

26. POTABLE WATER:

Testing of all potable water storage facilities and dispensing systems with a storage capacity of ten or more gallons, will be conducted by an independent testing laboratory approved by the Contracting Officer as follows:

- a. Prior to the commencement of work.
- b. Minimum of monthly, after start of work for the duration of the contract.
- c. After any repairs or modifications are made to the potable water storage or dispensing systems.
- d. After any intake of potable water into the storage system.

All samples shall meet state and local water quality standards for potable water. A copy of all test results will be forwarded to the Contracting Officer within seven working days for his review.

In the event a tested sample fails to meet state and local water quality standards, all dispensing outlets connected to the failing water storage shall be labeled as non-potable and other means of potable water shall be obtained until water quality can be provided to meet the required standards.

To insure potable water maintains water quality standards all portable potable water dispensing units shall be checked daily for cleanliness. All hoses used in the transfer of potable water shall be conspicuously marked and kept in such a manner as to keep them from being contaminated. These hoses shall be used for potable water transfer only.

27. PERFORMANCE EVALUATION OF CONTRACTOR:

As a minimum, the Contractor's performance will be evaluated upon final acceptance of the work. However, interim evaluation may be prepared at any time during contract performance when determined to be in the best interest of the Government.

The Contractor will be rated either exceptional, very good, satisfactory, marginal or unsatisfactory in the areas of Quality, Schedule, Cost Control, Management, Utilization of Small Business, Regulatory Compliance and Safety. The Contractor will be advised of any unsatisfactory rating, either in an individual element or in the overall rating, prior to completing the evaluation, and all Contractor comments will be made a part of the official records. Performance Evaluation Reports will be available to all DOD Contracting offices for their future use in determining Contractor responsibility, in compliance with DFARS 36.201(c)(1).

ATTACHMENT 1

Hopper Speed Chart

Island 1	Island 2	Weeks	Newport	Columbia	Lindholm	Terrapin	Stuyv.	Bayport	Liberty	Glenn E	
1500000	1500000	1500000	1500000	1500000	1500000	1500000	1500000	1500000	1500000	1500000	Gross Yardage
3594	3594	4009	4167	4387	4023	6400	9846	4830	6466	13572	Hopper Capacity
300	300	450	230	110	450	100	1000	250	87	270	Retained Material
3294	3294	3559	3937	4277	3573	6300	8846	4580	6379	13302	Effective Capacity
1976.4	1976.4	2135.4	2362.2	2566.2	2143.8	3780	5307.6	2748	3827.4	7981.2	60% Load
26.6	26.6	26.6	26.6	26.6	26.6	26.96	27.32	26.6	26.96	26.96	Haul Distance
9.87	10.56	9.19	9.67	12.48	12.26	10.89	11.44	10.34	12.19	12.25	MPH Loaded
10.97	11.97	10.54	11.02	12.8	12.42	11.88	12.78	12.54	13.62	14.86	MPH Light
2.70	2.52	2.89	2.75	2.13	2.17	2.48	2.39	2.57	2.21	2.20	Travel Time to Dump
2.42	2.22	2.52	2.41	2.08	2.14	2.27	2.14	2.12	1.98	1.81	Travel Time to Cut
0.5	0.5	0.5	0.5	0.75	0.5	0.5	0.5	0.5	0.5	0.5	Pump, turn, dump time
5.62	5.24	5.92	5.66	4.96	4.81	5.25	5.03	5.19	4.69	4.52	Total Cycle time
758.96	758.96	702.44	635.00	584.52	699.69	396.83	282.61	545.85	391.91	187.94	Number of cycles
4265.20	3977.81	4157.19	3597.01	2898.96	3366.47	2081.36	1420.37	2835.01	1838.49	848.57	Total Hours
4397.00	4101.00	4286.00	3708.00	2989.00	3471.00	2146.00	1464.00	2923.00	1895.00	875.00	97% efficiency Hours

SECTION 01 00 01

GENERAL CONTRACT REQUIREMENTS

**U.S. ARMY CORPS OF ENGINEERS SAFETY AND HEALTH REQUIREMENTS
MANUAL, EM 385- 1-1**

This paragraph applies to contracts and purchase orders that require the contractor to comply with EM 385-1-1 (e.g., contracts that include the Accident Prevention clause at FAR 52.236-13 and/or other safety provisions). EM 385-1-1 and its changes are available at <http://www.usace.army.mil/CESO/Pages/EM385-1-1.aspx>. The Contractor shall be responsible for complying with the current edition and all changes posted on the web through the date that is 10 calendar days prior to the date offers are due. If the solicitation is amended to extend the time set for receipt of offers, the 10 calendar days rule stated above shall be applied against the amended date. (For example, if offers are due on 10 April, all changes posted on or before 31 March shall apply to the contract. If the time for receipt of offers is extended from 10 April to 20 April, all changes posted on or before 10 April shall apply to the contract.)

AFFILIATED BIDDERS

(a) Business concerns are affiliates of each other when, either directly or indirectly, (1) one concern controls or has the power to control the other, or (2) a third party controls or has the power to control both.

(b) Each bidder shall submit with its bid an affidavit stating that it has no affiliates, or containing the following information.

(1) The names and addresses of all affiliates of the bidder.

(2) The names and addresses of all persons and concerns exercising control or ownership of the bidder and any or all of its affiliates, and whether they exercise such control or ownership as common officers, directors, stockholders, holding controlling interest, or otherwise.

Please check when applicable:

_____ The offeror certifies that it has no affiliates.

_____ The offeror certifies that it is affiliated with the concerns designated on an attached affidavit.

MANPOWER REPORTING - DEC 2012

The Office of the Assistant Secretary of the Army (Manpower & Reserve Affairs) operates and maintains a secure Army data collection site where the contractor will report ALL contractor

manpower (including subcontractor manpower) required for performance of this contract. The contractor is required to completely fill in all the information in the format using the following web address “<https://cmra.army.mil>. The required information includes:

- (1) Contracting Office, Contracting Officer, Contracting Officer’s Technical Representative;
- (2) Contract number, including task and delivery order number;
- (3) Beginning and ending dates covered by reporting period;
- (4) Contractor name, address, phone number, e-mail address, identity of contractor employee entering data;
- (5) Estimated direct labor hours (including subcontractors);
- (6) Estimated direct labor dollars paid this reporting period (including subcontractors);
- (7) Total payments (including subcontractors);
- (8) Predominant Federal Service Code (FSC) reflecting services provided by contractor (and separate predominant FSC for each subcontractor if different);
- (9) Estimated data collection cost;
- (10) Organizational title associated with the Unit Identification Code (UIC) for the Army Requiring Activity (the Army Requiring Activity is responsible for providing the contractor with its UIC for the purposes of reporting this information);
Note: UIC for Mobile District Civil Works funded projects is W2SR04 and Military funded projects is W07404. If you are unsure of the funding type, contact your COR or Contract Specialist.
- (11) Locations where contractor and subcontractors perform the work (specified by zip code in the United States and nearest city, country, when in an overseas location, using standardized nomenclature provided on website);
- (12) Presence of deployment or contingency contract language; and
- (13) Number of contractor and subcontractor employees deployed in theater this reporting period (by country).

As part of its submission, the contractor will also provide the estimated total cost (if any) incurred to comply with this reporting requirement. Reporting period will be the period of performance not to exceed 12 months ending September 30 of each government fiscal year and must be reported by 31 October of each calendar year. Contractors may use a direct XML data transfer to the database server or fill in the fields on the website. The XML direct transfer is a format for transferring files from a contractor’s systems to the secure web site without the need

for separate data entries for each required data element at the web site. The specific formats for the XML direct transfer may be downloaded from the web site.

(End of clause)

DESCRIPTION OF WORK

In general, the work shall consist of rental of a Hopper Dredge and Attendant Plant with Operators for maintenance dredging in Alabama, Mississippi, Florida

NOTE: The above general outline of features of the work does not in any way limit the responsibility of the Contractor to perform all work and furnish all plant, labor, equipment and materials required by the specifications and the drawings referred to therein. The cost of this work is estimated to be between \$1,000,000.00 and \$5,000,000.00.

MANUALS AND PUBLICATIONS

Engineering manuals and Concrete Research Division Publications may be obtained from the addresses given below.

Engineering Manuals: U. S. Army, Corps of Engineers
Publications Depot
2803 -52nd Avenue
Hyattsville, MD 20781-1102

Concrete Research Division Publications:

U.S. Army Engineer Waterways Experiment Station
ATTN: Publications Distribution Unit
P.O. Box 631
Vicksburg, MS 39180

BULLETIN BOARD

Immediately upon beginning of work under this contract, the Contractor shall provide at the job site a weatherproof glass-covered bulletin board for displaying the fair employment poster, wage rates, and safety bulletins and posters. Emergency telephone numbers and reporting instructions for ambulance, physician, hospital, fire and police shall be posted. The bulletin board shall be located in a conspicuous place easily accessible to all and legible copies of the aforementioned data shall be displayed until work under the contract is completed. No direct payment will be made for the bulletin board.

PRESERVATION OF HISTORICAL, ARCHEOLOGICAL AND CULTURAL RESOURCES

(a) If known historical, archeological and cultural resources exist within the Contractor's work area, they have been designated on the contract drawings. The Contractor shall install protection

for these resources as shown on the drawings and shall be responsible for their preservation during the contract.

(b) If, during construction activities, the Contractor observes items that might have historical or archeological value, such observations shall be reported immediately to the Contracting Officer so that the appropriate authorities may be notified and a determination can be made as to their significance and what, if any, special disposition of the finds should be made. The Contractor shall cease all activities that may result in the destruction of these resources and shall prevent his employees from trespassing on, removing, or otherwise damaging such resources.

REQUIRED INSURANCE

The Contractor shall procure and maintain during the entire period of his performance under this contract, the following minimum insurance in accordance with the Contract Clause entitled "Insurance-Work on a Government Installation." Workmen's Compensation and Employers' liability Insurance:

Workmen's Compensation and Occupational Disease Coverage in accordance with statutory limits. Employers' Liability Coverage with a minimum limit of \$100,000.

Comprehensive Automobile Liability Insurance:

Bodily injury coverage with minimum limits of \$200,000 per person and \$500,000 per occurrence. Property Damage Coverage with a minimum limit of \$20,000 per occurrence.

Comprehensive General Liability Insurance:

Bodily injury coverage with minimum limits of \$500,000 per occurrence.

WORK IN QUARANTINED AREA

The work called for by this contract involves activities in counties quarantined by the Department of Agriculture to prevent the spread of certain plant pests which may be present in the soil. The Contractor agrees that all construction equipment and tools to be moved from such counties shall be thoroughly cleaned of all soil residues at the construction site with water under pressure and that hand tools shall be thoroughly cleaned by brushing or other means to remove all soil. In addition, if this contract involves the identification, shipping, storage, testing, or disposal of soils from such a quarantined area, the Contractor agrees to comply with the provisions of ER 1110-1-5 and attachments, a copy of which will be made available by the Contracting Officer upon request. The Contractor agrees to assure compliance with this obligation by all subcontractors.

PROHIBITION AGAINST CONTRACTING WITH INDIVIDUALS OR ENTITIES DESIGNATED AS SIGNIFICANT NARCOTICS TRAFFICKERS

Pursuant to Executive Order 12978 entitled "Blocking Assets and Prohibiting Transactions with Significant Narcotic Traffickers" dated October 21, 1995, the offeror certifies that it has not and

will not be involved in business transactions with individuals or business entities designated as significant narcotics traffickers under this Executive Order. For a current listing of specially designated nationals and blocked persons, contact the Office of Foreign Assets Control, Department of the Treasury, Washington, DC 22201; telephone 202/622-2420.

(End of clause)

CONTRACTOR PAYMENT REQUEST

A copy of CESAM Form 1151 entitled PROMPT PAYMENT CERTIFICATION AND SUPPORTING DATA FOR CONTRACTOR PROGRESS PAYMENT INVOICE is included hereinafter, with instructions, following the Wage Rates. This form will be used in conjunction with the CONTRACT CLAUSE entitled PAYMENTS UNDER FIXED-PRICE CONSTRUCTION CONTRACTS. The contracting Officer will provide copies of the form to the Contractor upon request. The Contractor shall complete the form, sign the certification and submit it with each progress payment invoice.

KEY PERSONNEL, SUBCONTRACTORS AND OUTSIDE ASSOCIATES OR CONSULTANTS

Any key in-house personnel, subcontractors and outside associates or consultants required by the Contractor in connection with the services covered by the contract will be limited to individuals or firms that were specifically identified and agreed to during negotiations. The Contractor shall obtain the Contracting Officer's written consent before making any substitution for these designated key personnel, subcontractors, associates, or consultants.

REQUESTS FOR INFORMATION

Any questions about this solicitation, including technical questions about plans and specifications, shall be submitted to the Bidder's Inquiry Portal in ProjNet at <http://www.projnet.org/projnet> using the following inquiry key:

Bidder Inquiry Key: JA2FN6-KQHGJ5

Questions shall be submitted no later than ~~May 17, 2017~~ **June 14, 2017** at 2:00 p.m. Central Time to allow time for a response, and amendment to the solicitation if necessary.

For technical questions, no other means of communication, fax, or telephone will be accepted. Oral exchanges between Offerors or Bidders and the government prior to award of the contract will not be binding. Any information concerning this solicitation will be furnished to all Offerors or Bidders as an amendment to the solicitation if the information is necessary to the submittal of offers or bids.

The Solicitation Number is: W91278-17-B-0002

Offerors or Bidders are requested to review the solicitation and amendments in their entirety.

SECTION 01330

SUBMITTAL PROCEDURES

03/01

PART 1 GENERAL

1.3 SUBMITTAL IDENTIFICATION (SD)

All submittals shall be provided in electronic format unless otherwise directed by the COR or stated in the specifications.

SD-01 Preconstruction Submittals

The Contractor shall bring to this conference the following items in either complete or draft form – the Task Order will need to be awarded before some of these plans can be submitted:

- (1) Accident Prevention Plan
- (2) Activity Hazard Analysis
- (3) Job Hazard Analysis for each employee classification
- (4) Material Safety Data Sheets
- (5) List of First Aid and CPR trained personnel
- (6) Letter appointing representatives
- (7) List of Sub-Contractors
- (8) Quality Control Plan
- (9) Dredge Plant Instrumentation Plan
- (10) Environmental Protection Plan (including Pollution Control Plan)
- (11) Deposition Plan
- (12) Survey Plan (submit complete plan at preconstruction conference)

SD-02 Shop Drawings

Drawings, diagrams and schedules specifically prepared to illustrate some portion of the work.

Diagrams and instructions from a manufacturer or fabricator for use in producing the product and as aids to the contractor for integrating the product or system into the project.

Drawings prepared by or for the contractor to show how multiple systems and interdisciplinary work will be coordinated.

SD-03 Product Data

Catalog cuts, illustrations, schedules, diagrams, performance charts, instructions and brochures illustrating size, physical appearance and other characteristics of materials or equipment for some portion of the work.

Samples of warranty language when the contract requires extended product warranties.

SD-04 Samples

Physical examples of materials, equipment or workmanship that illustrate functional and aesthetic characteristics of a material or product and establish standards by which the work can be judged.

Color samples from the manufacturer's standard line (or custom color samples if specified) to be used in selecting or approving colors for the project.

Field samples and mock-ups constructed on the project site establish standards by which the ensuring work can be judged. Includes assemblies or portions of assemblies which are to be incorporated into the project and those which will be removed at conclusion of the work.

SD-05 Design Data

Calculations, mix designs, analyses or other data pertaining to a part of work.

SD-06 Test Reports

Report signed by authorized official of testing laboratory that a material, product or system identical to the material, product or system to be provided has been tested in accord with specified requirements. (Testing must have been within three years of date of contract award for the project.)

Report which includes findings of a test required to be performed by the contractor on an actual portion of the work or prototype prepared for the project before shipment to job site.

Report which includes finding of a test made at the job site or on sample taken from the job site, on portion of work during or after installation.

Investigation reports

Daily checklists

Final acceptance test and operational test procedure

SD-07 Certificates

Statements signed by responsible officials of manufacturer of product, system or material attesting that product, system or material meets specification requirements. Must be dated after award of project contract and clearly name the project.

Document required of Contractor, or of a supplier, installer or subcontractor through Contractor, the purpose of which is to further quality of orderly progression of a portion of the work by documenting procedures, acceptability of methods or personnel qualifications.

Confined space entry permits.

SD-08 Manufacturer's Instructions

Preprinted material describing installation of a product, system or material, including special notices and Material Safety Data sheets concerning impedances, hazards and safety precautions.

SD-09 Manufacturer's Field Reports

Documentation of the testing and verification actions taken by manufacturer's representative to confirm compliance with manufacturer's standards or instructions.

Factory test reports.

SD-10 Operation and Maintenance Data

Data intended to be incorporated in operations and maintenance manuals.

SD-11 Closeout Submittals

Documentation to record compliance with technical or administrative requirements or to establish an administrative mechanism.

As-built drawings.

Special warranties.

Posted operating instructions.

Training plan.

1.2 SUBMITTAL CLASSIFICATION

Submittals are classified as follows:

1.2.1 Government Approved

Governmental approval is required for extensions of design, critical materials, deviations, equipment whose compatibility with the entire system must be checked, and other items be designated by the Contracting Officer. Within the terms of the Contract Clause entitled "Specifications and Drawings for Construction," they are considered to be "shop drawings".

1.2.2 Information Only

All submittals not requiring Government approval will be for information only. They are not considered to be "shop drawings" within the terms of the Contract Clause referred to above.

1.3 APPROVED SUBMITTALS

The Contracting Officer's approval of submittals shall not be construed as a complete check, but will indicate only that the general method of construction, materials, detailing and other information are satisfactory. Approval will not relieve the Contractor of the responsibility for any error which may exist, as the Contractor under the CQC requirements of this contract is responsible for dimensions, the design of adequate connections and details, and the satisfactory construction of all work. After submittals have been approved by the Contracting Officer, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a substitution is necessary.

1.4 DISAPPROVED SUBMITTALS

The Contractor shall make all corrections required by the Contracting Officer and promptly furnish a corrected submittal in the form and number of copies specified for the initial submittal. If the Contractor considers any correction indicated on the submittals to constitute a change to the contract, a notice in accordance with the Contract Clause "Changes" shall be given promptly to the Contracting Officer.

1.5 WITHHOLDING OF PAYMENT

Payment for materials incorporated in the work will not be made if required approvals have not been obtained.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.1 GENERAL

The Contractor shall make submittals as required by the specifications. The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work covered in the respective sections. Units of weights and measures used on all submittals shall be the same as those used in the contract drawings. Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements. Prior to submittal, all items shall be checked and approved by the Contractor's Quality Control (CQC) representative and each item shall be stamped, signed, and dated by the CQC representative indicating action taken. Proposed deviations from the contract requirements shall be clearly identified. Submittals shall include items such as: Contractor's, manufacturer's, or fabricator's drawings; descriptive literature including (but not limited to) catalog cuts, diagrams, operating charts or curves; test reports; test cylinders; samples; O&M manuals (including parts list); certifications, warranties; and other such required submittals. Submittals requiring Government approval shall be scheduled and made prior to the acquisition of the material or equipment covered thereby. Samples remaining upon completion of the work shall be picked up and disposed of in accordance with manufacturer's Material Safety Data Sheets (MSDS) and in compliance with existing laws and regulations.

3.2 SUBMITTAL REGISTER

At the beginning of this section is a listing of items identified in the specifications as requiring submittals. The list is not all inclusive and additional submittals may be required by other parts of the contract. The contractor is required to complete the attached submittal form and submit to the Contracting Officer for approval within 15 calendar days after Notice to Proceed. The approved submittal register will serve as a scheduling document for submittals and will be used to control submittal actions throughout the contract period. The submit dates and need dates used in the submittal register shall be coordinated with dates in the contractor prepared progress schedule. Updates to the submittal register showing the contractor action codes and actual dates with government action codes and actual dates shall be submitted monthly or until all submittals have been satisfactorily completed. When the progress schedule is revised, the submittal register shall also be revised and both submitted for approval.

3.3 SCHEDULING

Submittals covering component items forming a system or items that are interrelated shall be scheduled to be coordinated and submitted concurrently. Certifications to be submitted with the pertinent drawings shall be so scheduled. Adequate time (a

minimum of 30 calendar days exclusive of mailing time) shall be allowed and shown on the register for review and approval. No delay damages or time extensions will be allowed for time lost in late submittals. An additional 15 calendar days shall be allowed and shown on the register for review and approval of submittals for food service equipment and refrigeration and HVAC control systems and 30 additional days for review of systems furniture, interior design packages and color boards.

3.4 TRANSMITTAL FORM (ENG FORM 4025)

The sample transmittal form (ENG FORM 4025) attached to this section shall be used for submitting both Government approved and information only submittals in accordance with the instructions on the reverse side of the form. These forms will be furnished to the Contractor. These form shall be properly completed by filling out all the heading blank spaces and identifying each item submitted. Special care shall be exercised to ensure proper listing of the specification paragraph and/or sheet number of the contract drawings pertinent to the data submittal for each item.

3.5 SUBMITTAL PROCEDURES

Submittals shall be made as follows:

3.5.1 Procedures

Detailed submittal procedures will be further discussed with the contractor at the pre-construction conference.

3.5.2 Deviations

For submittals which include proposed deviations requested by the Contractor, the column "variation" of ENG Form 4025 shall be checked. The Contractor shall set forth in writing the reason for any deviations and annotate such deviations on the submittal. The Government reserves the right to rescind inadvertent approval of submittals containing unnoted deviations.

3.6 CONTROL OF SUBMITTALS

The Contractor shall carefully control his procurement operations to ensure that each individual submittal is made on or before the Contractor scheduled submittal date shown on the approved "Submittal Register."

3.7 GOVERNMENT APPROVED SUBMITTALS

Upon completion of review of submittals requiring Government approval, the submittals will be identified as having received approval by being so stamped and

dated. 4 copies of the submittal will be retained by the Contracting Officer and 2 copies of the submittal will be returned to the Contractor.

3.8 INFORMATION ONLY SUBMITTALS

Normally submittals for information only will not be returned. Approvals of the Contracting Officer is not required on information only submittals. The Government reserves the right to require the Contractor to resubmit any item found not to comply with the contract. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporated in the work; and does not relieve the Contractor of the requirement to furnish samples for testing by the Government in those instances where the technical specification so prescribe.

3.9 STAMPS

Stamps used by the Contractor on the submittal data to certify that the submittal meets contract requirements shall be similar to the following:

CONTRACTOR
(Firm Name)
_____ Approved
_____ Approved with corrections as noted on submittal data and/or attached sheets(s).
SIGNATURE: _____
TITLE: _____
DATE: _____

-- End of Section --

SECTION 01 35 26

GOVERNMENTAL SAFETY REQUIREMENTS
11/15

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF SAFETY ENGINEERS (ASSE/SAFE)

ASSE/SAFE A10.34	(2001; R 2012) Protection of the Public on or Adjacent to Construction Sites
ASSE/SAFE A10.44	(2014) Control of Energy Sources (Lockout/Tagout) for Construction and Demolition Operations
ASSE/SAFE Z244.1	(2003; R 2014) Control of Hazardous Energy Lockout/Tagout and Alternative Methods
ASSE/SAFE Z359.0	(2012) Definitions and Nomenclature Used for Fall Protection and Fall Arrest
ASSE/SAFE Z359.1	(2007) Safety Requirements for Personal Fall Arrest Systems, Subsystems and Components
ASSE/SAFE Z359.11	(2014) Safety Requirements for Full Body Harnesses
ASSE/SAFE Z359.12	(2009) Connecting Components for Personal Fall Arrest Systems
ASSE/SAFE Z359.13	(2013) Personal Energy Absorbers and Energy Absorbing Lanyards
ASSE/SAFE Z359.14	(2014) Safety Requirements for Self-Retracting Devices for Personal Fall Arrest and Rescue Systems
ASSE/SAFE Z359.15	(2014) Safety Requirements for Single Anchor Lifelines and Fall Arresters for Personal Fall Arrest Systems
ASSE/SAFE Z359.2	(2007) Minimum Requirements for a Comprehensive Managed Fall Protection Program
ASSE/SAFE Z359.3	(2007) Safety Requirements for Positioning and Travel Restraint Systems
ASSE/SAFE Z359.4	(2013) Safety Requirements for Assisted-Rescue and Self-Rescue Systems,

Subsystems and Components

ASSE/SAFE Z359.6 (2009) Specifications and Design
Requirements for Active Fall Protection
Systems

ASSE/SAFE Z359.7 (2011) Qualification and Verification
Testing of Fall Protection Products

ASME INTERNATIONAL (ASME)

ASME B30.20 (2013; INT Oct 2010 - May 2012)
Below-the-Hook Lifting Devices

ASME B30.22 (2010) Articulating Boom Cranes

ASME B30.26 (2015; INT Jun 2010 - Jun 2014) Rigging
Hardware

ASME B30.3 (2016) Tower Cranes

ASME B30.5 (2014) Mobile and Locomotive Cranes

ASME B30.8 (2015) Floating Cranes and Floating
Derricks

ASME B30.9 (2014; INT Feb 2011 - Nov 2013) Slings

ASTM INTERNATIONAL (ASTM)

ASTM F855 (2015) Standard Specifications for
Temporary Protective Grounds to Be Used on
De-energized Electric Power Lines and
Equipment

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 1048 (2003) Guide for Protective Grounding of
Power Lines

IEEE C2 (2012; Errata 1 2012; INT 1-4 2012; Errata
2 2013; INT 5-7 2013; INT 8-10 2014; INT
11 2015; INT 12 2016) National Electrical
Safety Code

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 10 (2013) Standard for Portable Fire
Extinguishers

NFPA 241 (2013; Errata 2015) Standard for
Safeguarding Construction, Alteration, and
Demolition Operations

NFPA 51B (2014) Standard for Fire Prevention During
Welding, Cutting, and Other Hot Work

NFPA 70 (2014; AMD 1 2013; Errata 1 2013; AMD 2
2013; Errata 2 2013; AMD 3 2014; Errata

3-4 2014; AMD 4-6 2014) National
Electrical Code

NFPA 70E (2015; ERTA 1 2015) Standard for
Electrical Safety in the Workplace

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1 (2014) Safety and Health Requirements
Manual

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910 Occupational Safety and Health Standards

29 CFR 1910.146 Permit-required Confined Spaces

29 CFR 1910.147 Control of Hazardous Energy (Lock Out/Tag
Out)

29 CFR 1910.333 Selection and Use of Work Practices

29 CFR 1915 Confined and Enclosed Spaces and Other
Dangerous Atmospheres in Shipyard
Employment

29 CFR 1915.89 Control of Hazardous Energy
(Lockout/Tags-Plus)

29 CFR 1926 Safety and Health Regulations for
Construction

29 CFR 1926.1400 Cranes and Derricks in Construction

29 CFR 1926.16 Rules of Construction

29 CFR 1926.450 Scaffolds

29 CFR 1926.500 Fall Protection

CPL 2.100 (1995) Application of the Permit-Required
Confined Spaces (PRCS) Standards, 29 CFR
1910.146

1.2 DEFINITIONS

1.2.1 Competent Person (CP)

The CP is a person designated in writing, who, through training, knowledge and experience, is capable of identifying, evaluating, and addressing existing and predictable hazards in the working environment or working conditions that are dangerous to personnel, and who has authorization to take prompt corrective measures with regards to such hazards.

1.2.2 Competent Person, Confined Space

The CP, Confined Space, is a person meeting the competent person requirements as defined EM 385-1-1 Appendix Q, with thorough knowledge of OSHA's Confined Space Standard, 29 CFR 1910.146, and designated in writing

to be responsible for the immediate supervision, implementation and monitoring of the confined space program, who through training, knowledge and experience in confined space entry is capable of identifying, evaluating and addressing existing and potential confined space hazards and, who has the authority to take prompt corrective measures with regard to such hazards.

1.2.3 Competent Person, Cranes and Rigging

The CP, Cranes and Rigging, as defined in EM 385-1-1 Appendix Q, is a person meeting the competent person, who has been designated in writing to be responsible for the immediate supervision, implementation and monitoring of the Crane and Rigging Program, who through training, knowledge and experience in crane and rigging is capable of identifying, evaluating and addressing existing and potential hazards and, who has the authority to take prompt corrective measures with regard to such hazards.

1.2.4 Competent Person, Excavation/Trenching

A CP, Excavation/Trenching, is a person meeting the competent person requirements as defined in EM 385-1-1 Appendix Q and 29 CFR 1926, who has been designated in writing to be responsible for the immediate supervision, implementation and monitoring of the excavation/trenching program, who through training, knowledge and experience in excavation/trenching is capable of identifying, evaluating and addressing existing and potential hazards and, who has the authority to take prompt corrective measures with regard to such hazards.

1.2.5 Competent Person, Fall Protection

The CP, Fall Protection, is a person meeting the competent person requirements as defined in EM 385-1-1 Appendix Q and in accordance with ASSE/SAFE Z359.0, who has been designated in writing by the employer to be responsible for immediate supervising, implementing and monitoring of the fall protection program, who through training, knowledge and experience in fall protection and rescue systems and equipment, is capable of identifying, evaluating and addressing existing and potential fall hazards and, who has the authority to take prompt corrective measures with regard to such hazards.

1.2.6 Competent Person, Scaffolding

The CP, Scaffolding is a person meeting the competent person requirements in EM 385-1-1 Appendix Q, and designated in writing by the employer to be responsible for immediate supervising, implementing and monitoring of the scaffolding program. The CP for Scaffolding has enough training, knowledge and experience in scaffolding to correctly identify, evaluate and address existing and potential hazards and also has the authority to take prompt corrective measures with regard to these hazards. CP qualifications must be documented and include experience on the specific scaffolding systems/types being used, assessment of the base material that the scaffold will be erected upon, load calculations for materials and personnel, and erection and dismantling. The CP for scaffolding must have a documented, minimum of 8-hours of scaffold training to include training on the specific type of scaffold being used (e.g. mast-climbing, adjustable, tubular frame), in accordance with EM 385-1-1 Section 22.B.02.

1.2.7 Competent Person (CP) Trainer

A competent person trainer as defined in EM 385-1-1 Appendix Q, who is qualified in the material presented, and who possesses a working knowledge of applicable technical regulations, standards, equipment and systems related to the subject matter on which they are training Competent Persons. A competent person trainer must be familiar with the typical hazards and the equipment used in the industry they are instructing. The training provided by the competent person trainer must be appropriate to that specific industry. The competent person trainer must evaluate the knowledge and skills of the competent persons as part of the training process.

1.2.8 High Risk Activities

High Risk Activities are activities that involve work at heights, crane and rigging, excavations and trenching, scaffolding, electrical work, and confined space entry.

1.2.9 High Visibility Accident

A High Visibility Accident is any mishap which may generate publicity or high visibility.

1.2.10 Load Handling Equipment (LHE)

LHE is a term used to describe cranes, hoists and all other hoisting equipment (hoisting equipment means equipment, including crane, derricks, hoists and power operated equipment used with rigging to raise, lower or horizontally move a load).

1.2.11 Medical Treatment

Medical Treatment is treatment administered by a physician or by registered professional personnel under the standing orders of a physician. Medical treatment does not include first aid treatment even though provided by a physician or registered personnel.

1.2.12 Near Miss

A Near Miss is a mishap resulting in no personal injury and zero property damage, but given a shift in time or position, damage or injury may have occurred (e.g., a worker falls off a scaffold and is not injured; a crane swings around to move the load and narrowly misses a parked vehicle).

1.2.13 Operating Envelope

The Operating Envelope is the area surrounding any crane or load handling equipment. Inside this "envelope" is the crane, the operator, riggers and crane walkers, other personnel involved in the operation, rigging gear between the hook, the load, the crane's supporting structure (i.e. ground or rail), the load's rigging path, the lift and rigging procedure.

1.2.14 Qualified Person (QP)

The QP is a person designated in writing, who, by possession of a recognized degree, certificate, or professional standing, or extensive knowledge, training, and experience, has successfully demonstrated their ability to solve or resolve problems related to the subject matter, the

work, or the project.

1.2.15 Qualified Person, Fall Protection (QP for FP)

A QP for FP is a person meeting the requirements of EM 385-1-1 Appendix Q, and ASSE/SAFE Z359.0, with a recognized degree or professional certificate and with extensive knowledge, training and experience in the fall protection and rescue field who is capable of designing, analyzing, and evaluating and specifying fall protection and rescue systems.

1.2.16 Recordable Injuries or Illnesses

Recordable Injuries or Illnesses are any work-related injury or illness that results in:

- a. Death, regardless of the time between the injury and death, or the length of the illness;
- b. Days away from work (any time lost after day of injury/illness onset);
- c. Restricted work;
- d. Transfer to another job;
- e. Medical treatment beyond first aid;
- f. Loss of consciousness; or
- g. A significant injury or illness diagnosed by a physician or other licensed health care professional, even if it did not result in (a) through (f) above.

1.2.17 USACE Property and Equipment

Interpret "USACE" property and equipment specified in USACE EM 385-1-1 as Government property and equipment.

1.2.18 Load Handling Equipment (LHE) Accident or Load Handling Equipment Mishap

A LHE accident occurs when any one or more of the eight elements in the operating envelope fails to perform correctly during operation, including operation during maintenance or testing resulting in personnel injury or death; material or equipment damage; dropped load; derailment; two-blocking; overload; or collision, including unplanned contact between the load, crane, or other objects. A dropped load, derailment, two-blocking, overload and collision are considered accidents, even though no material damage or injury occurs. A component failure (e.g., motor burnout, gear tooth failure, bearing failure) is not considered an accident solely due to material or equipment damage unless the component failure results in damage to other components (e.g., dropped boom, dropped load, or roll over). Document any mishap that meets the criteria described in the Contractor Significant Incident Report (CSIR) using the Crane High Hazard working group mishap reporting form.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation;

submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Accident Prevention Plan (APP); G, SO

SD-06 Test Reports

Monthly Exposure Reports

Notifications and Reports

Accident Reports; G, SO

LHE Inspection Reports

SD-07 Certificates

Crane Operators/Riggers

Standard Lift Plan; G, SO

Critical Lift Plan ; G, SO

Naval Architecture Analysis; G, SO

Activity Hazard Analysis (AHA)

Confined Space Entry Permit

Hot Work Permit

Certificate of Compliance

License Certificates

1.4 MONTHLY EXPOSURE REPORTS

Provide a Monthly Exposure Report and attach to the monthly billing request. This report is a compilation of employee-hours worked each month for all site workers, both Prime and subcontractor. Failure to submit the report may result in retention of up to 10 percent of the voucher.

1.5 SITE QUALIFICATIONS, DUTIES, AND MEETINGS

1.5.1 Personnel Qualifications

1.5.1.1 Site Safety and Health Officer (SSHO)

Provide an SSHO that meets the requirements of EM 385-1-1 Section 1. The SSHO must ensure that the requirements of 29 CFR 1926.16 are met for the project. Provide a Safety oversight team that includes a minimum of one (1) person at each project site to function as the Site Safety and Health Officer (SSHO). The SSHO or an equally-qualified Alternate SSHO must be at the work site at all times to implement and administer the Contractor's

safety program and government-accepted Accident Prevention Plan. The SSHO and Alternate SSHO must have the required training, experience, and qualifications in accordance with EM 385-1-1 Section 01.A.17, and all associated sub-paragraphs.

If the SSHO is off-site for a period longer than 24 hours, an equally-qualified alternate SSHO must be provided and must fulfill the same roles and responsibilities as the primary SSHO. When the SSHO is temporarily (up to 24 hours) off-site, a Designated Representative (DR), as identified in the AHA may be used in lieu of an Alternate SSHO, and must be on the project site at all times when work is being performed. Note that the DR is a collateral duty safety position, with safety duties in addition to their full time occupation.

1.5.1.2 Contractor Quality Control (QC) Manager:

The Contractor Quality Control Manager cannot be the SSHO on this project, even though the QC has safety inspection responsibilities as part of the QC duties.

1.5.1.3 Competent Person Qualifications

Provide Competent Persons in accordance with EM 385-1-1, Appendix Q and herein. Competent Persons for high risk activities include confined space, cranes and rigging, excavation/trenching, fall protection, and electrical work. The CP for these activities must be designated in writing, and meet the requirements for the specific activity (i.e. competent person, fall protection).

The Competent Person identified in the Contractor's Safety and Health Program and accepted Accident Prevention Plan, must be on-site at all times when the work that presents the hazards associated with their professional expertise is being performed. Provide the credentials of the Competent Persons(s) to the Contracting Officer for information in consultation with the Safety Office.

1.5.1.3.1 Competent Person for Confined Space Entry

Provide a Confined Space (CP) Competent Person who meets the requirements of EM 385-1-1, Appendix Q, and herein. The CP for Confined Space Entry must supervise the entry into each confined space.

Since this work involves marine operations that handle combustible or hazardous materials, this person must have the ability to understand and follow through on the air sampling, Personal Protective Equipment (PPE), and instructions of a Marine Chemist, Coast Guard authorized persons, or Certified Industrial Hygienist. Confined space and enclosed space work must comply with NFPA 306, OSHA 29 CFR 1915, Subpart B, "Confined and Enclosed Spaces and Other Dangerous Atmospheres in Shipyard Employment," or as applicable, 29 CFR 1910.147 for general industry.

1.5.1.3.2 Competent Person for Fall Protection

Provide a Competent Person for Fall Protection who meets the requirements of EM 385-1-1, Section 21.C.04 and herein.

1.5.1.4 Qualified Trainer Requirements

Individuals qualified to instruct the 40 hour contract safety awareness course, or portions thereof, must meet the definition of a Competent Person Trainer, and, at a minimum, possess a working knowledge of the following

subject areas: EM 385-1-1, Electrical Standards, Lockout/Tagout, Fall Protection, Confined Space Entry for Construction; Excavation, Trenching and Soil Mechanics, and Scaffolds in accordance with 29 CFR 1926.450, Subpart L.

Instructors are required to:

- a. Prepare class presentations that cover construction-related safety requirements.
- b. Ensure that all attendees attend all sessions by using a class roster signed daily by each attendee. Maintain copies of the roster for at least five (5) years. This is a certification class and must be attended 100 percent. In cases of emergency where an attendee cannot make it to a session, the attendee can make it up in another class session for the same subject.
- c. Update training course materials whenever an update of the EM 385-1-1 becomes available.
- d. Provide a written exam of at least 50 questions. Students are required to answer 80 percent correctly to pass.
- e. Request, review and incorporate student feedback into a continuous course improvement program.

1.5.1.5 USACE Dredging Contract Requirements

1.5.1.5.1 Dredging Safety Personnel Requirements

- a. Provide a minimum of one full time SSHO assigned per project site for the primary working shift.
- b. For a project involving multiple work shifts, provide one full-time SSHO for each additional shift. Provide one Collateral Duty Safety Officer (CDSO) on a dredge and one at the dredged material placement site. During these shifts, the SSHO must be available at all times to assist with emergency situations.
- c. For individual dredging projects or sites with a dredge crew and fill crew on watch of 8 employees or less, a CDSO must be appointed, instead of an SSHO. The CDSO assumes the same responsibilities as a full-time SSHO.
- d. An example of one dredging project site is reflected in each of the following:
 - (1) a mechanical dredge, tug(s) and scow(s), scow route, and material placement site; or
 - (2) a hydraulic pipeline dredge, attendant plant, and material placement site; or,
 - (3) a hopper dredge (include land-based material placement site - if applicable.
- e. For Hopper Dredges with the U.S. Coast Guard, documented crews may designate an officer as a Collateral Duty Safety Officer (CDSO) instead of having a full-time SSHO onboard if the officer meets the SSHO training and experience requirements.

1.5.1.5.2 SSHO Requirements for Dredging

- a. In addition to requirements stated elsewhere in this specification, an individual serving as a SSHO must be present at the project site, located so that they have full mobility and reasonable access to all major work operations, for at least one shift in each 24 hour period when work is being performed. The SSHO must be available during their shift for immediate verbal consultation and notification, either by phone or radio.
- b. The SSHO is a full-time, dedicated position, except as noted above, who must report to a senior project (or corporate) official. When the SSHO is permitted to be a collateral duty, the SSHO is not permitted to be in another position requiring continuous mechanical or equipment operations, such as equipment operators.
- c. The SSHO must inspect all work areas and operations during initial set-up and at least monthly observe and provide personal oversight on each shift during dredging operations for projects with many work sites, more often for those with less work sites.
- d. If the SSHO is off-site for a period longer than 24 hours, another qualified SSHO must be provided and fulfill the same roles and responsibilities as the SSHO during their absence.

1.5.1.5.3 Collateral Duty Safety Officer (CDSO) Requirements for Dredging

- a. A CDSO is an individual who is assigned collateral duty safety responsibilities in addition to their full-time occupation, and who supports and supplements the SSHO efforts in managing, implementing and enforcing the Contractor's Safety and Health Program. The assigned CDSO must be an individual(s) with work oversight responsibilities, such as master, mate, fill foreman, or superintendent. A CDSO must not be an employee responsible for continuous mechanical or equipment operations, such as an equipment operator.
- b. A CDSO performs safety program tasks as assigned by the SSHO and must report safety findings to the SSHO. The SSHO must document results of safety findings and provide information for inclusion in the CQC reports to the Contracting Officer.

1.5.1.5.4 Safety Personnel Training Requirements for Dredging

A SSHO and a CDSO for dredging contracts must take either a formal classroom or online OSHA 30-hour Construction Safety Course, or an equivalent 30 hours of formal classroom or online safety and health training covering the subjects of the OSHA 30-hour Course in accordance with EM 385-1-1 Appendix A, paragraph 3.d.(3), applicable to dredging work, and given by qualified instructors. In exception to EM 385-1-1, Section 01.A.17, comply with the following:

- a. The SSHO must maintain competency through having taken 8 hours of formal classroom or online safety and health related coursework every year. Hours spent as an instructor in such courses will be considered the same as attending them, but each course only gets credit once (for example, instructing a 1-hour asbestos awareness course 5 times in a year provides one hour credit for training).
- b. The SSHO and a CDSO must have a minimum of three years of experience within the past five years in one of the following:

- (1) Supervising/managing dredging activities

- (2) Supervising/managing marine construction activities
- (3) Supervising/managing land-based construction activities
- (4) Work managing safety programs or processes
- (5) Conducting hazard analyses and developing controls in activities or environments with similar hazards

1.5.1.6 Crane Operators/Riggers

Provide Operators meeting the requirements in EM 385-1-1, Section 15.B for Riggers and Section 16.B for Crane Operators. In addition, for mobile cranes with Original Equipment Manufacturer (OEM) rated capacities of 50,000 pounds or greater, designate crane operators qualified by a source that qualifies crane operators (i.e., union, a government agency, or an organization that tests and qualifies crane operators). Provide proof of current qualification.

1.5.2 Personnel Duties

1.5.2.1 Duties of the Site Safety and Health Officer (SSHO)

The SSHO must:

- a. Conduct daily safety and health inspections and maintain a written log which includes area/operation inspected, date of inspection, identified hazards, recommended corrective actions, estimated and actual dates of corrections. Attach safety inspection logs to the Contractors' daily quality control report.
- b. Conduct mishap investigations and complete required accident reports. Report mishaps and near misses.
- c. Use and maintain OSHA's Form 300 to log work-related injuries and illnesses occurring on the project site for Prime Contractors and subcontractors, and make available to the Contracting Officer upon request. Post and maintain the Form 300A on the site Safety Bulletin Board.
- d. Maintain applicable safety reference material on the job site.
- e. Attend the pre-construction conference, pre-work meetings including preparatory meetings, and periodic in-progress meetings.
- f. Review the APP and AHAs for compliance with EM 385-1-1, and approve, sign, implement and enforce them.
- g. Establish a Safety and Occupational Health (SOH) Deficiency Tracking System that lists and monitors outstanding deficiencies until resolution.
- h. Ensure subcontractor compliance with safety and health requirements.
- i. Maintain a list of hazardous chemicals on site and their material Safety Data Sheets (SDS).
- j. Maintain a weekly list of high hazard activities involving energy, equipment, excavation, entry into confined space, and elevation, and be prepared to discuss details during QC Meetings.

- k. Provide and keep a record of site safety orientation and indoctrination for Contractor employees, subcontractor employees, and site visitors.

Superintendent, QC Manager, and SSHO are subject to dismissal if the above duties are not being effectively carried out. If Superintendent, QC Manager, or SSHO are dismissed, project work will be stopped and will not be allowed to resume until a suitable replacement is approved and the above duties are again being effectively carried out.

1.5.3 Meetings

1.5.3.1 Preconstruction Conference

- a. Contractor representatives who have a responsibility or significant role in accident prevention on the project must attend the preconstruction conference. This includes the project superintendent, Site Safety and Occupational Health officer, quality control manager, or any other assigned safety and health professionals who participated in the development of the APP (including the Activity Hazard Analyses (AHAs) and special plans, program and procedures associated with it).
- b. Discuss the details of the submitted APP to include incorporated plans, programs, procedures and a listing of anticipated AHAs that will be developed and implemented during the performance of the contract. This list of proposed AHAs will be reviewed at the conference and an agreement will be reached between the Contractor and the Contracting Officer as to which phases will require an analysis. In addition, establish a schedule for the preparation, submittal, and Government review of AHAs to preclude project delays.
- c. Deficiencies in the submitted APP, identified during the Contracting Officer's review, must be corrected, and the APP re-submitted for review prior to the start of construction. Work is not permitted to begin work until an APP is established that is acceptable to the Contracting Officer.

1.5.3.2 Safety Meetings

Conduct safety meetings to review past activities, plan for new or changed operations, review pertinent aspects of appropriate AHA (by trade), establish safe working procedures for anticipated hazards, and provide pertinent Safety and Occupational Health (SOH) training and motivation. Conduct meetings at least once a month for all supervisors on the project location. The SSHO, supervisors, or foremen must conduct meetings at least once a week for the trade workers. Document meeting minutes to include the date, persons in attendance, subjects discussed, and names of individual(s) who conducted the meeting. Maintain documentation on-site and furnish copies to the Contracting Officer on request. Notify the Contracting Officer of all scheduled meetings 7 calendar days in advance.

1.6 ACCIDENT PREVENTION PLAN (APP)

A qualified person must prepare the written site-specific APP. Prepare the APP in accordance with the format and requirements of EM 385-1-1, Appendix A, and as supplemented herein. Cover all paragraph and subparagraph elements in EM 385-1-1, Appendix A. The APP must be job-specific and address any unusual or unique aspects of the project or activity for which it is written. The APP must interface with the Contractor's overall safety and health program referenced in the APP in the applicable APP element, and made site-specific. Describe the methods to evaluate past safety performance of potential subcontractors in the selection process. Also, describe innovative methods used to ensure and monitor safe work practices

of subcontractors. The Government considers the Prime Contractor to be the "controlling authority" for all work site safety and health of the subcontractors. Contractors are responsible for informing their subcontractors of the safety provisions under the terms of the contract and the penalties for noncompliance, coordinating the work to prevent one craft from interfering with or creating hazardous working conditions for other crafts, and inspecting subcontractor operations to ensure that accident prevention responsibilities are being carried out. The APP must be signed by an officer of the firm (Prime Contractor senior person), the individual preparing the APP, the on-site superintendent, the designated SSHO, the Contractor Quality Control Manager, and any designated Certified Safety Professional (CSP) or Certified Health Physicist (CIH). The SSHO must provide and maintain the APP and a log of signatures by each subcontractor foreman, attesting that they have read and understand the APP, and make the APP and log available on-site to the Contracting Officer. If English is not the foreman's primary language, the Prime Contractor must provide an interpreter.

Submit the APP to the Contracting Officer 15 calendar days prior to the date of the preconstruction conference for acceptance. Work cannot proceed without an accepted APP. Once reviewed and accepted by the Contracting Officer, the APP and attachments will be enforced as part of the contract. Disregarding the provisions of this contract or the accepted APP is cause for stopping of work, at the discretion of the Contracting Officer, until the matter has been rectified. Continuously review and amend the APP, as necessary, throughout the life of the contract. Changes to the accepted APP must be made with the knowledge and concurrence of the Contracting Officer, project superintendent, SSHO and Quality Control Manager. Incorporate unusual or high-hazard activities not identified in the original APP as they are discovered. Should any severe hazard exposure (i.e. imminent danger) become evident, stop work in the area, secure the area, and develop a plan to remove the exposure and control the hazard. Notify the Contracting Officer within 24 hours of discovery. Eliminate and remove the hazard. In the interim, take all necessary action to restore and maintain safe working conditions in order to safeguard onsite personnel, visitors, the public (as defined by ASSE/SAFE A10.34), and the environment.

1.6.1 Names and Qualifications

Provide plans in accordance with the requirements outlined in Appendix A of EM 385-1-1, including the following:

- a. Names and qualifications (resumes including education, training, experience and certifications) of site safety and health personnel designated to perform work on this project to include the designated Site Safety and Health Officer and other competent and qualified personnel to be used. Specify the duties of each position.
- b. Qualifications of competent and of qualified persons. As a minimum, designate and submit qualifications of competent persons for each of the following major areas: excavation; scaffolding; fall protection; hazardous energy; confined space; health hazard recognition, evaluation and control of chemical, physical and biological agents; and personal protective equipment and clothing to include selection, use and maintenance.

1.6.2 Plans

Provide plans in the APP in accordance with the requirements outlined in Appendix A of EM 385-1-1, including the following:

1.6.2.1 Confined Space Entry Plan

Develop a confined or enclosed space entry plan in accordance with EM 385-1-1, applicable OSHA standards 29 CFR 1910, 29 CFR 1915, and 29 CFR 1926, OSHA Directive CPL 2.100, and any other federal, state and local regulatory requirements identified in this contract. Identify the qualified person's name and qualifications, training, and experience. Delineate the qualified person's authority to direct work stoppage in the event of hazardous conditions. Include procedure for rescue by contractor personnel and the coordination with emergency responders. (If there is no confined space work, include a statement that no confined space work exists and none will be created.)

1.6.2.2 Standard Lift Plan (SLP)

Plan lifts to avoid situations where the operator cannot maintain safe control of the lift. Prepare a written SLP in accordance with EM 385-1-1, Section 16.A.03, using Form 16-2 for every lift or series of lifts (if duty cycle or routine lifts are being performed). The SLP must be developed, reviewed and accepted by all personnel involved in the lift in conjunction with the associated AHA. Signature on the AHA constitutes acceptance of the plan. Maintain the SLP on the LHE for the current lift(s) being made. Maintain historical SLPs for a minimum of 3 months.

1.6.2.3 Critical Lift Plan - Crane or Load Handling Equipment

Provide a Critical Lift Plan as required by EM 385-1-1, Section 16.H.01, using Form 16-3. Critical lifts require detailed planning and additional or unusual safety precautions. Develop and submit a critical lift plan to the Contracting Officer 30 calendar days prior to critical lift. Comply with load testing requirements in accordance with EM 385-1-1, Section 16.F.03.

In addition to the requirements of EM 385-1-1, Section 16.H.02, the critical lift plan must include the following:

- a. For lifts of personnel, demonstrate compliance with the requirements of 29 CFR 1926.1400 and EM 385-1-1, Section 16.T.
- b. For barge mounted mobile cranes, provide a Naval Architecture Analysis and include an LHE Manufacturer's Floating Service Load Chart in accordance with the criteria from the selected standard in EM 385-1-1, Section 16.L.02. The Floating Service Load Chart must provide a table of rated load versus boom angle and radius. The Floating Service Load Chart must also provide the maximum allowable machine list and trim associated with the tabular loads and radii provided. If the Manufacturer's Floating Service Load Chart is not available, a floating service load chart may be developed and provided by a qualified Registered Professional Engineer (RPE), competent in the field of floating cranes. The Load Chart must be in accordance with the criteria from the selected standard in EM 385-1-1, Section 16.L; provide a table of rated load versus boom angle and radius; provide the maximum allowable machine list and machine trim associated with the tabular loads and radii provided; and be stamped by a RPE qualified and competent in the field of floating cranes. The RPE, competent in the field of floating cranes must stamp and certify (sign) that the Naval Architectural Analysis (NAA) meets the requirements of EM 385-1-1, Section 16.L.03.

- c. Multi-purpose machines, material handling equipment, and construction equipment used to lift loads that are suspended by rigging gear, require proof of authorization from the machine OEM that the machine is capable of making lifts of loads suspended by rigging equipment. Demonstrate that the operator is properly trained and that the equipment is properly configured to make such lifts and is equipped with a load chart.

1.6.2.4 Fall Protection and Prevention (FP&P) Plan

The plan must comply with the requirements of EM 385-1-1, Section 21.D and ASSE/SAFE Z359.2, be site specific, and address all fall hazards in the work place and during different phases of construction. Address how to protect and prevent workers from falling to lower levels when they are exposed to fall hazards above 6 feet. A competent person or qualified person for fall protection must prepare and sign the plan documentation. Include fall protection and prevention systems, equipment and methods employed for every phase of work, roles and responsibilities, assisted rescue, self-rescue and evacuation procedures, training requirements, and monitoring methods. Review and revise, as necessary, the Fall Protection and Prevention Plan documentation as conditions change, but at a minimum every six months, for lengthy projects, reflecting any changes during the course of construction due to changes in personnel, equipment, systems or work habits. Keep and maintain the accepted Fall Protection and Prevention Plan documentation at the job site for the duration of the project. Include the Fall Protection and Prevention Plan documentation in the Accident Prevention Plan (APP).

1.6.2.5 Rescue and Evacuation Plan

Provide a Rescue and Evacuation Plan in accordance with EM 385-1-1 Section 21.N and ASSE/SAFE Z359.2, and include in the FP&P Plan and as part of the APP. Include a detailed discussion of the following: methods of rescue; methods of self-rescue; equipment used; training requirement; specialized training for the rescuers; procedures for requesting rescue and medical assistance; and transportation routes to a medical facility.

1.6.2.6 Hazardous Energy Control Program (HECP)

Develop a HECP in accordance with EM 385-1-1 Section 12, 29 CFR 1910.147, 29 CFR 1910.333, 29 CFR 1915.89, ASSE/SAFE Z244.1, and ASSE/SAFE A10.44. Submit this HECP as part of the Accident Prevention Plan (APP). Conduct a preparatory meeting and inspection with all effected personnel to coordinate all HECP activities. Document this meeting and inspection in accordance with EM 385-1-1, Section 12.A.02. Ensure that each employee is familiar with and complies with these procedures.

1.7 ACTIVITY HAZARD ANALYSIS (AHA)

Before beginning each activity, task or Definable Feature of Work (DFOW) involving a type of work presenting hazards not experienced in previous project operations, or where a new work crew or subcontractor is to perform the work, the Contractor(s) performing that work activity must prepare an AHA. AHAs must be developed by the Prime Contractor, subcontractor, or supplier performing the work, and provided for Prime Contractor review and approval before submitting to the Contracting Officer. AHAs must be signed by the SSHO, Superintendent, QC Manager and the subcontractor Foreman performing the work. Format the AHA in accordance with EM 385-1-1, Section 1 or as directed by the Contracting Officer. Submit the AHA for review at

least 15 working days prior to the start of each activity task, or DFOW. The Government reserves the right to require the Contractor to revise and resubmit the AHA if it fails to effectively identify the work sequences, specific anticipated hazards, site conditions, equipment, materials, personnel and the control measures to be implemented.

AHAs must identify competent persons required for phases involving high risk activities, including confined entry, crane and rigging, excavations, trenching, electrical work, fall protection, and scaffolding.

1.7.1 AHA Management

Review the AHA list periodically (at least monthly) at the Contractor supervisory safety meeting, and update as necessary when procedures, scheduling, or hazards change. Use the AHA during daily inspections by the SSHO to ensure the implementation and effectiveness of the required safety and health controls for that work activity.

1.7.2 AHA Signature Log

Each employee performing work as part of an activity, task or DFOW must review the AHA for that work and sign a signature log specifically maintained for that AHA prior to starting work on that activity. The SSHO must maintain a signature log on site for every AHA. Provide employees whose primary language is other than English, with an interpreter to ensure a clear understanding of the AHA and its contents.

1.8 DISPLAY OF SAFETY INFORMATION

1.8.1 Safety Bulletin Board

Within one calendar day after commencement of work, erect a safety bulletin board at the job site. Where size, duration, or logistics of project do not facilitate a bulletin board, an alternative method, acceptable to the Contracting Officer, that is accessible and includes all mandatory information for employee and visitor review, may be deemed as meeting the requirement for a bulletin board. Include and maintain information on safety bulletin board as required by EM 385-1-1, Section 01.A.07. Additional items required to be posted include:

- a. Confined space entry permit.
- b. Hot work permit.

1.8.2 Safety and Occupational Health (SOH) Deficiency Tracking System

Establish a SOH deficiency tracking system that lists and monitors the status of SOH deficiencies in chronological order. Use the tracking system to evaluate the effectiveness of the APP. A monthly evaluation of the data must be discussed in the QC or SOH meeting with everyone on the project. The list must be posted on the project bulletin board and updated daily, and provide the following information:

- a. Date deficiency identified;
- b. Description of deficiency;
- c. Name of person responsible for correcting deficiency;

d. Projected resolution date;

e. Date actually resolved.

1.9 SITE SAFETY REFERENCE MATERIALS

Maintain safety-related references applicable to the project, including those listed in paragraph REFERENCES. Maintain applicable equipment manufacturer's manuals.

1.10 EMERGENCY MEDICAL TREATMENT

Contractors must arrange for their own emergency medical treatment. Government has no responsibility to provide emergency medical treatment.

1.11 NOTIFICATIONS and REPORTS

1.11.1 Mishap Notification

Notify the Contracting Officer as soon as practical, but no more than twenty-four hours, after any mishaps, including recordable accidents, incidents, and near misses, as defined in EM 385-1-1 Appendix Q, any report of injury, illness, load handling equipment (LHE) or rigging mishaps, or any property damage. The Contractor is responsible for obtaining appropriate medical and emergency assistance and for notifying fire, law enforcement, and regulatory agencies. Immediate reporting is required for electrical mishaps, to include Arc Flash; shock; uncontrolled release of hazardous energy (includes electrical and non-electrical); load handling equipment or rigging; fall from height (any level other than same surface); and underwater diving. These mishaps must be investigated in depth to identify all causes and to recommend hazard control measures.

Within notification include Contractor name; contract title; type of contract; name of activity, installation or location where accident occurred; date and time of accident; names of personnel injured; extent of property damage, if any; extent of injury, if known, and brief description of accident (for example, type of construction equipment used and PPE used). Preserve the conditions and evidence on the accident site until the Government investigation team arrives on-site and Government investigation is conducted. Assist and cooperate fully with the Government's investigation(s) of any mishap.

1.11.2 Accident Reports

- a. Conduct an accident investigation for recordable injuries and illnesses, property damage, and near misses as defined in EM 385-1-1, to establish the root cause(s) of the accident. Complete the applicable USACE Accident Report Form 3394, and provide the report to the Contracting Officer within 5 calendar day(s) of the accident. The Contracting Officer will provide copies of any required or special forms.
- b. Near Misses: Report all "Near Misses" to the GDA, using local mishap reporting procedures, within 24 hrs. The Contracting Officer will provide the Contractor the required forms. Near miss reports are considered positive and proactive Contractor safety management actions.
- c. Conduct an accident investigation for any load handling equipment accident (including rigging gear accidents) to establish the root

cause(s) of the accident. Complete the LHE Accident Report (Crane and Rigging Gear) form and provide the report to the Contracting Officer within 30 calendar days of the accident. Do not proceed with crane operations until cause is determined and corrective actions have been implemented to the satisfaction of the Contracting Officer. The Contracting Officer will provide a blank copy of the accident report form.

1.11.3 LHE Inspection Reports

Submit LHE inspection reports required in accordance with EM 385-1-1 and as specified herein with Daily Reports of Inspections.

1.11.4 Certificate of Compliance and Pre-lift Plan/Checklist for LHE and Rigging

Provide a FORM 16-1 Certificate of Compliance for LHE entering an activity under this contract and in accordance with EM 385-1-1. Post certifications on the crane.

Develop a Standard Lift Plan (SLP) in accordance with EM 385-1-1, Section 16.H.03 using Form 16-2 Standard Pre-Lift Crane Plan/Checklist for each lift planned. Submit SLP to the Contracting Officer for approval within 15 calendar days in advance of planned lift.

1.12 HOT WORK

1.12.1 Permit and Personnel Requirements

Submit and obtain a written permit prior to performing "Hot Work" (i.e. welding or cutting) or operating other flame-producing/spark producing devices, from the Fire Marshall. A permit is required from the Explosives Safety Office for work in and around where explosives are processed, stored, or handled. CONTRACTORS ARE REQUIRED TO MEET ALL CRITERIA BEFORE A PERMIT IS ISSUED. Provide at least two 20 pound 4A:20 BC rated extinguishers for normal "Hot Work". The extinguishers must be current inspection tagged, and contain an approved safety pin and tamper resistant seal. It is also mandatory to have a designated FIRE WATCH for any "Hot Work" done at this activity. The Fire Watch must be trained in accordance with NFPA 51B and remain on-site for a minimum of one hour after completion of the task or as specified on the hot work permit.

When starting work in the facility, require personnel to familiarize themselves with the location of the nearest fire alarm boxes and place in memory the emergency Fire Marshall's phone number. REPORT ANY FIRE, NO MATTER HOW SMALL, TO THE RESPONSIBLE FIRE MARSHALL IMMEDIATELY.

1.12.2 Work Around Flammable Materials

Obtain services from a NFPA Certified Marine Chemist for "HOT WORK" within or around flammable materials (such as fuel systems or welding/cutting on fuel pipes) or confined spaces (such as sewer wet wells, manholes, or vaults) that have the potential for flammable or explosive atmospheres.

Whenever these materials, except beryllium and chromium (VI), are encountered in indoor operations, local mechanical exhaust ventilation systems that are sufficient to reduce and maintain personal exposures to within acceptable limits must be used and maintained in accordance with manufacturer's instruction and supplemented by exceptions noted in

EM 385-1-1, Section 06.H

1.13 CONFINED SPACE ENTRY REQUIREMENTS.

Confined space entry must comply with Section 34 of EM 385-1-1, OSHA 29 CFR 1926, OSHA 29 CFR 1910, OSHA 29 CFR 1910.146, and OSHA Directive CPL 2.100. Any potential for a hazard in the confined space requires a permit system to be used.

1.13.1 Entry Procedures

Prohibit entry into a confined space by personnel for any purpose, including hot work, until the qualified person has conducted appropriate tests to ensure the confined or enclosed space is safe for the work intended and that all potential hazards are controlled or eliminated and documented. Comply with EM 385-1-1, Section 34 for entry procedures. Hazards pertaining to the space must be reviewed with each employee during review of the AHA.

1.13.2 Forced Air Ventilation

Forced air ventilation is required for all confined space entry operations and the minimum air exchange requirements must be maintained to ensure exposure to any hazardous atmosphere is kept below its action level.

1.13.3 Sewer Wet Wells

Sewer wet wells require continuous atmosphere monitoring with audible alarm for toxic gas detection.

1.13.4 Rescue Procedures and Coordination with Local Emergency Responders

Develop and implement an on-site rescue and recovery plan and procedures. The rescue plan must not rely on local emergency responders for rescue from a confined space.

1.14 DIVE SAFETY REQUIREMENTS

Develop a Dive Operations Plan, AHA, emergency management plan, and personnel list that includes qualifications, for each separate diving operation. Submit these documents to the District Dive Coordinator (DDC) for review and acceptance at least 15 working days prior to commencement of diving operations. These documents must be at the diving location at all times. Provide each of these documents as a part of the project file.

1.15 SEVERE STORM PLAN

In the event of a severe storm warning, the Contractor must:

- a. Secure outside equipment and materials and place materials that could be damaged in protected areas.
- b. Check surrounding area, including roof, for loose material, equipment, debris, and other objects that could be blown away or against existing facilities.
- c. Ensure that temporary erosion controls are adequate.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 CONSTRUCTION AND OTHER WORK

Comply with EM 385-1-1, NFPA 70, NFPA 70E, NFPA 241, the APP, the AHA, Federal and State OSHA regulations, and other related submittals and activity fire and safety regulations. The most stringent standard prevails.

PPE is governed in all areas by the nature of the work the employee is performing. Use personal hearing protection at all times in designated noise hazardous areas or when performing noise hazardous tasks. Safety glasses must be worn or carried/available on each person. Mandatory PPE includes:

- a. Hard Hat
- b. Long Pants
- c. Appropriate Safety Shoes
- d. Appropriate Class Reflective Vests

3.1.1 Worksite Communication

Employees working alone in a remote location or away from other workers must be provided an effective means of emergency communications (i.e., cellular phone, two-way radios, land-line telephones or other acceptable means). The selected communication must be readily available (easily within the immediate reach) of the employee and must be tested prior to the start of work to verify that it effectively operates in the area/environment. An employee check-in/check-out communication procedure must be developed to ensure employee safety.

3.1.2 Hazardous Material Exclusions

Notwithstanding any other hazardous material used in this contract, radioactive materials or instruments capable of producing ionizing/non-ionizing radiation (with the exception of radioactive material and devices used in accordance with EM 385-1-1 such as nuclear density meters for compaction testing and laboratory equipment with radioactive sources) as well as materials which contain asbestos, mercury or polychlorinated biphenyls, di-isocyanates, lead-based paint, and hexavalent chromium, are prohibited. The Contracting Officer, upon written request by the Contractor, may consider exceptions to the use of any of the above excluded materials. Low mercury lamps used within fluorescent lighting fixtures are allowed as an exception without further Contracting Officer approval. Notify the Radiation Safety Officer (RSO) prior to excepted items of radioactive material and devices being brought on base.

3.1.3 Unforeseen Hazardous Material

Contract documents identify materials such as PCB, lead paint, and friable and non-friable asbestos and other OSHA regulated chemicals (i.e. 29 CFR Part 1910.1000). If material(s) that may be hazardous to human health upon disturbance are encountered during construction operations, stop that portion of work and notify the Contracting Officer immediately. Within 14

calendar days the Government will determine if the material is hazardous. If material is not hazardous or poses no danger, the Government will direct the Contractor to proceed without change. If material is hazardous and handling of the material is necessary to accomplish the work, the Government will issue a modification pursuant to FAR 52.243-4, "Changes" and FAR 52.236-2, "Differing Site Conditions."

3.2 PRE-OUTAGE COORDINATION MEETING

Apply for utility outages at least 15 days in advance. As a minimum, the request must include the location of the outage, utilities being affected, duration of outage and any necessary sketches. Special requirements for electrical outage requests are contained elsewhere in this specification section. Once approved, and prior to beginning work on the utility system requiring shut down, attend a pre-outage coordination meeting with the Contracting Officer and the Public Utilities representative to review the scope of work and the lock-out/tag-out procedures for worker protection. No work will be performed on energized electrical circuits unless proof is provided that no other means exist.

3.3 CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT)

Provide and operate a Hazardous Energy Control Program (HECP) in accordance with EM 385-1-1 Section 12, 29 CFR 1910.333, 29 CFR 1915.89, and paragraph HAZARDOUS ENERGY CONTROL PROGRAM (HECP).

3.4 FALL PROTECTION PROGRAM

Establish a fall protection program, for the protection of all employees exposed to fall hazards. Within the program include company policy, identify roles and responsibilities, education and training requirements, fall hazard identification, prevention and control measures, inspection, storage, care and maintenance of fall protection equipment and rescue and evacuation procedures in accordance with ASSE/SAFE Z359.2 and EM 385-1-1, Sections 21.A and 21.D.

3.4.1 Training

Institute a fall protection training program. As part of the Fall Protection Program, provide training for each employee who might be exposed to fall hazards. Provide training by a competent person for fall protection in accordance with EM 385-1-1, Section 21.C. Document training and practical application of the competent person in accordance with EM 385-1-1, Section 21.C.04 and ASSE/SAFE Z359.2 in the AHA.

3.4.2 Fall Protection Equipment and Systems

Enforce use of personal fall protection equipment and systems designated (to include fall arrest, restraint, and positioning) for each specific work activity in the Site Specific Fall Protection and Prevention Plan and AHA at all times when an employee is exposed to a fall hazard. Protect employees from fall hazards as specified in EM 385-1-1, Section 21.

Provide personal fall protection equipment, systems, subsystems, and components that comply with EM 385-1-1 Section 21.I, 29 CFR 1926.500 Subpart M, ASSE/SAFE Z359.0, ASSE/SAFE Z359.1, ASSE/SAFE Z359.2, ASSE/SAFE Z359.3, ASSE/SAFE Z359.4, ASSE/SAFE Z359.6, ASSE/SAFE Z359.7, ASSE/SAFE Z359.11, ASSE/SAFE Z359.12, ASSE/SAFE Z359.13, ASSE/SAFE Z359.14, and ASSE/SAFE Z359.15.

3.4.2.1 Additional Personal Fall Protection

In addition to the required fall protection systems, other protection such as safety skiffs, personal floatation devices, and life rings, are required when working above or next to water in accordance with EM 385-1-1, Sections 21.0 through 21.0.06. Personal fall protection systems and equipment are required when working from an articulating or extendible boom, swing stages, or suspended platform. In addition, personal fall protection systems are required when operating other equipment such as scissor lifts. The need for tying-off in such equipment is to prevent ejection of the employee from the equipment during raising, lowering, travel, or while performing work.

3.4.2.2 Personal Fall Protection Harnesses

Only a full-body harness with a shock-absorbing lanyard or self-retracting lanyard is an acceptable personal fall arrest body support device. The use of body belts is not acceptable. Harnesses must have a fall arrest attachment affixed to the body support (usually a Dorsal D-ring) and specifically designated for attachment to the rest of the system. Snap hooks and carabiners must be self-closing and self-locking, capable of being opened only by at least two consecutive deliberate actions and have a minimum gate strength of 3,600 lbs in all directions. Use webbing, straps, and ropes made of synthetic fiber. The maximum free fall distance when using fall arrest equipment must not exceed 6 feet, unless the proper energy absorbing lanyard is used. Always take into consideration the total fall distance and any swinging of the worker (pendulum-like motion), that can occur during a fall, when attaching a person to a fall arrest system. All full body harnesses must be equipped with Suspension Trauma Preventers such as stirrups, relief steps, or similar in order to provide short-term relief from the effects of orthostatic intolerance in accordance with EM 385-1-1, Section 21.I.06.

3.4.3 Horizontal Lifelines (HLL)

Provide HLL in accordance with EM 385-1-1, Section 21.I.08.d.2. Commercially manufactured horizontal lifelines (HLL) must be designed, installed, certified and used, under the supervision of a qualified person, for fall protection as part of a complete fall arrest system which maintains a safety factor of 2 (29 CFR 1926.500). The competent person for fall protection may (if deemed appropriate by the qualified person) supervise the assembly, disassembly, use and inspection of the HLL system under the direction of the qualified person. Locally manufactured HLLs are not acceptable unless they are custom designed for limited or site specific applications by a Registered Professional Engineer who is qualified in designing HLL systems.

3.4.4 Guardrails and Safety Nets

Design, install and use guardrails and safety nets in accordance with EM 385-1-1, Section 21.F.01 and 29 CFR 1926 Subpart M.

3.4.5 Rescue and Evacuation Plan and Procedures

When personal fall arrest systems are used, ensure that the mishap victim can self-rescue or can be rescued promptly should a fall occur. Prepare a Rescue and Evacuation Plan and include a detailed discussion of the following: methods of rescue; methods of self-rescue or assisted-rescue; equipment used; training requirement; specialized training for the rescuers; procedures for requesting rescue and medical assistance; and transportation routes to a medical facility. Include the Rescue and Evacuation Plan within the Activity Hazard Analysis (AHA) for the phase of work, in the Fall Protection and Prevention (FP&P) Plan, and the Accident Prevention Plan (APP). The plan must comply with the requirements of

EM 385-1-1, ASSE/SAFE Z359.2, and ASSE/SAFE Z359.4.

3.5 EQUIPMENT

3.5.1 Material Handling Equipment (MHE)

- a. Material handling equipment such as forklifts must not be modified with work platform attachments for supporting employees unless specifically delineated in the manufacturer's printed operating instructions. Material handling equipment fitted with personnel work platform attachments are prohibited from traveling or positioning while personnel are working on the platform.
- b. The use of hooks on equipment for lifting of material must be in accordance with manufacturer's printed instructions. Material Handling Equipment Operators must be trained in accordance with OSHA 29 CFR 1910, Subpart N.
- c. Operators of forklifts or power industrial trucks must be licensed in accordance with OSHA.

3.5.2 Load Handling Equipment (LHE)

- a. Equip cranes and derricks as specified in EM 385-1-1, Section 16.
- b. Notify the Contracting Officer 15 working days in advance of any LHE entering the activity, in accordance with EM 385-1-1, Section 16.A.02, so that necessary quality assurance spot checks can be coordinated. Contractor's operator must remain with the crane during the spot check. Rigging gear must comply with OSHA and ASME B30.9 Standards.
- c. Comply with the LHE manufacturer's specifications and limitations for erection and operation of cranes and hoists used in support of the work. Perform erection under the supervision of a designated person (as defined in ASME B30.5). Perform all testing in accordance with the manufacturer's recommended procedures.
- d. Comply with ASME B30.5 for mobile and locomotive cranes, ASME B30.22 for articulating boom cranes, ASME B30.3 for construction tower cranes, ASME B30.8 for floating cranes and floating derricks, ASME B30.9 for slings, ASME B30.20 for below the hook lifting devices and ASME B30.26 for rigging hardware.
- e. Under no circumstance must a Contractor make a lift at or above 90 percent of the cranes rated capacity in any configuration.
- f. When operating in the vicinity of overhead transmission lines, operators and riggers must be alert to this special hazard and follow the requirements of EM 385-1-1 Section 11, and ASME B30.5 or ASME B30.22 as applicable.
- g. Do not use crane suspended personnel work platforms (baskets) unless the Contractor proves that using any other access to the work location would provide a greater hazard to the workers or is impossible. Do not lift personnel with a line hoist or friction crane.
Additionally,
submit a specific AHA for this work to the Contracting Officer.
Ensure the

activity and AHA are thoroughly reviewed by all involved personnel.

- h. Inspect, maintain, and recharge portable fire extinguishers as specified in NFPA 10, Standard for Portable Fire Extinguishers.
- i. All employees must keep clear of loads about to be lifted and of suspended loads.
- j. Use cribbing when performing lifts on outriggers.
- k. The crane hook/block must be positioned directly over the load. Side loading of the crane is prohibited.
- l. A physical barricade must be positioned to prevent personnel access where accessible areas of the LHE's rotating superstructure poses a risk of striking, pinching or crushing personnel.
- m. Maintain inspection records in accordance by EM 385-1-1, Section 16.D, including shift, monthly, and annual inspections, the signature of the person performing the inspection, and the serial number or other identifier of the LHE that was inspected. Records must be available for review by the Contracting Officer.
- n. Maintain written reports of operational and load testing in accordance with EM 385-1-1, Section 16.F, listing the load test procedures used along with any repairs or alterations performed on the LHE. Reports must be available for review by the Contracting Officer.
- o. Certify that all LHE operators have been trained in proper use of all safety devices (e.g. anti-two block devices).
- p. Take steps to ensure that wind speed does not contribute to loss of control of the load during lifting operations. At wind speeds greater than 20 mph, the operator, rigger and lift supervisor must cease all crane operations, evaluate conditions and determine if the lift may proceed. Base the determination to proceed or not on wind calculations per the manufacturer and a reduction in LHE rated capacity if applicable. Include this maximum wind speed determination as part of the activity hazard analysis plan for that operation.

3.5.3 Machinery and Mechanized Equipment

- a. Proof of qualifications for operator must be kept on the project site for review.
- b. Manufacture specifications or owner's manual for the equipment must be on-site and reviewed for additional safety precautions or requirements that are sometimes not identified by OSHA or USACE EM 385-1-1. Incorporate such additional safety precautions or requirements into the AHAs.

3.6 ELECTRICAL

Perform electrical work in accordance with EM 385-1-1, Appendix A, Sections 11 and 12.

3.6.1 Conduct of Electrical Work

As delineated in EM 385-1-1, electrical work is to be conducted in a de-energized state unless there is no alternative method for accomplishing the work. In those cases obtain an energized work permit from the

Contracting Officer. The energized work permit application must be accompanied by the AHA and a summary of why the equipment/circuit needs to be worked energized. Underground electrical spaces must be certified safe for entry before entering to conduct work. Cables that will be cut must be positively identified and de-energized prior to performing each cut. Attach temporary grounds in accordance with ASTM F855 and IEEE 1048. Perform all high voltage cable cutting remotely using hydraulic cutting tool. When racking in or live switching of circuit breakers, no additional person other than the switch operator is allowed in the space during the actual operation. Plan so that work near energized parts is minimized to the fullest extent possible. Use of electrical outages clear of any energized electrical sources is the preferred method.

When working in energized substations, only qualified electrical workers are permitted to enter. When work requires work near energized circuits as defined by NFPA 70, high voltage personnel must use personal protective equipment that includes, as a minimum, electrical hard hat, safety shoes, insulating gloves and electrical arc flash protection for personnel as required by NFPA 70E. Insulating blankets, hearing protection, and switching suits may also be required, depending on the specific job and as delineated in the Contractor's AHA. Ensure that each employee is familiar with and complies with these procedures and 29 CFR 1910.147.

3.6.2 Qualifications

Electrical work must be performed by QP personnel with verifiable credentials who are familiar with applicable code requirements. Verifiable credentials consist of State, National and Local Certifications or Licenses that a Master or Journeyman Electrician may hold, depending on work being performed, and must be identified in the appropriate AHA. Journeyman/Apprentice ratio must be in accordance with State, Local and Host Nation requirements applicable to where work is being performed.

3.6.3 Arc Flash

Conduct a hazard analysis/arc flash hazard analysis whenever work on or near energized parts greater than 50 volts is necessary, in accordance with NFPA 70E.

All personnel entering the identified arc flash protection boundary must be QPs and properly trained in NFPA 70E requirements and procedures. Unless permitted by NFPA 70E, no Unqualified Person is permitted to approach nearer than the Limited Approach Boundary of energized conductors and circuit parts. Training must be administered by an electrically qualified source and documented.

3.6.4 Grounding

Ground electrical circuits, equipment and enclosures in accordance with NFPA 70 and IEEE C2 to provide a permanent, continuous and effective path to ground unless otherwise noted by EM 385-1-1.

Check grounding circuits to ensure that the circuit between the ground and a grounded power conductor has a resistance low enough to permit sufficient current flow to allow the fuse or circuit breaker to interrupt the current.

3.6.5 Testing

Temporary electrical distribution systems and devices must be inspected, tested and found acceptable for Ground-Fault Circuit Interrupter (GFCI) protection, polarity, ground continuity, and ground resistance before initial use, before use after modification and at least monthly. Monthly

IDIQ Contract for Rental of Hopper Dredge
With Attendant Plant and Operators for
Maintenance Dredging in Alabama, Mississippi, Florida

W91278-17-B-0002

inspections and tests must be maintained for each temporary electrical
distribution system, and signed by the electrical CP or QP.

-- End of Section --

SECTION 01 45 00.15 10

RESIDENT MANAGEMENT SYSTEM CONTRACTOR MODE(RMS CM)
11/16

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this section to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1 (2014) Safety and Health Requirements
Manual

1.2 Contract Administration

The Government will use the Resident Management System (RMS) to assist in its monitoring and administration of this contract. The Contractor uses the Government-furnished Construction Contractor Mode of RMS, referred to as RMS CS, to record, maintain, and submit various information throughout the contract period. The Contractor mode user manuals, updates, and training information can be downloaded from the RMS web site (<http://rms.usace.army.mil>). The joint Government-Contractor use of RMS facilitates electronic exchange of information and overall management of the contract. QCS provides the means for the Contractor to input, track, and electronically share information with the Government in the following areas:

- Administration
- Finances
- Quality Control
- Submittal Monitoring
- Scheduling
- Import/Export of Data

1.2.1 Correspondence and Electronic Communications

For ease and speed of communications, exchange correspondence and other documents in electronic format to the maximum extent feasible between the Government and Contractor. Correspondence, pay requests and other documents comprising the official contract record are also be provided in paper format, with signatures and dates where necessary. Paper documents will govern, in the event of discrepancy with the electronic version.

1.2.2 Other Factors

Particular attention is directed to Contract Clause, "Schedules for Construction Contracts", Contract Clause, "Payments", Section 01 32 01.00 10 PROJECT SCHEDULE, Section 01 33 00 SUBMITTAL PROCEDURES, and Section 01 45 00.00 10 QUALITY CONTROL, which have a direct relationship to the reporting to be accomplished through RMS. Also, there is no separate payment for establishing and maintaining the RMS database; costs associated will be included in the contract pricing for the work.

1.3 RMS SOFTWARE

RMS is a Windows-based program that can be run on a Windows based PC meeting the requirements as specified in Section 1.3. The Government will make available the RMS software to the Contractor after award of the construction contract. Prior to the Pre-Construction Conference, the Contractor will be responsible to download, install and use the latest version of the RMS software from the Government's RMS Internet Website. Any program updates of RMS will be made available to the Contractor via the Government RMS Website as the updates become available.

1.3.1 RMS CONTRACTOR'S MODE (CM)

RMS Contractor's Mode or RMS CM is the replacement for Quality Control System or QCS. The database remains the same. References to RMS in this specification includes RMS CM.

1.4 SYSTEM REQUIREMENTS

The following is the minimum system configuration required to run RMS and Contractor Mode:

Minimum RMS System Requirements	
Hardware	
Windows-based PC	1.5 GHz 2 core or higher processor
RAM	8 GB
Hard drive disk	200 GB space for sole use by the QCS system
Monitor	Screen resolution 1366 x 768
Mouse or other pointing device	
Windows compatible printer	Laser printer must have 4 MB+ of RAM
Connection to the Internet	minimum 4 Mbs per user
Software	
MS Windows	Windows 7 x 64 bit (RMS requires 64 bit O/S) or newer
Word Processing software	Viewer for MS Word 2013, MS Excel 2013, or newer
Microsoft.NET Framework	Coordinate with Government QA Representative for free version required

Minimum RMS System Requirements	
Email	MAPI compatible
Virus protection software	Regularly upgraded with all issued manufacturer's updates and is able to detect most zero day viruses.

1.5 RELATED INFORMATION

1.5.1 RMS User Guide

After contract award, download instructions for the installation and use of RMS from the Government RMS Internet Website.

1.6 CONTRACT DATABASE

Prior to the pre-construction conference, the Government will provide the Contractor with basic contract award data to use for RMS. The Government will provide data updates to the Contractor as needed. These updates will generally consist of submittal reviews, correspondence status, Quality Assurance(QA) comments, and other administrative and QA data.

1.7 DATABASE MAINTENANCE

Establish, maintain, and update data in the RMS database throughout the duration of the contract at the Contractor's site office. Submit data updates to the Government (e.g., daily reports, submittals, RFI's, schedule updates, payment requests) using RMS. The RMS database typically includes current data on the following items:

1.7.1 Administration

1.7.1.1 Contractor Information

Contain within the database the Contractor's name, address, telephone numbers, management staff, and other required items. Within 7 calendar days of receipt of RMS software from the Government, deliver Contractor administrative data in electronic format in RMS.

1.7.1.2 Subcontractor Information

Contain within the database the name, trade, address, phone numbers, and other required information for all subcontractors. A subcontractor is listed separately for each trade to be performed. Assign each subcontractor/trade a unique Responsibility Code, provided in RMS. Within 7 calendar days of receipt of RMS software from the Government, deliver subcontractor administrative data in electronic format.

1.7.1.3 Correspondence

Identify all Contractor correspondence to the Government with a serial number. Prefix correspondence initiated by the Contractor's site office with "S". Prefix letters initiated by the Contractor's home (main) office with "H". Letters are numbered starting from 0001. (e.g., H-0001 or S-0001). The Government's letters to the Contractor will be prefixed with "C".

1.7.1.4 Equipment

Contain within the Contractor's RMS database a current list of equipment planned for use or being used on the jobsite, including the most recent and planned equipment inspection dates.

1.7.1.5 Management Reporting

RMS includes a number of reports that Contractor management can use to track the status of the project. The value of these reports is reflective of the quality of the data input, and is maintained in the various sections of RMS. Among these reports are: Progress Payment Request worksheet, Quality Assurance/Quality Control (QA/QC) comments, Submittal Register Status, Three-Phase Control checklists.

1.7.1.6 Request For Information (RFI)

Exchange all Requests For Information (RFI) using the Built-in RFI generator and tracker in RMS.

1.7.2 Finances

1.7.2.1 Pay Activity Data

Include within the RMS database a list of pay activities that the Contractor develops in conjunction with the construction schedule. The sum of pay activities equals the total contract amount, including modifications. Each pay activity must be assigned to a Contract Line Item Number (CLIN). The sum of the activities equals the amount of each CLIN. The sum of all CLINs equals the contract amount.

1.7.2.2 Payment Requests

Prepare all progress payment requests using RMS. Complete the payment request worksheet, prompt payment certification, and payment invoice in RMS. Update the work completed under the contract, measured as percent or as specific quantities, at least monthly. After the update, generate a payment request report using RMS. Submit the payment request, prompt payment certification, and payment invoice with supporting data using RMS CM. If permitted by the Contracting Officer, email or a optical disc may be used. A signed paper copy of the approved payment request is also required and will govern in the event of discrepancy with the electronic version.

1.7.3 Quality Control (QC)

RMS provides a means to track implementation of the 3-phase QC Control System, prepare daily reports, identify and track deficiencies, document progress of work, and support other Contractor QC requirements. Maintain this data on a daily basis. Entered data will automatically output to the RMS generated daily report. Provide the Government a Contractor Quality Control (CQC) Plan within the time required in Section 01 45 00.00 10 QUALITY CONTROL. Within seven calendar days of Government acceptance, submit a RMS update reflecting the information contained in the accepted CQC Plan: schedule, pay activities, features of work, submittal register, QC requirements, and equipment list.

1.7.3.1 Daily Contractor Quality Control (CQC) Reports.

RMS includes the means to produce the Daily CQC Report. The Contractor can use other formats to record basic Quality Control (QC) data. However, the Daily CQC Report generated by RMS must be the Contractor's official report. Summarize data from any supplemental reports by the Contractor and consolidate onto the RMS-generated Daily CQC Report. Submit daily CQC Reports as required by Section 01 45 00.00 10 QUALITY CONTROL. Electronically submit reports to the Government within 24 hours after the date covered by the report. Also provide the Government a signed, printed copy of the daily CQC report.

1.7.3.2 Deficiency Tracking.

Use RMS to track deficiencies. Deficiencies identified by the Contractor will be numerically tracked using its Quality Control (QC) punch list items. Maintain a current log of its QC punch list items in the RMS database. The Government will log the deficiencies it has identified using its Quality Assurance (QA) punch list items. The Government's QA punch list items will be included in its export file to the Contractor. Regularly update the correction status of both QC and QA punch list items.

1.7.3.3 QC Requirements

Develop and maintain a complete list of QC testing and required structural and life safety special inspections required by the International Code Council (ICC), transferred and installed property, and user training requirements in RMS. Update data on these QC requirements as work progresses, and promptly provide the information to the Government via RMS.

1.7.3.4 Three-Phase Control Meetings

Maintain scheduled and actual dates and times of preparatory and initial control meetings in RMS.

1.7.3.5 Labor and Equipment Hours

Log labor and equipment exposure hours on a daily basis. The labor and equipment exposure data will be rolled up into a monthly exposure report.

1.7.3.6 Accident/Safety Reporting

The Government will issue safety comments, directions, or guidance whenever safety deficiencies are observed. The Government's safety comments will be provided via RMS CM. Regularly update the correction status of the safety comments. In addition, utilize RMS to advise the Government of any accidents occurring on the jobsite. A brief supplemental entry of an accident is not to be considered as a substitute for completion of mandatory reports, e.g., ENG Form 3394 and OSHA Form 300.

1.7.3.7 Features of Work

Include a complete list of the features of work in the RMS database. A feature of work is associated with multiple pay activities. However, each pay activity (see subparagraph "Pay Activity Data" of paragraph "Finances") will only be linked to a single feature of work.

1.7.3.8 Hazard Analysis

Use RMS CM to develop a hazard analysis for each feature of work included in the CQC Plan. The Activity Hazard Analysis will include information required by EM 385-1-1, paragraph 01.A.13.

1.7.4 Submittal Management

The Government will provide the initial submittal register in electronic format. Thereafter, maintain a complete list of submittals, including completion of data columns. Dates when submittals are received and returned by the Government will be included. Use RMS CM to track and transmit submittals. ENG Form 4025, submittal transmittal form, and the submittal register update is produced using RMS. RMS will be used to update, store and exchange submittal registers and transmittals. In addition to requirements stated in specification 01 33 00, actual submittals are to be stored in RMS CM, with hard copies also provided. Exception will be where the Contracting Officer specifies only hard copies required, where size of document cannot be saved in RMS CM, and where samples, spare parts, color boards, and full size drawings are to be provided.

1.7.5 Schedule

Develop a construction schedule consisting of pay activities, in accordance with Section 01 32 01.00 10 PROJECT SCHEDULE. Input and maintain in the RMS database the schedule either manually or by using the Standard Data Exchange Format (SDEF) (see Section 01 32 01.00 10 PROJECT SCHEDULE). Include with each pay request the updated schedule. Provide electronic copies of transmittals.

1.7.6 Import/Export of Data

RMS includes the ability to import schedule data using SDEF.

1.8 IMPLEMENTATION

Use of RMS CM as described in the preceding paragraphs is mandatory. Ensure that sufficient resources are available to maintain contract data within the RMS CM system. RMS CM is an integral part of the Contractor's management of quality control.

1.9 MONTHLY COORDINATION MEETING

Update the RMS CM database each workday. At least monthly, generate and submit a schedule update. At least one week prior to submittal, meet with the Government representative to review the planned progress payment data submission for errors and omissions.

Make required corrections prior to Government acceptance of the export file and progress payment request. Payment requests accompanied by incomplete or incorrect data submittals will not be accepted. The Government will not process progress payments until all required corrections are processed.

1.10 NOTIFICATION OF NONCOMPLIANCE

The Contracting Officer will notify the Contractor of any detected noncompliance with the requirements of this specification. Take immediate corrective action after receipt of such notice. Such notice, when

delivered to the Contractor at the work site, will be deemed sufficient for the purpose of notification.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 45 01

USACE QUALITY CONTROL

PART 1 GENERAL

1.1 REFERENCES

1.2 PAYMENT

PART 2 PRODUCTS

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

3.2 QUALITY CONTROL PLAN

3.2.1 Content of the CQC Plan

3.2.2 Additional Requirements for Design Quality Control (DQC) Plan

3.2.3 Acceptance of Plan

3.2.4 Notification of Changes

3.3 COORDINATION MEETING

3.4 QUALITY CONTROL ORGANIZATION

3.4.1 Personnel Requirements

3.4.2 CQC System Manager

3.4.3 Organizational Changes

3.5 SUBMITTALS AND DELIVERABLES

3.6 CONTROL

3.6.1 Preparatory Phase

3.6.2 Initial Phase

3.6.3 Follow-up Phase

3.6.4 Additional Preparatory and Initial Phases

3.7 RESERVED

3.8 COMPLETION INSPECTION

3.8.1 Punch-Out Inspection

3.8.2 Pre-Final Inspection

3.8.3 Final Acceptance Inspection

3.9 DOCUMENTATION

3.10 SAMPLE FORMS

3.11 NOTIFICATION OF NONCOMPLIANCE

SECTION 01 45 01

USACE QUALITY CONTROL

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

(2008) Minimum Requirements for Agencies Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction

(2008) Standard Specification for Agencies Engaged in the Testing and/or Inspection of Materials Used in Construction

U.S. ARMY CORPS OF ENGINEERS (USACE)

ER 1110-1-12

(2006) Quality Management

1.2 PAYMENT

Separate payment will not be made for providing and maintaining an effective Quality Control program, and all associated costs will be included in the applicable Bid Schedule unit or lump-sum prices.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

Establish and maintain an effective quality control (QC) system in compliance with the Contract Clause titled "Inspection of Construction." QC consist of plans, procedures, and organization necessary to produce an end product which complies with the contract requirements. Cover all construction operations, both onsite and offsite, and be keyed to the proposed construction sequence.

The project superintendent will be held responsible for the quality of work and is subject to removal by the Contracting Officer for non-compliance with the quality requirements specified in the contract. In this context the highest level manager responsible for the overall construction activities at the site, including quality and production is the project superintendent. The project superintendent must maintain a physical presence at the site at all times and is responsible for all construction and related activities at the site, except as otherwise acceptable to the Contracting Officer.

3.2 QUALITY CONTROL PLAN

Submit no later than 15 days after receipt of notice to proceed, the Contractor Quality Control (CQC) Plan proposed to implement the requirements of the Contract Clause titled "Inspection of Construction." The Government will consider an interim plan for the first 30 days of operation. Construction will be permitted to begin only after acceptance of the CQC Plan or acceptance of an interim plan applicable to the particular feature of work to be started. Work outside of the accepted interim plan will not be permitted to begin until acceptance of a CQC Plan or another interim plan containing the additional work.

3.2.1 Content of the CQC Plan

Include, as a minimum, the following to cover all construction operations, both onsite and offsite, including work by subcontractors, fabricators, suppliers, and purchasing agents:

- a. A description of the quality control organization, including a chart showing lines of authority and acknowledgment that the CQC staff will implement the three phase control system for all aspects of the work specified. Include a CQC System Manager who reports to the project superintendent.
- b. The name, qualifications (in resume format), duties, responsibilities, and authorities of each person assigned a CQC function.
- c. A copy of the letter to the CQC System Manager signed by an authorized official of the firm which describes the responsibilities and delegates sufficient authorities to adequately perform the functions of the CQC System Manager, including authority to stop work which is not in compliance with the contract. Letters of direction to all other various quality control representatives outlining duties, authorities, and responsibilities will be issued by the CQC System Manager. Copies of these letters must be furnished to the Government.
- d. Procedures for scheduling, reviewing, certifying, and managing submittals, including those of subcontractors, offsite fabricators, suppliers, and purchasing agents.

These procedures must be in accordance with Section 01 33 00 SUBMITTAL PROCEDURES.

- e. Control, verification, and acceptance testing procedures for each specific test to include the test name, specification paragraph requiring test, feature of work to be tested, test frequency, and person responsible for each test. (Laboratory facilities approved by the Contracting Officer must be used.)
- f. Procedures for tracking preparatory, initial, and follow-up control phases and control, verification, and acceptance tests including documentation.
- g. Procedures for tracking construction deficiencies from identification through acceptable corrective action. Establish verification procedures that identified deficiencies have been corrected.
- h. Reporting procedures, including proposed reporting formats.
- i. A list of the definable features of work. A definable feature of work is a task which is separate and distinct from other tasks, has separate control requirements, and may be identified by different trades or disciplines, or it may be work by the same trade in a different environment. Although each section of the specifications may generally be considered as a definable feature of work, there are frequently more than one definable features under a particular section. This list will be agreed upon during the coordination meeting.

3.2.3 Acceptance of Plan

Acceptance of the Contractor's plan is required prior to the start of construction. Acceptance is conditional and will be predicated on satisfactory performance during the construction. The Government reserves the right to require the Contractor to make changes in his CQC Plan and operations including removal of personnel, as necessary, to obtain the quality specified.

3.2.4 Notification of Changes

After acceptance of the CQC Plan, notify the Contracting Officer in writing of any proposed change. Proposed changes are subject to acceptance by the Contracting Officer.

3.3 COORDINATION MEETING

After the Preconstruction Conference, before start of construction and prior to acceptance by the Government of the CQC Plan, meet with the Contracting Officer or Authorized Representative and discuss the Contractor's quality control system. Submit the CQC Plan a minimum of 5 calendar days prior to the Coordination Meeting. During the meeting, a mutual understanding of the system details must be developed, including the forms for recording the CQC operations, control activities, testing, administration of the system for both

onsite and offsite work, and the interrelationship of Contractor's Management and control with the Government's Quality Assurance. Minutes of the meeting will be prepared by the Government, signed by both the contractor and the Contracting Officer and will become a part of the contract file. There may be occasions when subsequent conferences will be called by either party to reconfirm mutual understandings and/or address deficiencies in the CQC system or procedures which may require corrective action by the Contractor.

3.4 QUALITY CONTROL ORGANIZATION

3.4.1 Personnel Requirements

The requirements for the CQC organization are a CQC System Manager and sufficient number of additional qualified personnel to ensure safety and contract compliance. The Safety and Health Manager must receive direction and authority from the CQC System Manager and serve as a member of the CQC staff. Personnel identified in the technical provisions as requiring specialized skills to assure the required work is being performed properly will also be included as part of the CQC organization. The Contractor's CQC staff must maintain a presence at the site at all times during progress of the work and have complete authority and responsibility to take any action necessary to ensure contract compliance. The CQC staff will be subject to acceptance by the Contracting Officer. Provide adequate office space, filing systems and other resources as necessary to maintain an effective and fully functional CQC organization. Promptly complete and furnish all letters, material submittals, shop drawing submittals, schedules and all other project documentation to the CQC organization. The CQC organization shall be responsible to maintain these documents and records at the site at all times, except as otherwise acceptable to the Contracting Officer.

3.4.2 CQC System Manager

Identify as CQC System Manager an individual within the onsite work organization who is responsible for overall management of CQC and have the authority to act in all CQC matters for the Contractor. The CQC System Manager must be a graduate engineer, graduate architect, or a graduate of construction management, or a person with a minimum of 2 years of dredging experience on work similar to this contract. This CQC System Manager must be on the site at all times during construction and be employed by the prime Contractor. The CQC System Manager must be assigned no other duties. Identify in the plan an alternate to serve in the event of the CQC System Manager's absence. The requirements for the alternate are the same as the CQC System Manager.

3.4.4 Additional Requirement

In addition to the above experience and/or education requirements the CQC System Manager shall have completed the course entitled "Construction Quality Management For Contractors". This course is periodically offered at the Mobile District Corps of Engineers.

3.4.3 Organizational Changes

The Contractor shall maintain the CQC staff at full strength at all times. When it is necessary to make changes to the CQC staff, the Contractor shall revise the CQC Plan to reflect the changes and submit the changes to the Contracting Officer for acceptance.

3.5 SUBMITTALS AND DELIVERABLES

Submittals, if needed, shall be made as specified in Section 01 33 00 SUBMITTAL PROCEDURES. The CQC organization shall be responsible for certifying that all submittals and deliverables are in compliance with the contract requirements. When Section 23 08 00.00 10 COMMISSIONING OF HAVAC SYSTEMS are included in the contract, the submittals required by those sections must be coordinated with Section 01 33 00 SUBMITTAL PROCEDURES to ensure adequate time is allowed for each type of submittal required.

3.6 CONTROL

Contractor Quality Control is the means by which the Contractor ensures that the construction, to include that of subcontractors and suppliers, complies with the requirements of the contract. At least three phases of control shall be conducted by the CQC System Manager for each definable feature of the construction work as follows:

3.6.1 Preparatory Phase

This phase shall be performed prior to beginning work on each definable feature of work, after all required plans/documents/materials are approved/accepted, and after copies are at the work site. This phase shall include:

- a. A review of each paragraph of applicable specifications, reference codes, and standards. A copy of those sections of referenced codes and standards applicable to that portion of the work to be accomplished in the field shall be made available by the Contractor at the preparatory inspection. These copies shall be maintained in the field and available for use by Government personnel until final acceptance of the work.
- b. A review of the contract drawings.

- c. A check to assure that all materials and/or equipment have been tested, submitted, and approved.
- d. Review of provisions that have been made to provide required control inspection and testing.
- e. Examination of the work area to assure that all required preliminary work has been completed and is in compliance with the contract.
- f. A physical examination of required materials, equipment, and sample work to assure that they are on hand, conform to approved shop drawings or submitted data, and are properly stored.
- g. A review of the appropriate activity hazard analysis to assure safety requirements are met.
- h. Discussion of procedures for controlling quality of the work including repetitive deficiencies. Document construction tolerances and workmanship standards for that feature of work.
- i. A check to ensure that the portion of the plan for the work to be performed has been accepted by the Contracting Officer.
- j. Discussion of the initial control phase.
- k. The Government shall be notified at least 24 hours in advance of beginning the preparatory control phase. This phase shall include a meeting conducted by the CQC System Manager and attended by the superintendent, other CQC personnel (as applicable), and the foreman responsible for the definable feature. The results of the preparatory phase actions shall be documented by separate minutes prepared by the CQC System Manager and attached to the daily CQC report. The Contractor shall instruct applicable workers as to the acceptable level of workmanship required in order to meet contract specifications.

3.6.2 Initial Phase

This phase shall be accomplished at the beginning of a definable feature of work. The following shall be accomplished:

- a. A check of work to ensure that it is in full compliance with contract requirements. Review minutes of the preparatory meeting.
- b. Verify adequacy of controls to ensure full contract compliance. Verify required control inspection and testing.

- c. Establish level of workmanship and verify that it meets minimum acceptable workmanship standards. Compare with required sample panels as appropriate.
- d. Resolve all differences.
- e. Check safety to include compliance with and upgrading of the safety plan and activity hazard analysis. Review the activity analysis with each worker.
- f. The Government shall be notified at least 24 hours in advance of beginning the initial phase. Separate minutes of this phase shall be prepared by the CQC System Manager and attached to the daily CQC report. Exact location of initial phase shall be indicated for future reference and comparison with follow-up phases.
- g. The initial phase should be repeated for each new crew to work onsite, or any time acceptable specified quality standards are not being met.

3.6.3 Follow-up Phase

Daily checks shall be performed to assure control activities, including control testing, are providing continued compliance with contract requirements, until completion of the particular feature of work. The checks shall be made a matter of record in the CQC documentation. Final follow-up checks shall be conducted and all deficiencies corrected prior to the start of additional features of work which may be affected by the deficient work. The Contractor shall not build upon nor conceal non-conforming work.

3.6.4 Additional Preparatory and Initial Phases

Additional preparatory and initial phases shall be conducted on the same definable features of work if: the quality of on-going work is unacceptable; if there are changes in the applicable CQC staff, onsite production supervision or work crew; if work on a definable feature is resumed after a substantial period of inactivity; or if other problems develop.

3.7 RESERVED

3.8 COMPLETION INSPECTION

3.8.1 Punch-Out Inspection

Near the end of the work, or any increment of the work established by a time stated in the SPECIAL CONTRACT REQUIREMENTS Clause, "Commencement, Prosecution, and Completion of Work", or by the specifications, the CQC Manager shall conduct an inspection of the work. A

punch list of items which do not conform to the approved drawings and specifications shall be prepared and included in the CQC documentation, as required by paragraph DOCUMENTATION. The list of deficiencies shall include the estimated date by which the deficiencies will be corrected. The CQC System Manager or staff shall make a second inspection to ascertain that all deficiencies have been corrected. Once this is accomplished, the Contractor shall notify the Government that the facility is ready for the Government Pre-Final inspection.

3.8.2 Pre-Final Inspection

The Government will perform the pre-final inspection to verify that the facility is complete and ready to be occupied. A Government Pre-Final Punch List may be developed as a result of this inspection. The Contractor's CQC System Manager shall ensure that all items on this list have been corrected before notifying the Government, so that a Final inspection with the customer can be scheduled. Any items noted on the Pre-Final inspection shall be corrected in a timely manner. These inspections and any deficiency corrections required by this paragraph shall be accomplished within the time slated for completion of the entire work or any particular increment of the work if the project is divided into increments by separate completion dates.

3.8.3 Final Acceptance Inspection

The Contractor's Quality Control Inspection personnel, plus the superintendent or other primary management person, and the Contracting Officer's Representative shall be in attendance at the final acceptance inspection. Additional Government personnel including, but not limited to, those from Base/Post Civil Facility Engineer user groups, and major commands may also be in attendance. The final acceptance inspection will be formally scheduled by the Contracting Officer based upon results of the Pre-Final inspection. Notice shall be given to the Contracting Officer at least 14 days prior to the final acceptance inspection and shall include the Contractor's assurance that all specific items previously identified to the Contractor as being unacceptable, along with all remaining work performed under the contract, will be complete and acceptable by the date scheduled for the final acceptance inspection. Failure of the Contractor to have all contract work acceptably complete for this inspection will be cause for the Contracting Officer to bill the Contractor for the Government's additional inspection cost in accordance with the contract clause titled "Inspection of Construction".

3.9 DOCUMENTATION

The Contractor shall maintain current records providing factual evidence that required quality control activities and/or tests have been performed. These

records shall include the work of subcontractors and suppliers and shall be on an acceptable form that includes, as a minimum, the following information:

- a. Contractor/subContractor and their area of responsibility.
- b. Operating plant/equipment with hours worked, idle, or down for repair.
- c. Work performed each day, giving location, description, and by whom. When Network Analysis (NAS) is used, identify each phase of work performed each day by NAS activity number.
- d. Test and/or control activities performed with results and references to specifications/drawings requirements. The control phase shall be identified (Preparatory, Initial, Follow-up). List of deficiencies noted, along with corrective action.
- e. Quantity of materials received at the site with statement as to acceptability, storage, and reference to specifications/drawings requirements.
- f. Submittals and deliverables reviewed, with contract reference, by whom, and action taken.
- g. Offsite surveillance activities, including actions taken.
- h. Job safety evaluations stating what was checked, results, and instructions or corrective actions.
- i. Instructions given/received and conflicts in plans and/or specifications.
- j. Contractor's verification statement.

These records shall indicate a description of trades working on the project; the number of personnel working; weather conditions encountered; and any delays encountered. These records shall cover both conforming and deficient features and shall include a statement that equipment and materials incorporated in the work and workmanship comply with the contract. The original and one copy of these records in report form shall be furnished to the Government daily within 24 hours after the date covered by the report, except that reports need not be submitted for days on which no work is performed. As a minimum, one report shall be prepared and submitted for every 7 days of no work and on the last day of a no work period. All calendar days shall be accounted for throughout the life of the contract. The first report following a day of no work shall be for that day only. Reports shall be signed and dated by the CQC System Manager. The report from the CQC System Manager shall include copies of test reports and copies of reports prepared by all subordinate quality control personnel.

3.10 SAMPLE FORMS

Sample forms enclosed at the end of this section.

3.11 NOTIFICATION OF NONCOMPLIANCE

The Contracting Officer will notify the Contractor of any detected noncompliance with the foregoing requirements. The Contractor shall take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the work site, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

--End of Section--

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 45 01.10

USACE QUALITY CONTROL SYSTEM (QCS)

PART 1 GENERAL

- 1.1 Contract Administration
 - 1.1.1 Correspondence and Electronic Communications
 - 1.1.2 Other Factors
- 1.2 QCS SOFTWARE
- 1.3 SYSTEM REQUIREMENTS
- 1.4 RELATED INFORMATION
 - 1.4.1 QCS User Guide
 - 1.4.2 Contractor Quality Control (CQC) Training
- 1.5 CONTRACT DATABASE
- 1.6 DATABASE MAINTENANCE
 - 1.6.1 Administration
 - 1.6.1.1 Contractor Information
 - 1.6.1.2 Subcontractor Information
 - 1.6.1.3 Correspondence
 - 1.6.1.4 Equipment
 - 1.6.1.5 Management Reporting
 - 1.6.1.6 Request For Information (RFI)
 - 1.6.2 Finances
 - 1.6.2.1 Pay Activity Data
 - 1.6.2.2 Payment Requests
 - 1.6.3 Quality Control (QC)
 - 1.6.3.1 Daily Contractor Quality Control (CQC) Reports.
 - 1.6.3.2 Deficiency Tracking.
 - 1.6.3.3 QC Requirements
 - 1.6.3.4 Three-Phase Control Meetings
 - 1.6.3.5 Labor and Equipment Hours
 - 1.6.3.6 Accident/Safety Reporting
 - 1.6.3.7 Features of Work
 - 1.6.3.8 Hazard Analysis
 - 1.6.4 Submittal Management
 - 1.6.5 Schedule
 - 1.6.6 Import/Export of Data
- 1.7 IMPLEMENTATION
- 1.8 DATA SUBMISSION VIA CD-ROM
 - 1.8.1 File Medium
 - 1.8.2 CD-ROM Labels
 - 1.8.3 File Names

1.9 MONTHLY COORDINATION MEETING
1.10 NOTIFICATION OF NONCOMPLIANCE

PART 2 PRODUCTS

PART 3 EXECUTION

-- End of Section Table of Contents -

SECTION 01 45 01.10

USACE QUALITY CONTROL SYSTEM (QCS)

PART 1 GENERAL

1.1 Contract Administration

The Government will use the Resident Management System for Windows (RMS) to assist in its monitoring and administration of this contract. The Contractor must use the Government-furnished Construction Contractor Module of RMS, referred to as QCS, to record, maintain, and submit various information throughout the contract period. The Contractor module, user manuals, updates, and training information can be downloaded from the RMS web site. This joint Government-Contractor use of RMS and QCS will facilitate electronic exchange of information and overall management of the contract. QCS provides the means for the Contractor to input, track, and electronically share information with the Government in the following areas:

Administration

Finances

Quality Control

Submittal Monitoring

Scheduling

Import/Export of Data

1.1.1 Correspondence and Electronic Communications

For ease and speed of communications, both Government and Contractor will, to the maximum extent feasible, exchange correspondence and other documents in electronic format. Correspondence, pay requests and other documents comprising the official contract record will also be provided in paper format, with signatures and dates where necessary. Paper documents will govern, in the event of discrepancy with the electronic version.

1.1.2 Other Factors

Particular attention is directed to Contract Clause, "Schedules for Construction Contracts", Contract Clause, "Payments", Section 01 33 00 SUBMITTAL PROCEDURES, and Section 01 45 01 USACE QUALITY CONTROL, which have a direct relationship to the reporting to be accomplished through QCS. Also, there is no separate payment for establishing and maintaining the QCS database; all costs associated therewith will be included in the contract pricing for the work.

1.2 QCS SOFTWARE

QCS is a Windows-based program that can be run on a stand-alone personal computer or on a network. The Government will make available the QCS software to the Contractor after award of the construction contract. Prior to the Pre-Construction Conference, the Contractor will be responsible to download, install and use the latest version of the QCS software from the Government's RMS Internet Website. Upon specific justification and request by the Contractor, the Government can provide QCS on CD-ROM. Any program updates of QCS will be made available to the Contractor via the Government RMS Website as they become available.

1.3 SYSTEM REQUIREMENTS

The following is the minimum system configuration that the Contractor must have to run QCS:

IBM-compatible PC with 1000 MHz Pentium or higher processor 256+ MB RAM for workstation / 512+ MB RAM for server 1 GB hard drive disk space for sole use by the QCS system 3-1/2 inch high-density floppy drive Compact Disk (CD) Reader 8x speed or higher SVGA or higher resolution monitor (1024x768, 256 colors) Mouse or other pointing device Windows compatible printer. (Laser printer must have 4 MB+ of RAM) Connection to the Internet, minimum 56k BPS

Software

MS Windows 2000 or higher QAS-Word Processing software: MS Word 2000 or newer Latest version of: Netscape Navigator, Microsoft Internet

Explorer, or other browser that supports HTML 4.0 or higher Electronic mail (E-mail) MAPI compatible Virus protection software that is regularly upgraded with all issued manufacturer's updates

1.4 RELATED INFORMATION

1.4.1 QCS User Guide

After contract award, download instructions for the installation and use of QCS from the Government RMS Internet Website. In case of justifiable difficulties, the Government will provide the Contractor with a CD-ROM containing these instructions.

1.4.2 Contractor Quality Control (CQC) Training

The use of QCS will be discussed with the Contractor's QC System Manager during the mandatory CQC Training class.

1.5 CONTRACT DATABASE

Prior to the pre-construction conference, the Government will provide the Contractor with basic contract award data to use for QCS. The Government will provide data updates to the Contractor as needed, generally by using the Government's SFTP repository built into QCS import/export function. These updates will generally consist of submittal reviews, correspondence status, QA comments, and other administrative and QA data.

1.6 DATABASE MAINTENANCE

Establish, maintain, and update data in the QCS database throughout the duration of the contract at the Contractor's site office. Submit data updates to the Government (e.g., daily reports, submittals, RFI's, schedule updates, payment requests, etc.) using the Government's SFTP repository built into QCS export function. If permitted by the Contracting Officer, e-mail or CD-ROM may be used instead of E-mail (see Paragraph DATA SUBMISSION VIA CD-ROM). The QCS database typically includes current data on the following items:

1.6.1 Administration

1.6.1.1 Contractor Information

Contain within the database the Contractor's name, address, telephone numbers, management staff, and other required items. Within 14 calendar days of receipt of QCS software from the Government, deliver Contractor administrative data in electronic format.

1.6.1.2 Subcontractor Information

Contain within the database the name, trade, address, phone numbers, and other required information for all subcontractors. A subcontractor must be listed separately for each trade to be performed. Assign each subcontractor/trade a unique Responsibility Code, provided in QCS. Within 14 calendar days of receipt of QCS software from the Government, deliver subcontractor administrative data in electronic format.

1.6.1.3 Correspondence

Identify all Contractor correspondence to the Government with a serial number. Prefix correspondence initiated by the Contractor's site office with "S". Prefix letters initiated by the Contractor's home (main) office with "H". Letters must be numbered starting from 0001. (e.g., H-0001 or S-0001). The Government's letters to the Contractor will be prefixed with "C".

1.6.1.4 Equipment

Contain within the Contractor's QCS database a current list of equipment planned for use or being used on the jobsite, including the most recent and planned equipment inspection dates.

1.6.1.5 Management Reporting

QCS includes a number of reports that Contractor management can use to track the status of the project. The value of these reports is reflective of the quality of the data input, and is maintained in the various sections of QCS. Among these reports are: Progress Payment Request worksheet, QA/QC comments, Submittal Register Status, Three-Phase Inspection checklists.

1.6.1.6 Request For Information (RFI)

Exchange all Requests For Information (RFI) using the Built-in RFI generator and tracker in QCS.

1.6.2 Finances

1.6.2.1 Pay Activity Data

Include within the QCS database a list of pay activities that the Contractor must develop in conjunction with the construction schedule. The sum of all pay activities must be equal to the total contract amount, including modifications. Group pay activities Contract Line Item Number (CLIN); the sum of the activities must equal the amount of each CLIN. The total of all CLINs equals the Contract Amount.

1.6.2.2 Payment Requests

Prepare all progress payment requests using QCS. Complete the payment request worksheet, prompt payment certification, and payment invoice in QCS. Update the work completed under the contract, measured as percent or as specific quantities, at least monthly. After the update, generate a payment request report using QCS. Submit the payment request, prompt payment certification, and payment invoice with supporting data using the Government's SFTP repository built into QCS export function. If permitted by the Contracting Officer, e-mail or a CD-ROM may be used. A signed paper copy of the approved payment request is also required, which will govern in the event of discrepancy with the electronic version.

1.6.3 Quality Control (QC)

QCS provides a means to track implementation of the 3-phase QC Control System, prepare daily reports, identify and track deficiencies, document progress of work, and support other Contractor QC requirements. Maintain this data on a daily basis. Entered data will automatically output to the QCS generated daily report. Provide the Government a Contractor Quality Control (CQC) Plan within the time required in Section 01 45 01 USACE QUALITY CONTROL. Within seven calendar days of Government acceptance, submit a QCS update reflecting the information contained in the accepted CQC Plan: schedule, pay activities, features of work, submittal register, QC requirements, and equipment list.

1.6.3.1 Daily Contractor Quality Control (CQC) Reports.

QCS includes the means to produce the Daily CQC Report. The Contractor may use other formats to record basic QC data. However, the Daily CQC Report generated by QCS must be the Contractor's official report. Summarize data from any supplemental reports by the Contractor and consolidate onto the QCS-generated Daily CQC Report. Submit daily CQC Reports as required by Section 01 45 01 USACE QUALITY CONTROL. Electronically submit reports to the Government within 24 hours after the date covered by the report. Also provide the Government a signed, printed copy of the daily CQC report.

1.6.3.2 Deficiency Tracking.

Use QCS to track deficiencies. Deficiencies identified by the Contractor will be numerically tracked using QC punch list items. Maintain a current log of its QC punch list items in the QCS database. The Government will log the deficiencies it has identified using its QA punch list items. The Government's QA punch list items will be included in its export file to the Contractor. Regularly update the correction status of both QC and QA punch list items.

1.6.3.3 QC Requirements

Develop and maintain a complete list of QC testing and required structural and life safety special inspections required by the International Code Council (ICC), transferred and installed property, and user training requirements in QCS. Update all data on these QC requirements as work progresses, and promptly provide this information to the Government via QCS.

1.6.3.4 Three-Phase Control Meetings

Maintain scheduled and actual dates and times of preparatory and initial control meetings in QCS.

1.6.3.5 Labor and Equipment Hours

Log labor and equipment exposure hours on a daily basis. This data will be rolled up

into a monthly exposure report.

1.6.3.6 Accident/Safety Reporting

The Government will issue safety comments, directions, or guidance whenever safety deficiencies are observed. The Government's safety comments will be included in its export file to the Contractor. Regularly update the correction status of the safety comments. In addition, utilize QCS to advise the Government of any accidents occurring on the jobsite. This brief supplemental entry is not to be considered as a substitute for completion of mandatory reports, e.g., ENG Form 3394 and OSHA Form 300.

1.6.3.7 Features of Work

Include a complete list of the features of work in the QCS database. A feature of work may be associated with multiple pay activities. However, each pay activity (see subparagraph "Pay Activity Data" of paragraph "Finances") will only be linked to a single feature of work.

1.6.3.8 Hazard Analysis

Use QCS to develop a hazard analysis for each feature of work included in the CQC Plan. Address any hazards, or potential hazards, that may be associated with the work.

1.6.4 Submittal Management

The Government will provide the initial submittal register in electronic format. Thereafter, maintain a complete list of all submittals, including completion of all data columns. Dates on which submittals are received and returned by the Government will be included in its export file to the Contractor. Use QCS to track and transmit all submittals. ENG Form 4025, submittal transmittal form, and the submittal register update must be produced using QCS. QCS and RMS will be used to update, store and exchange submittal registers and transmittals, but will not be used for storage of actual submittals.

1.6.5 Schedule

Develop a construction schedule consisting of pay activities, in accordance with Section 01 32 01.00 10 PROJECT SCHEDULE. Input and maintain in the QCS database this schedule either manually or by using the Standard Data Exchange Format (SDEF) (see Section 01 32 01.00 10 PROJECT SCHEDULE). Include with each pay request the updated schedule.

1.6.6 Import/Export of Data

QCS includes the ability to export Contractor data to the Government and to import submittal register and other Government-provided data from RMS, and schedule data using SDEF.

1.7 IMPLEMENTATION

Contractor use of QCS as described in the preceding paragraphs is mandatory. Ensure that sufficient resources are available to maintain its QCS database, and to provide the Government with regular database updates. QCS shall be an integral part of the Contractor's management of quality control.

1.8 DATA SUBMISSION VIA CD-ROM

The Government-preferred method for Contractor's submission of QCS data is by using the Government's SFTP repository built into QCS export function. Other data should be submitted using E-mail with file attachment(s). For locations where this is not feasible, the Contracting Officer may permit use of CD-ROM for data transfer. Export data onto CDs using the QCS built-in export function. If used, submit CD-ROMs in accordance with the following:

1.8.1 File Medium

Submit in English required data on CD-ROM conforming to industry standards used in the United States.

1.8.2 CD-ROM Labels

Affix a permanent exterior label to each CD-ROM submitted. Indicate on the label in English, the QCS file name, full contract number, contract name, project location, data date, name and telephone number of person responsible for the data.

1.8.3 File Names

The files will be automatically named by the QCS software. The naming convention established by the QCS software must not be altered.

1.9 MONTHLY COORDINATION MEETING

Update the QCS database each workday. At least monthly, generate and submit an export file to the Government with schedule update and progress payment request. As required in Contract Clause "Payments", at least one week prior to submittal, meet with the Government representative to review the planned progress payment data submission for errors and omissions.

Make all required corrections prior to Government acceptance of the export file and

progress payment request. Payment requests accompanied by incomplete or incorrect data submittals will be returned. The Government will not process progress payments until an acceptable QCS export file is received.

1.10 NOTIFICATION OF NONCOMPLIANCE

The Contracting Officer will notify the Contractor of any detected noncompliance with the requirements of this specification. Take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the work site, will be deemed sufficient for the purpose of notification.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section -

MOBILE HARBOR

SECTION 01 57 20.00 10

ENVIRONMENTAL PROTECTION 09/08

PART 1 GENERAL

1.1 APPLICABLE REGULATIONS

The Contractor and their subcontractors in the performance of this contract, shall comply with all applicable Federal, State, and local laws and regulations concerning environmental pollution control and abatement, all applicable provisions of the Corps of Engineers Manual, EM 385-1-1, entitled "Safety and Health Requirements", in effect on the date of solicitation, and the specific requirements stated elsewhere in the contract specifications.

1.2 SCOPE

The work covered by this section consists of furnishing all labor, materials and equipment, and performing all work required for the prevention of environmental pollution during the dredging activities for the Mobile Harbor project, except for those measures set forth in other Technical Provisions of these specifications. For the purpose of this specification, environmental pollution is defined as: a) the presence of chemical, physical, or biological elements or agents that adversely affect human health or welfare; b) unfavorably alter ecological balances; c) affect other species of designated importance of man; or d) degrade the utility of the environment for aesthetic and recreational purposes. The control of environmental pollution requires consideration of air, water, and land, and involves noise control, solid waste management, as well as control of other pollutants.

1.3 SUBCONTRACTORS

The Contractor and their subcontractors shall comply with all requirements under the terms and conditions set out in the permits or certifications issued by the Alabama Department of Environmental Management (ADEM) and in compliance with the provisions of the Contract and applicable Federal, state, and local environmental laws and regulations. Compliance with the provisions of this section by subcontractors shall be the responsibility of the Contractor.

- a. The Contractor shall submit an Environmental Protection Plan, in accordance with provisions as specified.
- b. The Contractor shall record on daily reports any problems in complying with laws, regulations and ordinances, and corrective action taken.

c. The Contractor shall prepare a listing of resources needing protection (i.e., upland vegetation, wetlands, oyster reefs, submerged aquatic vegetation, air quality, noise levels, surface and groundwater quality, fish and wildlife, historical, archeological, and cultural resources) within authorized work areas.

d. The Contractor shall prepare a pollution prevention plan that identifies all potentially hazardous substances on the job site and the intended actions to be taken to prevent the accidental or intentional introduction of such materials into the air, the water or the ground.

e. The Contractor shall set out the procedures to be followed to correct pollution of the environment due to accident, natural causes or failure to follow the procedures identified in the environmental protection plan.

f. The Contractor shall keep dredging and placement activities under surveillance and shall exercise all necessary controls to minimize damage to the environment by noise from equipment and various activities. Areas that have noise levels greater than 85-dB continuously or 140-dB peak (unweighted) impulse must be designated as noise hazardous areas. These work areas must have caution signs displayed at the perimeter of the noise area indicating the presence of hazardous noise levels and requiring the use of hearing protection devices.

g. The Contractor shall detail special provisions taken to meet Federal, state, and local laws and regulations regarding the storage and handling of solid and hazardous waste materials.

1.4 PAYMENT

No separate payment will be made for work covered under this section and all costs in connection therewith will be considered a subsidiary obligation of the Contractor and covered under the contract unit and/or lump sum prices in the Bidding Schedule.

1.5 ENVIRONMENTAL PROTECTION PLAN

Prior to commencement of the work, the Contractor shall, after receipt of Notice of Award of the Contract and at least 7 days prior to the Preconstruction Conference, submit in writing the above Environmental Protection Plan, and shall meet with representative(s) of the Contracting Office to develop mutual understanding relative to compliance with this provision and administration of the environmental protection program.

1.6 NOTIFICATION

The Contracting Officer will notify the Contractor in writing of any observed noncompliance with Federal, State, or local environmental laws or regulations, permits, and other elements of the Contractor's Environmental Protection plan. The Contractor shall, after receipt of such notice, inform the Contracting Officer of the proposed corrective action and take such action when approved by the Contracting Officer. The Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No time extensions shall be granted or equitable adjustments allowed to the Contractor for any such suspensions. This is in addition to any other actions the Contracting Officer may take under the contract, or in accordance with the Federal Acquisition Regulation or Federal Law.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION

3.1 PROTECTION OF WATER RESOURCES

The Contractor shall not pollute any water bodies including streams, lakes, bays, estuaries, or other marine or fresh waters with fuels, oils, acids, or any other harmful materials. It is the responsibility of the Contractor to investigate and comply with all applicable Federal, state, county, and municipal laws concerning water pollution. The discharge of plastics of any kind within estuarine or marine waters is strictly prohibited. All work under this contract shall also be performed in such a manner that objectionable conditions will not be created in proximity to the project areas.

a. The Contracting Officer Representative will designate the proposed areas for excavation and the location of approved placement areas. No other areas are approved for the placement or excavation of material.

b. The Contractor shall comply with all turbidity and monitoring standards and other conditions set forth in the water quality standards as specified by the Alabama Department of Environmental Management (ADEM). The Government will monitor turbidity (NTU's) in the work area throughout the life of the contract to ensure that the Contractor complies with the permit requirements. Turbidity measurements must be taken daily at the dredge and discharge sites and a background location to be determined by the Contractor. The turbidity monitoring report (included in the Environmental Compliance Appendix) shall be filled out and submitted weekly to the Contracting Officer who will then forward to the Mobile District coastal Environment Staff: Ms. Lekesha Reynolds, PD-EC by email Lekesha.w.reynolds@usace.army.mil. The Contractor shall provide the

name(s) and credentials of the person(s) responsible for turbidity monitoring in the Environmental Protection Plan. If turbidity at the placement site exceeds 50 NTUs above background levels outside the prescribed mixing zones, as specified in the permit, the contractor shall cease activities until corrective actions have been taken and turbidity levels have returned to within compliance levels. Should work stoppage occur, the Contractor shall immediately notify the Contracting Officer Representative.

c. Special measures shall be taken to prevent chemicals, fuels, oils, and greases at the beach placement site or along the pipeline from entering area waters, at all times.

d. Contractor shall maintain Best Management Practices (BMPs) at all times during operations to minimize turbidity at both the dredge and placement sites.

e. Discharge of any pollutant into the watercourse is strictly prohibited, except as otherwise specified or allowed in other sections of the Technical Specifications.

f. Wastewater shall be processed, filtered, ponded, or otherwise treated prior to their release from project area into waterways.

g. All dredging equipment must have approved marine sanitation devices. Staging areas must have approved onsite wastewater treatment facilities.

3.2 MOBILE OCEAN DREDGED MATERIAL DISPOSAL SITE (ODMDS)

Placement of the dredged sediments within the ODMDS will be conducted in accordance with the conditions specified below in the Section 103 concurrence letter from U.S. Environmental Protection Agency (EPA) and the Site Management and Monitoring Plan (SMMP). Both of these documents are included in the Environmental Compliance Appendix.

a. Mobile Maintenance Ocean Disposal Conditions

(1) A bathymetry survey of the ODMDS release zone will be conducted within three months prior to initiation of disposal activities.

(2) A bathymetry survey of the ODMDS release zone will be conducted within thirty days of completion of disposal activities.

(3) All disposal will be initiated at least 330 feet within the boundaries of the Mobile ODMDS.

(4) The following special conditions for Dredging Units 02, 06/07, and 10/11 will be followed:

(a) Disposal operations with disposal volumes of less than or equal to 10,800 cubic yards per load have no further restrictions.

(b) For volumes in excess of 10,800 cubic yards, the disposal vessel must dispose at speeds less than 3 knots (kts) (accuracy of +/-1 kts) and no more than one hopper bin may open simultaneously.

(c) Disposal logs shall be maintained for each load in excess of 10,800 cubic yards. The logs will include at a minimum the following:

- i. - load number
- ii. disposal vessel name and type (e.g. scow)
- iii. estimated volume of load
- iv. description of material disposed
- v. source of dredged material
- vi. date, time and location at start and completion of disposal event.

(d) Disposal logs shall be submitted with the Post-disposal summary report, or upon request.

(e) Dredging Unit MH 10-02 is defined as Mobile River Channel 141+00 to 156+00. Dredging Unit MH10-06/07 is defined as the Mobile Bay Channel 759+00 to 824+00. Dredging Unit MH10-10/11 is defined as the Mobile Bay Channel 1594+00 to 1760+10.

3.3 RECORDING AND PRESERVING HISTORICAL AND ARCHEOLOGICAL FINDS

All items having any apparent historical or archeological interest, which are discovered in the course of any removing of material and placement activities shall be carefully preserved. The Contractor shall leave the archaeological find undisturbed and immediately report the find to the Contracting Officer Representative and the Mobile District Archeological Staff (attn: Mr. Michael Fedoroff, PD-EI 251-694-4114) so the proper authorities may be notified. Existing historical, archeological and cultural resources within the Contractor's work area will be so designated by the Contracting Officer Representative. All activities associated with these resources shall be coordinated through the Mobile District Archeological Staff (attn: Mr. Michael Fedoroff, PD-EI 251-694-4114).

3.4 PROTECTION OF LAND RESOURCES

The environmental resources within the project boundaries and those outside the limits of permanent work under this contract shall be protected during the entire period of this contract. The Contractor shall confine their activities to areas defined by the drawings and specifications. The Contractor shall perform a preconstruction survey, which includes but is not limited to photographs, and provide this to the Contracting Officer Representative prior to dredging and placement activities.

- a. It is intended that the land resources outside the limits of permanent work completed under this contract be preserved in their present condition or be restored to natural conditions, after completion of dredging and placement activities.
- b. The Contractor's field offices, staging areas, stockpile storage, and temporary buildings shall be placed in an area approved by the Contracting Officer Representative. The Contracting Officer Representative shall approve all temporary movement or relocation of Contractor facilities.
- c. The Contractor shall be required to maintain all work areas within or without the project boundaries free from dust that would cause a hazard or nuisance to others.
- d. The Contractor shall obliterate all signs of temporary support facilities such as haul roads, work areas, structures, foundations of temporary structures, or any other vestiges of activities as directed by the Contracting Officer Representative.
- e. The Contractor shall construct or install all temporary and permanent erosion and sedimentation control features at the placement site and along the pipeline route.
- f. Solid wastes (excluding clearing debris) includes any waste generated by the Contractor which meets the most complete definition of solid waste as described by Federal, state and local laws and regulations. Solid waste shall be placed in containers that are emptied on a regular schedule. All handling and disposal shall be conducted to prevent spillage and contamination.
- g. Hazardous waste shall be stored, removed from the work area and disposed of in accordance with Federal, state and local laws and regulations.
- h. The Contractor shall use drainage ditches, low ground pressure equipment, matting, geogrids, and/or other types of soil reinforcement as necessary to enable vehicle traffic and other activity.

3.5 PROTECTION OF FISH AND WILDLIFE

The Contractor shall at all times perform all work and take such steps required to prevent any significant interference or disturbance (as determined by the Contracting Officer Representative) to fish and wildlife.

- a. The Contractor will not be permitted to alter water flows or otherwise disturb native habitats adjacent to the project area, which, in the opinion of the Contracting Officer Representative or their appointed representative, are critical to fish or wildlife. Fouling or polluting of water will not be permitted.
- b. The Contractor must perform all work within compliance specifications of the permit issued by the Alabama Department of Environmental Management (ADEM) which is included in the Environmental Compliance Appendix.
- c. Threatened and Endangered Species: The Contractor shall take all necessary precautions to ensure that activities conducted during the course of this project do not adversely impact listed threatened and endangered species. The Contractor shall instruct all personnel associated with the project of the potential presence of manatees, sea turtles, and Gulf sturgeon in the area, and the need to avoid collisions with and harming these animals. All construction personnel shall be advised that there are civil and criminal penalties for harming, harassing, or killing manatees, sea turtles, Gulf sturgeon, dolphins or whales; or destroying or adversely modifying critical habitat of these species which are protected under the Marine Mammal Protection Act of 1972, the Endangered Species Act of 1973. The Contractor must take special precautions to ensure adequate protection for wildlife resources.

(1) The Contractor shall adhere to all Federal, State, and local laws and regulations including the 2003 NMFS Gulf Regional Biological Opinion (GRBO) and subsequent amendments.

(2) The Contractor shall coordinate all activities associated with these resources with the Coastal Environment Team, Mobile District (attn: Ms. LeKesha Reynolds, PD-EC at 251-690-3260 or Ms. Jenny Jacobson, PD-E at 251-690-2724).

(3) If there are any incidents (live or dead) involving threatened or endangered species, the Contractor shall notify the Contracting Officer, Contracting Officer Representative, and the following individual(s) **within 24 hours**:

- Ms. Lekesha Reynolds 251-690-3260 (251-327-8650 (after-hours) or Ms. Jennifer Jacobson 251-690-2724, U.S. Army Corps of Engineers, PD-EC

The Contracting Officer will direct the contractor as to any required shutdown procedures or necessary changes in dredge operation as to reduce the likelihood of additional incidents. The contractor shall suspend dredging immediately if:

- a. Two or more turtle incidents occur within 24 hours
- b. Two turtles incidents, of the same species, occur during dredging
- c. Four turtle incidents, regardless of species, occur during dredging
- d. One gulf sturgeon incident during dredging

d. Protection of Manatees: See "Standard Manatee Construction Conditions" in Environmental Compliance Appendix.

(1) Manatee Sighting: If a manatee(s) is sighted within 100 yards of the project area, all appropriate precautions shall be implemented by the Contractor to ensure protection of the manatee. These precautions shall include the operation of all moving equipment no closer than 50 feet of a manatee. If a manatee is closer than 50 feet to moving equipment or the project area, the equipment shall be shut down and all construction activities shall cease within the waterway to ensure protection of the manatee. Construction activities shall not resume until the manatee has departed the project area. Animals must not be herded away or harassed into leaving. If construction activity shall cease, the Contractor shall notify the Contracting Officer.

(2) Manatee Signs: Prior to commencement of construction, each vessel involved in construction activities shall display at the vessel control station, or in a prominent location visible to all employees operating the vessel, a temporary sign at least 8-1/2" x 11" reading, "CAUTION: MANATEE HABITAT/IDLE SPEED IS REQUIRED IN CONSTRUCTION AREA." In the absence of a vessel, a temporary 3' x 4' sign reading "CAUTION: MANATEE AREA" shall be posted adjacent to the issued construction permit. A second temporary sign measuring 8-1/2" x 11" reading "CAUTION: MANATEE HABITAT. IDLE SPPED IS REQUIRED IF OPERATIING A VESSEL IN THE CONSTRUCTION AREA. ALL EQUIPMENT MUST BE SHUTDOWN IMMEDIATELY IF A MANATEE COMES WITHIN 50 FEET OF OPERATION. ALL COLLISIONS WITH AND/OR INJURY TO A MANATEE SHALL BE REPORTED IMMEDIATELY TO THE USFWS IN DAPHNE (251-441-5181)" shall be posted at the dredge operator control station and at a location prominently adjacent to the issued construction permit. The Contractor shall remove the signs upon completion of construction.

(3) Manatee Sighting Reports: Any collisions with a manatee, or sighting of any injured or incapacitated manatee, shall be reported immediately to the Contracting Officer or their appointed representative.

(4) Report Submission: The Contractor shall maintain a log detailing sightings, collisions, or injuries to manatees occurring during the contract period. All data in original form shall be forwarded directly to the Mobile District, Planning and Environmental Division, Coastal Environment Team, P.O. Box 2288 Mobile, Alabama 36628-0001, (Attn: Ms. Lekesha Reynolds) and the Area Engineer within 10 days of collection.

e. Protection of Sea Turtles and Gulf Sturgeon - Hopper Dredging Only: the Contractor shall implement the following conditions:

(1) Observers: The contractor shall supply NMFS-approved protected species observers to be aboard the hopper dredges to monitor the hopper dredged material, screening, and dragheads for sea turtles and Gulf sturgeon. Observer coverage shall be 100 percent (24 hr/day). During transit to and from the placement area, the observer shall monitor from the bridge during daylight hours for the presence of endangered species. During dredging operations, while dragheads are submerged, the observer shall continuously monitor the inflow and/or overflow screening for turtles and Gulf sturgeon and/or parts of these species. Upon completion of each load cycle, dragheads should be monitored as the draghead is lifted from the sea surface and is placed on the saddle in order to assure that any sea turtle that may be impinged is not lost or unaccounted for. Observers shall physically inspect dragheads and inflow and overflow screening/boxes for threatened and endangered species takes.

(2) New Operations and Dredging Endangered Species System (ODESS) Reporting System (preferred): The ODESS system, which consists of a tablet computer with an Internet connection, shall be a standalone system, exclusive to other systems, and shall have USACE ODESS data collection and reporting software, referred to as the ODESS Field collector (FC) tool, installed by USACE ODESS support personnel. In the event hardware or software problems prevent the storage or transmission of the collected data, paper copies of the latest ODESS forms and information shall be maintained and submitted to ODESS support and the USACE Inspector or Contracting Officer Representative according to the schedule outlined in the contract specifications. Hardware and Software requirements for the system can be found at the end of this section.

Prior to the initiation of the project, Observers shall be familiar with the operation of the ODESS FC tool and proficient in its use so as to be able to prepare and transmit the results of their observations. ODESS system

webinar training can be requested by contacting ODESS Support at ODESS@usace.army.mil or 1-877-840-8024.

Depending on the target audience (Observer, dredging Contractor, USACE District personnel, or other Federal agencies), ODESS training could, in addition to the webinar training, consist of demonstrating the steps involved in setting up the FC tool on the dredge, loading Observer-collected data and attachments into the FC tool, submitting these data and attachments to the ODESS database, and/or navigating around the ODESS public website to view and pull down data and/or decision-making information for later analysis.

(3) ODESS Monitoring Reports (preferred): Observers shall record the results of the threatened and endangered species monitoring in the ODESS system by filling in the appropriate electronic forms on the ODESS FC tool and transmitting the data to the ODESS database. If there is an issue with recording data straight to the FC tool due to the logistical nature of how the Observer is collecting this data, paper copies of these forms can be downloaded from the ODESS public website (<http://dgm.usace.army.mil/odess/#/download>) and later entered into the FC tool when the Observer has the best opportunity.

Prior to the start of dredging, Observers shall verify that the ODESS FC tool is installed and operational on a dredge's dedicated tablet computer and that a viable Internet connection is available. In addition, before a project is initiated, on the ODESS FC tool homepage Observers shall retrieve (or "pull down") project-specific information from the ODESS database and perform a one-time setup of the dredging project by establishing the dredge name and time zone. During the project, the following forms shall be used in the FC tool and submitted to the ODESS database at the indicated reporting frequency:

(a) Load Data Form: Observers shall complete the Load Data Form, including a description of screen contents and sea conditions, based on their observations. This form shall be completed and transmitted to the ODESS database for each load. At the end of each Observer shift, or when an Internet signal is available (not to exceed 24 hours from the start of the shift), the Observer shall submit all of their Load Data Forms. If this is not possible due to hardware or software problems, the Observer shall revert to email submission of the forms to ODESS@usace.army.mil and Lekesha.W.Reynolds@usace.army.mil.

(b) Sea Turtle Incidental Data Form: If a sea turtle or its remains are identified during a load inspection, after the appropriate parties are notified via telephone, a Sea Turtle Incidental Data Form shall

be completed and submitted to the ODESS database as soon as possible (not to exceed 12 hours after the incident). Any applicable documentation (scanned copies of the paper Observer load and incident forms, species photos, etc.) shall be included as electronic attachments (.JPG or .PDF) and submitted using the FC tool.

(c) Sturgeon Incidental Data Form: If a sturgeon or sturgeon parts are identified during a load, after the appropriate parties are notified, a Sturgeon Incidental Data Form shall be completed and submitted to the ODESS database as soon as possible (not to exceed 12 hours after the incident). Any applicable documentation (scanned copies of the paper Observer load and incident forms, species photos, etc.) shall be included as electronic attachments (.JPG or .PDF) and submitted using the FC tool.

(d) Marine Mammal Observation Data Form: If a large whale is observed, both the Dredge Load and the Marine Mammal Observation Data Forms shall be completed and submitted (not to exceed 12 hours after the observation) to ODESS Support at ODESS@usace.army.mil consistent with the endangered species compliance section of the contract specification.

(3) The contractor shall provide a digital camera, with an image resolution capability of 300 dpi, in order to photographically report all incidental sea turtle and Gulf sturgeon takes during dredging operations. Immediately following an incidental take of a sea turtle or Gulf sturgeon, images shall be provided to accompany load data and incidental take forms submitted to the ODESS system. The nature of findings shall be fully described in the incidental take forms including references to photographs.

(4) Screening: Sea turtle observers are required on hopper dredges and shall provide for 100% inflow screening of dredged material; 100% overflow screening is recommended. If conditions prevent 100% inflow screening, inflow screening may be reduced gradually, as further detailed in the following paragraph, but 100% overflow screening is then required.

(5) Screen Size: The hopper's inflow screens shall have 4-inch by 4-inch screening. If the Contracting Officer Representative, in consultation with observers and the draghead operator, determines that the draghead is clogging and reducing production substantially, the screens may be modified sequentially: mesh size may be increased to 6-inch by 6-inch, then 9-inch by 9-inch, then 12-inch by 12-inch openings. Further clogging may compel removal of the screening altogether, in which case effective 100% overflow screening would be required.

The Contactor Officer Representative shall request permission before doing so by contacting Mobile District Coastal Environmental Team (Ms.

Lekesha Reynolds 251-690-3260) prior to the reductions in screening. The Contactor shall provide an explanation for such reduction in the dredging report.

(6) Dredging Pumps: Standard operating procedure shall be that dredging pumps are disengaged by the operator when the dragheads are not firmly on the bottom, to prevent impingement or entrainment of sea turtles within the water column.

(7) Sea Turtle Deflector Requirements:

(a) Sea Turtle Deflecting Draghead: A state-of-the-art rigid deflector draghead must be used on all hopper dredges in all Gulf of Mexico channels and sand mining sites at all times of the year and shall be installed while performing hopper dredging operations under this contract. The contractor shall submit drawings showing the proposed sea turtle deflector device and its attachment to the equipment being used. Drawings submitted shall include the approach angle for any and all depths to be dredged during the dredging. A copy of the approved drawings and calculations shall be available on the vessel during the dredging.

(b) Hopper Dredge Equipment: Hopper dredge drag heads shall be equipped with rigid sea turtle deflectors, which are rigidly attached. No dredging shall be performed by the hopper dredge without a turtle deflector device that has been approved by the Contracting Officer Representative.

(c) Deflector Design: The leading v-shaped portion of the deflector shall have an included angle of less than 90 degrees. Internal reinforcement shall be installed in the deflector to prevent structural failure of the device. The leading edge of the deflector shall be designed to have a plowing effect of at least 6" depth when the drag head is being operated. Appropriate instrumentation or indicator shall be used and kept in proper calibration to insure the critical "approach angle."

If adjustable depth deflectors are installed, they shall be rigidly attached to the drag head using either a hinged aft attachment point or an aft trunnion attachment point in association with an adjustable pin front attachment point or cable front attachment point with a stop set to obtain the 6" plowing effect. This arrangement allows fine-tuning the 6" plowing effect for varying depths. After the deflector is properly adjusted there shall be NO openings between the deflector and the drag head that are more than 4" by 4".

(8) Training - Personnel on Hopper Dredges: The USACE may, as necessary, conduct thorough training on measures of dredge operation that will minimize takes of sea turtles and Gulf sturgeon. It shall be the goal of each hopper dredging operation to establish operating procedures that are consistent with those that have been used successfully during hopper dredging in other regions of the coastal United States, and which have proven effective in reducing turtle/dredge interactions.

(9) Monitoring Reports: The results of the monitoring shall be recorded on the appropriate observation forms. Observation forms shall include a daily report sheet and a weekly summary sheet. Observation sheets shall be completed regardless of whether any takes occur. Electronic copies of all data in its original form shall be forwarded to the Mobile District Coastal Environment Team (Attn: Ms. Lekesha Reynolds; fax number 251-690-2727 or e-mail Lekesha.W.Reynolds@usace.army.mil) within 10 days of collection. Copies of forms submitted shall be legible with a minimum of smudges or blackened areas.

f. Sea Turtle and Gulf Sturgeon Trawling and Relocation – Trawling and relocation shall be conducted during Hopper Dredging within Mobile Bay Bar Channel unless otherwise directed by the Contracting Officer Representative. Trawling outside of the Bar Channel is not required unless there is a take. The Contractor shall implement the following Trawling and Relocation conditions:

(1) Trawling Requirements: Relocation trawling shall be conducted to remove sea turtles and Gulf sturgeon from the dredging area(s) during dredging to help prevent entrainment by the dredge. Sea Turtle and Gulf sturgeon Trawling and Relocation, as specified herein, will be at the option and in the discretion of the Government to aid in preventing sea turtle and Gulf sturgeon incidents during dredging operations with the approved turtle deflector in place. Trawling shall begin at least 12 hours prior to dredging. Based on the trawling results, the Government will make a decision on whether or not there is a need to continue trawling. Methods and equipment shall be standardized including data sheets, nets, trawling direction to tide, length of station, length of tow, and number of tows per station. Data on each tow shall be recorded in on Trawling Report form. The trawler shall be equipped with 60-foot nets constructed from 8-inch mesh (stretch) fitted with mud rollers and flats as specified in the Turtle Trawl Nets Specifications appended to the end of this Section. Paired net tows shall be made for 12 hours per day or night, as directed by the Contracting Officer or their appointed representative. The tows shall be performed in shifts, to be determined by the Contracting Officer or their appointed representative. The trawler shall be available for operation 24

hours a day. If two (2) separate trawlers are required, they shall operate side-by-side, as much as practicable. If multiple dredges are utilized, the trawler(s) shall be used for each dredge actively performing dredging operations. If the dredging operations are coordinated so that only one (1) dredge is actively dredging, trawler(s) shall be required for only that dredge. If dredging operations cease for a period of 12 hours or more, relocation trawling shall be conducted for a minimum of 4 hours prior to resuming dredging operations. The trawler(s) shall be positioned ahead of the hopper dredge and as close to the hopper dredge as safely possible to give maximum coverage ahead of the dredging cut. The dredge and trawler(s) shall work closely together to implement techniques and procedures that will minimize the opportunity for turtles and Gulf sturgeon to enter the dredging path between the trawler(s) and dredge. NOTE: ALL TRAWLING ACTIVITIES, VESSELS AND EQUIPMENT SHALL COMPLY WITH THE CONTRACTOR'S ACCIDENT PREVENTION PLAN AND THE REQUIREMENTS OF EM 385-1-1, U.S. ARMY CORPS OF ENGINEERS SAFETY AND HEALTH REQUIREMENTS MANUAL. Trawling shall be conducted with and against the tidal flow at a speed between 2.5 to 3.5 knots using repetitive 15- to 30-minute (total time) trawls in the work area. Trawl tow-time duration shall not exceed 30 minutes (doors in - doors out) and trawl speeds shall not exceed 3.5 knots. Positions at the beginning and end of each tow shall be determined from the Global Positioning System (GPS) equipment. Tow speed shall be recorded at the approximate midpoint of each tow. Acceptable GPS criteria shall be in accordance with EM 1110-1-1003, paragraph 5.3 and Table 5-1. This EM 1110-1-1003 can be located at the following website: <http://www.publications.usace.army.mil/USACEPublications/EngineerManuals.aspx> or can be purchased directly from the Government Printing Office by calling (202) 512-1800. The postal address is Superintendent of Documents, P. O. Box 371954, Pittsburgh, Pennsylvania 15250-7954 or on line at <http://bookstore.gpo.gov/>.

(2) Water Quality and Physical Measurements: Water temperature measurements shall be taken at the water surface each day using a laboratory thermometer. Weather conditions shall be recorded from visual observations and instruments on the trawler. Weather conditions, air temperature, wind velocity and direction, sea state-wave height, and precipitation shall be recorded on the Trawling Report form. High and low tides shall be recorded.

(3) Approved Sea Turtle Trawling and Relocation Supervisor: Trawling shall be conducted under the supervision of a crewmember that possesses the required permits for handling endangered species, experienced in sea turtle capture or is a NMFS-approved observer. A letter of approval from NMFS shall be provided to the Contracting Officer or their appointed representative prior to commencement of trawling.

(4) Repair and Replacement of Damaged Trawl Nets: The Contractor, at the time of mobilization, shall provide trawl nets, which meet the requirements specified in the Turtle Trawl Net Specifications at the end of this section. Trawl nets that are damaged shall be repaired or replaced by the Contractor at no additional expense to the Government. Tools, supplies and materials for repairing nets shall be kept aboard the trawler. In the event of damage to trawl nets, one hour shall be allowed to either repair or replace them. The Contractor shall have at least one set of replacement nets immediately available at all times, to insure that the dredging work is not adversely delayed due to trawler down-time for replacing damaged nets. It is recommended that a second set of replacement nets be available aboard the trawler.

(5) Equipment Breakdown: The contractor shall be placed in a non-pay status when trawling equipment breakdown is such that the trawler does not operate during the day. Pay time shall resume when trawling operations recommence.

(6) Suspension of Dredging and Relocation Trawling: Should there be dangerously high seas that would cause the trawler to leave the dredging area when relocation trawling is required, the dredge may continue to operate, as long as no turtles or Gulf sturgeon are taken and subject to the discretion of the Contracting Officer.

(7) Turtle Excluder Devices: Approval for trawling for sea turtles without Turtle Excluder Devices (TEDs) on hopper dredge dragheads must be obtained from NMFS (contact Eric Hawk at 727-551-5773). Any necessary State or Federal clearances for the capture and relocation of sea turtles shall also be obtained. Approvals shall be submitted to the Contracting Officer or their appointed representative prior to trawling.

(8) Handling During Trawling: Sea turtles and sturgeon captured pursuant to relocation trawling shall be handled in a manner designed to ensure their safety and viability, and shall be released over the side of the vessel, away from the propeller, and only after ensuring that the vessel's propeller is in the neutral, or disengaged, position (i.e., not rotating). Resuscitation guidelines are located in the Environmental Compliance Appendix.

(9) Captured Turtle and Gulf Sturgeon Holding Conditions: Turtles and Gulf sturgeon may be held briefly for the collection of important scientific measurements, prior to their release. Captured turtles shall be kept moist, and shaded whenever possible, until they are released, according to the requirements below. Captured Gulf sturgeon shall be held in a suitable

well-aerated seawater enclosure until they are released according to the requirements below.

(a) Take and Release Time During Trawling - Turtles: Turtles shall be kept no longer than 12 hours prior to release and shall be released not less than three (3) nautical miles (nmi) from the excavation site. If two or more released turtles are later recaptured, subsequent turtle captures shall be released not less than (5) five nautical miles away. If it can be done safely and without injuries to the turtle, turtles may be transferred onto another vessel for transport to the release area to enable the relocation trawler to keep sweeping the dredge site without interruption. Minor skin abrasions resulting from trawl capture are considered non-injurious. Injured sea turtles shall be immediately transported to the nearest sea turtle rehabilitation facility such as the Institute for Marine Mammal Studies (MMS), 10801 Dolphin Ln, Gulfport, MS 39503, phone 1-888-767-3657, or 1-228-896-9182 and email contactus@imms.org. Also notify the Coastal Environmental Team, Mobile District, Ms. Lekesha Reynolds by phone at 251-690-3260 office or by email at Lekesha.w.reynolds@usace.army.mil. . Observer(s), or their appointed representative(s), shall transport injured turtles to a rehabilitation facility as soon as possible. The NOAA Fisheries-approved turtle transporters shall be used for this purpose.

FLORIDA (partial list)

Gulf World
15412 Front Beach Rd
Panama City Beach, FL 32413
Tel. 850-234-5271

Florida's Gulfarium
1010 Miracle Strip Parkway SE
Ft. Walton Beach, FL 32548
Tel. 850-243-9046

Emerald Coast Wildlife Rescue
406 Mountain Dr
Destin, FL 32541
Tel. 850-/650-1880

(b) Take and Release Time During Trawling - Gulf Sturgeon: Gulf sturgeon shall be released immediately after capture, away from the dredge site, unless the trawl vessel is equipped with a suitable well-aerated seawater holding tank, container, trough or pool where a maximum of one sturgeon may be held for not longer than 30

minutes before it must be released or relocated away from the dredge site.

(10) Scientific Measurements: When safely possible, all turtles shall be measured (standard carapace measurements including body depth), tagged, weighed, and a tissue sample taken prior to release. When safely possible, all Gulf sturgeon shall be measured (fork length and total length), tagged, weighed, and a tissue sample taken prior to release. Any external tags shall be noted and data recorded onto the Tagging form. Only NMFS approved protected species Observers or Observer candidates in training under the direct supervision of a NMFS-approved observer shall conduct the tagging/measuring/weighing/tissue sampling operations.

(11) Turtle Flipper External Tagging: All sea turtles captured by relocation trawling shall be flipper-tagged prior to release with external tags which shall be obtained prior to the start of dredging from the University of Florida's Archie Carr Center for Sea Turtle Research. The NMFS-approved protected species observer aboard these relocation trawlers shall flipper-tag with external tags (e.g., Inconel tags) captured sea turtles. Columbus crabs or other organisms living on external sea turtle surfaces may also be sampled and removed.

(12) PIT Tagging: PIT tagging of sea turtles and Gulf sturgeon is not required if the NMFS-approved protected species observer does not have prior training or experience in said activity. However, if the observer has received prior training in PIT tagging procedures, then the observer shall PIT tag the animal prior to release (in addition to the standard external tagging):

(a) Sea turtle PIT tagging must then be performed in accordance with the protocol detailed at NMFS' Southeast Fisheries Science Center's web page:

<http://www.sefsc.noaa.gov/species/turtles/observers.htm>.

(b) Gulf sturgeon PIT tagging must then be performed in accordance with the protocol detailed at the NMFS SERO PRD Web site.

(c) PIT tags used must be sterile, individually wrapped tags to prevent disease transmission. PIT tags should be 125 kHz, glass-encapsulated tags-the smallest ones made.

(13) Other Sampling Procedures: All other tagging and external or internal sampling procedures (e.g., blood letting, laparoscopies, anal and gastric lavages, mounting satellite or radio transmitters, etc.) performed on live sea turtles or live sturgeon are not permitted unless the observer

holds a valid sea turtle or sturgeon research permit authorizing this activity, either as the permit holder, or as designated agent of the permit holder.

(14) Trawler Reporting: At the end of each week, a summary detailing the week's relocation trawling (number of tows, details about turtles/sturgeons relocated, etc) shall be emailed by the contractor to Ms. Lekesha Reynolds of the Mobile District Coastal Environment Staff at Lekesha.W.Reynolds@usace.army.mil. The results of each trawl shall be recorded on the Trawling Report. Sample forms are provided in Appendix B. Following completion of the project, an electronic copy of the trawling reports shall be forwarded to Ms. Lekesha Reynolds at: Lekesha.W.Reynolds@usace.army.mil within 10 working days of dredging completion. Copies of the reports shall also be furnished to Ms. Rachel Sweeney, National Marine Fisheries Service, by email at rachel.sweeney@noaa.gov.

g. Collateral or "Piggy Back" Research - Hopper Dredging/Trawling Relocation Only: Any sea turtle research activities proposed by the contractor, or outside parties, to be conducted in association with USACE funded actions, including endangered species monitoring, relocation trawling operations, or use of turtles acquired by these operations shall comply with the following general requirements, and any specific requirements developed by the Corps on a case-by-case basis as requests are received:

(1) The USACE shall be given at least 60 days to review and comment on any such research proposals. The point of contact for this review is Dena Dickerson at the Engineer Research and Development Center (ERDC) in Vicksburg MS.

(2) No such research shall be conducted without the express consent of USACE.

(3) The USACE shall be given the opportunity to review and comment on any potential publication or interpretation of resulting data prior to release. The point of contact for this review is Dena Dickerson at the ERDC.

(4) The party or parties conducting the research shall possess a valid research permit pursuant to Section 10 of the Endangered Species Act; and will be responsible for any other Federal, State or local permits or authorizations required, including any requirement of the National Environmental Policy Act (NEPA).

(5) Any injuries, including lethal takes resulting from sea turtle handling activity beyond USACE contract requirements shall be the responsibility of the researcher.

- (6) Acknowledgment that the research was conducted with the assistance of USACE shall be included in any resulting publication or report, at the discretion of USACE.
- (7) Research activities shall not hinder USACE contracted operations, nor result in any additional cost to the Government;
- (8) Research personnel not directly employed by USACE contractors or subcontractors shall not board contracted vessels without signing an appropriate waiver of liability and/or other documents required by USACE.
- h. PIT-Tag Scanning - Hopper Dredging/Trawling Relocation Only: All sea turtles and Gulf sturgeon captured by relocation trawling or hopper dredges shall be thoroughly scanned for the presence of PIT tags prior to release using a multi-frequency scanner powerful enough to read multiple frequencies (including 125 128, 134 and 400-kHz tags) and read tags deeply embedded deep in muscle tissue (e.g., manufactured by Trovan, Biomark, or Avid). Turtles whose scans show they have been previously PIT tagged shall be externally flipper tagged. The data collected (PIT tag scan data and external tagging data) shall be submitted to NOAA, NMFS, Southeast Fisheries Science Center, Attn: Lisa Belskis, 75 Virginia Beach Drive, Miami, Florida 33149. All data collected shall be submitted in electronic format within 60 working days to Lisa.Belskis@noaa.gov; and Sheryan.Epperly@noaa.gov. Sea turtle external flipper tag and PIT tag data generated and collected by relocation trawlers shall also be submitted to the Cooperative Marine Turtle Tagging Program (CMTTP), on the appropriate CMTTP form, at the University of Florida's Archie Carr Center for Sea Turtle Research.
- Gulf sturgeon data (PIT tag scan data and external tagging data) shall be submitted within 60 days of project completion to NOAA, National Marine Fisheries Service, Protected Resources Division, 263 13th Avenue South, St. Petersburg, Florida 33701, or by fax: (727)824-5309; or by e-mail: takereport.nmfsser@noaa.gov, Attn: Dr. Stephania Bolden.
- i. Handling Fibropapillomatose Turtles: NMFS-approved protected species observers onboard a relocation trawler or hopper dredges are not required to handle or sample the viral fibropapillomatose tumors if they believe there is a health hazard to themselves and choose not to. When handling sea turtles infected with fibropapilloma tumors shall either: 1) clean all equipment that comes in contact with the turtle (tagging equipment, tape measures, etc.) with mild bleach solution, between the processing of each turtle or 2) maintain a separate set of sampling equipment for handling animals displaying fibropapilloma tumors or lesions.

j. Requirement and Authority to Conduct Tissue sampling for Genetic Analyses - Hopper Dredging/Trawling Relocation Only: All alive or dead sea turtles and Gulf sturgeon captured by relocation trawling or dredging shall be tissue-sampled prior to release by a NMFS-approved protected species observer.

(1) Sea turtle tissue samples shall be taken in accordance with NMFS' Southeast Fisheries Science Centers' (SEFSC) procedures for sea turtle genetic analyses (included in the Environmental Compliance Appendix). Tissue samples shall be properly stored and mailed within 60 days of completion of dredging project, to NOAA, National Marine Fisheries Service, Southeast Fisheries Science Center, Attn: Lisa Belskis, 75 Virginia Beach Drive, Miami, Florida 33149.

(2) Gulf sturgeon tissue samples (i.e., fin clips or barbel clips) shall be taken in accordance with NMFS SERO's Protected Resources Division's Gulf sturgeon Tissue Sampling Protocol found at NMFS SERO PRD Website. Tissue samples shall be properly stored and mailed to SERO PRD (Attn: Dr. Stephania Bolden) within 60 days of dredging completion.

m. Equipment Lighting: During the sea turtle nesting season and emergence season May 1 to October 31, lighting on offshore or onshore equipment shall be minimized through reduction, shielding, lowering, and appropriate placement to avoid excessive illumination of the water's surface and nesting beach while meeting all Coast Guard, COE EM 385-1-1, and OSHA requirements. Light intensity of lighting plants should be reduced to the minimum standard required by U.S. Coast Guard and/or OSHA for General Construction areas, in order not to misdirect sea turtles. Shields should be affixed to the light housing and be large enough to block light from all lamps from being transmitted outside the construction area.

3.6 PROTECTION OF AIR RESOURCES

All fuel burning equipment shall be properly maintained to prevent violations of State or Federal Air Pollution Standards or interference with inhabitants of the area by causing drastic changes in their accustomed environment. If burning is required, the Contractor should obtain a burning permit from the local fire department, if necessary. Daily inspections will be made of all fuel burning equipment. Immediate corrective action shall be taken if exhaust emissions are found to be excessive.

3.7 MAINTENANCE OF POLLUTION CONTROL FACILITIES DURING DREDGING AND PLACEMENT ACTIVITIES

During the life of this contract, the Contractor shall maintain all facilities constructed for pollution control as long as the operations creating the particular pollutant are being carried out or until the material concerned has become stabilized to the extent that pollution is no longer being created. During the dredging period the Contractor should conduct frequent training courses for his maintenance personnel. The curricula should include methods of detection of pollution, familiarity with pollution standards and measures for prevention or mitigation of environmental pollution.

3.8 SANITATION

The Contractor must provide suitable sanitation devices for the proper storage of all sanitary sewage. The Contractor shall ensure that all floating plant operates according to an approved waste management plan as required by 33 CFR Part 151. The dumping of sanitary sewage effluent and/or solids into the waters surrounding the job is strictly prohibited.

ENVIRONMENTAL COMPLIANCE APPENDIX

Turtle Trawl Net Specifications

Turtle Trawl Net Specifications

DESIGN: 4 Seam, 4 Legged, 2 Bridal Trawl Net

WEBBING: 4 inch bar, 8 inch stretch

Top - 36 Gauge Twisted Nylon Dipped

Side - 36 Gauge Twisted Nylon Dipped

Bottom - 84 Gauge Braided Nylon Dipped

NET LENGTH: 60 ft from cork line to cod end

BODY TAPER: 2 to 1

WING END HEIGHT: 6 feet

CENTER HEIGHT: Dependent on depth of trawl - 14 to 18 feet

COD END: Length 50 meshes x 4 inches equals 16.7 feet

Webbing 2 inch bar, 4 inch stretch, 84 gauge braid nylon

Dipped, 80 meshes around, 40 rigged meshes with $\frac{1}{4}$ x 2
inch choker rings, 1 each $\frac{1}{2}$ x 4 inch at end

Cod End Cover - none

Chaffing Gear - none

HEAD ROPE: 60 ft $\frac{1}{2}$ inch combination rope (braid nylon with
stainless cable center)

FOOT ROPE: 65 ft $\frac{1}{2}$ inch combination rope

LEG LINE: Top - 6 ft, Bottom - 6 ft

FLOATS: Size - Tuna Floats (football style), Diameter - 7

Inches; Length - 9 inches; number 12 each;

Spacing - center of top net 2 inches apart

MUD ROLLERS: Size - 5 inch Diameter, 5.5 inch length

Number - 22 each; spacing - 3 ft attached with $\frac{3}{8}$ inch

Polypropylene rope (replaced with snap on roller when
broken)

TICKLER CHAINS: NONE (Discontinued - but previously used $\frac{1}{4}$
inch x 74 ft galvanized chain)

WEIGHT: 20 ft of $\frac{1}{4}$ inch galvanized chain on each wing, 40 ft
per net looped and tied

DOOR SIZE: 7 ft x 40 inches (or 8 ft x 40 inches); Shoe - 1 inch
X 6 inch: bridles - $\frac{3}{8}$ inch high test chain

CABLE LENGTH: (Bridle Length, Total) : $\frac{7}{16}$ inch x 240-300 ft
varies with bottom conditions

FLOAT BALL: NONE

LAZY LINES: 1 inch nylon

PICKUP LINES: $\frac{3}{8}$ inch polypropylene

WHIP LINES: 1 inch nylon

ODESS System Requirements and Forms

HARDWARE REQUIREMENTS FOR THE ODESS SYSTEM

The dredge shall be equipped and the contractor is responsible for an ODESS hardware system consisting of a tablet computer, wireless keyboard, wireless mouse and data modem (or equivalent onboard internet connection) along with a proper tote bag and setup location for the afore mentioned hardware components. If a hardware problem occurs, or if a part of the system is physically damaged, the Contractor shall be responsible for repairing it within 48 hours of determination of the condition. The contractor shall also keep ODESS personnel updated on the status of the onboard ODESS system and the progress of any repairs.

Computer

The Contractor shall provide a dedicated onboard tablet computer for use by the observers and shall have ODESS software installed on it prior to project initiation. This computer shall be located and oriented to allow data entry and data viewing. It must meet or exceed the following specifications:

Tablet Hardware Component	Specification
CPU	Intel or AMD processor with a (non-overclocked) clock speed of at least 2.4 gigahertz (GHz)
Hard Disk	128 gigabytes (GB); solid state internal storage
RAM	4 gigabytes (GB)
Network Adapter	Internal wired or wireless network hardware to match internet connection
Video Adapter	Support for 1024x768 resolution at 16-bit color depth
Display	>= 10.8 in.
Integrated Camera	2MP HD webcam (front); 8MP (back)
Ports	1 free USB port

Internet Access

The Contractor shall maintain an Internet connection capable of transmitting data to the ODESS database. The telemetry system shall always be available and have connectivity in the contract area. If connectivity is lost, unsent data shall be stored locally within the FC tool and transmitted upon restoration of connectivity. The Contractor shall acquire and install all necessary hardware and software to make the Internet connection available for data transmission to the ODESS database. The hardware and software must be configured to allow remote

access to the computer by USACE ODESS personnel. Coordination between the dredging company's IT and ODESS Support may be required in order to configure remote access through any security, firewall, router, and telemetry systems. Telemetry systems must be capable of meeting these minimum reporting requirements in all operating conditions.

SOFTWARE REQUIREMENTS

ODESS personnel shall be responsible for installing and testing all ODESS software tools on the dedicated onboard ODESS tablet computer. No other software which conflicts with the ODESS function of recording and transmitting data shall be installed on the tablet computer. The Contractor shall be responsible for installing and/or maintaining any necessary manufacturer-provided software for the installed hardware. If any software problem occurs, the Contractor shall contact ODESS Support at ODESS@usace.army.mil or 1-877-840-8024.

The ODESS tablet computer shall have the following minimum software installed in support of the ODESS system:

Software	Specification
Operating System	Windows 10, Contractor-installed
Browser**	Chrome, Internet Explorer, Contractor-installed
ODESS Software	Field Collector (FC) tool, USACE ODESS Support Installed
Remote Access Software	Team Viewer, USACE ODESS Support-installed

**Latest version recommended, Chrome is preferred



**Operations and Dredging Endangered Species System
(ODESS)
USACE Sea Turtle Deflector Checklist for Hopper Dredges
for USACE and USACE/Army-Permitted Projects**

1. Read the contract plans and specs and/or all applicable permits (Dept. of the Army Permit, State Permits) to determine the contract or permit requirements for the protection of endangered sea turtles. (Each District spec or permit may be different.)
2. Read the Biological Opinion and any USACE Protocol, if available.
3. Develop a list of inspection requirements:
 - a. Deflector leading edge angle (90° or less).
 - b. Approach angle or leading edge plowing depth (6" or more).
 - c. Aft rigid attachment of the deflector to the draghead (hinged or trunnion).
 - d. Forward deflector attachment point (adjustable pinned or cable/chain with stop).
 - e. Opening between draghead and deflector (4" x 4" max).
 - f. Dredged material screening requirement (yes/no).
 - g. Screen type requirement (inflow, overflow, or both).
 - h. Inflow basket screen openings (4" x 4" max) and dredged material screening (100%).
 - i. Lighting of the inflow and overflow screens and proper access for cleaning (must meet EM 385-1-1).
 - j. UXO (Unexploded Ordnance) screening in use (yes/no).
 - k. Structural design of the deflector (per the approved deflector submittal).
 - l. Dredge operational requirements (starting/stopping the dredge pump, draghead plugging, raising the draghead, turning the dredge).



- m. Dredging Quality Management (DQM) dredging data recording requirement. Is dredging data recording (drag elevation, slurry density, and velocity) required by specs or permit? If so, is it being collected, is DQM turned on, and is data being submitted?
 - n. Turtle trawling requirement. Is turtle trawling required by specs or permit? If so, is it being performed?
 - o. Turtle observer requirements (12 or 24 hours).
 - p. A copy of the approved turtle deflector submittal is on board the vessel.
 - q. Copies of the contract plans and specs or the Dept. of the Army permit are on board the vessel.
4. Review the turtle deflector submittal. (Do not allow dredging to start until the submittal is approved.)
- a. Structural soundness.
 - b. Deflector leading edge angle (90° or less).
 - c. Approach angles submitted for the project's dredging depths.
 - d. 4" x 4" opening between the deflector and the draghead.
 - e. Aft rigid deflector attachment to draghead (hinged or trunnion).
 - f. Forward deflector attachment point (adjustable pinned or cable/chain with stop).
5. Ensure that the Contractor Quality Control (CQC) performs a pre-dredging inspection. The CQC is required to review and inspect all items in section 3.
6. Ensure that the CQC performs a startup-dredging inspection:
- a. The CQC is required to check the turtle deflector to see if the deflector is installed and adjusted for the required dredge depth of the project in accordance with the approved deflector submittal.
 - b. The CQC is required to ensure that the drag tenders are operating the dredge pump and draghead in accordance with the specs/permit.
 - c. The CQC should perform a paint test to ensure that the deflector is plowing at least 6" into the dredge material while the dragtender is consistently maintaining the submitted and approved approach angle to a tolerance of +0 to -4°.
 - d. The CQC should note the inspection results in the Quality Control (QC) Daily Report.
7. Quality Assurance (QA) should perform a dredging operation inspection soon after the dredge starts dredging:
- a. Review and inspect all items in section 3.

- b. Inspect the turtle deflector to ensure that the deflector is installed and adjusted for the required dredge depth of the project in accordance with the approved deflector submittal.
- c. Require the contractor to perform a paint test to ensure that the deflector is plowing at least 6" into the dredge material while the dragtender is consistently maintaining the submitted and approved approach angle to a tolerance of +0 to -4°. (While over-penetration of the deflector may reduce production and increase fuel consumption of the dredge, it is allowed.)
- d. Ride the dredge through at least one dredging cycle (from dredging to the dump and then back to the dredge site).
- e. Watch the dragtender to ensure that he/she is operating the dredging equipment in accordance with the plans and specs:
 - i. Starting the dredge pump only when the draghead is firmly on the bottom by watching the slurry specific gravity and swell compensator.
 - ii. Reducing the slurry velocity to the dredge pump idle speed velocity before raising the draghead off the bottom.
 - iii. Consistently maintaining the approach angle to a tolerance of +0 to -4° whenever the draghead is on the bottom and the dredge pump is operating
 - iv. Raising the draghead off the bottom due to draghead plugging or ship crabbing.
- f. Ensure that the lockout tagout procedure for cleaning the inflow and overflow screens meets EM 385-1-1.
- g. Talk to the turtle observers to ensure that they are aware of contract and permit requirements and that they are inspecting the screens and deflectors and reporting any required maintenance to the dredge personnel. Also ensure that correct turtle observer forms are being used and filled out properly.
- h. Talk to the dredge Captain about maintaining the screens and deflectors.
- i. Ensure that DQM data is being sent to the National Dredging Quality Management Program.
- j. Note all pre-dredge/post-dredge and followup inspections in the QA and the QC Daily Reports.

Project Name: _____

Project Location: _____

Contract No.: _____

Dept. of the Army Permit No.: _____

Dredging Company Name: _____

Dredge Name: _____

Contractor CQC Inspector's Name: _____

USACE Inspector Name: _____

Office Symbol: _____ Date of Inspection: _____

Comments: _____



Operations & Dredging Endangered Species System (ODESS)



US Army Corps
of Engineers

Dredge Load

District	Project	Contract	Dredge	Dredging Company
Load Number (Required)/Date	Start Date (Required)	Start Time (24 hours) (Required)	Stop Date (Required)	Stop Time (24 hours) (Required)

Port Screen Condition <input type="checkbox"/> Excellent <input type="checkbox"/> Good <input type="checkbox"/> Fair <input type="checkbox"/> Bad Starboard Screen Condition <input type="checkbox"/> Excellent <input type="checkbox"/> Good <input type="checkbox"/> Fair <input type="checkbox"/> Bad Overflow Screen Condition <input type="checkbox"/> Excellent <input type="checkbox"/> Good <input type="checkbox"/> Fair <input type="checkbox"/> Bad Inflow Screen Percent <input type="checkbox"/> 25% <input type="checkbox"/> 50% <input type="checkbox"/> 75% <input type="checkbox"/> 100% Overflow Screen Percent <input type="checkbox"/> 25% <input type="checkbox"/> 50% <input type="checkbox"/> 75% <input type="checkbox"/> 100% Other Screen Percent <input type="checkbox"/> 25% <input type="checkbox"/> 50% <input type="checkbox"/> 75% <input type="checkbox"/> 100% # Dragheads Used <input type="text"/> Draghead Length (ft) <input type="text"/>	Draghead Width (ft) <input type="text"/> Draghead Type <input type="checkbox"/> California Style <input type="checkbox"/> IHC <input type="checkbox"/> IHC + Water Injection <input type="checkbox"/> Wild Dragon <input type="checkbox"/> Other (Specify) <input type="text"/> Deflector Condition <input type="checkbox"/> Good <input type="checkbox"/> Fair <input type="checkbox"/> Poor <input type="checkbox"/> None UXO Screening in Use? <input type="checkbox"/> Yes <input type="checkbox"/> No Material Type <input type="checkbox"/> Clay <input type="checkbox"/> Consolidated Material <input type="checkbox"/> Mud <input type="checkbox"/> Other <input type="checkbox"/> Rock <input type="checkbox"/> Sand - Course <input type="checkbox"/> Sand - Fine <input type="checkbox"/> Sand - Medium <input type="checkbox"/> Sand - Mixed <input type="checkbox"/> Shell <input type="checkbox"/> Silt <input type="checkbox"/> Unknown	Weather Conditions <input type="checkbox"/> Sunny <input type="checkbox"/> Cloudy <input type="checkbox"/> Partly Cloudy Beaufort Sea Scale <input type="checkbox"/> 0 (0-1 kn, 0-0 ft) <input type="checkbox"/> 1 (1-3 kn, 0-1 ft) <input type="checkbox"/> 2 (4-6 kn, 1-2 ft) <input type="checkbox"/> 3 (6-10 kn, 2-3.5 ft) <input type="checkbox"/> 4 (10-16 kn, 3.5-6 ft) <input type="checkbox"/> 5 (16-21 kn, 6-9 ft) <input type="checkbox"/> 6 (21-27 kn, 9-13 ft) <input type="checkbox"/> 7 (27-33 kn, 13-19 ft) <input type="checkbox"/> 8 (33-40 kn, 19-25 ft) <input type="checkbox"/> 9 (40-47 kn, 25-32 ft) <input type="checkbox"/> 10 (47-55 kn, 32-41 ft) <input type="checkbox"/> 11 (55-63 kn, 41-52 ft) <input type="checkbox"/> 12 (>63 kn, >52 ft) Wave Height (ft) <input type="text"/> Wind Speed (k) <input type="text"/> Wind Direction (°) <input type="text"/> Tide <input type="checkbox"/> High <input type="checkbox"/> Low <input type="checkbox"/> Slack <input type="checkbox"/> Rising <input type="checkbox"/> Falling <input type="checkbox"/> Unknown	Air Temp (°C) <input type="text"/> Surface Water Temp (°C) <input type="text"/> Mid-Depth Water Temp (°C) <input type="text"/> Bottom Water Temp (°C) <input type="text"/> Trawling Being Conducted? <input type="checkbox"/> Yes <input type="checkbox"/> No Any Incidents Involving Endangered or Protected Species? <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, Which Species? (Complete a Turtle or Sturgeon Incident form) <input type="checkbox"/> Marine Mammal <input type="checkbox"/> Sea Turtle <input type="checkbox"/> Sturgeon <input type="checkbox"/> Other <input type="checkbox"/> Unknown Whale Sighting Notification Received? <input type="checkbox"/> Yes <input type="checkbox"/> No Alert Sent to District? <input type="checkbox"/> Yes <input type="checkbox"/> No	Screen Contents 1 Port Screen Contents (incl. # of each item) <input type="text"/> 2 Starboard Screen Contents (incl. # of each item) <input type="text"/> 3 Overflow Screens Contents (incl. # of each item) <input type="text"/> 4 Other Screen or Location (Specify) <input type="text"/> Contents (incl. # of each item) <input type="text"/> 5 Port Draghead Contents (incl. # of each item) <input type="text"/> 6 Starboard Draghead Contents (incl. # of each item) <input type="text"/>
---	--	---	---	--

Comments

# Observers Used/24 Hours <input type="text"/>	% Monitoring/Project <input type="checkbox"/> None <input type="checkbox"/> 75% <input type="checkbox"/> 25% <input type="checkbox"/> 100% <input type="checkbox"/> 50%	Observer(s) Name(s) (Req. Print) <input type="text"/>	Observer(s) Signature(s) <input type="text"/>	Observer(s) Company <input type="text"/>
--	---	---	---	--

Notes:

- **Screen Contents**— Examples include sea turtle (sp.), sturgeon (sp.), shark (sp.), ray (sp.), other fish of note (sp.), horseshoe crab, blue crab, other crab species, coral, jellyballs, other species of note, environmental debris, and trash.

ODESS form 1(7) - 07/11/16



Operations & Dredging Endangered Species System (ODESS) Marine Mammal Observation



**US Army Corps
of Engineers®**

District <input style="width: 90%;" type="text"/>	Project <input style="width: 90%;" type="text"/>	Contract <input style="width: 90%;" type="text"/>	
Dredge <input style="width: 90%;" type="text"/>	Dredging Company <input style="width: 90%;" type="text"/>	Load Number (Required)/Date <input style="width: 90%;" type="text"/>	
Start Date (Required) <input style="width: 90%;" type="text"/>	Start Time (24 hours) (Required) <input style="width: 90%;" type="text"/>	End Date (Required) <input style="width: 90%;" type="text"/>	
End Time (24 hours) (Required) <input style="width: 90%;" type="text"/>			

Beaufort Sea State <input type="checkbox"/> 0 (0-1 kn, 0-0 ft) <input type="checkbox"/> 1 (1-3 kn, 0-1 ft) <input type="checkbox"/> 2 (4-6 kn, 1-2 ft) <input type="checkbox"/> 3 (6-10 kn, 2-3.5 ft) <input type="checkbox"/> 4 (10-16 kn, 3.5-6 ft) <input type="checkbox"/> 5 (16-21 kn, 6-9 ft) <input type="checkbox"/> 6 (21-27 kn, 9-13 ft)	<input type="checkbox"/> 7 (27-33 kn, 13-19 ft) <input type="checkbox"/> 8 (33-40 kn, 19-25 ft) <input type="checkbox"/> 9 (40-47 kn, 25-32 ft) <input type="checkbox"/> 10 (47-55 kn, 32-41 ft) <input type="checkbox"/> 11 (55-63 kn, 41-52 ft) <input type="checkbox"/> 12 (>63 kn, >52 ft)	Species Observed (Required) <input type="checkbox"/> Bryde's/Sai Whale # <input style="width: 40px;" type="text"/> Est. Length (ft.) <input style="width: 40px;" type="text"/> <input type="checkbox"/> Fin Whale # <input style="width: 40px;" type="text"/> Est. Length (ft.) <input style="width: 40px;" type="text"/> <input type="checkbox"/> Humpback Whale # <input style="width: 40px;" type="text"/> Est. Length (ft.) <input style="width: 40px;" type="text"/> <input type="checkbox"/> Manatee # <input style="width: 40px;" type="text"/> Est. Length (ft.) <input style="width: 40px;" type="text"/> <input type="checkbox"/> Minke Whale # <input style="width: 40px;" type="text"/> Est. Length (ft.) <input style="width: 40px;" type="text"/> <input type="checkbox"/> Pilot Whale # <input style="width: 40px;" type="text"/> Est. Length (ft.) <input style="width: 40px;" type="text"/> <input type="checkbox"/> Right Whale # <input style="width: 40px;" type="text"/> Est. Length (ft.) <input style="width: 40px;" type="text"/> <input type="checkbox"/> Unknown # <input style="width: 40px;" type="text"/> Est. Length (ft.) <input style="width: 40px;" type="text"/>
--	---	---

Air Temp (°C) <input style="width: 90%;" type="text"/>	Water Temp (°C) <input style="width: 90%;" type="text"/>	Winds (K) <input style="width: 90%;" type="text"/>	Seas (ft) <input style="width: 90%;" type="text"/>	Cloud Cover (%) <input style="width: 90%;" type="text"/>
---	---	---	---	---

Magnetic Bearing to Sighting <input style="width: 90%;" type="text"/>	Estimated Distance <input style="width: 90%;" type="text"/>	Vessel's Heading <input style="width: 90%;" type="text"/>	Heading of Animal(s) <input style="width: 90%;" type="text"/>
--	--	--	--

Coloration <input style="width: 90%;" type="text"/>	Fins or Flippers Observed <input style="width: 90%;" type="text"/>
--	---

Behaviors Observed <div style="height: 100px; border: 1px solid black;"></div>	Surfacing Intervals Time <input style="width: 90%;" type="text"/> Surfacing Intervals Distance <input style="width: 90%;" type="text"/>
---	--

Comments (Was the behavior of the animal(s) affected by the vessel? How far did the animal(s) move? Who was notified?)

Observer(s) Name(s) (Required; Print) <input style="width: 90%;" type="text"/>	Observer(s) Signature(s) <input style="width: 90%;" type="text"/>	Observer(s) Company <input style="width: 90%;" type="text"/>
---	--	---

ODESS Form 4(7) - 071116



Operations & Dredging Endangered Species System (ODESS) Sturgeon Incident



**US Army Corps
of Engineers®**

District <input style="width: 100%;" type="text"/>	Project <input style="width: 100%;" type="text"/>	Contract <input style="width: 100%;" type="text"/>						
Dredge <input style="width: 100%;" type="text"/>	Dredging Company <input style="width: 100%;" type="text"/>	<u>Species (Required)</u> <input type="checkbox"/> Atlantic <input type="checkbox"/> Gulf <input type="checkbox"/> Unknown <input type="checkbox"/> Green <input type="checkbox"/> Shortnose						
Load Number (Required)/Date <input style="width: 100%;" type="text"/>	Recovery Date (Required) <input style="width: 100%;" type="text"/>	Recovery Time (24 hours) (Required) <input style="width: 100%;" type="text"/>						
Is this a Take? (Required) <input type="checkbox"/> Yes <input type="checkbox"/> No								
Incident/Take Description								
<table border="0" style="width: 100%;"> <tr> <td style="width: 33%; vertical-align: top;"> <u>Location Specimen Recovered</u> <input type="checkbox"/> Deck <input type="checkbox"/> Hopper <input type="checkbox"/> Draghead <input type="checkbox"/> Overflow Screen (Circle one) <input type="checkbox"/> Inflow Cage (Circle one) <input type="checkbox"/> Starboard/Port/Other <input type="checkbox"/> Starboard/Port/Other <input type="checkbox"/> Pipe </td> <td style="width: 33%; vertical-align: top;"> <u>Specimen Condition</u> <input type="checkbox"/> Alive <input type="checkbox"/> Dead <input type="checkbox"/> Fresh Dead <input type="checkbox"/> Moderately Decomposed </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> Severely Decomposed <input type="checkbox"/> Skeleton <input type="checkbox"/> Skeleton Old Bone <input type="checkbox"/> Undetermined </td> </tr> <tr> <td colspan="2"></td> <td style="vertical-align: top;"> Rows of Preanal Shields (SSN = 1/ATL = 2) <input style="width: 100%;" type="text"/> </td> </tr> </table>			<u>Location Specimen Recovered</u> <input type="checkbox"/> Deck <input type="checkbox"/> Hopper <input type="checkbox"/> Draghead <input type="checkbox"/> Overflow Screen (Circle one) <input type="checkbox"/> Inflow Cage (Circle one) <input type="checkbox"/> Starboard/Port/Other <input type="checkbox"/> Starboard/Port/Other <input type="checkbox"/> Pipe	<u>Specimen Condition</u> <input type="checkbox"/> Alive <input type="checkbox"/> Dead <input type="checkbox"/> Fresh Dead <input type="checkbox"/> Moderately Decomposed	<input type="checkbox"/> Severely Decomposed <input type="checkbox"/> Skeleton <input type="checkbox"/> Skeleton Old Bone <input type="checkbox"/> Undetermined			Rows of Preanal Shields (SSN = 1/ATL = 2) <input style="width: 100%;" type="text"/>
<u>Location Specimen Recovered</u> <input type="checkbox"/> Deck <input type="checkbox"/> Hopper <input type="checkbox"/> Draghead <input type="checkbox"/> Overflow Screen (Circle one) <input type="checkbox"/> Inflow Cage (Circle one) <input type="checkbox"/> Starboard/Port/Other <input type="checkbox"/> Starboard/Port/Other <input type="checkbox"/> Pipe	<u>Specimen Condition</u> <input type="checkbox"/> Alive <input type="checkbox"/> Dead <input type="checkbox"/> Fresh Dead <input type="checkbox"/> Moderately Decomposed	<input type="checkbox"/> Severely Decomposed <input type="checkbox"/> Skeleton <input type="checkbox"/> Skeleton Old Bone <input type="checkbox"/> Undetermined						
		Rows of Preanal Shields (SSN = 1/ATL = 2) <input style="width: 100%;" type="text"/>						
Location Comment								
# Dorsal Scutes (SSN = 8-13/ATL = 7-16) <input style="width: 100%;" type="text"/>	# Lateral Scutes (SSN = 22-33/ATL = 24-35) <input style="width: 100%;" type="text"/>	# Ventral Scutes (SSN = 7-11/ATL = 6-9) <input style="width: 100%;" type="text"/>						
Fork Length (cm/in) <input style="width: 100%;" type="text"/>	Standard Length (cm/in) <input style="width: 100%;" type="text"/>	Total Length (cm/in) <input style="width: 100%;" type="text"/>						
Mouth Width (cm/in) <input style="width: 100%;" type="text"/>	Head Width at Eyes (cm/in) <input style="width: 100%;" type="text"/>	Other (cm/in) <input style="width: 100%;" type="text"/>						
Genetic Samples Taken? <input type="checkbox"/> Yes <input type="checkbox"/> No	Samples Frozen/Preserved? <input type="checkbox"/> Yes <input type="checkbox"/> No	Photo Attached? (If Yes, label the species, date, geographic site, and dredge name on the photo) <input type="checkbox"/> Yes <input type="checkbox"/> No						
Comments								

Use these diagrams to illustrate the specimen/part that was recovered.

Observer(s) Name(s) (Required; Print) <input style="width: 100%; height: 30px;" type="text"/>	Observer(s) Signature(s) <input style="width: 100%; height: 30px;" type="text"/>	Observer(s) Company <input style="width: 100%; height: 30px;" type="text"/>
--	---	--

ODESS Form 3(6)-071116



Operations & Dredging Endangered Species System (ODESS) Turtle Incident



US Army Corps
of Engineers

District <input style="width: 100%;" type="text"/>	Project <input style="width: 100%;" type="text"/>	Contract <input style="width: 100%;" type="text"/>
Dredge <input style="width: 100%;" type="text"/>	Dredging Company <input style="width: 100%;" type="text"/>	<u>Species (Required)</u> <input type="checkbox"/> Green <input type="checkbox"/> Hawksbill <input type="checkbox"/> Kemp's Ridley <input type="checkbox"/> Leatherback <input type="checkbox"/> Loggerhead <input type="checkbox"/> Unknown
<u>Load Number (Required)/Date</u> <input style="width: 100%;" type="text"/>	<u>Is this a Take? (Required)</u> <input type="checkbox"/> Yes <input type="checkbox"/> No	
<u>Recovery Date (Required)</u> <input style="width: 100%;" type="text"/>	<u>Recovery Time (24 hours) (Required)</u> <input style="width: 100%;" type="text"/>	Incident/Take Description <div style="height: 100px;"></div>
Air Temp (°C) <input style="width: 100%;" type="text"/>	Surface Water Temperature (°C) <input style="width: 100%;" type="text"/>	
Mid-Depth Water Temperature (°C) <input style="width: 100%;" type="text"/>	Bottom Water Temperature (°C) <input style="width: 100%;" type="text"/>	
<u>Location Specimen Recovered</u> <input type="checkbox"/> Deck <input type="checkbox"/> Draghead <input type="checkbox"/> Inflow Cage (Circle one) Starboard/Port/Other		
<u>Location Comment</u> <div style="height: 40px;"></div>		<u>Age Class</u> <input type="checkbox"/> Juvenile (10.1-80 cm) <input type="checkbox"/> Sub-Adult (80.1-87 cm) <input type="checkbox"/> Adult (>87 cm) <input type="checkbox"/> Unknown
<u>Tag Type</u> <input type="checkbox"/> Flipper <input type="checkbox"/> Other (Specify) <input style="width: 50px;" type="text"/> <input type="checkbox"/> Pit		<u>Gender</u> <input type="checkbox"/> Female <input type="checkbox"/> Male <input type="checkbox"/> Unknown
Tag Number <input style="width: 100%;" type="text"/>	Plastron Length (cm/in) <input style="width: 100%;" type="text"/>	Carapace Straight Length (cm/in) <input style="width: 100%;" type="text"/>
Tag Date <input style="width: 100%;" type="text"/>	Plastron Width (cm/in) <input style="width: 100%;" type="text"/>	Carapace Straight Width (cm/in) <input style="width: 100%;" type="text"/>
<u>Genetic Samples Taken?</u> <input type="checkbox"/> Yes <input type="checkbox"/> No		Carapace Curved Length (cm/in) <input style="width: 100%;" type="text"/>
<u>Final Disposition of Specimen</u> <div style="height: 20px;"></div>		Carapace Curved Width (cm/in) <input style="width: 100%;" type="text"/>
Use these diagrams to illustrate the specimen/part that was recovered.		
<div style="display: flex; justify-content: space-around;"> </div>		Comments <div style="height: 100px;"></div>
<div style="display: flex; justify-content: space-between;"> <div> <u>Observer(s) Name(s) (Required; Print)</u> <input style="width: 100%;" type="text"/> </div> <div> <u>Observer(s) Signature(s)</u> <input style="width: 100%;" type="text"/> </div> <div> <u>Observer(s) Company</u> <input style="width: 100%;" type="text"/> </div> </div>		

ODESS Form 2(6) - 071116

[illegible]

Cooperative Marine Turtle Tagging Program (CMTTP) Tagging Data Form

**COOPERATIVE MARINE TURTLE TAGGING PROGRAM (CMTTP)
TAGGING DATA FORM**

SPECIES: _____	DATE CAPTURED: DAY ____ MO ____ YR ____	DATE RELEASED: DAY ____ MO ____ YR ____
TAG NUMBERS (LIST ALL NUMBERS AND LETTER PREFIXES; CIRCLE TAG NUMBERS ALREADY ON THE TURTLE [= "OLD TAGS"]):		
LEFT FRONT: _____	RIGHT FRONT: _____	LEFT REAR: _____
PIT TAG #: _____		LOCATION OF PIT TAG: _____
WAS TURTLE CARRYING TAGS WHEN ENCOUNTERED?: YES NO IF YES, THEN CIRCLE CORRECT STATEMENT:		
1. RECAPTURE OF SAME PROJECT TURTLE (EITHER WITHIN SEASON OR BETWEEN SEASONS)		
2. RECAPTURE OF DIFFERENT PROJECT TURTLE (NOT A TAG YOUR GROUP APPLIED)		
TAG RETURN ADDRESS:		
ORGANIZATION TAGGING AND/OR RELEASING TURTLE (INCLUDE AREA CODE/PHONE NUMBER; AND EMAIL):		
PROJECT TYPE (CIRCLE ONE):		
[NESTING BEACH]	[TANGLE NET]	[POUND NET]
[HAND CATCH]	[STRANDING]	[OTHER, DESCRIBE]
IF NESTING BEACH: DID TURTLE NEST? YES NO UNDETERMINED		
FACILITY WHERE TURTLE WAS BEING HELD:		
DESCRIBE CAPTURE LOCATION. BE SPECIFIC, INCLUDE COUNTY AND LAT/LONG IF AVAILABLE		
DESCRIBE RELEASE LOCATION. BE SPECIFIC, INCLUDE COUNTY AND LAT/LONG IF AVAILABLE.		
TURTLE MEASUREMENTS:		
STRAIGHT CARAPACE LENGTH (SCLMINIMUM):	_____ CM	_____ INCHES
STRAIGHT CARAPACE LENGTH (SCLNOTCH-TIP):	_____ CM	_____ INCHES
STRAIGHT CARAPACE WIDTH (SCW):	_____ CM	_____ INCHES
CURVED CARAPACE LENGTH (CCLMINIMUM):	_____ CM	_____ INCHES
CURVED CARAPACE LENGTH (CCLNOTCH-TIP):	_____ CM	_____ INCHES
CURVED CARAPACE WIDTH (CCW):	_____ CM	_____ INCHES
WEIGHT:	_____ KG	_____ LBS
TURTLE WAS INSPECTED AND/OR SCANNED FOR:		
TAG SCARS:	YES NO	WHERE LOCATED?
PIT TAGS:	YES NO	WHAT FREQUENCY?
MAGNETIC WIRES:	YES NO	WHERE LOCATED?
LIVING TAGS:	YES NO	WHERE LOCATED?
ADDITIONAL REMARKS OR DATA ON BACK OF FORM: YES NO		
<p align="center">MAIL COMPLETED FORM TO: ARCHIE CARR CENTER FOR SEA TURTLE RESEARCH, DEPARTMENT OF ZOOLOGY, PO Box 118525 UNIVERSITY OF FLORIDA, GAINESVILLE, FL 32611 USA and SCDNR Marine Turtle Program, PO Box 12559, Charleston, SC 29422</p>		

Protocol for Collecting Tissue from Live and Dead Turtles for Genetic Analysis

Appendix II:

PROTOCOL FOR COLLECTING TISSUE FROM DEAD TURTLES FOR GENETIC ANALYSIS

Method for Dead Turtles

<<<IT IS CRITICAL TO USE A NEW SCALPEL BLADE AND GLOVES FOR EACH TURTLE TO AVOID CROSS-CONTAMINATION OF SAMPLES>>>

1. Put on a new pair of latex gloves.
2. Use a new disposable scalpel to cut out an approx. 1 cm (½ in) cube (bigger is NOT better) piece of muscle. Easy access to muscle tissue is in the neck region or on the ventral side where the front flippers "insert" near the plastron. It does not matter what stage of decomposition the carcass is in.
3. Place the muscle sample on a hard uncontaminated surface (plastron will do) and make slices through the sample so the buffer solution will penetrate the tissue.
4. Put the sample into the plastic vial containing saturated NaCl with 20% DMSO *(SEE BELOW)
5. Use the pencil to write the stranding ID number (observer initials, year, month, day, turtle number by day), species, state and carapace length on the waterproof paper label and place it in the vial with the sample.
EXAMPLE: For a 35.8 cm curved carapace length green turtle documented by Jane M. Doe on July 15, 2001 in Georgia, the label should read "JMD20010715-01, C. mydas, Georgia, CCL=35.8 cm". If this had been the third turtle Jane Doe responded to on July 15, 2001, it would be JMD20010715-03.
6. Label the outside of the vial with the same information (stranding ID number, species, state and carapace length) using the permanent marker.
7. Place clear scotch tape over the writing on the vial to protect it from being smeared or erased.
8. Wrap parafilm around the cap of the vial by stretching it as you wrap.
9. Place vial within whirlpak and close.
10. Dispose of the scalpel.
11. Note on the stranding form that a part was salvaged, indicating that a genetic sample was taken and specify the location on the turtle where the sample was obtained.
12. Submit the vial with the stranding report to your state coordinator. State coordinators will forward the reports and vials to NMFS for processing and archiving.

*The 20% DMSO buffer in the plastic vials is nontoxic and nonflammable. Handling the buffer without gloves may result in exposure to DMSO. This substance soaks into skin very rapidly and is commonly used to alleviate muscle aches. DMSO will produce a garlic/oyster taste in the mouth along with breath odor. The protocol requires that you WEAR gloves each time you collect a sample and handle the buffer vials.

The vials (both before and after samples are taken) should be stored at room temperature or cooler. If you don't mind the vials in the refrigerator, this will prolong the life of the sample. DO NOT store the vials where they will experience extreme heat (like in your car!) as this could cause the buffer to break down and not preserve the sample properly.

Questions:

Sea Turtle Program
NOAA/NMFS/SEFSC
75 Virginia Beach Drive
Miami, FL 33149
305-361-4207

THANK YOU FOR COLLECTING SAMPLES FOR SEA TURTLE GENETIC RESEARCH!!

Genetic Sample Kit Materials – DEAD turtles

- latex gloves
- single-use scalpel blades (Fisher Scientific 1-800-766-7000, cat. # 08-927-5A)
- plastic screw-cap vial containing saturated NaCl with 20% DMSO, wrapped in parafilm
- waterproof paper label, 1/4" x 4"
- pencil to write on waterproof paper label
- permanent marker to label the plastic vials
- scotch tape to protect writing on the vials
- piece of parafilm to wrap the cap of the vial
- whirl-pak to return/store sample vial

Appendix III:

PROTOCOL FOR COLLECTING TISSUE FROM LIVE TURTLES FOR GENETIC ANALYSIS

Method for Live Turtles

<<<IT IS CRITICAL TO USE A NEW BIOPSY PUNCH AND GLOVES FOR EACH TURTLE TO AVOID CROSS-CONTAMINATION OF SAMPLES>>>

1. Turn the turtle over on its back.
2. Put on a new pair of latex gloves.
3. Swab the entire cap of the sample vial with alcohol.
4. Wipe the ventral and dorsal surfaces of the rear flipper 5-10 cm from the posterior edge with the Betadine/iodine swab.
5. Place the vial under the flipper edge to use the cleaned cap as a hard surface for the punch.
6. Press a new biopsy punch firmly into the flesh as close to the posterior edge as possible and rotate one complete turn. Cut all the way through the flipper to the cap of the vial.
7. Wipe the punched area with Betadine/iodine swab; rarely you may need to apply pressure to stop bleeding.
8. Use a wooden skewer to transfer the sample from the biopsy punch into the plastic vial containing saturated NaCl with 20% DMSO *(SEE BELOW)
9. Use the pencil to write the stranding ID number (observer initials, year, month, day, turtle number by day), species, state and carapace length on the waterproof paper label and place it in the vial with the sample.
EXAMPLE: For a 35.8 cm curved carapace length green turtle documented by Jane M. Doe on July 15, 2001 in Georgia, the label should read "JMD20010715-01, *C. mydas*, Georgia, CCL=35.8 cm". If this had been the third turtle Jane Doe responded to on July 15, 2001, it would be JMD20010715-03.
10. Label the outside of the vial with the same information (stranding ID number, species, state and carapace length) using the permanent marker.
11. Place clear scotch tape over the writing on the vial to protect it from being smeared or erased.
12. Wrap parafilm around the cap of the vial by stretching it as you wrap.
13. Place vial within whirlpak and close.
14. Dispose of the biopsy punch.
15. Note on the stranding form that a part was salvaged, indicating that a genetic sample was taken and specify the location on the turtle where the sample was obtained.
16. Submit the vial with the stranding report to your state coordinator. State coordinators will forward the reports and vials to NMFS for processing and archiving.

*The 20% DMSO buffer in the plastic vials is nontoxic and nonflammable. Handling the buffer without gloves may result in exposure to DMSO. This substance soaks into skin very rapidly and is commonly used to alleviate muscle aches. DMSO will produce a garlic/oyster taste in the mouth along with breath odor. The protocol requires that you WEAR gloves each time you collect a sample and handle the buffer vials.

The vials (both before and after samples are taken) should be stored at room temperature or cooler. If you don't mind the vials in the refrigerator, this will prolong the life of the sample. DO NOT store the vials where they will experience extreme heat (like in your car!) as this could cause the buffer to break down and not preserve the sample properly.

Questions:

Sea Turtle Program
NOAA/NMFS/SEFSC
75 Virginia Beach Drive
Miami, FL 33149
305-361-4207

THANK YOU FOR COLLECTING SAMPLES FOR SEA TURTLE GENETIC RESEARCH!!

Genetic Sample Kit Materials – LIVE turtles

- latex gloves
- alcohol swabs
- Betadine/iodine swabs
- 4-6 mm biopsy punch – sterile, disposable (Moore Medical Supply 1-800-678-8678, part #0052442)
- plastic screw-cap vial containing saturated NaCl with 20% DMSO, wrapped in parafilm
- wooden skewer
- waterproof paper label, 1/4" x 4"
- pencil to write on waterproof paper label
- permanent marker to label the plastic vials
- scotch tape to protect writing on the vials
- piece of parafilm to wrap the cap of the vial
- whirl-pak to return/store sample vial



Sea Turtle Handling and Resuscitation Guidelines

Appendix IV: SEA TURTLE HANDLING AND RESUSCITATION GUIDELINES

Any sea turtles taken incidentally during the course of fishing or scientific research activities must be handled with due care to prevent injury to live specimens, observed for activity, and returned to the water according to the following procedures:

A) Sea turtles that are actively moving or determined to be dead (as described in paragraph (B)(4) below) must be released over the stern of the boat. In addition, they must be released only when fishing or scientific collection gear is not in use, when the engine gears are in neutral position, and in areas where they are unlikely to be recaptured or injured by vessels.

B) Resuscitation must be attempted on sea turtles that are comatose or inactive by:

1. Placing the turtle on its bottom shell (plastron) so that the turtle is right side up and elevating its hindquarters at least 6 inches (15.2 cm) for a period of 4 to 24 hours. The amount of elevation depends on the size of the turtle; greater elevations are needed for larger turtles. Periodically, rock the turtle gently left to right and right to left by holding the outer edge of the shell (carapace) and lifting one side about 3 inches (7.6 cm) then alternate to the other side. Gently touch the eye and pinch the tail (reflex test) periodically to see if there is a response.
2. Sea turtles being resuscitated must be shaded and kept damp or moist but under no circumstance be placed into a container holding water. A water-soaked towel placed over the head, carapace, and flippers is the most effective method in keeping a turtle moist.
3. Sea turtles that revive and become active must be released over the stern of the boat only when fishing or scientific collection gear is not in use, when the engine gears are in neutral position, and in areas where they are unlikely to be recaptured or injured by vessels. Sea turtles that fail to respond to the reflex test or fail to move within 4 hours (up to 24, if possible) must be returned to the water in the same manner as that for actively moving turtles.
4. A turtle is determined to be dead if the muscles are stiff (rigor mortis) and/or the flesh has begun to rot; otherwise, the turtle is determined to be comatose or inactive and resuscitation attempts are necessary.

Any sea turtle so taken must not be consumed, sold, landed, offloaded, transshipped, or kept below deck.

These guidelines are adapted from 50 CFR § 223.206(d)(1). Failure to follow these procedures is therefore a punishable offense under the Endangered Species Act.

Online Resources

REFERENCE THE GRBO AND REVISIONS ONLINE AT:

http://sero.nmfs.noaa.gov/protected_resources/section_7/freq_biop/documents/dredge_bo/nov_19_2003_gom_rbo.pdf

http://sero.nmfs.noaa.gov/protected_resources/section_7/freq_biop/documents/dredge_bo/f13976_02187-sad_grbo_revision_1.pdf

http://sero.nmfs.noaa.gov/protected_resources/section_7/freq_biop/documents/dredge_bo/f13817_revision_2_grbo.pdf

Water Quality and Coastal Zone Consistency Certifications

LANCE R. LEFLEUR
DIRECTOR



Alabama Department of Environmental Management
adem.alabama.gov

1400 Coliseum Blvd. 36110-2400 ■ Post Office Box 301463
Montgomery, Alabama 36130-1463
(334) 271-7700 ■ FAX (334) 271-7950

ROBERT J. BENTLEY
GOVERNOR

March 9, 2017

Mr. Curtis M. Flakes, Chief
Planning and Environmental Division
Department of the Army
Mobile District, Corps of Engineers
Post Office Box 2288
Mobile, AL 36628-0001

RE: State of Alabama Concurrence with the U.S. Army Corps of Engineers' Coastal Consistency Determination
Mobile Harbor Federal Navigation Project
U.S. Army Corps of Engineers (USACE) Joint Public Notice: FP16-MH01-04
Alabama Department of Environmental Management (ADEM) Tracking Code: 2017-181-FC-FAA-COEP

Dear Mr. Flakes:

The ADEM received the USACE's consistency determination - required by Title 15CFR Subpart C - on January 4, 2017. Pursuant to Title 15CFR §930.41 and based upon review of the information submitted by the USACE, by this letter the ADEM hereby notifies the USACE of its concurrence with the USACE's consistency determination.

Should the proposed activity be modified, a revised consistency determination may be necessary pursuant to Title 15CFR 930.46. Contact the Mobile-Coastal office anytime with questions. Always include the ADEM tracking code above when corresponding on this matter.

Sincerely,

Anthony Scott Hughes, Chief
Field Operations Division

ASH/jsb/cap

File: CZCERT/46024

cc: Larry Parson, USACE (Sent Via Email Only: larry.e.parson@usace.army.mil)
Rosemary Hall, EPA (Sent Via Email Only: Hall.Rosemary@epamail.epa.gov)
Josh Rowell, USFWS (Sent Via Email Only: Josh_Rowell@fws.gov)
Mark Thompson, NMFS (Sent Via Email Only: Mark.Thompson@noaa.gov)
Carl Ferraro, ADCNR (Sent Via Email Only: Carl.Ferraro@dcnr.alabama.gov)
Phillip Hinesley, ADCNR (Sent Via Email Only: Phillip.Hinesley@dcnr.alabama.gov)

Birmingham Branch
110 Vulcan Road
Birmingham, AL 35209-4702
(205) 942-6168
(205) 941-1603 (FAX)

Decatur Branch
2715 Sandlin Road, S.W.
Decatur, AL 35603-1333
(256) 353-1713
(256) 340-9359 (FAX)



Mobile Branch
2204 Perimeter Road
Mobile, AL 36615-1131
(251) 450-3400
(251) 479-2593 (FAX)

Mobile-Coastal
3664 Dauphin Street, Suite B
Mobile, AL 36608
(251) 304-1176
(251) 304-1189 (FAX)

LANCE R. LEFLEUR
DIRECTOR



Alabama Department of Environmental Management
adem.alabama.gov

1400 Coliseum Blvd. 36110-2400 ■ Post Office Box 301463
Montgomery, Alabama 36130-1463
(334) 271-7700 ■ FAX (334) 271-7950

ROBERT J. BENTLEY
GOVERNOR

March 9, 2017

Mr. Curtis M. Flakes, Chief
Planning and Environmental Division
Department of the Army
Mobile District, Corps of Engineers
Post Office Box 2288
Mobile, AL 36628-0001

RE: State of Alabama Water Quality Certification (WQC) Pursuant to Clean Water Act (CWA) §401(a)
Mobile Harbor Federal Navigation Project
U.S. Army Corps of Engineers (USACE) Joint Public Notice: FP16-MH01-04
Alabama Department of Environmental Management (ADEM) Tracking Code: 2017-181-WQC-COEP

Dear Mr. Flakes:

The ADEM received a copy of the USACE's joint public notice on January 4, 2017 and has completed its review of all submitted materials related to the USACE's proposal to continue with operations and maintenance of the Mobile Harbor Navigation Project as previously described in Public Notice Numbers FP86-MH06-2, FP91-MH07-4, FP95-MH07-2, FP97-MH08-02, FP97-MH09-02, FP11-MH01-06, and FP14-MH01-10.

Action pertinent to WQC is required by CWA §401(a)(1), 33 U.S.C. §1251, *et. seq.* If conducted in accordance with the conditions prescribed herein, there is reasonable assurance that the discharge resulting from the approved activity will not violate applicable water quality standards established under §303 of the CWA and §22-22-9(g), *Code of Alabama* (1975). By this letter, the ADEM notifies the USACE that CWA §401 WQC is hereby **granted**. This WQC terminates coincidentally with the expiration of FP16-MH01-04. This WQC only addresses potential discharges to state waters resulting from activities proposed in the USACE's application. This WQC does not negate the USACE's responsibility to acquire all other needed permits nor does this WQC, in any way, imply that the proposed activities comply with the requirements of any other jurisdictional entity nor does it imply that the project can or will be approved by any other jurisdictional entity. ADEM certifies that there are no applicable effluent limitations under §301 and §302 nor applicable standards under §306 and §307 of the CWA in regard to the activities specified.

In recognition that projects are site specific in nature and conditions can change during project implementation, the ADEM reserves the right to request additional information or request additional management measures to be implemented, as necessary on a case-by-case basis, in order to ensure the protection of water quality and coastal resources. Deviation from the approved project design may necessitate additional coordination.

This WQC does not convey any property rights in either real or personal property, or any exclusive privileges, nor does it authorize any injury to persons or property or invasion of other private rights, trespass, or any infringement of Federal, State, or local laws or regulations and in no way purports to vest in the USACE title to lands now owned by the State of Alabama nor shall it be construed as acquiescence by the State of Alabama of lands owned by the State that may be in the USACE's possession. This concurrence is not transferable without prior written notice and approval of the ADEM. Upon such notice, the Director may require submission of additional information.

To protect water quality, the following conditions must be incorporated as part of FP16-MH01-04:

1. The USACE and/or its assigns shall implement appropriate best management practices (BMPs) to minimize turbidity impacts to the maximum extent practicable. Turbidity generated by the activity must not cause substantial visible contrast nor result in an increase of more than fifty (50) Nephelometric turbidity units (NTU) above background in state waters.
2. Upon the loss or failure of any treatment facility, BMP, or other management control measure as identified by responsible on-site staff during day to day construction operations or as identified by ADEM technical staff during facility inspections, the USACE and/or its assigns shall, where necessary to maintain compliance with this WQC, suspend, cease, reduce, or otherwise control work/activity and all discharges until effective treatment is restored and immediately notify the ADEM Mobile-Coastal office at (251) 304-1176 of resultant work stoppage.

Birmingham Branch
110 Vulcan Road
Birmingham, AL 35209-4702
(205) 942-6168
(205) 941-1603 (FAX)

Decatur Branch
2715 Sandlin Road, S.W.
Decatur, AL 35603-1333
(256) 353-1713
(256) 340-9359 (FAX)



Mobile Branch
2204 Perimeter Road
Mobile, AL 36615-1131
(251) 450-3400
(251) 479-2593 (FAX)

Mobile-Coastal
3664 Dauphin Street, Suite B
Mobile, AL 36608
(251) 304-1176
(251) 304-1189 (FAX)

IDIQ Contract for Rental of Hopper Dredge
With Attendant Plant and Operators for
Maintenance Dredging in Alabama, Mississippi, Florida


W91278-17-B-0002

U.S. Army Corps of Engineers
2017-181-WQC-COEP
Page 2 of 2

3. The USACE and/or its assigns are responsible for the condition of the spoil disposal areas for the life of the placement activity and until the disposal areas are reclaimed or adequately stabilized, and for pumping and discharge rates to ensure settling of suspended solids within the confines of the spoil disposal areas sufficient to ensure that turbidity in the return water will not cause substantial visible contrast within the receiving waters, or result in an increase of 50 NTUs above background turbidity levels in the receiving waters.

Contact the Mobile-Coastal office anytime with questions. Always include the ADEM tracking code above when corresponding on this matter.

Sincerely,



Anthony Scott Hughes, Chief
Field Operations Division

ASH/jsb/cap

File: 401WQ/46024

cc: Larry Parson, USACE (Sent Via Email Only: larry.e.parson@usace.army.mil)
Rosemary Hall, EPA (Sent Via Email Only: Hall.Rosemary@epamail.epa.gov)
Josh Rowell, USFWS (Sent Via Email Only: Josh_Rowell@fws.gov)
Mark Thompson, NMFS (Sent Via Email Only: Mark.Thompson@noaa.gov)
Carl Ferraro, ADCNR (Sent Via Email Only: Carl.Ferraro@dcnr.alabama.gov)
Phillip Hinesley, ADCNR (Sent Via Email Only: Phillip.Hinesley@dcnr.alabama.gov)

Letter from U.S. Fish and Wildlife Service



United States Department of the Interior

FISH AND WILDLIFE SERVICE
1208-B Main Street
Daphne, Alabama 36526

IN REPLY REFER TO:

2012-I-0311

JAN 18 2017

LeKesha W. Reynolds
Chief, Coastal Environmental Team
U.S. Army Engineer District Mobile
P.O. Box 2288
Mobile, AL 36628-0001

Dear Ms. Reynolds:

This is the report of the U.S. Fish and Wildlife Service (Service), concerning your letter of December 23, 2016 and public notice FP16-MH01-04, in which the U.S. Army Corps of Engineers (Corps), Mobile District is proposing continued maintenance dredging and disposal effort for the Mobile Harbor Federal Navigation Project, Mobile County, Alabama. The Mobile Harbor Project is divided into three general areas: the river channel section, the bay channel section, and the bar channel section. The river channel section involves the continued maintenance dredging (1.2 mcy annually) and placement of material from the mouth of the Mobile River to the Cochrane Bridge, approximately four miles. The River channel would be dredged to a total depth of 40 feet plus two feet of advanced maintenance and two feet of allowable overdepth dredging. The bay channel section extends 29 miles from near the mouth of Mobile Bay to the mouth of the Mobile River. Approximately 4.3 mcy of material would be removed annually to a depth of 45 feet plus two feet of advanced maintenance and two feet of allowable overdepth dredging. The bar channel section extends eight miles from the Gulf of Mexico to Mobile Bay. Approximately 300,000 cubic yards of material would be removed annually to a total depth of 47 feet plus two feet of advanced maintenance and two feet of allowable overdepth dredging.

Dredged material is proposed to be removed from the channels by dragline/clamshell, hydraulic pipeline and/or hopper dredge, and all material would be placed in previously approved upland disposal sites. We understand that in the event where emergency dredging activities are required; the Corps is proposing to use Galliard Island in addition to the other disposal areas. The emergency option would be necessary when there is insufficient hopper dredge capability to meet these increased needs. Material placed on Galliard Island would only occur in accordance with the Migratory Bird Treaty Act and any associated regulatory agency agreements. Following are the Service comments concerning this federal project as it relates to the Marine Mammal Protection Act of 1972 ((16 U.S.C. 1361-1407), and the Endangered Species Act of 1973 (87 Stat. 884, as amended; 16 Cr.S.C. 1531 et seq.).

Your letter states that where hopper dredging equipment will be used for the project the Corps will adhere to the Regional Biological Opinion (RBO) for Dredging of Gulf of Mexico

PHONE: 251-441-5181

FAX: 251-441-6222

Ms. LeKesha W. Reynolds

2

Navigation Channels and Sand Mining Areas Using Hopper Dredges by COE Galveston, New Orleans, Mobile, and Jacksonville Districts (Consultation Number F/SER/2000/01287). Therefore, by strictly adhering to the conditions of the RBO, we believe that adverse impacts to sea turtles during the dredging and disposal operation will be minimal.

Gulf sturgeon (*Acipenser oxyrinchus desotoi*), particularly juveniles, may be affected by dredging impacts on water quality or food availability, or by direct physical contact. If the following condition is implemented we believe that there will be no adverse impact and formal consultation will not be required. If a Gulf sturgeon is observed, halt operations until the species has left the area. If this step cannot be exercised or there is an occurrence of collision with and/or injury to a sturgeon as a result of the proposed project, then work should cease and further consultation with this office should be undertaken. We request that the Corps report to this office any observation of a sturgeon within the area during project operations.

The Service is also concerned about the potential indirect or direct physical impact on endangered Florida manatees (*Trichechus manatus latirostris*) which may be migrating through the project area during the proposed construction operation. Direct impacts could occur from boat, barge, dredge operation or other construction activities. Because manatees are known to seasonally occur near the area slated for dredging, and could be affected by this activity, we believe that this project, as described, may affect the manatee.

The Corps has historically agreed to implement the "Standard Manatee Construction Conditions" that were referred to in your letter. The Service believes that if these conditions are implemented then there will be no adverse impact to the manatee and formal consultation will not be required. If these steps cannot be exercised or there is an occurrence of collision with and/or injury to a manatee as a result of the proposed project, then further consultation with this office should be undertaken. We request that any observation of a manatee within the area during project operations be reported to this office.

Based on the information provided, and review of our records, we concur with your determination that this project may affect, but is not likely to adversely affect federally listed species. We appreciate the opportunity to comment on your project. For further discussion, please contact Josh Rowell of my staff at (251) 441-5836.

Sincerely,



William J. Pearson
Field Supervisor
Alabama Ecological Services Field Office

Letter from Alabama State Historic Preservation Officer



ALABAMA HISTORICAL COMMISSION

468 South Perry Street
Montgomery, Alabama 36130-0900
334-242-3184 / Fax: 334-240-3477

Lisa D. Jones
Executive Director
State Historic Preservation Officer

January 18, 2017

Curtis M. Flakes
Corps of Engineers
P.O. Box 2288
Mobile, AL 36628-0001

Re: AHC 09-0199
Maintenance Dredging and Placement Activities/Mobile Harbor Navigation Project
Public Notice No. FP16-MH01-04
Mobile County

Dear Mr. Flakes:

Our records indicate that we have previously concurred with this project this project. We continue to concur with project activities provided the scope of work remains the same. However, if the scope of work has changed, further consultation with our office will be necessary.

Should artifacts or archaeological features be encountered during project activities, work shall cease and our office shall be consulted immediately. Artifacts are objects made, used or modified by humans. They include but are not excluded to arrowheads, broken pieces of pottery or glass, stone implements, metal fasteners or tools, etc. Archaeological features are stains in the soil that indicate disturbance by human activity. Some examples are post holes, building foundations, trash pits and even human burials. This stipulation shall be placed on the construction plans to insure contractors are aware of it.

We appreciate your commitment to helping us preserve Alabama's historic archaeological and architectural resources. Should you have any questions, please contact Amanda McBride at 334.230.2692 or Amanda.McBride@ahc.alabama.gov. Have the AHC tracking number referenced above available and include it with any future correspondence.

Sincerely,

Lee Anne Wofford
Deputy State Historic Preservation Officer

LAW/AMH/amh

THE STATE HISTORIC PRESERVATION OFFICE
www.ahc.alabama.gov

Section 103 Concurrence from EPA



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 4

ATLANTA FEDERAL CENTER
61 FORSYTH STREET
ATLANTA, GEORGIA 30303-8960

OCT 20 2015

Mr. Curtis M. Flakes, Chief
Planning and Environmental Division
Mobile District Corps of Engineers
P.O. Box 2288
Mobile, Alabama 36628-0001

Dear Mr. Flakes:

This letter is in regard to your April 30, 2015, request for concurrence on the suitability for ocean disposal of maintenance dredged material from the Mobile Harbor Federal navigation channel, Alabama. Additional information was received on May 28, 2015 regarding current velocities within the channel. In a June 11, 2015, letter, the U.S. Environmental Protection Agency (EPA) acknowledged receipt of this information and requested, in accordance with Section 103(c)(2) of the Marine Protection, Research, and Sanctuaries Act (MPRSA), an extension to the original 45-day review period. The EPA requested additional information regarding the water quality modeling efforts and elutriate tests via email on June 26, 2015. Several conversations occurred between our agencies to ensure requested information was adequately addressed. A response was received on August 3, 2015. Final water quality modeling runs were received on September 4, 2015.

The Mobile Harbor project consists of maintenance dredging of the existing 47-foot by 600-foot Mobile Bar Channel, the existing 45-foot by 400-foot Mobile Bay channel, the existing 40-foot by 500 to 700-foot Mobile River Channel, a 40-foot by 800-1,000-foot turning basin opposite the Alabama State Port Authority (ASPA), and a 40-foot by 1,000-foot by 1,600-foot turning basin south of the Cochrane Bridge. The dredging would be performed with a tolerance of up to 2 feet of advanced maintenance plus 2 feet of overdepth dredging. All depths are mean lower low water. Dredged material volumes are estimated to be approximately 2.9 million cubic yards, annually. However, depending upon the availability of other planned placement options, the maximum potential annual volume could be as high as 5.6 million cubic yards. The dredging, transport, and placement of proposed dredged material at the Mobile Ocean Dredged Material Disposal Site (ODMDS) are expected to be performed by hopper, mechanical, and hydraulic dredges, depending upon location within the channel.

The EPA, Region 4, has completed its review of your Section 103 Evaluation Report and supporting documents and has completed an independent evaluation of the dredged material. The EPA concurs with your determination that the proposed dumping at the Mobile ODMDS will comply with the criteria set forth in 40 CFR § 227 subject to conditions as outlined below. A brief discussion of the compliance of the material with the criteria is provided below.

1. Exclusion Criteria – 40 CFR § 227.13(b)

Dredged material from the outer bar channel (sample stations MHX-13 and MHX-14) meets the criteria set forth in 40 CFR § 227.13(b)(1) as this material is composed predominately of sand, gravel, rock, or any other naturally occurring bottom material with particle sizes larger than silt, and the material is found in areas of high current or wave energy such as streams with large bed loads or coastal areas with shifting bars and channels. The samples analyzed from this area were classified as sand and silty sand with less than 10 percent fines. Additionally, currents in this area frequently exceed 30cm/sec. Dredged material from the outer bar channel (sample stations MHX-12 and MHX-15) meets the criteria set forth in 40 CFR 227.13(b)(3) as this material is substantially the same as the substrate at the Mobile ODMDS and is far removed from known sources of pollution to provide a reasonable assurance that such material has not been contaminated by such pollution. Material from this area is clay and clayey sands as is the material at the Mobile ODMDS. It is also seaward of the barrier islands. The material seaward of station 1760+10 is therefore environmentally acceptable for ocean disposal without further testing.

The remaining material proposed to be disposed at the Mobile ODMDS does not meet the criteria of paragraph (b) of this section and therefore, further testing was required as discussed below.

2. Water Column and Suspended Phase Determinations - 40 CFR § 227.6(c)(1&2) and 227.27(a&b)

For these tests, ammonia and lindane exceeded the Water Quality Criteria (WQC) prior to any dilution. However, only small dilutions of 1.35:1 and 3.22:1 were required to meet the WQC and these dilutions were more than met as discussed below. Therefore, it is not expected that the WQC will be exceeded after four hours at any time outside of the Mobile ODMDS boundaries.

Bioassays on three appropriately sensitive marine organisms were conducted. Water quality modeling was performed to demonstrate that adequate dilution would be achieved to meet the Limiting Permissible Concentration (LPC) after 4 hours and at all times outside the disposal site. Required dilutions ranged from 146:1 to 434:1. Modeled dilutions, subject to conditions (see enclosure 1) exceeded the required dilution in all cases. Accordingly, it is concluded that the liquid phase of the material is in compliance with 40 CFR § 227.6(c)(1&2) and § 227.27(a&b) provided compliance with the restrictions described in enclosure 1.

3. Benthic Determinations - 40 CFR § 227.6(c)(3) and § 227.27(b)

Solid phase toxicity evaluation: Ten-day toxicity tests were conducted using worms (*Neanthes arenaceodentata*) and amphipods (*Leptocheirus plumulosus*). These organisms are appropriately sensitive benthic marine organisms and are good predictors of adverse effects to benthic marine communities. For all dredging units, the amphipod toxicity result was within 20 percent of the reference/control and the worm toxicities were within 10 percent of the reference. These results show that the solid phase of the material is not likely to cause significant mortality and meets the solid phase toxicity criteria of §227.6(c)(3) and § 227.27(b).

Solid phase bioaccumulation evaluation: Twenty-eight day bioaccumulation tests were conducted on all project sediments using two appropriately sensitive benthic marine organisms, *Nereis virens* and *Macoma nasuta*. Tissue concentrations were compared to Food and Drug Administration (FDA) Action Levels. None of the contaminants, for which there are FDA Action Levels, exceed such thresholds in the tissues of organisms exposed to project sediments. Concentrations of contaminants in tissues of organisms exposed to project sediments were then compared to concentrations in tissues of organisms exposed to a reference sediment. Zinc, dioxin, and PAHs were found to be statistically higher in some samples as compared to the reference. When the bioaccumulation of contaminants in tissues exposed to dredged material exceeds that exposed to reference sediments, general risk-based evaluations must be conducted to evaluate compliance with 40 CFR § 227.13(c)(3). The EPA conducted such an evaluation. Two PAHs from station MH10-03 exceed the EPA's background tissue levels for the northern Gulf of Mexico and therefore warranted further analysis through a discussion of the eight factors in the Green Book. Although the PAHs exceeded reference values by a factor of 300 to 400, EPA concluded that there is no potential for undesirable effects due to bioaccumulation as a result of the presence of individual chemicals or of the solid phase of the dredged material as a whole. Accordingly, it is concluded that the solid phase of the material proposed for disposal meets the ocean disposal criteria at 40 CFR §227.6(c)(3) and § 227.27(b).

Pursuant to Section 104(a)(4) of the MPRSA, ocean disposal permits must be conditioned to assure consistency with approved Site Management and Monitoring Plans (SMMP). The Mobile ODMDS SMMP was developed in March 2015. This letter of concurrence is conditional upon implementation through contract conditions of the requirements of the Mobile ODMDS SMMP and the enclosed list of conditions. This determination of compliance is valid for a period of three years from the date of this letter. If you have any questions regarding this determination or management of the Mobile ODMDS, please contact Ms. Jennifer Derby at (404) 562-9401.

Sincerely,



James D. Giattina, Director
Water Protection Division

Enclosure

Mobile Maintenance Dredging
Ocean Disposal Conditions

1. A bathymetry survey of the ODMDS release zone will be conducted within three months prior to initiation of disposal activities.
2. A bathymetry survey of the ODMDS release zone will be conducted within thirty days of completion of disposal activities.
3. Disposal monitoring data will be collected and submitted to the EPA on a weekly basis consistent with the requirements of the March 2015 Mobile ODMDS SMMP.
4. A Post-disposal summary report will be submitted to the EPA within 90 days of completion of disposal activities.
5. All disposal will be initiated at least 330 feet within the boundaries of the Mobile ODMDS.
6. Special conditions for Dredging Units 02, 06/07, and 10/11 in order to comply with 40 CFR § 227.6(c)(1&2) and § 227.27(a&b):
 - a. Disposal operations with disposal volumes of less than or equal to 10,800 cubic yards per load have no further restrictions.
 - b. For volumes in excess of 10,800 cubic yards, the disposal vessel must dispose at speeds less than 3 knots (kts) (accuracy of +/-1 kts) and no more than one hopper bin may open simultaneously.
 - c. Disposal logs shall be maintained for each load in excess of 10,800 cubic yards. The logs will include at a minimum the following:
 - i. DQM load number
 - ii. Date, time, and vessel speed at initiation of disposal
 - iii. Volume of disposal
 - iv. Date, time, and vessel speed of opening and closing of each hopper bin
 - d. Disposal logs shall be submitted with the Post-disposal summary report (condition 4 above) or upon request.
 - e. Dredging Unit MH10-02 is defined as Mobile River Channel 141+00 to 156+00. Dredging Unit MH10-06/07 is defined as the Mobile Bay Channel 759+00 to 824+00. Dredging Unit MH10-10/11 is defined as the Mobile Bay Channel 1594+00 to 1760+10.

Mobile Harbor ODMDS Site Management and Monitoring Plan (SMMP)

March 2015





Mobile
OCEAN DREDGED MATERIAL DISPOSAL SITE



U.S. Army Corps
of Engineers

SITE MANAGEMENT AND MONITORING PLAN



John J. Chyba 30 APRIS
Date
John J. Chyba
Colonel, U.S. Army
District Commander
Mobile District
U.S. Army Corps of Engineers
Mobile, Alabama

Heather McTeer Toney
Regional Administrator
U.S. Environmental Protection Agency
Region 4
Atlanta, Georgia

This plan is effective from the date of EPA and USACE signature for a period not to exceed four years.

**MOBILE OCEAN DREDGED MATERIAL DISPOSAL SITE
SITE MANAGEMENT AND MONITORING PLAN**

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1.0 INTRODUCTION	1
2.0 SITE MANAGEMENT	1
2.1 Disposal Site Characteristics.....	2
2.2 Management Objectives.....	3
2.3 Disposal History and Dredged Material Volumes	3
2.4 Dredged Material Characteristics	3
2.4.1 Associated Beach Quality Materials.....	3
2.4.2 Dredged Material Quality Verification	4
2.5 Time of Disposal.....	4
2.6 Disposal Technique.....	4
2.7 Disposal Location	4
2.8 Permit and Contract Conditions.....	5
2.9 Permit Process.....	5
2.10 Information Management of Dredged Material Placement Activities.....	5
3.0 SITE MONITORING	5
3.1 Baseline Monitoring.....	6
3.2 Disposal Monitoring	7
3.3 Post Discharge Monitoring	8
3.4 Disposal Effects Monitoring	8
3.5 Reporting and Data Formatting	10
3.5.1 Project Initiation and Violation Reporting.....	10
3.5.2 Disposal Monitoring Data.....	10
3.5.3 Post Disposal Summary Reports.....	10
3.5.4 Environmental Monitoring.....	10
4.0 MODIFICATION OF THE MOBILE SMMP	10
5.0 REFERENCES	11

LIST OF TABLES

<u>Table No.</u>	<u>Title</u>	<u>Page</u>
Table 1.	Site Coordinates	2
Table 2.	Summary of Permit and Contract Conditions	5
Table 3.	Surveys and Studies Conducted at or in the vicinity of the Mobile ODMDs	9
Table 4.	Site Monitoring Strategies and Thresholds for Action	9

LIST OF FIGURES

<u>Figure No.</u>	<u>Title</u>	<u>Page</u>
Figure 1.	Mobile ODMDs Location Map	2

Mobile ODMDs SMMP

March 2015

Mobile ODMDs
Site Management and Monitoring Plan

1.0 INTRODUCTION

It is the responsibility of the U.S. Environmental Protection Agency (EPA) and the U.S. Army Corps of Engineers (USACE) under the Marine Protection, Research, and Sanctuaries Act (MPRSA) of 1972 to manage and monitor each of the Ocean Dredged Material Disposal Sites (ODMDs) designated by the EPA pursuant to Section 102 of MPRSA. Section 102(c)(3) of the MPRSA requires development of a Site Management and Monitoring Plan (SMMP) for each ODMDs and review and revision of the SMMP not less frequently than every 10 years. The 1996 document, *Guidance Document for Development of Site Management Plans for Ocean Dredged Material Disposal Sites* (EPA/USACE, 1996) and the EPA Region 4 and USACE South Atlantic Division (SAD) Memorandum of Understanding (EPA/USACE, 2007) have been used as guidance in developing this SMMP.

Specific responsibilities of EPA and the USACE are:

EPA: EPA is responsible for designating/de-designating MPRSA Section 102 ODMDs, for implementing and evaluating environmental effects of disposal dredged material at these sites, and for reviewing and concurring on dredged material suitability determinations.

USACE: The USACE is responsible for evaluating dredged material suitability, issuing MPRSA Section 103 permits, regulating site use, and developing and implementing disposal monitoring programs.

The SMMP provisions shall be requirements for all dredged material disposal activities at the site. All Section 103 (MPRSA) ocean disposal permits or contract specifications shall be conditioned as necessary to assure consistency with the SMMP.

2.0 SITE MANAGEMENT

Section 228.3 of the Ocean Dumping Regulations (40 CFR 220-229) states: "Management of a site consists of regulating times, rates, and methods of disposal and quantities and types of materials disposed of; developing and maintaining effective ambient monitoring programs for the site; conducting disposal site evaluation studies; and recommending modifications in site use and/or designation."

2.1 Disposal Site Characteristics

The designation of the Mobile ODMDS can be found in 40 CFR 228.15(h)(14). Coordinates in the CFR are provided in NAD 27. The Mobile ODMDS is a 4.75 square nautical mile (nmi²) area.

Table 1: Site Coordinates

Geographic (NAD 27)	
30°10'00"N	88°07'42"W
30°10'24"N	88°05'12"W
30°09'24"N	88°04'42"W
30°08'30"N	88°05'12"W
30°08'30"N	88°08'12"W

The site (see Figure 1) lies on the shallow continental shelf, 4 nmi offshore Mobile Point, Alabama with an average depth of 14 meters. Physical, chemical, and biological conditions at the ODMDS are described in, "Final Environmental Impact Statement for the Pensacola, FL, Mobile, AL, and Gulfport, MS Dredged Material Disposal Site Designation." (EPA, 1987)



Figure 1: Mobile ODMDS Location Map.

2.2 Management Objectives. Appropriate management of an ODMDS is aimed at assuring that disposal activities will not unreasonably degrade or endanger human health, welfare, the marine environment or economic potentialities (MPRSA §103(a)). The primary objectives in the management of these ODMDSs are:

- Protection of the marine environment;
- Documentation of disposal activities and compliance; and
- Maintenance of a long term disposal alternative for dredged material, while encouraging beneficial use where practical.

The following sections provide the framework for meeting these objectives to the extent possible.

2.3 Disposal History and Dredged Material Volumes. Disposal history can be found at the Ocean Disposal Database maintained by the USACE (<http://el.erdc.usace.army.mil/odd/>). The Mobile ODMDS and the Mobile North ODMDS (selected by the USACE pursuant to Section 103 of the MPRSA) have been used for disposal of 120 million cubic yards since 1987 (USACE, 2014). Currently, the average annual disposal volume is about 4 million cys. The composition of the dredged material is primarily silts and clays. Future volumes and rates of disposal, from both Federal and private applicants, are expected to be similar to previous years. However, this estimate may increase if it is determined feasible to deepen and widen the Federal channel into Mobile Harbor to its currently authorized project dimensions. Also, the Mobile Harbor Turning Basin constructed in 2010 requires annual maintenance dredging of about 425,000 cubic yards per year which may go to the ODMDS (USACE, 2014). The USACE has estimated the remaining capacity of the Mobile ODMDS at 15 million cubic yards based on projected volumes and the remaining capacity the ODMDS has an estimated life of four years (USACE 2014). EPA in cooperation with the Mobile District is in the process of expanding the Mobile ODMDS through preparation of an Environmental Assessment and rulemaking and expects to expand the site within the next four years.

2.4 Dredged Material Characteristics.

2.4.1 Associated Beach Quality Materials. USACE Beneficial Use of Dredged Material EM 1110-2-5026 requires dredged material be maximized within the coastal system. Dredged materials that qualify for beach or near-shore placement per the applicable State standards shall be beneficially placed in such location, to the maximum extent practicable. It is expected that the applicable State will exercise its authority and responsibility, regarding beach nourishment, to the full extent during any future permitting activities. Beneficial use of beach compatible dredged material for beach nourishment is strongly encouraged and supported by EPA. Most sandy material is placed in the Sand Island Beneficial Use Area located due east of the ODMDS (USACE, 2014).

2.4.2 Dredged Material Quality Verification. The suitability of dredged material for ocean disposal must be verified by the USACE and agreed to via written concurrence from EPA prior to disposal. Verification will be valid for three years from the most current verification.

Verification process:

- 1) Case-specific evaluation against the exclusion criteria (40 CFR 227.13(b)).
- 2) Determination of testing requirements for non-excluded material based on the potential of sediment contamination since last verification.
- 3) When applicable, execute testing and determination of suitability of non-excluded material for ocean disposal.

Verification documentation for suitability will be completed prior to use of the ODMDS. Documentation will be in the form of a MPRSA Section 103 Evaluation. Potential testing and the Evaluation will follow the procedures outlined in the 1991 EPA/USACE Dredged Material Testing Manual and 2008 Southeast Regional Implementation Manual (SERIM) or the appropriate updated versions. This includes how dredging projects will be subdivided into project segments for sampling and analysis. The MPRSA Section 103 Evaluation will be in the form outlined in Appendix C of the SERIM. Water Quality Compliance determinations will be made using the STFATE (ADDAMS) model. Only material determined to be suitable and in compliance with the Ocean Dumping Criteria (40 CFR Part 227) through the verification process by the USACE and EPA, Region 4 can be disposed in this ODMDS.

2.5 Time of disposal. At present no restrictions have been determined to be necessary for disposal related to seasonal variations in ocean current or biotic activity at the Mobile ODMDS.

2.6 Disposal Technique. No specific disposal technique is required for the site. In order to protect sea turtles and Gulf sturgeon, the National Marine Fisheries Service, Protected Resources Division requires monitoring according to guidance outlined in the *Regional Biological Opinion for Dredging of Gulf of Mexico Navigation Channels and Sand Mining ("Borrow") Areas Using Hopper Dredges by USACE Galveston, New Orleans, Mobile, and Jacksonville Districts* (NMFS, 2003 and amended 2005 & 2007). In addition, standard surveillance and evasive measures to protect sea turtles and marine mammals shall be employed during all disposal operations at the ODMDS.

2.7 Disposal Location. 40 CFR §227.28 requires all disposals to occur at least 330 feet (100 meters) inside any site boundaries. Release zones may be established by the USACE in consultation with EPA at the time of site use for operational reasons or to insure compliance with the Ocean Dumping Criteria (40 CFR Part 227). Disposal shall be initiated within the applicable release zone boundary and completed (i.e. doors closed) prior to leaving the ODMDS boundaries. Placement methods, which prevent mounding of dredged materials from becoming an unacceptable navigation hazard, will be used. Dredged material shall be disposed so that at no point will depths less than -25 feet Mean Lower Low Water (MLLW) occur (i.e., a clearance of

25 feet above the bottom will be maintained). The physical removal or leveling of material above -25 feet MLLW is a management alternative should mounds greater than that elevation occur. Disposal shall not occur closer than 1,300 feet to any oil and gas rigs that may be present within the site boundaries.

2.8 Permit and Contract Conditions. The disposal monitoring and post-disposal monitoring requirements described under Site Monitoring will be included as permit conditions on all MPRSA Section 103 permits and will be incorporated in the contract language for all federal projects. A summary of the management and monitoring requirements to be included are listed in Table 2.

Table 2. Summary of Permit and Contract Conditions

Condition	Reference
Dredged Material Suitability and Term of Verification	SMMP page 3, Southeast Regional Implementation Manual
Disposal within Appropriate Zones	SMMP page 4
Pre and Post Bathymetric Surveys	SMMP pages 6,8
Disposal Monitoring and Recording of Disposal Locations	SMMP pages 7-8
Reporting Requirements: Disposal Summary Reports within 90 Days of Project Completion	SMMP page 10

2.9 Permit Process. All disposal of dredged material in the ocean, with the exception of Federal Civil Works projects, requires an ocean dumping permit issued by the USACE pursuant to Section 103 of the MPRSA. A summary of the permitting process can be found at: http://www.epa.gov/region4/water/oceans/Dredged_Material_Permit_Process.htm.

2.10 Information Management of Dredged Material Placement Activities. EPA Region 4 and USACE SAD have agreed on an eXtensible Markup Language (XML) standard for sharing of disposal monitoring data (see also Section 3.5).

3.0 SITE MONITORING

The MPRSA establishes the need for including a monitoring program as part of the Site Management Plan. Site monitoring is conducted to ensure the environmental integrity of a disposal site and the areas surrounding the site and to verify compliance with the site designation criteria, any special management conditions, and with permit requirements. Monitoring programs should be flexible, cost effective, and based on scientifically sound procedures and methods to meet site-specific monitoring needs. The intent of the program is to provide the following:

- (1) Information indicating whether the disposal activities are occurring in compliance with the permit and site restrictions;
- (2) Information indicating the short-term and long-term fate of materials disposed of in the marine environment.
- (3) Information concerning the short-term and long-term environmental impacts of the disposal.

The main purpose of a disposal site monitoring program is to determine whether dredged material site management practices, including disposal operations at the site, need to be changed to avoid significant adverse impacts.

3.1 Baseline Monitoring. The results of investigations presented in the designation EIS (EPA, 1987) and subsequent surveys listed in Table 3 will serve as the main body of data for the monitoring of the impacts associated with the use of the Mobile ODMDS. A bathymetric survey will be conducted by the USACE or site user within three (3) months prior to project disposal for projects expected to exceed 50,000 cubic yards. Bathymetric surveys will be used to monitor the disposal mound to insure a navigation hazard is not produced, to assist in verification of material placement, to monitor bathymetry changes and trends and to insure that the site capacity is not exceeded, i.e., the mound does not exceed the site boundaries. Surveys will conform to the minimum performance standards for Corps of Engineers Hydrographic Surveys as described in the USACE Engineering Manual, EM1110-2-1003, Hydrographic Surveying dated November 30, 2013 [http://www.publications.usace.army.mil/Portals/76/Publications/EngineerManuals/EM_1110-2-1003.pdf] or updates. The number and length of transects required will be sufficient to encompass the release zone and a 500 foot-wide area around it. The surveys will be taken along lines spaced at 500-foot intervals or less. The minimum performance standards from Table 3-1 in Hydrographic Surveying shall be followed. Horizontal location of the survey lines and depth sounding points will be determined by an automated positioning system utilizing a differential global positioning system. The vertical datum will be referenced to prescribed NOAA Mean Lower Low Water (MLLW) datum. The horizontal datum should be referenced to the local State Plane Coordinate System (SPCS) for that area or in Geographical Coordinates (latitude-longitude). The horizontal reference datum should be the North American Datum of 1983 (NAD 83). No additional pre-disposal monitoring is required.

Mobile ODMDS SMMP

March 2015

Table 3. Surveys and Studies Conducted at or in the vicinity of the Mobile ODMDS

Survey/Study Title	Conducted By:	Date	Purpose	Results
<i>Analysis & Synthesis of Oceanic Conditions in the Mississippi Sound Offshore Region</i>	USACE	March 1984	Determine the direction and amount of sediment transport from a dredged material disposal site.	Circulation patterns within the site are controlled by astronomical tides, winds, and freshwater discharges.
Sediment Mapping	UGA Center for Applied Isotopes for EPA	2002	Characterization of bottom sediments using gamma spectrometry	- Baseline Survey
Mobile ODMDS Expansion Survey	USACE/EPA	May 2010	Collect physical, chemical and biological data on sediments and water	-Collected and analyzed 30 sediment and 10 water samples covering entire ODMDS
Mobile ODMDS Post Oil Spill Sediment Sampling	USACE	December 2010	Determine if any oil from the Deep Water Horizon Oil Spill has contaminated the sediments.	-Test results released February 2011 indicate there were no discernible changes in the sediment quality attributed to the Deepwater Horizon Oil Spill
Bathymetric Survey	USACE	Before and After Event	Monitor bathymetry changes	- Safe navigation depths have been maintained

3.2 Disposal Monitoring. For all disposal activities, an electronic tracking system (ETS) must be utilized. The ETS will provide surveillance of the transportation and disposal of dredged material. The ETS will be maintained and operated to continuously track the horizontal location and draft condition (accuracy \pm 0.1 foot) of the disposal vessel (i.e. hopper dredge or disposal scow) from the point of dredging to the disposal site and return to the point of dredging. Data shall be collected at least every 0.25 nautical mile or every 4 minutes during travel to and from the ODMDS and twelve seconds or every 30 feet of travel, while the hull status is open within the ODMDS. In addition to the continuous tracking data, the following trip information shall be electronically recorded for each disposal cycle:

- a. Load Number
- b. Disposal Vessel Name and Type (e.g. scow)
- c. Estimated volume of Load
- d. Description of Material Disposed
- e. Source of Dredged Material
- f. Date, Time and Location at Initiation and Completion of Disposal Event

It is expected that disposal monitoring will be conducted utilizing the Dredging Quality Management (DQM) system for Civil Works projects [see <http://dqm.usace.army.mil/Specifications/Index.aspx>], although other systems are acceptable. Disposal monitoring and ETS data will be reported to EPA Region 4 on a weekly basis (within one week of disposal) utilizing the eXtensible Markup Language (XML) specification and protocol per Section 3.5. EPA Region 4 and the USACE District shall be notified within 24 hours if disposal occurs outside of the ODMDS or specified disposal zone or if excessive leakage occurs.

3.3 Post Discharge Monitoring. The USACE or other site user will conduct a bathymetric survey consistent with the pre-disposal survey requirements within 30 days after disposal project completion. Surveys will not be required for projects less than 50,000 cubic yards. If a release zone is utilized and adhered to, the number and length of the transects required will be sufficient to encompass the release zone and a 500 foot wide area around it. Bathymetric surveys will be used to monitor the disposal mound to insure a navigation hazard is not produced, to assist in verification of material placement, to monitor bathymetry changes and trends and to insure that the site capacity is not exceeded, i.e., the mound does not exceed the site boundaries.

3.4 Disposal Effects Monitoring. Based on the type and volume of material disposed and impacts of concern, various monitoring surveys can be used to examine if and the direction the disposed dredged material is moving, and what environmental effect the material is having on the site and adjacent areas. At the current time, no nearby biological resources have been identified that are of concern for potential impact. The Mobile ODMDS is at least one nautical mile from all known fish havens, artificial reefs, and fishing areas. The site has been characterized as dispersive. This means that it is expected that material will be moved outside the site boundaries. It is also expected that this material will not move in distinct mounds, but instead will blend with the surrounding environment causing a progressive transition to sediments containing a higher percentage of silt and clay. Changes in sediment composition will likely alter the benthic community structure. However, based on previous benthic studies, it is unlikely that permanent or long-term adverse impacts will result due to changes in sediment composition. At a minimum, a Trend Assessment Survey (40 CFR 228.13) will be conducted approximately every ten years.

Mobile ODMDS SMMP March 2015

Table 4. Site Monitoring Strategies and Thresholds for Action

Goal	Technique	Sponsor	Rationale	Frequency	Threshold for Action	Management Options	
						Threshold Not Exceeded	Threshold Exceeded
Trend Assessment	Water and Sediment Quality, Benthic Community Analysis (40CFR228.13)	U.S. EPA	Periodically evaluate the impact of disposal on the marine environment (40CFR 228.9)	Approximately every 10 years	-Absence from the site of pollution sensitive biota -Progressive non-seasonal changes in water or sediment quality	Continue Monitoring per site specific SMMP	-Conduct Environmental Effects Monitoring or Advanced Environmental Effects Monitoring per site specific SMMP. -Review dredged material evaluation procedures
Insure Safe Navigation Depth & Monitor Bathymetric Trends	Bathymetry	Site User	Determine height of mound and any excessive mounding	Pre & Post disposal for projects greater than 50,000 cy	Mound height > -30 feet mean lower low water (MLLW) Mound height > -25 feet MLLW	Continue Monitoring	-Modify future disposal method/placement -Restrict disposal volumes - Physically level material
Compliance	Disposal Site Use Records in EPA Region 4's XML format	Site User	-Insure management requirements are being met -To assist in site monitoring	Report weekly during the project	Disposal records required by SMMP are not submitted or are incomplete	Continue Monitoring	-Restrict site use until requirements are met

3.5 Reporting and Data Formatting.

3.5.1 Project Initiation and Violation Reporting. The USACE or other site user shall notify EPA 15 days prior to the beginning of a dredging cycle or project disposal. The user is also required to notify the USACE and the EPA within 24 hours if a violation of the permit and/or contract conditions related to MPRSA Section 103 or SMMP requirements occur during disposal operations.

3.5.2 Disposal Monitoring Data. It is expected that disposal monitoring will be conducted utilizing the Dredge Quality Management (DQM) system for Civil Works projects [see <http://dqm.usace.army.mil/Specifications/Index.aspx>], although other systems are acceptable. Disposal monitoring data shall be provided to EPA Region 4 electronically on a weekly basis (within one week of disposal event). Data shall be provided per the EPA Region 4 XML format and delivered as an attachment to an email to DisposalData.R4@epa.gov. The XML format is available from EPA Region 4.

3.5.3 Post Disposal Summary Reports. A Post Disposal Summary Report shall be provided to EPA within 90 days after project completion. These reports should include: dredging project title; permit number and expiration date (if applicable); contract number; name of contractor(s) conducting the work, name and type of vessel(s) disposing material in the ODMDS; disposal timeframes for each vessel; volume disposed at the ODMDS (total paid and un paid *in situ* volume, and gross volume reported by dredging contractor in the disposal logs), number of loads to ODMDS, type of material disposed at the ODMDS; identification by load number of any misplaced material; dates of pre and post disposal bathymetric surveys of the ODMDS and a narrative discussing any violation(s) of the 103 concurrency and/or permit (if applicable). The narrative should include a description of the violation, indicate the time it occurred and when it was reported to the EPA and USACE, discuss the circumstances surrounding the violation, and identify specific measures taken to prevent reoccurrence. The Post Disposal Summary Report should be accompanied by the bathymetry survey results (plot and X,Y,Z ASCII data file), a summary scatter plot of all disposal start locations, and a summary table of the trip information required by Section 3.2 with the exception of the disposal completion data. If all data is provided in the required XML format, scatter plots and summary tables will not be necessary.

3.5.4 Environmental Monitoring. Disposal effects monitoring shall be coordinated with and be provided to appropriate federal and state agencies as specified in the site specific SMMP to be developed. Reports prepared by or for EPA will be posted to EPA's website at: <http://www.epa.gov/region4/water/oceans/sites.html> or alternative EPA website.

4.0 MODIFICATION OF THE MOBILE ODMDS SMMP

This SMMP will be effective for four years from the date of signature. It is expected that EPA will expand the Mobile ODMDS within four years and a new SMMP will be developed for the

expanded ODMDS and supersede this SMMP.

5.0 REFERENCES

ANAMAR Environmental Consulting, Inc. 2010. Final Report Mobile ODMDS Designation Survey Mobile, AL. W91278-08-D-0053. Project 09-0011, May 2010.

Center for Applied Isotope Studies, 1996. Postdisposal Areal Mapping of Sediment Chemistry at the Mobile, Mississippi ODMDS. EPA Contract No. 68-C2-0134, April 8, 1996.

EA Engineering, Science, and Technology, Inc. Draft Report Post-Oil Spill Surface Sediment Evaluation: Mobile Harbor Federal Navigation Channels Mobile, AL. February 2011.

Fredette, Thomas J., Nelson, David A., Clausner, James E., and Anders, Fred J. 1990. *Guidelines for Physical and Biological Monitoring of Aquatic Dredged Material Disposal Sites*, Technical Report D-90-12, US Army Engineer Waterways Experiment Station, Vicksburg, MS.

NMFS. (2003). Regional Biological Opinion for Dredging of Gulf of Mexico Navigation Channels and Sand Mining ("Borrow") Areas Using Hopper Dredging by USACE Galveston, New Orleans, Mobile, and Jacksonville Districts (Consultation Number F/SER/2000/01287), NOAA, NMFS, Southeast Regional Office, Protected Resources Division, St. Petersburg, FL, 121 pp.

Pequegnat, Willis E., Gallaway, Benny J., and Wright, Thomas D., 1990. *Revised Procedural Guide for Designation Surveys of Ocean Dredged Material Disposal Sites*, Technical Report D-90-8, US Army Engineer Waterways Experiment Station, Vicksburg, MS.

U.S. Army Corps of Engineers (COE). 2002. *Engineering & Design - Hydrographic Surveying*. Engineering Manual 1110-2-1003, Department of the Army, Washington D.C.

U.S. Army Corps of Engineers Mobile District (USACE). 2014. *Working Draft Environmental Assessment for the Proposed Expansion Mobile Section 102 ODMDS* November 2014.

U.S. Environmental Protection Agency, 1987. *Final Environmental Impact Statement for the Pensacola, FL, Mobile, AL, and Gulfport, MS Dredged Material Disposal Site Designation*. EPA Region 4, January 27, 1987.

U.S. Environmental Protection Agency and U.S. Army Corps of Engineers, 1991. *Evaluation of Dredged Material Proposed for Ocean Disposal (Testing Manual)*, February 1991. Prepared by Environmental Protection Agency Office of Marine and Estuarine Protection and Department of Army United States Army Corps of Engineers under EPA Contract No. 68-C8-0105.

Mobile ODMDS SMMP

March 2015

U.S. Environmental Protection Agency and U.S. Army Corps of Engineers, 1996. *Guidance Document for Development of Site Management Plans for Ocean Dredged Material Disposal Sites*, February 1996. Prepared by Environmental Protection Agency Office of Water and Department of Army United States Army Corps of Engineers.

U.S. Environmental Protection Agency, Region 4, 2007. *Dredged Material Ocean Disposal Verification System - Specifications for Data Submittal*, revised October 30, 2007. Prepared by Wetlands and Marine Regulatory Section.

U.S. Environmental Protection Agency Region 4 and U.S. Army Corps of Engineers South Atlantic Division, 2008. *Southeast Regional Implementation Manual Requirements and Procedures for Evaluation of the Ocean Disposal of Dredged Material in Southeastern Atlantic and Gulf Coastal Waters*, August 2008.

This page intentionally left blank

APPENDIX A

WATER COLUMN EVALUATIONS
NUMERICAL MODEL (STFATE) INPUT
PARAMETERS

This page intentionally left blank

Water Column Evaluations
Numerical Model (STFATE) Input Parameters
Mobile ODMDS

SITE DESCRIPTION

Parameter	Value	Units
Number of Grid Points (left to right)	80	
Number of Grid Points (top to bottom)	80	
Spacing Between Grid Points (left to right)	250	ft
Spacing Between Grid Points (top to bottom)	250	ft
Constant Water Depth	46	ft
Roughness Height at Bottom of Disposal Site	.005 ¹	ft
Slope of Bottom in X-Direction	0	Deg.
Slope of Bottom in Z-Direction	0	Deg.
Number of Points in Ambient Density Profile Point ¹	3	
Ambient Density at Depth = 3 ft	1.0206	g/cc
Ambient Density at Depth = 26 ft	1.0206	g/cc
Ambient Density at Depth = 46 ft	1.0207	g/cc

¹ from EPA Mobile ODMDS Designation Survey Report (2009) for Zone A

AMBIENT VELOCITY DATA

Parameter	Value	Units
Profile ²	2-Point at constant depth	
X-Direction Velocity = 11 feet	0.12	ft/sec
Z-Direction Velocity = 11 feet	-0.41	ft/sec
X-Direction Velocity = 33 feet	0.22	ft/sec
Z-Direction Velocity = 33 feet	-0.37	ft/sec

² from EPA Mobile ODMDS Designation Survey Report (2009)

DISPOSAL OPERATION DATA

Parameter	Value	Units
Location of Disposal Point from Top of Grid	10,000	ft
Location of Disposal Point from Left Edge of Grid	10,000	ft
Dumping Over Depression	0	

INPUT, EXECUTION AND OUTPUT


Parameter	Value	Units
Location of the Upper Left Corner of the Disposal Site - Distance from Top Edge	5,455	ft
Location of the Upper Left Corner of the Disposal Site - Distance from Left Edge	3,414	ft
Location of the Lower Right Corner of the Disposal Site - Distance from Top Edge	14,545	ft
Location of the Lower Right Corner of the Disposal Site - Distance from Left Edge	16,586	ft
Duration of Simulation	14,400	sec
Long Term Time Step	600	sec

COEFFICIENTS

Parameter	Keyword	Value
Settling Coefficient	BETA	0.000 ¹
Apparant Mass Coefficient	CM	1.000 ¹
Drag Coefficient	CD	0.500 ¹
Form Drag for Collapsing Cloud	CDRAG	1.000 ¹
Skin Friction for Collapsing Cloud	CFRIC	0.010 ¹
Drag for an Ellipsoidal Wedge	CD3	0.100 ¹
Drag for a Plate	CD4	1.000 ¹
Friction Between Cloud and Bottom	FRICTN	0.010 ¹
4/3 Law Horizontal Diffusion Dissipation Factor	ALAMDA	0.001 ¹
Unstratified Water Vertical Diffusion Coefficient	AKYO	Pritchard Expression
Cloud/Ambient Density Gradient Ratio	GAMA	0.250 ¹
Turbulent Thermal Entrainment	ALPHAO	0.235 ¹
Entrainment in Collapse	ALPHAC	0.100 ¹
Stripping Factor	CSTRIP	0.003 ¹

¹ Model Default Value

Mobile ODMDS STFATE Input Parameters



Mobile ODMDS Background Water Concentration.	
Chemicals of Concern	Background Concentration Levels (µg/l)
Arsenic	1.66 ¹
Cadmium	0.01 ¹
Chromium (VI)	0.75 ¹
Copper	1.11 ¹
Lead	0.75 ¹
Mercury	0.10 ^{1,3}
Nickel	0.75 ¹
Selenium	0.23 ¹
Silver	0.005 ¹
Zinc	3.78 ¹
Cyanide	
Tributyltin (TBT)	0.025 ^{2,3}
Aldrin	0.005 ^{1,3}
Chlordane	0.10 ^{1,3}
DDT	0.05 ^{1,3}
Dieldrin	0.005 ^{1,3}
alpha - Endosulfan	0.005 ^{1,3}
beta - Endosulfan	0.005 ^{1,3}
Endrin	0.005 ^{1,3}
gamma-BHC (Lindane)	0.005 ^{1,3}
Heptachlor	0.005 ^{1,3}
Heptachlor Epoxide	0.005 ^{1,3}
Toxaphene	.25 ^{1,3}
Pentachlorophenol	5.0 ^{2,3}

¹ Mobile ODMDS Site Designation Study (2010)

² Pensacola ODMDS Trend Assessment Study (2013)

³ Analyte not detected. Value based on one half the reporting limit.

APPENDIX B
TEMPLATE
For
MPRSA Section 103 Permits

This page left blank intentionally.

**TEMPLATE
GENERIC SPECIAL CONDITIONS
FOR MPRSA SECTION 103 PERMITS
Mobile-North ODMS**

I. DISPOSAL OPERATIONS

A. For this permit, the term disposal operations shall mean: navigation of any vessel used in disposal of operations, transportation of dredged material from the dredging site to the Mobile ODMS, proper disposal of dredged material at the disposal area within the Mobile ODMS, and transportation of the hopper dredge or disposal barge or scow back to the dredging site.

B. The Mobile ODMS is defined as the polygon with corner coordinates as follows:

Site Coordinates

Geographic (NAD 27)	
30°10'00"N	88°07'42"W
30°10'24"N	88°05'12"W
30°09'24"N	88°04'42"W
30°08'30"N	88°05'12"W
30°08'30"N	88°08'12"W

C. No more than [NUMBER] cubic yards of dredged material excavated at the location defined in [REFERENCE LOCATION IN PERMIT] are authorized for disposal at the Mobile ODMS.

D. The permittee shall use an electronic positioning system to navigate to and from the Mobile ODMS. For this section of the permit, the electronic positioning system will be as per the DQM specifications. If the electronic positioning system fails or navigation problems are detected, all disposal operations shall cease until the failure or navigation problems are corrected.

E. The permittee shall certify the accuracy of the electronic positioning system proposed for use during disposal operations at the Mobile ODMS. The certification shall be accomplished by providing current certification documentation from the National DQM Program for scow and hopper dredge

instrumentation systems. The National DQM certification is valid for one year from the date of certification.

F. The permittee shall not allow any water or dredged material placed in a hopper dredge or disposal barge or scow to flow over the sides or leak from such vessels during transportation to the Mobile ODMS.

G. A disposal operations inspector and/or captain of any tugboat, hopper dredge or other vessel used to transport dredged material to the Mobile ODMS shall insure compliance with disposal operation conditions defined in this permit.

1. If the disposal operations inspector or the captain detects a violation, he shall report the violation to the permittee immediately.

2. The permittee shall contact the U.S. Army Corps of Engineers, Mobile District's Regulatory Branch (251) 690-2658 and EPA Region 4 at (404) 562-9395 to report the violation within twenty-four (24) hours after the violation occurs. A complete written explanation of any permit violation shall be included in the post-dredging report.

H. When dredged material is disposed, no portion of the hopper dredge or disposal barge or scow shall be outside of the boundaries of the Mobile ODMS as defined in Special Condition B. Additionally, disposal shall occur within a specified disposal zone defined as [DEFINE COORDINATES AND SIZE OF DISPOSAL ZONE]. Disposal shall not occur closer than 1,300 feet to any oil and gas rigs that may be present within the site boundaries.

I. The permittee shall use an automated disposal verification system that is certified by the National DQM program to continuously track the horizontal location and draft condition of the disposal vessel (hopper dredge or disposal barge or scow) to and from the Mobile ODMS. This real-time information is available on-line to the Mobile District and will be provided to the EPA Region 4 via email using the eXtensible Markup Language (XML) specification and protocol. Data shall be provided per the EPA Region 4 XML format and delivered as an attachment to an email to DisposalData.R4@epa.gov. The XML format is available from EPA Region 4.

J. The permittee shall conduct a bathymetric survey of the Mobile ODMS within 30 days following project completion.

1. The number and length of the survey transects shall be sufficient to encompass the defined disposal zone within the Mobile ODMS and a 500 foot wide area around the disposal zone. The transects shall be spaced at 500-foot intervals or less with a depth recording density of 20 to 70 feet.

2. Vertical accuracy of the survey shall be ± 0.1 feet. Horizontal location of the survey lines and depth sounding points will be determined by an automated positioning system utilizing either microwave line of site system or differential global positioning system. The vertical datum will be referenced to prescribed NOAA Mean Lower Low Water (MLLW) datum. MLLW is 1.8 feet below NGVD 1929. The horizontal datum will be Alabama State Plane (zone 2301 MS East) or Geographic (NAD 1983). State Plane coordinates shall be reported to the nearest 0.10 foot and latitude and longitude coordinates shall be reported as degrees and decimal minutes to the nearest 0.01 minutes.

K. The permittee has read and agrees to assure that they are in compliance with the requirements of the Mobile ODMS Site Management and Monitoring Plan.

II. REPORTING REQUIREMENTS

A. The permittee shall send the U.S. Army Corps of Engineers, Mobile District's Regulatory Branch and EPA Region 4's Wetlands, Oceans and Streams Protection Branch (61 Forsyth Street, Atlanta, GA 30303) a notification of commencement of work at least fifteen (15) days before initiation of any dredging operations authorized by this permit.

B. The permittee shall submit to the U.S. Army Corps of Engineers weekly disposal monitoring reports. These reports shall contain the information described in Special Condition I.1.

C. The permittee shall develop and send one (1) copy of the disposal summary report to the Mobile District's Regulatory Branch and one (1) copy of the disposal summary report to EPA Region 4 documenting compliance with all general and special conditions defined in this permit. The disposal summary report shall be sent within 90 days after completion of the disposal operations authorized by this permit. The disposal summary report shall include the following information:

1. The report shall indicate whether all general and special permit conditions were met. Any violations of the permit shall be explained in detail.

2. The disposal summary report shall include the following information: USACE permit number, actual start date and completion date of dredging and disposal operations, total cubic yards disposed at the Mobile ODMS, locations of disposal events, and post disposal bathymetric survey results (in hard and electronic formats).

This page intentionally left blank

APPENDIX C

TYPICAL CONTRACT LANGUAGE
FOR IMPEMENTING THE
MOBILE ODMDS SMMP REQUIREMENTS

This page intentionally left blank

TYPICAL CONTRACT LANGUAGE FOR IMPEMENTING SMMP
REQUIREMENTS

3.3 DISPOSAL OF DREDGED MATERIAL

3.3.1 General

All material dredged shall be transported to and deposited in the disposal area(s) designated on the drawings. The approximate maximum and average distance to which the material will have to be transported are as follows:

Disposal Area	Maximum Distance Statute Miles	Average Distance Statute Miles
---------------	-----------------------------------	-----------------------------------

Mobile ODMDs

[INSERT DISPOSAL AREA 2]	[XX miles]	[XX miles]
-----------------------------	------------	------------

[IF MATERIAL FROM DIFFERENT PROJECT AREAS GO TO DIFFERENT
DISPOSAL AREAS, IT COULD BE SPECIFIED HERE]

3.3.2 Ocean Disposal Notification

- a. The contractor shall notify EPA Region 4 's Wetlands, Oceans and Streams Protection Branch (61 Forsyth Street, Atlanta, GA 30303) at least 15 calendar days and the local Coast Guard Captain of the Port at least 5 calendar days prior to the first ocean disposal. The notification will be by certified mail with a copy to the Contracting Officer. The following information shall be included in the notification:
 - (1) Project designation; Corps of Engineers' Contracting Officer's name and contract number; and, the Contractor's name, address, and telephone number.
 - (2) Port of departure.
 - (3) Location of ocean disposal area (and disposal zone if required).
 - (4) Schedule for ocean disposal, giving date and time proposed for first ocean disposal.

3.3.3 Ocean Dredged Material Disposal Sites (ODMDs)

The material excavated shall be transported to and deposited in the Mobile ODMDs shown on the drawings. When dredged material is disposed, no portion of the hopper dredge or disposal barge or scow shall be outside of the boundaries of the Mobile ODMDs as shown on the drawings. Additionally, disposal shall be initiated within the disposal release zone defined by the following coordinates:

C-1

[insert coordinates for appropriate release zone]

Vertices	Geographic NAD 83		State Plane NAD 83	
Center				
North				
West				
South				
East				

3.3.4 Logs

The Contractor shall keep a log for each load placed in the Mobile ODMDS. The log entry for each load shall include:

- Load Number
- Disposal Vessel Name and Type (e.g. scow)
- Estimated volume of Load
- Description of Material Disposed
- Source of Dredged Material
- Date, Time and Location at Initiation and Completion of Disposal Event

At the completion of dredging and at any time upon request, the log(s) shall be submitted in paper and electronic formats to the Contracting Officer for forwarding to the appropriate agencies.

3.3.5 Overflow, Spills and Leaks

Water and dredged materials shall not be permitted to overflow or spill out of barges, hopper dredges, or dump scows during transport to the disposal site(s). Failure to repair leaks or change the method of operation which is resulting in overflow or spillage will result in suspension of dredging operations and require prompt repair or change of operation to prevent overflow or spillage as a prerequisite to the resumption of dredging.

3.3.6 Electronic Tracking System (ETS) for Ocean Disposal Vessels

The Contractor shall furnish an ETS for surveillance of the movement and disposition of dredged material during dredging and ocean disposal. This ETS shall be established, operated and maintained by the Contractor to continuously track in real-time the horizontal location and draft condition of the disposal vessel (hopper dredge or disposal barge or scow) for the entire dredging cycle, including dredging area and disposal area. The ETS shall be capable of displaying and recording in real-time the disposal vessel's draft and location.

[FOR DQM PROJECTS]


See: <http://dqm.usace.army.mil/Specifications/Index.aspx>


For scows, the monitoring profile, TDS profile or Ullage profile shall be used.

3.3.6.1 Misplaced Materials

Materials deposited outside of the disposal zone specified in 3.3.3 will be classified as misplaced material and will result in a suspension of dredging operations. Redredging of such materials will be required as a prerequisite to the resumption of dredging unless the Contracting Officer, at his discretion, determines that redredging of such material is not practical. If redredging of such material is not required then the quantity of such misplaced material shall be deducted from the Contractor's pay quantity. If the quantity for each misplaced load to be deducted cannot initially be agreed to by both the Contractor and Contracting Officer, then an average hopper/scow load quantity for the entire contract will be used in the determination. Misplaced loads may also be subject to penalty under the Marine, Protection, Research and Sanctuaries Act. Materials deposited above the maximum indicated elevation or outside of the disposal area template shown will require the redredging or removal of such materials at the Contractor's expense. In addition, the Contractor must notify the Contracting Officer and the Environmental Protection Agency Region 4's Wetlands, Oceans and Streams Protection Branch (61 Forsyth Street, Atlanta, GA 30303) within 24 hours of a misplaced dump or any other violation of the Site Management and Monitoring Plan for the Mobile ODMDS. Corrective actions must be implemented by the next dump and the Contracting Officer must be informed of actions taken.

Sea Turtle Deflector Specification





Turbidity Monitoring Report

TURBIDITY MONITORING REPORT
IRVINGTON SITE OFFICE
CONTRACT NUMBER:

=====

DATE: _____ REPORT NO. # _____

TIME OF DAY SAMPLE TAKEN: _____ hrs

WEATHER CONDITIONS: _____

DIRECTION OF WATER FLOW: _____ TIDAL STAGE: _____

WATER TEMP: _____ ° WIND SPEED _____ (MPH)

WAVE CONDITIONS (CALM, CHOPPY, ROUGH): _____

=====

TURBIDITY MEASUREMENT TAKEN APPROX. _____ FT. FROM DREDGE

TURBIDITY MEASUREMENT TAKEN APPROX. _____ FT. FROM DISCHARGE

DISCHARGE IS APPROX. _____ FT FROM DREDGE WITH AZIMUTH _____ °

DEPTH AT DREDGE: _____ FT. DEPTH AT DISCHARGE: _____ FT.

SURFACE TURBIDITY AT DREDGE: _____ NTU

MID-DEPTH TURBIDITY AT DREDGE: _____ NTU

SURFACE TURBIDITY AT DISCHARGE: _____ NTU D/A #: 11, SECTION 1a

MID-DEPTH TURBIDITY AT DISCHARGE: _____ NTU

=====

BACKGROUND TURBIDITY TAKEN APPROX. _____ FT FROM DREDGE

AZIMUTH FROM DREDGE: _____ °

WATER DEPTH: _____ FT

SURFACE TURBIDITY: _____ NTU MID-DEPTH TURBIDITY: _____ NTU

=====

REMARKS (VISIBLE PLUME, ETC.): Sea too rough for samples _____

INSPECTOR: _____

Standard Manatee Conditions

STANDARD MANATEE CONSTRUCTION CONDITIONS
April 2003

- a. The lessee/grantee shall instruct all personnel associated with the project of the potential presence of manatees and the need to avoid collisions with manatees. All construction personnel are responsible for observing water-related activities for the presence of manatees.
- b. The lessee/grantee shall advise all construction personnel that there are civil and criminal penalties for harming, harassing, or killing manatees which are protected under the Marine Mammal Protection Act of 1972 and the Endangered Species Act of 1973.
- c. Siltation barriers shall be made of material in which manatees cannot become entangled, are properly secured, and are regularly monitored to avoid manatee entrapment. Barriers must not block manatee entry to, or exit from, essential habitat.
- d. All vessels associated with the construction project shall operate at "no wake/idle" speeds at all times while in the construction area and while in water where the draft of the vessel provides less than a four-foot clearance from the bottom. All vessels will follow routes of deep water whenever possible.
- e. If manatees are seen within 100 yards of the active daily construction/dredging operation or vessel movement, all appropriate precautions shall be implemented to ensure their protection. These precautions shall include the operation of all moving equipment no closer than 50 feet of a manatee. Operation of any equipment closer than 50 feet to a manatee shall necessitate immediate shutdown of that equipment. Activities will not resume until the manatee(s) has departed the project area of its own volition.
- f. Any collision with and/or injury to a manatee shall be reported immediately to Mr. Paul Nicaise at (228) 493-6631 of the U.S. Fish and Wildlife Service in Jackson, Mississippi.
- g. Temporary signs concerning the manatees shall be posted prior to and during all construction/dredging activities. All signs are to be removed by the lessee/grantee upon completion of the project. A sign measuring at least 3 ft. by 4 ft. which reads *Caution: Manatee Area* will be posted in a location prominently visible to water related construction crews. A second sign should be posted if vessels are associated with the construction, and should be placed visible to the vessel operator. The second sign should be at least 8'.6" by 11" which reads *Caution: Manatee Habitat. Idle speed is required if operating a vessel #7 the construction area. All equipment must be shutdown if a manatee comes within 50 feet of operation. Any collision with and/or injury to a manatee shall be reported immediately to the U.S. Fish and Wildlife Service in Jackson, Mississippi (228-493-6631).*

IDIQ Contract for Rental of Hopper Dredge
With Attendant Plant and Operators for
Maintenance Dredging in Alabama, Mississippi, Florida

W91278-17-B-0002



SECTION 35 20 23.23

NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM HOPPER DREDGE 4/30/15

PART 1 GENERAL

1.1 DESCRIPTION

The work under this contract requires use of the National Dredging Quality Management Program (DQM) to monitor the dredge's status at all times during the contract and manage data history.

This performance-based specification section identifies the minimum required output and precision and instrumentation requirements. The requirements may be satisfied using equipment and technical procedures selected by the Contractor.

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office responsible for review of the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00, "SUBMITTAL PROCEDURES":

SD-01, Preconstruction Submittals

Dredge Plant Instrumentation Plan Revisions or Addendum; G, SAM-OP-J

SD-06, Test Reports

Data Appropriately Archived e-mail, section 3.2.10; G, SAM-OP-GW

SD-07, Certificates

Letter of National Dredging Quality Management Program Certification; G, SAM-OP-GW

1.3 PAYMENT

No separate payment shall be made for installation, operation and maintenance of the DQM certified system as specified herein for the duration of the dredging operations; all costs in connection therewith shall be considered a subsidiary

obligation of the Contractor and covered under the contract unit prices for dredging in the bidding schedule.

1.4 NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM CERTIFICATION

The Contractor is required to have a current certification from the DQM for the hopper dredge instrumentation system to be used under this contract. Criteria for certification shall be based on the most recent specification posted on the DQM website (<http://dqm.usace.army.mil/Specifications/Index.aspx>). Compliance with these criteria shall be verified by annual on-site quality assurance (QA) checks conducted by DQM Support Center Data Acquisition and Analysis Team, and by periodic review of the transmitted data. DQM Certification is valid for one year from the date of the annual QA checks. Certification is contingent upon the system's ability to continuously meet the performance requirements as outlined in sections 3.3 and 3.5. If issues with data quality are not corrected within 48 hours, the system certification shall be revoked and additional QA checks by the Data Acquisition Team may be necessary.

Annual DQM Certification shall be based on:

- A series of QA checks as described in Section 3.4 “Compliance Quality Assurance Checks”
- Verification of data acquisition and transfer (Section 3.3)
- Review of the Dredge Plant Instrumentation Plan (DPIP) as described in Section 1.5

The dredging contractor shall have personnel who are familiar with the system instrumentation and who have the ability to recalibrate the sensors on site during the QA process. The dredging contractor shall coordinate pickup times and locations and provide transportation to and from any platform with a DQM system to team personnel in a timely manner. As a general rule, Data Acquisition and Analysis Team personnel will come with PPE consisting of hardhats, steel toe boots, and life jackets. If additional safety equipment is needed, such as eye protection, safety harnesses, work gloves or personal location beacons, these items shall be provided to the team while on site. It is the dredging contractor's obligation to inform the QA team if the location designated for the QA checks has any site specific safety concerns prior to their arrival on site.

The owner or operator of the dredge shall contact the DQM at DQM-AnnualQA@rpsgroup.com on an annual basis, or at least three weeks prior to certification expiration, to schedule QA checks for renewal. This notification is meant to make the Data Acquisition Team aware of a target date for the annual QA checks for the dredge. At least one week prior to the target date, the dredging contractor shall contact the Data Acquisition team and verbally coordinate a specific date and location. The contractor shall then follow-up this conversation with a written e-mail confirmation. The owner/operator shall coordinate the QA

checks with all local authorities, including but not limited to, the local USACE contracting officer.

Re-certification is required for any yard work which produces modification to displacement (i.e. change in dredge lines, repositioning or repainting hull marks), modification to bin volume (change in bin dimensions or addition or subtraction of structure) or changes in sensor type or location; these changes shall be reported in the sensor log section of the DPIP. A system does not have to be transmitting data between jobs, however in order to retain its certification during this period, the system sensors or hardware should not be disconnected or removed from the dredge. If the system is powered down, calibration coefficients shall be retained.

1.5 DREDGE PLANT INSTRUMENTATION PLAN (DPIP)

The Contractor shall have a digital copy of the DPIP on file with the National DQM Support Center. The Contractor shall also maintain a copy of the DPIP on the dredge while working on site which is easily accessible to government personnel at all times. This document shall describe the sensors used, configuration of the system, how sensor data will be collected, how quality control on the data will be performed, and how sensors/data reporting equipment will be calibrated and repaired if they fail. A description of computed dredge specific data and how the sensor data will be transmitted to the DQM Database will also be included. The Contractor shall submit to the DQM Support Center any addendum or modifications made to the plan, subsequent to its original submission, prior to start of work.

The DPIP shall include the following as a minimum:

(DPIP must have table of contents in the following order and tabs separating sections)

Cover Page	Dredge Name Date Photo of plant
------------	---------------------------------------

Table of Contents

New page	Dredge Contacts Dredging Company <ul style="list-style-type: none">• Dredge Point of Contact on-site• Phone Number• e-mail address Dredge Monitoring System Provider <ul style="list-style-type: none">• Dredge Monitoring System Point of Contact• Telephone Number• e-mail address
----------	--

New page

Table of dredge characteristics

- Dimensions of dredge
- Dimensions of hopper
- Method of disposal
- Capacity
- Minimum and maximum digging depth
- Minimum and maximum drafts and displacements
- RPM and velocity range
- ID of suction and discharge pipes

New page

Sensor data collection method

- Any averaging
- Route from sensors to DQM computer
- Internet connection type and provider

Sensor descriptions, locations and calibration methods

- Positioning system
 - Brand name, model and accuracy
 - Any calculation done external to the instrumentation
 - Sensor location with referenced dimensions
- Dredge heading instrumentation
 - Brand name, model and accuracy
 - Any calculation done external to the instrumentation
- Hull status
 - Brand name, model and accuracy
 - Any calculation done external to the instrumentation
 - Sensor location with referenced dimensions
 - Calibration procedure
- Draft
 - Brand name, model and accuracy
 - Any calculation done external to the instrumentation
 - Sensor location with referenced dimensions
 - Calibration procedure
- Ullage
 - Brand name, model and accuracy
 - Any calculation done external to the instrumentation
 - Sensor location with referenced dimensions
 - Calibration procedure
- Dragarm depths
 - Brand name, model and accuracy
 - Any calculation done external to the instrumentation
 - Sensor location with referenced dimensions
 - Calibration procedure
- Density
 - Brand name, model and accuracy
 - Any calculation done external to the instrumentation

- Sensor location with referenced dimensions including pipe diameter
 - Calibration procedure
- Velocity
 - Brand name, model and accuracy
 - Any calculation done external to the instrumentation
 - Sensor location with referenced dimensions including pipe diameter
 - Calibration procedure
- Pump RPM
 - Brand name, model and accuracy
 - Any calculation done external to the instrumentation
 - Sensor location with referenced dimensions
 - Calibration procedure
- Pumpout (if instrumented)
 - Brand name, model and accuracy
 - Any calculation done external to the instrumentation
 - Sensor location with referenced dimensions
 - Calibration procedure

Calculated Parameters

- Displacement:
 - Method used by Contractor to calculate displacement
 - Tables listing (fresh and salt water) displacement as a function of draft in feet and tenths of feet
- Hopper Volume:
 - Method used by Contractor to calculate hopper volume
 - Table listing the hopper volume as a function of hopper ullage in feet and tenths of feet
 - Description of datum for ullage sounding measurements
- Drag Head Position
 - Method used by Contractor to calculate drag head position
- Load number
 - Method used to increment load number

Quality Control

- Description of Contractors quality control process
- Log of sensor calibrations, repairs and modifications

Appendices

- Hydrostatic curves
- Certified Displacement and Volume Tables
- Legible Dimensioned Drawings of the Dredge with units in feet
 - A typical plan of the dredge showing:
 - Overall dredge and hopper dimensions

- Locations of required sensors referenced to uniform longitudinal and transverse reference points
- Distance between the draft sensors
- Distance between the ullage sensors
- Dimensions of dragarm
- A profile view of the dredge showing:
 - Overall dredge and hopper dimensions
 - Distance between draft sensors and draftmarks
 - Locations of required sensors referenced to uniform vertical and longitudinal reference points
- Typical vessel cross section through the hopper
- Sensor manuals and certificates of calibration

Any changes to the computation methods shall be approved by the National Dredging Quality Management Program Support Center prior to their implementation.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 REQUIREMENTS FOR REPORTED DATA

The Contractor shall provide, operate and maintain all hardware and software to meet these specifications. The Contractor shall be responsible for replacement, repair and calibration of sensors and other necessary data acquisition equipment needed to supply the required data.

Repairs shall be completed within 48 hours of any sensor failure. Upon completion of a repair, replacement, installation, modification or calibration the Contractor shall notify the Contracting Office's Representative (COR). The COR may request re-calibration of sensors or other hardware components at any time during the contract as deemed necessary.

The Contractor shall keep a log of sensor repair, replacement, installation, modification and calibration in the dredge's onboard copy of the DPIP. The log shall contain a three-year history of sensor maintenance to include: the time of sensor failures (and subsequent repairs), the time and results of sensor calibrations, the time of sensor replacements, and the time that backup sensor systems are initiated to provide required data. It shall also contain the name of the person responsible for the sensor work.

Sensors installed shall be capable of collecting parameters within specified accuracies and resolutions indicated in the following subsections.

Reported sensor values for ullage, draft and draghead depth should represent a weighted average with the highest and lowest values not included in the calculated average for the given interval. This information should be documented in the DPIP sections that say “Calculations done external to the instrumentation”.

3.1.1 Date and Time

The date and time shall be reported to the nearest second and referenced to UTC time based on a 24 hour format; mm/dd/yyyy hh:mm:ss. The reported time shall be the time reported by the GPS in the NMEA string.

3.1.2 Load Number

A load number shall document the end of a disposal event. Load numbering will begin at number 1 at the start of the contract, and will be incremented by 1 at the completion of each disposal event or emptying of the hopper. Whenever possible, the load number shall be calculated off of the sensors aboard the dredge, and shall be a mathematically repeatable routine. Efforts shall be made to include logic that avoids false load number increments while also not allowing the routine to miss any disposal event. If manual incrementing of the load number is in place, extra attention shall be paid to this value in the contractor’s quality control process (section 3.5).

3.1.3 Horizontal Positioning

All locations shall be obtained using a Positioning System operating with a minimum accuracy level of 1 to 3 meters horizontal Circular Error Probable (CEP). Positions shall be reported as Latitude/Longitude WGS 84 in decimal degrees. West Longitude and South Latitude values are reported as negative.

3.1.3.1 Vessel Horizontal Positioning

Geographic coordinates of the vessel as indicated by the location of the GPS antenna.

3.1.3.2 Draghead Horizontal Positioning

Geographic coordinates of the heel on centerline of the draghead(s). Any offset calculations from the GPS antenna should be described in the DPIP.

3.1.4 Hull status

Open/closed status of the hopper dredge, corresponding to the split/non-split condition of a split hull hopper dredge shall be monitored. For dredges with hopper doors, the status of a single door that is the first opened during normal disposal operations may be monitored. An “OPEN” value shall indicate the

hopper door is open, or in the case of split hull dredges, the hull is split. A “CLOSED” value indicates the hopper doors are closed, or in the case of split hull dredges, the hull is not split. *For this contract, hull status shall register closed prior to leaving the disposal area.*

3.1.5 Dredge Course

Dredge course-over-ground (COG) shall be provided using industry standard equipment. The Contractor shall provide dredge course over ground to the nearest whole degree with values from 000 (true north) to 359 degrees referenced to a clockwise positive direction convention.

3.1.6 Dredge Speed

Dredge speed-over-ground shall be provided in knots using industry standard equipment with a minimum accuracy of 1 knot and resolution to the nearest 0.1 knot.

3.1.7 Dredge Heading

Dredge heading shall be provided using industry standard equipment. The dredge heading shall be accurate to within 5 degrees and reported to the nearest whole degree, with values from 000 (true north) to 359 degrees referenced to a clockwise positive direction convention.

3.1.8 Tide

Tide data shall be obtained using appropriate equipment to give the water level with an accuracy of ± 0.1 feet and a resolution of 0.01 feet. Tide values above project datum described in the dredging specification shall be entered with a positive sign, those below with a negative sign.

3.1.9 Draft

All reported draft measurements shall be in feet, tenths and hundredths with an accuracy of ± 0.1 foot relative to observed physical draft readings. The measurements shall be reported at a resolution of two decimal places (hundredths of a foot). Reported forward draft value shall be equal to the sum of the visual forward port and starboard draft mark readings divided by 2. Reported aft draft value shall be equal to the sum of the visual aft port and starboard draft mark readings divided by 2. Forward draft, aft draft and average draft will be reported. Sensors shall be placed at an optimum location on the vessel to be reflective of observed physical draft mark readings at any trim or list. Minimum accuracies are conditional to relatively calm water. The sensor value reported shall be an average of at least 10 samples per event, remove at least one maximum value and one minimum value, and average the minimum 8 remaining values. When

average draft is calculated for the purpose of determining displacement, significant digits for average draft shall be maintained such that if forward draft was 0.15 and aft draft was 0.1 then the average draft would be 0.125.

3.1.10 Hopper Ullage Sounding

All reported ullage soundings shall be in feet, tenths and hundredths with an accuracy of ± 0.1 foot with respect to the combing, and be representative of the forward and aft extents of the hopper as close to centerline as is possible. The measurements shall be reported at a resolution of two decimal places (hundredths of a foot). Forward ullage and aft ullage soundings will be reported. Sensors should be mounted so as to avoid discharge flume turbulence, foam and any structure that could produce sidelobe errors. If sensors must be offset from centerline of the hopper they should be offset to opposite sides of the vessel. If more than one fore or one aft sensor is used, they shall be placed near the corners of the hopper and the average value of the fore sensors and the average value of the aft sensors shall be reported. The sensor value reported shall be an average of at least 10 samples per event, remove at least one maximum value and one minimum value, and average the minimum 8 remaining values. When average ullage is calculated for the purpose of determining hopper volume, significant digits for average ullage shall be maintained such that if forward ullage was 0.15 and aft ullage was 0.1 then the average ullage would be 0.125.

3.1.11 Hopper Volume

Hopper volume shall be reported in cubic yards, based on the most accurate method available for the dredge. The minimum standard of accuracy for hopper volume is interpolation from the certified hopper volume table, based on the average fore and aft ullage soundings.

3.1.12 Displacement

Dredge displacement shall be reported in long tons, based on the most accurate method available for the dredge. The minimum standard of accuracy for displacement is interpolation from the displacement table, based on the average draft. For this contract the density of water used to calculate displacement shall be _____ kg/cubic meter and shall be used for an additional interpolation between the fresh and salt water tables. *The water density used is project/location specific. 1000 kg/m³ (1g/cm³)- fresh water 1027 kg/m³ - 1030 kg/m³ (1.027g/cm³ - 1.03g/cm³)- salt water*

3.1.13 Empty Displacement

Empty displacement shall be reported in long tons, and shall be the lightship value of the dredge, or the weight of the dredge with no material in the hopper, adjusted for fuel and water consumption.

3.1.14 Draghead depths

Draghead depths shall be reported with an accuracy of ± 0.5 feet and a resolution to the nearest 0.1 feet as measured from the surface of the water with no tidal adjustments. Minimum accuracies are conditional to relatively calm water. The sensor value reported shall be an average of at least 10 samples per event, remove at least one maximum value and one minimum value, and average the minimum 8 remaining values.

3.1.15 Slurry Densities of Dragarms

A density metering device, calibrated according to the manufacturer's specifications, shall be used to record the slurry density of each dragarm to the nearest 0.0001 g/cc with an accuracy of ± 0.001 g/cc. If the manufacture does not specify a frequency of re-calibration, calibration shall be conducted prior to commencement of work.

3.1.16 Slurry Velocities of Dragarms

A flow metering device, calibrated according to the manufacturer's specifications, shall be used to record the slurry velocity of each dragarm to the nearest 0.0001 fps with an accuracy of ± 0.001 fps. If the manufacture does not specify a frequency of re-calibration, calibration shall be conducted prior to commencement of work. The slurry velocity shall be measured in the same pipeline inside diameter as that used for the slurry density measurement.

3.1.17 Pump RPM

Pump RPM shall be measured with the highest level of accuracy that is standard on the vessel operational displays, either at the bridge, at the drag tenders controls, or in the engine room. Dredges with multiple pumps per side shall report RPM for the pump that best describes the dredging process (typically the outboard pump). If requirements of section 3.1.19 are determined based on pump RPM, then that value shall be reported.

3.1.18 Sea Suction Valve for Dragarm

If sea suction can be taken to bypass suction through the draghead, the sea suction location and valve status will be reported. The status of the valve will change from "closed" to "open" when the valve starts to open and will register "closed" when the valve is fully closed. When applicable, the state of the latch will be reported as "true" or "false". The sea suction location shall be reported in a

standard non-changing name string of no more than 20 characters. These field values will always occur in the XML string as a set. The DQM system can only accommodate up to 4 unique sea suction locations. Suggested options for the naming convention can be found in the Example dataset in section 3.2.9, “Data Format”.

3.1.19 Pumpout

When the hopper dredge is being pumped out, a “True” value shall be reported; when it is not, a “False” value shall be reported. The only permissible values are “TRUE” and “FALSE”.

3.2 NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM SYSTEM REQUIREMENTS

Contractors DQM system shall be capable of collecting, displaying, and transmitting information to the DQM Database. The applicable parameters from section 3.1 shall be recorded as events locally and continually transmitted to the DQM Database anytime an internet connection is available. The Dredge shall be equipped with a DQM computer system consisting of a computer, monitor, keyboard, mouse, data modem, UPS, and network hub. The computer system shall be a standalone system, exclusive to the DQM monitoring system, and will have USACE DQM software installed on it. If a hardware problem occurs, or if a part of the system is physically damaged, then the Contractor shall be responsible for repairing it within 48 hours of determination of the condition.

3.2.1 Computer Requirements

The Contractor shall provide a dedicated on-board computer for use by the Dredging Quality Management system. This computer shall run the Corps’ software and receive data from the Contractor’s data reporting interface. This computer must meet or exceed the following performance specifications:

CPU: Intel or AMD processor with a (non-overclocked) clock speed of at least 3 gigahertz (GHz)

Hard drive: 250 gigabytes (GB); internal

RAM: 2 gigabytes

Ethernet adapter: 10 or 100 megabit (Mbit) internal network card with an RJ-45 connector

Video adapter: Must support resolution of 1024x768 at 16 bit color depth

Keyboard: Standard 101-key

- Mouse: Standard 2-button mouse
- Monitor: 17 inch viewable display; must support 1024x768 resolution at 16 bit color depth
- CD-ROM drive: 16X read speed/8X write speed
- Ports: 2 free Serial ports with standard 9-pin connectors; 1 free USB port
- Other hardware: Category 5 (Cat-5) cable with standard RJ-45 plugs connecting the network adapter to the network hub; one spare cable

Contractor shall install a fully-licensed copy of Windows 7 Professional Operating System on the computer specified above. Contractor shall also install any necessary manufacturer-provided drivers for the installed hardware.

This computer shall be located and oriented to allow data entry and data viewing, as well as to provide access to data ports for connection of external hardware. Location and orientation shall be subject to Contracting Officer's Representative's approval.

3.2.2 Software

The DQM computer's primary function is to transmit data to the DQM shore side database. No other software which conflicts with this function shall be installed on this computer. The DQM computer will have the USACE provided DQMOBS (Dredge Quality Management Onboard Software) installed on it by DQM personnel along with USACE selected software for remote support and management.

3.2.3 Network Hub

The DQM computer shall communicate via IEEE 802.3 Ethernet and the TCP/IP networking protocol. The Contractor shall provide a network hub to allow the temporary addition of the Contracting Officer's representative's portable computer to the computer network. The hub shall provide a minimum of four RJ-45 ports that support Category 5 (Cat-5) cable with standard RJ-45 plugs connecting the network adapter to the network hub; one spare cable shall be available on site to plug into the network hub.

3.2.4 UPS

The Contractor shall supply an Uninterruptible Power Supply (UPS) for the computer and networking equipment. The UPS shall provide backup power at

1kVA for a minimum of 10 minutes. The UPS shall interface to the DQM computer to communicate UPS status. The Contractor shall ensure that sufficient power outlets are available to run all specified equipment.

3.2.5 Internet Access

The Contractor shall maintain an internet connection capable of transmitting real time data to the DQM Server and supporting remote access, as well as enough additional band width to clear historically queued data when a connection is re-obtained. The telemetry system shall be always available and have connectivity in contract area. If connectivity is lost, unsent data shall be queued and transmitted upon restoration of connectivity. The Contractor shall acquire and install all necessary hardware and software to make the internet connection available for data transmission to the DQM web service. The hardware and software must be configured to allow the USACE DQM center remote access to this computer. Coordination between the dredging company's IT and DQM support may be required in order to configure remote access through any security, firewall, router, and telemetry systems. Telemetry systems must be capable of meeting these minimum reporting requirements in all operating conditions.

3.2.6 Data Routing Requirements

Onboard sensors shall continually monitor dredge conditions, operations and efficiency and route this information into the shipboard dredge-specific system computer (DSS) to assist in guiding dredge operations. Portions of this Contractor-collected information shall be routed to the DQM computer on a real-time basis. Standard sensor data shall be sent to the DQM computer via an RS-232 9600- or 19200-baud serial interface. The serial interface shall be configured as 8 bits no parity and no flow control.

3.2.7 Data Reporting Frequency

Data shall be logged as a series of events. Each event will consist of a data set containing dredge information as per section 3.1. Each set of measurements (i.e. time, position, etc...) will be considered an event. All required information in section 3.1 that are not an averaged variable (i.e. draft and ullage) shall be collected within one second of the reported time. A data string for an event shall be sent to the DQM computer every 6 to 12 seconds and this interval shall remain constant throughout the contract; data strings shall never be transmitted more frequently than once per every 5 seconds. Any averaged variable must be collected and computed within this sampling interval.

3.2.8 Data Format

Data shall be reported as an eXtensible Markup Language (W3C standard XML 1.0) document as indicated below. Line breaks and spaces are added for

readability, but the carriage return, line feed character combination is only added to delineate records (HOPPER_DREDGING_DATA tag) for actual data transmission.

```
<?xml version="1.0"?>
<HOPPER_DREDGING_DATA version = "2.0">
  <DREDGE_NAME> string32 </DREDGE_NAME>
  <HOPPER_DATA_RECORD>
    <DATE_TIME> time date string </DATE_TIME>
    <CONTRACT_NUMBER> string32 </CONTRACT_NUMBER>
    <LOAD_NUMBER> integer string </LOAD_NUMBER>
    <VESSEL_X coord_type = "LL"> floating point string </VESSEL_X>
    <VESSEL_Y coord_type = "LL"> floating point string </VESSEL_Y>
    <PORT_DRAG_X coord_type = "LL"> floating point string </PORT_DRAG_X>
    <PORT_DRAG_Y coord_type = "LL"> floating point string </PORT_DRAG_Y>
    <STBD_DRAG_X coord_type = "LL"> floating point string </STBD_DRAG_X>
    <STBD_DRAG_Y coord_type = "LL"> floating point string </STBD_DRAG_Y>
    <HULL_STATUS> OPEN/CLOSED string </HULL_STATUS>
    <VESSEL_COURSE> floating point string <VESSEL_COURSE >
    <VESSEL_SPEED> floating point string </VESSEL_SPEED>
    <VESSEL_HEADING> floating point string </VESSEL_HEADING>
    <TIDE> floating point string </TIDE>
    <DRAFT_FORE> floating point string </DRAFT_FORE>
    <DRAFT_AFT> floating point string </DRAFT_AFT>
    <ULLAGE_FORE> floating point string </ULLAGE_FORE>
    <ULLAGE_AFT> floating point string </ULLAGE_AFT>
    <HOPPER_VOLUME> floating point string </HOPPER_VOLUME>
    <DISPLACEMENT> floating point string </DISPLACEMENT>
    <EMPTY_DISPLACEMENT> floating point string </EMPTY_DISPLACEMENT>
    <DRAGHEAD_DEPTH_PORT> floating point string </DRAGHEAD_DEPTH_PORT>
    <DRAGHEAD_DEPTH_STBD> floating point string </DRAGHEAD_DEPTH_STBD>
    <PORT_DENSITY> floating point string </PORT_DENSITY>
    <STBD_DENSITY> floating point string </STBD_DENSITY>
    <PORT_VELOCITY> floating point string </PORT_VELOCITY>
    <STBD_VELOCITY> floating point string </STBD_VELOCITY>
    <PUMP_RPM_PORT> floating point string </PUMP_RPM_PORT>
    <PUMP_RPM_STBD> floating point string </PUMP_RPM_STBD>
    <VALVE_1_LOCATION> string32 </VALVE_1_LOCATION>
    <VALVE_1_STATUS> open/closed </VALVE_1_STATUS>
    <VALVE_1_LATCHED> true/false </VALVE_1_LATCHED>
    <VALVE_2_LOCATION> string32 </VALVE_2_LOCATION>
    <VALVE_2_STATUS> open/closed </VALVE_2_STATUS>
    <VALVE_2_LATCHED> true/false </VALVE_2_LATCHED>
    <VALVE_3_LOCATION> string32 </VALVE_3_LOCATION>
    <VALVE_3_STATUS> open/closed </VALVE_3_STATUS>
    <VALVE_3_LATCHED> true/false </VALVE_3_LATCHED>
    <VALVE_4_LOCATION> string32 </VALVE_4_LOCATION>
    <VALVE_4_STATUS> open/closed </VALVE_4_STATUS>
    <VALVE_4_LATCHED> true/false </VALVE_4_LATCHED>
    <PUMP_OUT_ON> true/false/unknown string </PUMP_OUT_ON>
  </HOPPER_DATA_RECORD>

</HOPPER_DREDGING_DATA>
Carriage return – ASCII value 13
Line Feed – ASCII value 10
```

Example

```
<?xml version="1.0"?>
<HOPPER_DREDGING_DATA version = "2.0">
  <DREDGE_NAME>Essayons</DREDGE_NAME>
  <HOPPER_DATA_RECORD>
    <DATE_TIME>04/11/2002 13:12:05</DATE_TIME>
    <CONTRACT_NUMBER>GDSNWP-11-G-0001</CONTRACT_NUMBER>
    <LOAD_NUMBER>102</LOAD_NUMBER>
    <VESSEL_X coord_type = "LL">-80.123333</VESSEL_X>
    <VESSEL_Y coord_type = "LL">10.123345</VESSEL_Y>
    <PORT_DRAG_X coord_type = "LL">-80.1233371</PORT_DRAG_X>
    <PORT_DRAG_Y coord_type = "LL">10.12335</PORT_DRAG_Y>
    <STBD_DRAG_X coord_type = "LL">-80.123339</STBD_DRAG_X>
    <STBD_DRAG_Y coord_type = "LL">10.123347</STBD_DRAG_Y>
    <HULL_STATUS>CLOSED</HULL_STATUS>
    <VESSEL_COURSE>258</VESSEL_COURSE>
    <VESSEL_SPEED>3.4</VESSEL_SPEED>
    <VESSEL_HEADING>302</VESSEL_HEADING>
    <TIDE>-0.1</TIDE>
    <DRAFT_FORE>10.05</DRAFT_FORE>
    <DRAFT_AFT>15.13</DRAFT_AFT>
    <ULLAGE_FORE>10.11</ULLAGE_FORE>
    <ULLAGE_AFT>10.22</ULLAGE_AFT>
    <HOPPER_VOLUME>2555.2</HOPPER_VOLUME>
    <DISPLACEMENT>4444.1</DISPLACEMENT>
    <EMPTY_DISPLACEMENT>2345.0</EMPTY_DISPLACEMENT>
    <DRAGHEAD_DEPTH_PORT>55.10</DRAGHEAD_DEPTH_PORT>
    <DRAGHEAD_DEPTH_STBD>53.21</DRAGHEAD_DEPTH_STBD>
    <PORT_DENSITY>1.02</PORT_DENSITY>
    <STBD_DENSITY>1.03</STBD_DENSITY>
    <PORT_VELOCITY>22.1</PORT_VELOCITY>
    <STBD_VELOCITY>23.3</STBD_VELOCITY>
    <PUMP_RPM_PORT> 55 </PUMP_RPM_PORT>
    <PUMP_RPM_STBD> 54 </PUMP_RPM_STBD>
    <VALVE_1_LOCATION> Starboard Dragarm </VALVE_1_LOCATION>
    <VALVE_1_STATUS>open</VALVE_1_STATUS>
    <VALVE_1_LATCHED>true</VALVE_1_LATCHED>
    <VALVE_2_LOCATION> Port Dragarm</VALVE_2_LOCATION>
    <VALVE_2_STATUS> closed</VALVE_2_STATUS>
    <VALVE_2_LATCHED>false</VALVE_2_LATCHED>
    <VALVE_3_LOCATION>Port Sea Chest</VALVE_3_LOCATION>
    <VALVE_3_STATUS> closed</VALVE_3_STATUS>
    <VALVE_3_LATCHED>false</VALVE_3_LATCHED>
    <VALVE_4_LOCATION>Starboard Sea Chest</VALVE_4_LOCATION>
```

```
<VALVE_4_STATUS>open </VALVE_4_STATUS>
<VALVE_4_LATCHED> false</VALVE_4_LATCHED>
<PUMP_OUT_ON>false</PUMP_OUT_ON>
</HOPPER_DATA_RECORD>
</HOPPER_DREDGING_DATA>
<cr>
<lf>
<DREDGE_NAME>Essayons</DREDGE_NAME>
  <HOPPER_DATA_RECORD>
    <DATE_TIME>04/11/2002 13:12:10</DATE_TIME>
    <CONTRACT_NUMBER>GDSNWP-11-G-0001</CONTRACT_NUMBER>
    <LOAD_NUMBER>102</LOAD_NUMBER>
    <VESSEL_X coord_type = "LL">-80.123334</VESSEL_X>
    <VESSEL_Y coord_type = "LL">10.123346</VESSEL_Y>
    <PORT_DRAG_X coord_type = "LL">-80.1233372</PORT_DRAG_X >
    <PORT_DRAG_Y coord_type = "LL">10.12336</PORT_DRAG_Y >
    <STBD_DRAG_X coord_type = "LL">-80.123340</STBD_DRAG_X >
    <STBD_DRAG_Y coord_type = "LL">10.123348</STBD_DRAG_Y >
    <HULL_STATUS>CLOSED</HULL_STATUS>
    <VESSEL_COURSE>259</VESSEL_COURSE>
    <VESSEL_SPEED>3.5</VESSEL_SPEED>
    <VESSEL_HEADING>300</VESSEL_HEADING>
    <TIDE>-0.1</TIDE>
    <DRAFT_FORE>10.00</DRAFT_FORE>
    <DRAFT_AFT>15.15</DRAFT_AFT>
    <ULLAGE_FORE>10.15</ULLAGE_FORE>
    <ULLAGE_AFT>10.20</ULLAGE_AFT>
    <HOPPER_VOLUME>2555.5</HOPPER_VOLUME>
    <DISPLACEMENT>4444.0</DISPLACEMENT>
    <EMPTY_DISPLACEMENT>2345.0</EMPTY_DISPLACEMENT>
    <DRAGHEAD_DEPTH_PORT>55.15</DRAGHEAD_DEPTH_PORT>
    <DRAGHEAD_DEPTH_STBD>53.19</DRAGHEAD_DEPTH_STBD>
    <PORT_DENSITY>1.00</PORT_DENSITY>
    <STBD_DENSITY>1.01</STBD_DENSITY>
    <PORT_VELOCITY>22.5</PORT_VELOCITY>
    <STBD_VELOCITY>23.3</STBD_VELOCITY>
    <PUMP_RPM_PORT> 55 </PUMP_RPM_PORT>
    <PUMP_RPM_STBD> 54 </PUMP_RPM_STBD>
    <VALVE_1_LOCATION> Starboard Dragarm </VALVE_1_LOCATION>
    <VALVE_1_STATUS>open</VALVE_1_STATUS>
    <VALVE_1_LATCHED>true</VALVE_1_LATCHED>
    <VALVE_2_LOCATION> Port Dragarm</VALVE_2_LOCATION>
    <VALVE_2_STATUS> closed</VALVE_2_STATUS>
    <VALVE_2_LATCHED>false</VALVE_2_LATCHED>
    <VALVE_3_LOCATION>Port Sea Chest</VALVE_3_LOCATION>
    <VALVE_3_STATUS> closed</VALVE_3_STATUS>
```



```

<VALVE_3_LATCHED>>false</VALVE_3_LATCHED>
<VALVE_4_LOCATION>Starboard Sea Chest</VALVE_4_LOCATION>
<VALVE_4_STATUS>open </VALVE_4_STATUS>
<VALVE_4_LATCHED> false</VALVE_4_LATCHED>
<PUMP_OUT_ON>>false</PUMP_OUT_ON>
</HOPPER_DATA_RECORD>
</HOPPER_DREDGING_DATA>
<cr>
<lf>

```

3.2.9 Data Reporting

The system shall transmit correctly formatted event data XML strings to the DQM Database continuously from mobilization until the last USACE post-dredging survey has been accepted. If the internet connection (section 3.2.6) is non-operable, manual backups from the dredge computer of the XML data string which would have been transmitted to the DQM computer over the serial connection shall be performed for each day the device is inoperable and submitted to the DQM center within 48 hours. This submission does not replace the requirement of correcting the issue affecting automatic transmission of data. In the event of data transfer, transmission, or hardware failure; a manually recorded disposal log shall be maintained. It shall consist of a series of events. These events are: start of dredging, end of dredging, pre-disposal and post-disposal events. Each event shall include: time stamp (GMT), position (Latitude and Longitude WGS84), draft, ullage, volume and displacement. Disposal logs shall be submitted on a daily basis to the Contracting Officer's Representative during the time when the system is not operational.

3.2.10 Contractor Data Backup

The Contractor shall maintain an archive of all data sent to the DQM computer during the dredging contract. The COR may require, at no increase in the contract price, that the Contractor provide a copy of these data covering specified time periods. The data shall be provided in the XML format which would have been transmitted to the DQM computer. There shall be no line breaks between the parameters; each record string shall be on separate line. Naming convention for the files shall be

```

<dredgename>_<StartYYYYMMddhhmmss>_<EndYYYYMMddhhmmss>.txt .

```

Data submission shall be via storage medium acceptable to the COR.

At the end of the dredging contract, the Contractor shall contact the National DQM Support Center prior to discarding the data to ensure it has been appropriately archived. The Contractor shall record in a separate section at the end of the dredge's on-board copy of the DPIIP the following information:

- a. Person who made the call
- b. The date of the call
- c. The DQM representative who gave permission to discard

The same day of the phone call and prior to discarding the data, the Contractor shall submit a "Data Appropriately Archived e-mail" to the local districts Contracting Officer's Representative with the above information, and Cc: the DQM Support Center representative providing permission. In addition to the above information, also include in the e-mail:

- d. Project name and contract number
- e. Dredge start and end dates
- f. Name of hopper dredge

3.3 PERFORMANCE REQUIREMENTS

The Contractor's DQM system shall be fully operational at the start of dredging operations and fully certified prior to moving dredge material on the contract (see Section 1.4, National Dredging Quality Management Program Certification). To meet contract requirements for operability, in addition to certification, the Contractor's system shall provide a data string with values for all parameters while operating, as described within the specifications. Additionally, all hardware shall be compliant with hardware requirements (Section 3.2). Quality data strings are considered to be those providing values for all parameters reported when operating according to the specification. Repairs necessary to restore data return compliance shall be made within 48 hours. If the Contractor fails to report required data within the specified time window for dredge measurements (see Sections 3.2.7 "Data Measurement Frequency" and 3.2.9 "Data Reporting"); the system will be declared not fully operational, and the Contractor will be assessed liquidated damages equivalent to the additional oversight hours that would be required for Corps personnel to be on site from the first full day after the system is deemed not operational through to the time when the system is returned to fully operational status. For this contract, the liquidated damages shall be \$2,550.00 per day.

3.4 COMPLIANCE QUALITY ASSURANCE CHECKS

Quality assurance checks are required prior to the commencement of dredging, and at the discretion of a COR periodically throughout the duration of the contract. Detailed instructions for performing these checks and a spreadsheet for recording the results are available at <http://dqm.usace.army.mil/Certifications/Index.aspx>. Incoming data shall be periodically reviewed to assure compliance with performance requirements outlined in section 3.3. In addition to making sure the data received meets the reporting requirements outlined in the sub sections under

section 3.1, a more detailed description of some of the quality assurance methods are outlined below.

For annual instrumentation checks and compliance monitoring, the DQM Data Acquisition Team personnel attempt to be as flexible as possible in performing their checks so as not to delay work; however, in order to expedite matters as much as possible, it is necessary that they receive the support and cooperation of the local district and dredging contractor. The dredging contractor shall coordinate pickup times and locations and provide transportation to and from any platform with a DQM certified system in a timely manner. Calibrations to the sensors should already be performed before DQM personnel arrive on site.

3.4.1 Draft & Displacement Check

The COR shall periodically verify the accuracy of the fore and aft system reported draft values by comparing the vessel hull draft marks to the corresponding sensor readings indicated on the DQM screen. The vessel's hull draft reading shall be viewed from a contractor supplied auxiliary vessel circling the dredge. The COR shall review the difference between averaged drafts recorded by the instruments and those estimated from the draft marks to insure that the system is operating within the acceptable accuracy of approximately ± 0.1 ft. in calm seas conditions. Reported draft values will be verified light, loaded, and at other intervals at the discretion of the COR. If sensors responsible for collecting draft values are not located on centerline, verification may be required under different trim and list conditions. If values are outside the acceptable range, the Contractor shall re-calibrate or repair system components as necessary. This check may be performed separately or as a part of the Water Load Test. For each system provided fore and aft draft, an average draft value will be calculated during the draft check, and the corresponding displacement will be verified longhand using the supplied draft/displacement tables.

3.4.2 Draghead Depth Check

The COR may require periodic calibration checks of the reported draghead depth using manual means such as tape measures or sounding lines to directly measure draghead depth. The Contractor shall furnish a steel tape, chain, or wire with clearly visible flags/tags placed at 1 foot increments within the operational range of the dragarm. These devices shall be capable of measuring the depth below the water surface to the lowest fixed point of each draghead (often the heel) with sufficient length to measure 5 feet more than the maximum project depth. Pressure sensors may be used to verify calibration of the draghead sensors only in areas where current flow past the vessel/dragarm cannot be reduced sufficiently to allow safe handling of manual measuring devices. Pressure sensors, used for this purpose shall be vented pressure gages and shall be subjected to an annual manufacturer's calibration. Prior to the dragarm depth check, the sensor shall be checked at a known depth, and may be required to be zeroed at this point

according to manufacturer's specifications. Care shall be taken not to kink the cable or restrict the vent during deployment.

The COR shall review the draghead depth data to insure that the system is operating within acceptable accuracy, and may direct the Contractor to re-calibrate or repair system components as necessary. If a bubbler type system is used, weekly calibration of the draghead sensors is recommended, as they are sensitive to environmental conditions.

3.4.3 Ullage Sounding & Volume Check

The COR shall periodically check the reported hopper ullage sounding using a tape measure or other distance measuring device. The Contractor shall furnish a clearly readable weighted tape, marked in tenths of a foot, capable of measuring throughout the full range of hopper depth. The weight for this tape shall be a 6-inch diameter disk weighing between 2 and 3 pounds. The COR shall review the hopper dredge ullage sounding data to insure that the system is operating within acceptable accuracy (0.1 feet). Reported ullage soundings will be verified light, loaded, and at other intervals at the COR's discretion. Measurements can be taken from multiple locations along the combing or from sensor location at the COR's discretion. If values are outside the acceptable range, the Contractor shall re-calibrate or repair system components as necessary. This check may be performed separately or as a part of the Water Load Test. For each sensor provided fore and aft ullage sounding value, an average ullage sounding value will be calculated during the ullage sounding check, and the corresponding volume will be verified longhand using the supplied hopper volume tables.

3.4.4 Position Check

During the QA checks the reported position of the dredge shall be verified by comparison with readings from a handheld GPS receiver. Throughout the contract, the COR shall periodically take readings from an independent GPS to verify locations.

3.4.5 Water Load Test

Water Tests shall consist of pumping the hopper dredge out to its lowest level and then filling it to capacity with water, taking ullage and draft measurements at both levels to determine hopper dredge volume and displacement. The objective of the water test is to validate the dredge's reported displacement and hopper volumes. If the results of the water test indicate that the system is not operating within acceptable accuracy, the Contractor shall correct the deficiencies causing the error, and repeat the water test until the results are acceptable.

The Contractor shall provide a handheld refractometer with automatic temperature compensation to measure the hopper dredge water specific gravity

during water tests. The refractometer shall be capable of measuring the hopper dredge water specific gravity with a resolution of 0.001 and minimum accuracy of ± 0.001 . The Contractor shall also provide a water-sampling device to retrieve a sufficient volume of water from various depths in the hopper dredge to accurately determine specific gravity with the refractometer, and a sufficient volume of deionized water for calibration of the device.

3.5 CONTRACTOR QUALITY CONTROL

Dredging contractor shall designate a quality control systems manager (QCSM), who shall develop and maintain daily procedures to ensure the contractor's quality control (CQC) of the DQM system. These methods shall include a procedure by which data being collected is checked against known values, telemetry is verified to be functioning, and the DQM computer is verified to be on and the DQMOBS is running. The Contractor Quality Control Plan which describes these methods and procedures shall be included in the DPIP as per section 1.5 Table of Contents, item 27. This is the only section which shall be submitted to the local district and is a required submittal prior to the start of the contract. CQC Reports may be required at the discretion of the QAR daily. Annotations shall be made in the CQC Report documenting all actions taken on each day of work including all deficiencies found and corrective actions taken.

3.6 LIST OF ITEMS TO BE PROVIDED BY THE CONTRACTOR

DPIP	Sec 1.5 Dredge Plant Instrumentation Plan
DQM SYSTEM	
Sensor Instrumentation	Sec. 3.1 Specifications for Reported Data
DQM Computer	Sec. 3.2 National Dredging Quality Management System Requirements
DREDGE DATA	
Event documentation	Sec. 3.2.9 Data Reporting
Dredge Data Backups	Sec 3.2.10 Contractor Data Backups
QA EQUIPMENT ON DREDGE	
Ullage tape	Sec. 3.4.3 Ullage Sounding & Volume Check
Dragarm depth chain	Sec. 3.4.2 Draghead Depth Check
Refractometer –measuring in grams/cubic centimeter with a resolution of 0.001 and a minimum accuracy of ± 0.001 with calibration water	Sec. 3.4.5 Water Load Test
Water sampling device	Sec. 3.4.5 Water Load Test

4. VERBAL INSTRUCTIONS RECEIVED: (List any instructions given by Government personnel on construction deficiencies. retesting required, etc., with action to be taken.)

5. REMARKS: (Cover any conflicts in plans, specifications or instructions: acceptability of incoming materials: offsite surveillance activities; progress of work, delays, causes and extent thereof; days of no work with reasons for same.)

6. SAFETY: (Include any infractions of approved safety plan, safety manual or instructions from Government personnel. Specify corrective action taken.)


INSPECTOR

CONTRACTOR'S CERTIFICATION: I certify that the above report is complete and correct and that all material and equipment used, work performed and tests conducted during this reporting period were in strict compliance with the contract plans and specifications except as noted above.

CONTRACTOR'S APPROVED AUTHORIZED REPRESENTATIVE

The graphic format for this 4'x 6' sign panel follows the legend guidelines and layout as specified below. The large 4'x 4' section of panel on the right is to be white with black legend. The 2'x 4' section of the sign on the left with the full Corps signature (reverse version) is to be screen printed Communications Red on the White background.

This sign is to be placed with the Safety Performance Sign (See Fig. 5d).

3"	21"	3"	42"	3"
4.5"	<p>Design and Construction Supervised by</p>  <p>US Army Corps of Engineers South Atlantic Division Mobile District</p>	<h1>Name of Project</h1> <p>Location: City and State</p> <p>Design By: US Army Corps of Engineers Mobile District</p> <p>Contractor: Name City and State</p>	6"	
2"			4.5"	
6.25"			4.5"	
10.5"			6"	
2.5"			2.25"	
2"			9.5"	
			1.875"	
			1.875"	
	1.875"			
		1.875"		
		7.75"		
3"	21"	1"	21"	3"

Legend Group 1: One to two-line description of Corps relationship to project
Color: White
Typeface: 1.25" Helvetica Regular
Maximum line length: 19"

Legend Group 2: Division\ District Name Placed below 10.5" Reverse Signature (6" Castle).
Color: White
Typeface: 1.25" Helvetica Regular

Legend Group 3: One- to three-line project title legend describes the work being done under this contract.
Color: Black
Typeface: 3" Helvetica Bold
Maximum line length: 42"

Legend Group 4: One- to two-line identification of project or facility (civil works) or name of sponsoring department (military).
Color: Black
Typeface: 1.5" Helvetica Regular
Maximum line length: 42"

Cross-align the first line of Legend Group 4 with the first line of the Corps Signature (US Army Corps) as shown.

Legend Groups 5a-b: One- to five-line identification of prime contractors including: type (architect, general contractor, etc.), corporate or firm name, city, state. Use of Legend Group 5 is optional.
Color: Black
Typeface: 1.25" Helvetica Regular
Maximum line length: 21"

All typography is flush left and rag right, upper and lower case with initial capitals only as shown. Letter- and word-spacing to follow Corps standards

Sign Type	Legend Size	Panel Size	Post Size	Specification Code	Mounting Height	Color Bkg/Lgd
CID-01	Various	4' x 6'	4" x 4"	HDO-3	48"	WH-RD/BK

CONSTRUCTION SIGN (CORPS OF ENGINEERS DESIGN)

(Use with Fig 5c)

Fig. 5b

All Construction Project Identification signs and Safety Performance signs are to be fabricated and installed as described below. The signs are to be erected at a location designated by the contracting officer and shall conform to size, format, and typographic standards.

The sign panels are to be fabricated from .75" High Density Overlay Plywood.

Sign graphics to be prepared on a white non-reflective vinyl film with positionable adhesive backing.

All graphics except for the Communications Red background with Corps signature on the project sign are to die-cut or computer cut nonreflective vinyl, pre-spaced legends prepared in the sizes and typefaces specified and applied to the background panel following the graphic formats shown.

The 2' x 4' Communications Red panel (to match PMS-032) with full Corps signature (reverse version) is to be screen printed on the white background identification of the District / Division may be applied under the signature with white cut vinyl letters prepared to Corps standards


Drill and insert six (6) .375 T-nuts from the front face of the HDO sign panel. Position holes as shown. Flange of T-nut to be flush with sign face

Apply Graphic panel to prepared HDO plywood panel following manufactures instructions

Sign uprights to be structural grade 4" x 4" treated Douglas Fur or Southern Yellow Pine. No 1 or better. Post to be 12' long Drill six (6) .375" mounting holes in uprights to align with T-nuts in sign panel. Countersink (5") back of hole to accept socket head cap screw (4" x .375").

Assemble sign panel and uprights. Imbed assembled sign panel and uprights in 4' hole. Local soil conditions and/or wind loading may require bolting additional 2" x 4" structs on inside face of uprights to reinforce installation shown.

Shown below the mounting diagram is a panel layout grid with spaces provided for project information. Photocopy this page and use as a worksheet when preparing sign Legend orders.



Construction Project Sign Legend Group 1

1 _____

2 _____

Legend Group 2 Division/District Names

1 _____

2 _____

Legend Group 3 Project Title

1 _____

2 _____

3 _____

Legend Group 4 Facility Name

1 _____

2 _____

Legend Group 5a: Contractor/A&E

1 _____

2 _____

3 _____

4 _____

5 _____

Legend Group 5b: Contractor/A&E

1 _____

2 _____

3 _____

4 _____

5 _____

Safety Performance Sign Legend Group 1: Project Title

1 _____

2 _____

Legend Group 2: Contractor/A&E

1 _____

2 _____

Each contractor's safety record is to be posted on Corps managed or supervised construction projects and mounted with the construction project identification sign.

The graphic format, color, size and type-faces used on the sign are to be reproduced exactly as specified below. The title with First Aid logo in the top section of the sign and the performance record captions are

standard for all signs of the type. Legend Groups 2 and 3 below identify the project and the contractor and are to be placed on the sign as shown.

Safety record numbers are mounted on individual metal plates and are screw-mounted to the background to allow for daily revisions to posted safety performance record.

Legend Group 1: Standard two-line title "Safety is a Job requirement" with (8 od.) Safety Green First Aid logo.
Color: to match PMS 347
Typeface: 3" Helvetica Bold
Color: Black


Legend Group 2: One to two-line project title legend describes the work being done under this contract and name of host project.
Color: Black
Typeface: 1.5" Helvetica Regular
Maximum line length: 42"

Legend Group 3: One to two-line identification: name of prime contractor and city, state address.
Color: Black
Typeface: 1.5" Helvetica Regular
Maximum line length: 42"


Legend Group 4: Standard safety record captions as shown.
Color: Black
Typeface: 12.5" Helvetica Regular

Replaceable numbers are to be mounted on white .060 aluminum plates and screw-mounted to background.
Color: Black
Typeface: 3" Helvetica Regular
Plate size: 2.5" x .5"

All typography is flush left and rag right. Upper and lower case with initial capitals only as shown. Letter- and word-spacing to follow Corps standards.





Sign Type	Legend Size	Panel Size	Post Size	Specification Code	Mounting Height	Color Bkg/Lgd
CID-02	various	4"x4"	4"x4"	HDO-3	48"	WH/BK-GR



SAFETY PERFORMANCE SIGN

Fig. 5d



NOTES.

1. DRAWING N.T.S.
2. ALL LUMBER TO BE PRESSURE TREATED
3. ALL LETTERING WILL BE DISPLAYED IN RED
4. CASTLE TO BE PAINTED RED W/WHITE OPENINGS
5. BORDER TO BE PAINTED REFLECTIVE RED
6. ALL OTHER LUMBER TO BE PAINTED WHITE
7. POST/STAKE HOLES TO BE BACKFILLED & TAMPED
8. SIGNS TO BE REMOVED UPON COMPLETION OF PROJECT
9. RESTORE SITE TO ORIGINAL CONDITION
10. LETTER SIZE AS SHOWN

